

April 18, 2014
BOARD OF COUNTY COMMISSIONERS
ORANGE COUNTY, FLORIDA
Y14-772-MM / ADDENDUM #3
ORANGE COUNTY CONVENTION CENTER EXHIBIT DRIVE PAVEMENT
REHABILITATION

Revised Bid Opening Date: April 24, 2014

This addendum is hereby incorporated into the bid documents of the project referenced above. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. Underlining indicates additions, deletions are indicated by ~~strikethrough~~.

A. The Bid Opening Date is changed from ~~April 22, 2014 at 2:00 P.M.~~ to April 24, 2014 at 2:00 P.M.

B. In Part D of the IFB, delete page D-3, the bid item schedule, in its' entirety and replace with the attached **REVISED PAGE D-3**, the revised bid item schedule.

Failure of a bidder to submit their bid using the revised bid item schedule shall result in their bid being found non-responsive.

C. Add the attached Section 02513, Asphalt Paving to the project specifications.

D. ADD the following paragraph to Specification Section 01150 – Measurements and Payment:

17. Superpave Asphaltic Concrete, shall be measured for payment by the weight of the mixture, in tons completed and accepted by the Engineer. The bid price and payment shall be full compensation for all materials, labor and equipment necessary to construct the pavement as shown in the plans and per Section 02513 of the Project Manual. Payment will be made under Pay Item No. 0334-1-3 – Superpave Asphaltic Concrete - per ton.

D. All other terms and conditions of the IFB remain the same.

E. The Proposer shall acknowledge receipt of this addendum by completing the applicable section in the solicitation or by completion of the acknowledgement information on the addendum. Either form of acknowledgement must be completed and returned not later than the date and time for receipt of the proposal.

Receipt acknowledged by:

Authorized Signature

Date Signed

Title

Name of Firm

**Y14-772-MM
EXHIBIT DRIVE
PAVEMENT REHABILITATION IMPROVEMENTS
REVISED BID SHEET**

REF.#	PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	AMOUNT	
1	101-1	MOBILIZATION (Note 1)	LS	1			
2	102-1	MAINTENANCE OF TRAFFIC/ UTILITIES	LS	1			
3	104-13	SEDIMENT BARRIER, SILT FENCING AND INLET PROTECTION	LS	1			
4	110-1	CLEARING AND GRUBBING	LS	1			
5	120-4	REGULAR EXCAVATION	LS	1			
6	285-7-11	6" BASE COURSE MATERIAL (CRUSHED CONCRETE, 300 PSI)	SY	1980			
7	334-1-3	SUPERPAVE ASPHALTIC CONCRETE	TN	10.5			
8	350-2-3	CEMENT CONCRETE PAVEMENT, REINFORCED, 8" (5,000 PSI)	SY	1980			
9	440-1-30	UNDERDRAIN, TYPE I	LF	589			
10	520-1-10	CURB & GUTTER CONC. (TYPE F)	LF	1227			
11	520-4	SPECIAL CONCRETE GUTTER (DROP CURB)	LF	48			
12	523-1	PATTERNED/ TEXTURED PAVEMENT (STAMPED CONCRETE), VEHICULAR AREAS	SY	103			
13	575-1	SODDING (MATCH EXISTING)	SY	300			
14	660-1	VEHICULAR DETECTOR ASSEMBLY, REPLACE	EA	8			
15	711-11-111	THERMOPLASTIC TRAFFIC STRIPE, 6" SOLID WHITE	LF	275			
16	711-11-125	THERMOPLASTIC TRAFFIC STRIPE, 24" SOLID WHITE	LF	37			
17	711-11-131	THERMOPLASTIC TRAFFIC STRIPE, 6" SKIP WHITE	LF	302			
18	711-11-170	THERMOPLASTIC TRAFFIC ARROW, STANDARD, WHITE	EA	8			
19	900-1	AS-BUILT PLANS ON MYLARS (BLACK-LINED)	LS	1			
20	900-2	INDEMNIFICATION	LS	1	\$100.00	\$100.00	
		ESTIMATED TOTAL BID AMOUNT				\$	
Note 1	Any amount of Mobilization in excess of 10% of the total of Roadway Bid Items with reference number 2 through 19 will be paid upon completion of all work in accordance with Technical Provision (TP) 101.						

REVISED
D-3

**Y14-772-MM
Addendum #3
April 18, 2014**

**SECTION 02513
ASPHALT PAVING**

PART 1 - GENERAL

1.1 SCOPE:

A. The work shall consist of furnishing all materials, labor and equipment for compacting subgrade, constructing a base course, priming the base course and constructing an asphaltic concrete surface course.

B. SUBMITTALS: Comply with the requirements of Section 01330 - Submittals

C. MATERIAL CERTIFICATES:

Provide copies of material certificates signed by material producer and Contractor, certifying that each material item meets or exceeds specified requirements.

D. CODE COMPLIANCE:

Comply with the Orange County Road Construction Specifications, latest edition, if more stringent than herein specified.

PART 2 - PRODUCTS

2.1 GENERAL:

A. All materials furnished hereunder shall comply with the applicable sections of the Florida Department of Transportation's (FDOT) "Standard Specifications for Road and Bridge Construction", latest edition, which are hereby incorporated into these specifications by reference.

B. MATERIALS:

General: Use locally available materials and gradations which exhibit a satisfactory record of previous installations.

1. Subgrade Stabilizing Material: FDOT Section 160 and Section 914.
2. Base Course: Soil-Cement Base (Primed), FDOT Section 921.
3. Asphaltic Concrete: Comply with FDOT Section 330 requirements and Section 334 for Superpave (SP 12.5) Asphaltic Concrete.
4. Prime and Tack Coats: Cut-back asphalt, grade RC-70, meeting FDOT Section 300.
5. Lane Marking Paint: FDOT Section 971, color as indicated.

PART 3 - EXECUTION

3.1 GENERAL:

A. All operations hereunder shall be conducted in strict compliance with the requirements of the Orange County Road Construction Specifications and with applicable sections of the FDOT Standard Specifications as follows:

- B. Subgrade Stabilization: FDOT Section 160
- C. Construction of Base Course: Match existing.
- D. Construction of Wearing Course: FDOT Section 330.
- E. Pavement Markings: FDOT Sections 710 and 711.

END OF SECTION 02513