

February 6, 2015

BOARD OF COUNTY COMMISSIONERS
ORANGE COUNTY, FLORIDA

ADDENDUM No. 3 / IFB No. Y15-741-PH
PUMP STATIONS No.'s 3257 BAY LAKES GRANADA, 3335 RAMSGATE CIRCLE,
3514 CYPRESS POINT PHASE 1 AND 3526 CYPRESS POINT PHASE 2
IMPROVEMENTS PACKAGE No. 7

Revised BID OPENING DATE: February ~~10~~ 17, 2015

This Addendum is hereby incorporated into the bid documents of the project referenced above. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. Additions are indicated by underlining, deletions are indicated by ~~strike through~~.

The bid opening is changed to February 17, 2015.

A. CLARIFICATIONS

- 1. Q: Please clarify whether the valve vaults for PS #3335, #3526, & #3514 shall be coated with a protective liner?**

A: Yes, all the existing valve vaults that will remain are to be coated. Existing valve vaults shall be coated using the approved material listed under "Coating for Existing Manholes" in OCU Appendix D, page 10 of 17.
- 2. Q: Drawing P200, note 9. States the contractor is to install wall sleeves for pipe entering and leaving the wet well. Is this note intended to be for new structures? Since we are rehabbing the existing structure, will cast-in-place wall sleeves be required?**

A: New wall sleeves will not be required when using existing openings, new compression seals within the existing openings are required. Compression seals shall be approved materials as listed under "FM Pipe Seals" in OCU Appendix D, page 12 of 17.
- 3. Q: Are the existing valve vaults to be coated?**

A: Yes, all the existing valve vaults that will remain are to be coated. Existing valve vaults shall be coated using the approved material listed under "Coating for Existing Manholes" in OCU Appendix D, page 10 of 17.

4. Q: Please provide the location and/or distance of the existing utility transformers for each of the four pump stations locations.

A: C400 shows and calls out the existing transformer location for PS #3514. The existing transformer for PS #3257 is located approximately 30 feet northeast of the existing northeast property corner and is called out as "EB" on drawing V100. The existing transformer for PS #3335 is located immediately adjacent to the southern property corner and is called out as "ET" on drawing V200. The existing transformer for PS #3526 is located at the southwest corner of the lift station tract and is called out as "EB" on drawing V300.

5. Q: Part B references 5 Pump Stations. Shouldn't it be four?

A: Yes.

B. ACKNOWLEDGEMENT OF ADDENDA

- a. The Proposer shall acknowledge receipt of this addendum by completing the applicable section in the solicitation or by completion of the acknowledgement information on the addendum. Either form of acknowledgement must be completed and returned not later than the date and time for receipt of proposal.
- b. All other terms, conditions and specifications remain the same.
- c. Receipt acknowledged by:

Authorized Signature

Date Signed

Title

Name of Firm