

June 26, 2015
BOARD OF COUNTY COMMISSIONERS
ORANGE COUNTY, FLORIDA

IFB Y15-790 PH, ADDENDUM NO. 1

MALCOLM ROAD WATER SUPPLY FACILITY PRODUCTION WELLS MR1, MR2,
MR3, MR5, AND MR6 DRILLING AND TESTING

BID OPENING DATE: July 14, 2015

This Addendum is hereby incorporated into the bid documents of the project referenced above. The following items are clarifications, corrections, additions, deletions, and/or revisions to and shall take precedence over the original documents. Additions are indicated by underlining.

A. The Bid Opening date is July 14, 2015 at 2:00 P.M.

B Questions and Answers

Question No. 1: We will be required to provide an office trailer for the county and engineer's use during the project. Can you identify where you will want it set up. A site close to the drilling location will require an extended run for the temporary electrical service running up the cost for the county. We would request that a site close to the site entrance be provided.

Response No. 1: *The Contractor shall locate the trailer within the construction site in a location agreed upon by the Contractor and the County's Representative.*

Question No. 2: The final may require an extended pipeline to the discharge point. Can you please identify the location and a preferred routing of that pipeline? If it is comparable to those on previous phases, the cost will not be insignificant, and we will need to plan accordingly to minimize those costs.

Response No. 2: *The discharge site will be within 1,800 feet from the well site. The discharge piping route will be approved by the County's Representative upon selection of the well to be tested.*

Question No. 3 Some areas of the site were identified as having gopher tortoises and other endangered or protected plants and animals. Are we going to be liable for a site survey to identify them? Can you also identify any requirements for dealing with any protected plants or animals?

Response No. 3: *Although it was indicated that the site vicinity is a wildlife prone area, at this time there are no signs of gopher tortoises and any other endangered or protected plants and animals*

within the proposed footprint of the wells. An environmental survey is not required to be performed by the Contractor for this site because of the nature of the work. The Contractor is expected to observe environmentally sensitive practices in a responsible manner while operating on site. The following are minimum general guidelines to be observed on site at all times:

- a. Notify the County Representative if a suspected active gopher tortoise burrow is found within a 25-ft radius of the well installation footprint.***
- b. Maintain a minimum 25-ft buffer from any suspected gopher tortoise burrow.***
- c. Do not handle or disturb gopher tortoises or any other wildlife encountered on site.***
- d. Stay within the agreed and established travel routes on site.***
- e. Do not discharge to or disturb existing wetlands on site.***
- f. Maintain a minimum of 50-ft buffer from the wetlands.***

C. ACKNOWLEDGEMENT OF ADDENDA

- a. The Proposer shall acknowledge receipt of this addendum by completing the applicable section in the solicitation or by completion of the acknowledgement information on the addendum. Either form of acknowledgement must be completed and returned not later than the date and time for receipt of proposal.
- b. All other terms, conditions and specifications remain the same.
- c. Receipt acknowledged by:

Authorized Signature

Date Signed

Title

Name of Firm