

July 9, 2015  
BOARD OF COUNTY COMMISSIONERS  
ORANGE COUNTY, FLORIDA

IFB Y15-790 PH, ADDENDUM NO. 4

MALCOLM ROAD WATER SUPPLY FACILITY PRODUCTION WELLS MR1, MR2,  
MR3, MR5, AND MR6 DRILLING AND TESTING

**REVISED BID OPENING DATE: July 14~~16~~, 2015**

This Addendum is hereby incorporated into the bid documents of the project referenced above. The following items are clarifications, corrections, additions, deletions, and/or revisions to and shall take precedence over the original documents. Additions are indicated by underlining.

**A. The Bid Opening date is changed to July 16, 2015 at 2:00 P.M.**

**B Questions and Answers**

Question No. 1: Per the specifications and district rules, The 30" intermediate casing and the 24" production casing will be fully grouted from bottom of string to surface with cement/ gravel in loss circulation zones. This means that a dual tube rotary installation of 24" casing and 30" casing with no grout method will not be accepted. Is this correct?

**Response No. 1: Correct. Dual tube rotary installation of 24" casing and 30" casing with no grout method will not be accepted.**

Question No. 2: In reference to the water supply on site, is either well MRLF-1 or MR-4 equipped with a pump?

**Response No. 2: No. A pump and a water meter must be provided by the Contractor at any of the selected make up water locations.**

**C. ACKNOWLEDGEMENT OF ADDENDA**

- a. The Proposer shall acknowledge receipt of this addendum by completing the applicable section in the solicitation or by completion of the acknowledgement information on the addendum. Either form of acknowledgement must be completed and returned not later than the date and time for receipt of proposal.
- b. All other terms, conditions and specifications remain the same.

c. Receipt acknowledged by:

---

Authorized Signature

---

Date Signed

---

Title

---

Name of Firm