

\*\*\*\*\*

**IFB NO. Y17-741-CC**

**INVITATION FOR BIDS  
FOR  
SHERIFF'S OFFICE COMMAND AND MONITOR CENTER**

\*\*\*\*\*

**PART H  
TECHNICAL SPECIFICATIONS**

**VOLUME II**



# SHERIFF'S OFFICE COMMAND AND MONITOR CENTER

Orange County Sheriff's Office

Central Operations Center

Orange County, Florida

## BID DOCUMENTS

### SPECIFICATIONS

Divisions **1, 2, 5, 6, 7, 8, 9, 13, 21, 22, 23, 26, 27 AND 28**


Project Location:

**Orange County Sheriff's Office**

**Operation Center**

255 West Colonial Drive

Orlando, Florida 32804



605 E. Robinson Street, Suite  
750

Orlando, FL 32801

407.648.7288 phone

AA0002809



Owner:

**Orange County Government**

**Capital Planning**

400 East South Street, Suite 500

Orlando, Florida 32801

COVER SHEET

TABLE OF CONTENTS

**DIVISION 01 - GENERAL REQUIREMENTS**

011000	SUMMARY
012500	SUBSTITUTION PROCEDURES SUBSTITUTION REQUEST FORM
012600	CONTRACT MODIFICATION PROCEDURES
012900	PAYMENT PROCEDURES
013100	PROJECT MANAGEMENT AND COORDINATION
013200	CONSTRUCTION PROGRESS DOCUMENTATION
013233	PHOTOGRAPHIC DOCUMENTATION
013300	SUBMITTAL PROCEDURES
013516	ALTERATION PROJECT PROCEDURES
014000	QUALITY REQUIREMENTS
014200	REFERENCES
015000	TEMPORARY FACILITIES AND CONTROLS
016000	PRODUCT REQUIREMENTS
017300	EXECUTION
017700	CLOSEOUT PROCEDURES

**DIVISION 02 - EXISTING CONDITIONS**

024119	SELECTIVE DEMOLITION
--------	----------------------

**DIVISION 05 – METALS**

055213	METAL PIPE AND TUBE RAILINGS
--------	------------------------------

**DIVISION 06 – WOODS, PLASTICS AND COMPOSITES**

062023	INTERIOR FINISH CARPENTRY
064116	PLASTIC-LAMINATE-FACED ARCHITECTURAL CASEWORK

**DIVISION 07 - THERMAL AND MOISTURE PROTECTION**

072100	BUILDING INSULATION
078413	PENETRATION FIRESTOPPING

**DIVISION 08 – OPENINGS**

081213	HOLLOW METAL FRAMES
081416	FLUSH WOOD DOORS
084126	ALL-GLASS ENTRANCES AND STOREFRONTS
085113	ALUMINUM WINDOWS
087100	DOOR HARDWARE
088000	GLAZING

**DIVISION 09 - FINISHES**

092216	NON-STRUCTURAL METAL FRAMING
092900	GYPSUM BOARD
095113	ACOUSTICAL PANELS CEILINGS
096513	RESILIENT BASE AND ACCESSORIES
096540	VINYL PLANK FLOORING
096813	CARPET TILE
096900	ACCESS FLOORING
099100	PAINTING

**DIVISION 13 – SPECIAL CONSTRUCTION**

134715	BULLET RESISTANT PANELS
--------	-------------------------

**DIVISION 21 – FIRE SUPPRESSION**

211313	WET-PIPE SPRINKLER SYSTEMS
--------	----------------------------

**DIVISION 22 – PLUMBING**

220719	PLUMBING PIPING INSULATION
221116	DOMESTIC WATER PIPING
221316	SANITARY WASTE AND VENT PIPING
224213	COMMERCIAL PLUMBING FIXTURES

**DIVISION 23 – HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)**

230593	TESTING, ADJUSTING, AND BALANCING FOR HVAC
230713	DUCT INSULATION
233113	METAL DUCTS
233300	AIR DUCT ACCESSORIES
233346	FLEXIBLE DUCTS
233600	AIR TERMINAL UNITS
233713	AIR DIFFUSERS AND GRILLES
238146	WATER-SOURCE UNITARY HEAT PUMPS

**DIVISION 26 – ELECTRICAL**

260519	LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES
260526	GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS
260529	HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS
260533	RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS
260544	SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING
260553	IDENTIFICATION FOR ELECTRICAL SYSTEMS
260923	LIGHTING CONTROL DEVICES
262416	PANELBOARDS
262726	WIRING DEVICES

ORANGE COUNTY SHERIFF'S OFFICE  
CENTRAL OPERATIONS CENTER -  
SHERIFF'S OFFICE COMMAND AND MONITOR CENTER  
ORANGE COUNTY, FLORIDA

TABLE OF CONTENTS

262816	ENCLOSED SWITCHES AND CIRCUIT BREAKERS
265100	INTERIOR LIGHTING
265119	LED INTERIOR LIGHTING

**DIVISION 27 – COMMUNICATIONS**

27 05 00	COMMON WORK RESULTS FOR COMMUNICATIONS
27 10 00	VOICE-DATA CABLE INFRASTRUCTURE
27 41 13	AUDIO VIDEO SYSTEM

**DIVISION 28 – ELECTRONIC SAFETY AND SECURITY**

28 21 10	INTRUSION DETECTION
28 22 10	ACCESS CONTROL SYSTEM
28 31 00	FIRE ALARM SYSTEM

END OF TABLE OF CONTENTS

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Project information.
2. Work covered by Contract Documents.
3. Access to site.
4. Coordination with occupants.
5. Work restrictions.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.

1.3 PROJECT INFORMATION

A. Project Identification: Orange County Sheriff's Office Central Operations Center

1. Project Location: Sheriff's Office Command and Monitor Center.

B. Owner: Orange County Government, 2500 West Colonial Drive Orlando, FL 32804

1. Owner's Representative: AJ Murray

C. Architect: Rhodes+Brito Architects, (407) 648-7288.

1.4 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work of Project is defined by the Contract Documents.

B. Type of Contract:

1. Project will be constructed under a single prime contract.

1.5 ACCESS TO SITE

- A. General: Contractor shall have limited use of Project site for construction operations as indicated on Drawings by the Contract limits and as indicated by requirements of this Section.
- B. Use of Site: Limit use of Project site to work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.
- C. Condition of Existing Building: Maintain portions of existing building affected by construction operations in a weathertight condition throughout construction period. Repair damage caused by construction operations.

1.6 COORDINATION WITH OCCUPANTS

- A. Full Owner Occupancy: Owner will occupy site and existing building(s) during entire construction period. Cooperate with Owner during construction operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with Owner's day-to-day operations. Maintain existing exits unless otherwise indicated.
  1. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Owner and approval of authorities having jurisdiction.
  2. Notify Owner not less than 72 hours in advance of activities that will affect Owner's operations.

1.7 WORK RESTRICTIONS

- A. Work Restrictions, General: Comply with restrictions on construction operations.
  1. Comply with limitations on use of public streets and with other requirements of authorities having jurisdiction.
- B. On-Site Work Hours: Limit work in the existing building to normal business working hours of 7:00 a.m. to 7:00 p.m., Monday through Friday, unless otherwise indicated.
- C. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after providing temporary utility services according to requirements indicated:
  1. Notify Owner not less than two days in advance of proposed utility interruptions.
  2. Obtain Owner's written permission before proceeding with utility interruptions.



- D. Noise, Vibration, and Odors: Coordinate operations that may result in high levels of noise and vibration, odors, or other disruption to Owner occupancy with Owner.
  - 1. Notify Owner not less than two days in advance of proposed disruptive operations.
  - 2. Obtain Owner's written permission before proceeding with disruptive operations.
- E. Nonsmoking Building: Smoking is not permitted within the building or within 25 feet (8 m) of entrances, operable windows, or outdoor-air intakes.
- F. Controlled Substances: Use of tobacco products and other controlled substances within the existing building is not permitted.
- G. Employee Identification: Owner will provide identification tags for Contractor personnel working on Project site. Require personnel to use identification tags at all times.
- H. Employee Screening: Comply with Owner's requirements for drug and background screening of Contractor personnel working on Project site.
  - 1. Maintain list of approved screened personnel with Owner's representative.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

## SECTION 012500 - SUBSTITUTION PROCEDURES

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Section Includes:

1. Administrative and procedural requirements for substitutions.

#### 1.2 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.

#### 1.3 SUBMITTALS

- A. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.

1. Substitution Request Form: Use Form attached.
2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
  - a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.
  - b. Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors that will be necessary to accommodate proposed substitution.
  - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable specification section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
  - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
  - e. Samples, where applicable or requested.
  - f. Certificates and qualification data, where applicable or requested.
  - g. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.
  - h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated
  - i. Research reports evidencing compliance with building code in effect for Project.
  - j. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided

- within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
- k. Cost information, including a proposal of change, if any, in the Contract Sum.
  - l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
  - m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within 10 days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 5 days of receipt of request, or 7 days of receipt of additional information or documentation, whichever is later.
- a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
  - b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

#### 1.4 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage qualified testing agency to perform compatibility tests recommended by manufacturers.

### PART 2 - PRODUCTS

#### 2.1 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately upon discovery of need for change, but not later than 10 days prior to time required for preparation and review of related submittals.
  - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied:
    - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
    - b. Requested substitution will not adversely affect Contractor's construction schedule.
    - c. Requested substitution has received necessary approvals of authorities having jurisdiction.
    - d. Requested substitution is compatible with other portions of the Work.
    - e. Requested substitution has been coordinated with other portions of the Work.
    - f. Requested substitution provides specified warranty.
    - g. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

- B. Substitutions for Convenience: Architect will consider requests for substitution if received within 30 days after the Notice to Proceed or effective date of contract.
  - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied:
    - a. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
    - b. Requested substitution does not require extensive revisions to the Contract Documents.
    - c. Requested substitution is consistent with the Contract Documents and will produce indicated results.
    - d. Requested substitution will not adversely affect Contractor's construction schedule.
    - e. Requested substitution has received necessary approvals of authorities having jurisdiction.
    - f. Requested substitution is compatible with other portions of the Work.
    - g. Requested substitution has been coordinated with other portions of the Work.
    - h. Requested substitution provides specified warranty.

PART 3 - EXECUTION (Not Used)

END OF SECTION 012500

**SUBSTITUTION  
REQUEST**  
(After the Bidding Phase)

---

Project: \_\_\_\_\_ Substitution Request Number: \_\_\_\_\_  
From: \_\_\_\_\_  
To: \_\_\_\_\_ Date: \_\_\_\_\_  
A/E Project \_\_\_\_\_ Number: \_\_\_\_\_  
Contract For: \_\_\_\_\_  
Re: \_\_\_\_\_

---

Specification Title: \_\_\_\_\_ Description: \_\_\_\_\_  
Section: \_\_\_\_\_ Page: \_\_\_\_\_ Article/Paragraph: \_\_\_\_\_

---

Proposed Substitution: \_\_\_\_\_  
Manufacturer: \_\_\_\_\_ Address: \_\_\_\_\_ Phone: \_\_\_\_\_  
Trade Name: \_\_\_\_\_ Model No.: \_\_\_\_\_  
Installer: \_\_\_\_\_  \_\_\_\_\_ Address: \_\_\_\_\_ Phone: \_\_\_\_\_

History:  New product  2-5 years old  5-10 yrs old  More than 10 years old  
Differences between proposed substitution and specified product: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Point-by-point comparative data attached - REQUIRED BY A/E

---

Reason for not providing specified item: \_\_\_\_\_  
\_\_\_\_\_

Similar Installation:  
Project: \_\_\_\_\_ Architect: \_\_\_\_\_  
Address: \_\_\_\_\_ Owner: \_\_\_\_\_  
Date Installed: \_\_\_\_\_

Proposed substitution affects other parts of Work:  No  Yes; explain \_\_\_\_\_  
\_\_\_\_\_

---

Savings to Owner for accepting substitution: \_\_\_\_\_ (\$ \_\_\_\_\_).  
Proposed substitution changes Contract Time:  No  Yes [Add] [Deduct] \_\_\_\_\_ days.

---

Supporting Data Attached:  Drawings  Product Data  Samples  Tests  Reports  \_\_\_\_\_

# SUBSTITUTION REQUEST (Continued)

The Undersigned certifies:

- Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product.
- Same warranty will be furnished for proposed substitution as for specified product.
- Same maintenance service and source of replacement parts, as applicable, is available.
- Proposed substitution will have no adverse effect on other trades and will not affect or delay progress schedule.
- Cost data as stated above is complete. Claims for additional costs related to accepted substitution which may subsequently become apparent are to be waived.
- Proposed substitution does not affect dimensions and functional clearances.
- Payment will be made for changes to building design, including A/E design, detailing, and construction costs caused by the substitution.
- Coordination, installation, and changes in the Work as necessary for accepted substitution will be complete in all respects.

Submitted \_\_\_\_\_ by: \_\_\_\_\_

Signed by: \_\_\_\_\_

Firm: \_\_\_\_\_

Address: \_\_\_\_\_

Telephone: \_\_\_\_\_

Attachments: \_\_\_\_\_

## A/E's REVIEW AND ACTION

- Substitution approved - Make submittals in accordance with Specification Section 013300.
- Substitution approved as noted - Make submittals in accordance with Specification Section 013300.
- Substitution rejected - Use specified materials.
- Substitution Request received too late - Use specified materials.

Signed by: \_\_\_\_\_ Date: \_\_\_\_\_

Additional Comments:     Contractor     Subcontractor     Supplier     Manufacturer     A/E     \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes the following:
1. Administrative and procedural requirements for handling and processing Contract modifications.

#### 1.2 MINOR CHANGES IN THE WORK

- A. Architect will issue supplemental instructions authorizing Minor Changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Architect's Supplemental Instructions."

#### 1.3 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
1. Proposal Requests issued by Architect are for information only. Do not consider them instructions either to stop work in progress or to execute the proposed change.
  2. After receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
    - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
    - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
    - c. Include costs of labor and supervision directly attributable to the change.
    - d. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- B. Contractor-Initiated Proposals: If latent or unforeseen conditions require modifications to the Contract, Contractor may propose changes by submitting a request for a change
1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
  2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.

3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
4. Include costs of labor and supervision directly attributable to the change.
5. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
6. Comply with requirements in Division 1 Section "Product Requirements" if the proposed change requires substitution of one product or system for product or system specified.

C. Proposal Request Form: Use AIA Document G709 for Proposal Requests.

#### 1.4 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701.

#### 1.5 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.

1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.

- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.

1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600



SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.

1.3 DEFINITIONS

- A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.
  - 1. Coordinate line items in the schedule of values with other required administrative forms and schedules, including the following:
    - a. Application for Payment forms with continuation sheets.
    - b. Submittal schedule.
    - c. Items required to be indicated as separate activities in Contractor's construction schedule.
  - 2. Submit the schedule of values to Architect at earliest possible date, but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
  - 1. Identification: Include the following Project identification on the schedule of
    - a. Project name and location.
    - b. Contractor's name and address.
    - c. Date of submittal.
  - 2. Arrange schedule of values consistent with format of AIA Document G703.

3. Arrange the schedule of values in tabular form with separate columns to indicate the following for each item listed:
  - a. Related Specification Section or Division.
  - b. Description of the Work.
  - c. Name of subcontractor.
  - d. Change Orders (numbers) that affect value.
  - e. Dollar value of the following, as a percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.
    - 1) Labor.
    - 2) Materials.
    - 3) Equipment.
4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with Project Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
5. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
6. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
  - a. Differentiate between items stored on-site and items stored off-site. If required, include evidence of insurance.
7. Provide separate line items in the schedule of values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
8. Purchase Contracts: Provide a separate line item in the schedule of values for each purchase contract. Show line-item value of purchase contract. Indicate owner payments or deposits, if any, and balance to be paid by Contractor.
9. Each item in the schedule of values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
  - a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the schedule of values or distributed as general overhead expense, at Contractor's option.
10. 10. Schedule Updating: Update and resubmit the schedule of values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

#### 1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
  1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.

- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
- C. Application for Payment Forms: Use forms acceptable to Architect and Owner for Applications for Payment. Submit forms for approval with initial submittal of schedule of values.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
  - 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
  - 2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
  - 3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
  - 4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.
- E. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored on-site and items stored off-site.
  - 1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment, for stored materials.
  - 2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
  - 3. Provide summary documentation for stored materials indicating the following:
    - a. Value of materials previously stored and remaining stored as of date of previous Applications for Payment.
    - b. Value of previously stored materials put in place after date of previous Application for Payment and on or before date of current Application for Payment.
    - c. Value of materials stored since date of previous Application for Payment and remaining stored as of date of current Application for Payment.
- F. Transmittal: Submit five signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
  - 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's liens from subcontractors, sub-subcontractors, and suppliers for construction period covered by the previous application.
  - 1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
  - 2. When an application shows completion of an item, submit conditional final or full waivers.

3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
  4. Submit final Application for Payment with or preceded by conditional final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
  5. Waiver Forms: Submit executed waivers of lien on forms, acceptable to Owner.
- H. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
1. List of subcontractors.
  2. Schedule of values.
  3. Contractor's construction schedule (preliminary if not final).
  4. Submittal schedule (preliminary if not final).
  5. List of Contractor's staff assignments.
  6. List of Contractor's principal consultants.
  7. Copies of building permits.
  8. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
  9. Initial progress report.
  10. Report of preconstruction conference.
  11. Certificates of insurance and insurance policies.
  12. Performance and payment bonds.
  13. Data needed to acquire Owner's insurance.
- I. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
  2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the work.
- J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
1. Evidence of completion of Project closeout requirements.
  2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
  3. Updated final statement, accounting for final changes to the Contract Sum.
  4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
  5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
  6. AIA Document G707, "Consent of Surety to Final Payment."

ORANGE COUNTY SHERIFF'S OFFICE  
CENTRAL OPERATIONS CENTER -  
SHERIFF'S OFFICE COMMAND AND MONITOR CENTER  
ORANGE COUNTY, FLORIDA

PAYMENT PROCEDURES  
SECTION 012900

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

## SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes the following:
  - 1. Administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
    - a. Coordination Drawings.
    - b. Project meetings.
    - c. Requests for Interpretation (RFIs).
- B. See Division 1 Section "Execution Requirements" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.

#### 1.2 DEFINITIONS

- A. RFI: Request from Contractor seeking interpretation or clarification of the Contract Documents.

#### 1.3 COORDINATION

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, that depend on each other for proper installation, connection, and operation.
  - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
  - 2. Coordinate installation of different components with other contractors to ensure maximum accessibility for required maintenance, service, and repair.
  - 3. Make adequate provisions to accommodate items scheduled for later installation.
  - 4. Where availability of space is limited, coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair of all components, including mechanical and electrical
- B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
  - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.

- C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other contractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
1. Preparation of Contractor's Construction Schedule.
  2. Preparation of the Schedule of Values.
  3. Installation and removal of temporary facilities and controls.
  4. Delivery and processing of submittals.
  5. Progress meetings.
  6. Preinstallation conferences.
  7. Project closeout activities.
  8. Startup and adjustment of systems.
  9. Project closeout activities.

#### 1.4 SUBMITTALS

- A. Coordination Drawings: Prepare Coordination Drawings if limited space availability necessitates maximum utilization of space for efficient installation of different components or if coordination is required for installation of products and materials fabricated by separate entities.
1. Content: Project-specific information, drawn accurately to scale. Do not base Coordination Drawings on reproductions of the Contract Documents or standard printed data. Include the following information, as applicable:
    - a. Indicate functional and spatial relationships of components of architectural, structural, civil, mechanical, and electrical systems.
    - b. Indicate dimensions shown on the Contract Drawings and make specific note of dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternate sketches to Architect for resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.
  2. Sheet Size: At least 8-1/2 by 11 inches but no larger than 30 by 40 inches.
  3. Number of Copies: Submit five (5) copies of each submittal. Architect and Consultants will each retain one copy.
  4. Refer to individual Sections for Coordination Drawing requirements for Work in those Sections.

#### 1.5 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site, unless otherwise indicated.
1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
  2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
  3. Minutes: Record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within three days of the meeting.

- B. Preconstruction Conference: Schedule a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement. Hold the conference at Project site or another convenient location. Conduct the meeting to review responsibilities and personnel assignments.
1. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
  2. Agenda: Discuss items of significance that could affect progress, including the following:
    - a. Tentative construction schedule.
    - b. Phasing.
    - c. Critical work sequencing and long-lead items.
    - d. Designation of key personnel and their duties.
    - e. Procedures for processing field decisions and Change Orders.
    - f. Procedures for RFIs.
    - g. Procedures for testing and inspecting.
    - h. Procedures for processing Applications for Payment.
    - i. Distribution of the Contract Documents.
    - j. Submittal procedures.
    - k. Preparation of Record Documents.
    - l. Use of the premises.
    - m. Work restrictions.
    - n. Owner's occupancy requirements.
    - o. Responsibility for temporary facilities and controls.
    - p. Construction waste management and recycling.
    - q. Parking availability.
    - r. Office, work, and storage areas.
    - s. Equipment deliveries and priorities.
    - t. First aid.
    - u. Security.
    - v. Progress cleaning.
    - w. Working hours.
  3. Minutes: Record and distribute meeting minutes.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.
1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
  2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
    - a. The Contract Documents.
    - b. Options.
    - c. Related RFIs.
    - d. Related Change Orders.
    - e. Purchases.
    - f. Deliveries.
    - g. Submittals.
    - h. Review of mockups.



- i. Possible conflicts.
  - j. Compatibility problems.
  - k. Time schedules.
  - l. Weather limitations.
  - m. Manufacturer's written recommendations.
  - n. Warranty requirements.
  - o. Compatibility of materials.
  - p. Acceptability of substrates.
  - q. Temporary facilities and controls.
  - r. Space and access limitations.
  - s. Regulations of authorities having jurisdiction.
  - t. Testing and inspecting requirements.
  - u. Installation procedures.
  - v. Coordination with other work.
  - w. Required performance results.
  - x. Protection of adjacent work.
  - y. Protection of construction and personnel.
3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
  4. Reporting: Distribute minutes of the meeting to each party present and to parties who should have been present.
  5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Progress Meetings: Conduct progress meetings at weekly intervals. Coordinate dates of meetings with preparation of payment requests.
1. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
  2. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
    - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's Construction Schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
      - 1) Review schedule for next period.
    - b. Review present and future needs of each entity present, including the following:
      - 1) Interface requirements.
      - 2) Sequence of operations.
      - 3) Status of submittals.
      - 4) Deliveries.
      - 5) Off-site fabrication.
      - 6) Access.
      - 7) Site utilization.

- 8) Temporary facilities and controls.
  - 9) Work hours.
  - 10) Hazards and risks.
  - 11) Progress cleaning.
  - 12) Quality and work standards.
  - 13) Status of correction of deficient items.
  - 14) Field observations.
  - 15) RFIs.
  - 16) Status of proposal requests.
  - 17) Pending changes.
  - 18) Status of Change Orders.
  - 19) Pending claims and disputes.
  - 20) Documentation of information for payment requests.
3. Minutes: Record the meeting minutes.
  4. Reporting: Distribute minutes of the meeting to each party present and to parties who should have been present.
    - a. Schedule Updating: Revise Contractor's Construction Schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

#### 1.6 REQUESTS FOR INTERPRETATION (RFIs)

- A. Procedure: Immediately on discovery of the need for interpretation of the Contract Documents, and if not possible to request interpretation at Project meeting, prepare and submit an RFI in the form specified.
  1. RFIs shall originate with Contractor. RFIs submitted by entities other than Contractor will be returned with no response.
  2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing interpretation and the following:
  1. Project name.
  2. Date.
  3. Name of Contractor.
  4. Name of Architect.
  5. RFI number, numbered sequentially.
  6. Specification Section number and title and related paragraphs, as appropriate.
  7. Drawing number and detail references, as appropriate.
  8. Field dimensions and conditions, as appropriate.
  9. Contractor's suggested solution(s). If Contractor's solution(s) impact the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
  10. Contractor's signature.
  11. Attachments: Include drawings, descriptions, measurements, photos, Product Data, Shop Drawings, and other information necessary to fully describe items needing interpretation.
- C. Architect's Action: Architect will review each RFI, determine action required, and return it. Allow seven working days for Architect's response for each RFI. RFIs received after 1:00 p.m. will be considered as received the following working day.

1. The following RFIs will be returned without action:
    - a. Requests for approval of submittals.
    - b. Requests for approval of substitutions.
    - c. Requests for coordination information already indicated in the Contract Documents.
    - d. Requests for adjustments in the Contract Time or the Contract Sum.
    - e. Requests for interpretation of Architect's actions on submittals.
    - f. Incomplete RFIs or RFIs with numerous errors.
  2. Architect's action may include a request for additional information, in which case Architect's time for response will start again.
  3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Division 1 Section "Contract Modification Procedures."
    - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.
- D. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within seven days if Contractor disagrees with response.
- E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly.
1. Project name.
  2. Name and address of Contractor.
  3. Name and address of Architect.
  4. RFI number including RFIs that were dropped and not submitted.
  5. RFI description.
  6. Date the RFI was submitted.
  7. Date Architect's response was received.
  8. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013100

## SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
1. Preliminary Construction Schedule.
  2. Contractor's Construction Schedule.
  3. Submittals Schedule.
  4. Material location reports.
  5. Field condition reports.
  6. Special reports.

#### 1.2 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.
1. Critical activities are activities on the critical path. They must start and finish on the planned early start and finish times.
  2. Predecessor activity is an activity that must be completed before a given activity can be started.
- B. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.
- C. Critical Path: The longest continuous chain of activities through the network schedule that establishes the minimum overall Project duration and contains no float.
- D. Event: The starting or ending point of an activity.
- E. Float: The measure of leeway in starting and completing an activity.
1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.
  2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the following activity.
  3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date. activities for greater detail.
- F. Major Area: A story of construction, a separate building, or a similar significant construction element.

- G. Milestone: A key or critical point in time for reference or measurement.
- H. Network Diagram: A graphic diagram of a network schedule, showing activities and activity relationships.

### 1.3 SUBMITTALS

- A. Submittals Schedule: Submit three copies of schedule. Arrange the following information in a tabular format:
  - 1. Scheduled date for first submittal.
  - 2. Specification Section number and title.
  - 3. Submittal category (action or informational).
  - 4. Name of subcontractor.
  - 5. Description of the Work covered.
  - 6. Scheduled date for Architect's final release or approval.
- B. Contractor's Construction Schedule: Submit two printed copies of initial schedule, one a reproducible print and one a blue- or black-line print, large enough to show entire schedule for entire construction period.
- C. CPM Reports: Concurrent with CPM schedule, submit three printed copies of each of the following computer-generated reports. Format for each activity in reports shall contain activity number, activity description, original duration, remaining duration, early start date, early finish date, late start date, late finish date, and total float.
  - 1. Activity Report: List of all activities sorted by activity number and then early start date, or actual start date if known.
  - 2. Logic Report: List of preceding and succeeding activities for all activities, sorted in ascending order by activity number and then early start date, or actual start date if known.
  - 3. Total Float Report: List of all activities sorted in ascending order of total float.
  - 4. Earnings Report: Compilation of Contractor's total earnings from commencement of the Work until most recent Application for Payment.
- D. Field Condition Reports: Submit two copies at time of discovery of differing conditions.
- E. Special Reports: Submit two copies at time of unusual event.

### 1.4 QUALITY ASSURANCE

- A. Prescheduling Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination." Review methods and procedures related to the Preliminary Construction Schedule and Contractor's Construction Schedule, including, but not limited to, the following:
  - 1. Review software limitations and content and format for reports.
  - 2. Verify availability of qualified personnel needed to develop and update schedule.
  - 3. Discuss constraints, including work stages area separations interim milestones and partial Owner occupancy.
  - 4. Review delivery dates for Owner-furnished products.

5. Review schedule for work of Owner's separate contracts.
6. Review time required for review of submittals and resubmittals.
7. Review requirements for tests and inspections by independent testing and inspecting agencies.
8. Review time required for completion and startup procedures.
9. Review and finalize list of construction activities to be included in schedule.
10. Review submittal requirements and procedures.
11. Review procedures for updating schedule.

## 1.5 COORDINATION

- A. Coordinate preparation and processing of schedules and reports with performance of construction activities and with scheduling and reporting of separate contractors.
- B. Coordinate Contractor's Construction Schedule with the Schedule of Values, list of subcontracts, Submittals Schedule, progress reports, payment requests, and other required schedules and reports.
  1. Secure time commitments for performing critical elements of the Work from parties involved.
  2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

## PART 2 - PRODUCTS

### 2.1 SUBMITTALS SCHEDULE

- A. Preparation: After development and acceptance of the Contractor's construction schedule, prepare a complete schedule of submittals utilizing Constructware database. Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, resubmittal, ordering, manufacturing, fabrication, and delivery when establishing dates.
  1. Submittal Schedule: Coordinate Submittals Schedule with list of subcontracts, the Schedule of Values, and Contractor's Construction Schedule.
    - a. Prepare the schedule on chronological order; include submittals required during the first 90 days of construction. Provide the following information.
      - 1) Scheduled date for the first submittal
      - 2) Related Section number.
      - 3) Submittal category.
      - 4) Name of subcontractor.
      - 5) Description of the part of the Work covered.
      - 6) Scheduled date for resubmittal.
      - 7) Scheduled date of the Architect's final release or approval.
  2. Initial Submittal: Submit concurrently with preliminary bar-chart schedule. Include submittals required during the first 90 days of construction. List those required to maintain

- orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
3. Final Submittal: Submit concurrently with the first complete submittal of Contractor's Construction Schedule.

## 2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Bar-Chart Schedule: Prepare a fully developed, horizontal-bar chart type Contractor's construction schedule. Submit within 30 days of the date established for "Commencement of the Work."
  1. Provide a separate time bar for each significant construction activity. Provide a continuous vertical line to identify the first working day of each week. Use the same breakdown of units of the Work as indicated in the Schedule of Values.
  2. Within each time bar indicate estimated completion percentage in 10 percent increments. As Work progresses, place a contrasting mark in each bar to indicate Actual Completion.
  3. Prepare the schedule on a sheet, or series of sheets, of stable transparency, or other reproducible media, of sufficient width to show data for the entire construction period.
  4. Secure time commitments for performing critical elements of the Work from parties involved. Coordinate each element on the schedule with other construction activities; include minor elements involved in the sequence of the Work. Show each activity in proper sequence. Indicate graphically sequences necessary for completion of related portions of the Work.
- B. Time Frame: Extend schedule from date established for commencement of the Work to date of Substantial Completion.
  1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- C. Activities: Treat each story or separate area as a separate numbered activity for each principal element of the Work. Comply with the following:
  1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
  2. Procurement Activities: Include procurement process activities for long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
  3. Submittal Review Time: Include review and resubmittal times indicated in Division 1 Section "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with Submittals Schedule.
  4. Startup and Testing Time: Include estimated number days for startup and testing.
  5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
- D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.
  1. Phasing: Arrange list of activities on schedule by phase. Provide notations on the schedule to show how the sequence of the Work is affected by requirements for phased

- completion to permit Work by separate contractors and partial occupancy by the Owner prior to Substantial Completion.
2. Products Ordered in Advance: Include a separate activity for each product. Include delivery date indicated in Division 1 Section "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
  3. Owner-Furnished Products: Include a separate activity for each product. Include delivery date indicated in Division 1 Section "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
  4. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, testing and installation.
  5. Area Separations: Identify each major area of construction for each major portion of the Work. Indicate where each construction activity within a major area must be sequenced or integrated with other construction activities.
- E. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and Final Completion.
- F. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis using fragnets to demonstrate the effect of the proposed change on the overall project schedule.
- G. Computer Software: Prepare schedules using a program that has been developed specifically to manage construction schedules.

### 2.3 CONTRACTOR'S CONSTRUCTION SCHEDULE (CPM SCHEDULE)

- A. General: Prepare network diagrams using AON (activity-on-node) format.
- B. Preliminary Network Diagram: Submit diagram within 14 days of date established for commencement of the Work. Outline significant construction activities for the first 90 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.
- C. CPM Schedule: Prepare Contractor's Construction Schedule using a CPM network analysis diagram.
1. Develop network diagram in sufficient time to submit CPM schedule so it can be accepted for use no later than 30 days after date established for commencement of the Work.
  2. Conduct educational workshops to train and inform key Project personnel, including subcontractors' personnel, in proper methods of providing data and using CPM schedule information.
  3. Establish procedures for monitoring and updating CPM schedule and for reporting progress. Coordinate procedures with progress meeting and payment request dates.
  4. Use "one workday" as the unit of time.
- D. CPM Schedule Preparation: Prepare a list of all activities required to complete the Work. Using the preliminary network diagram, prepare a skeleton network to identify probable critical paths.
1. Activities: Indicate the estimated time duration, sequence requirements, and relationship of each activity in relation to other activities. Include estimated time frames for the following activities:



- a. Preparation and processing of submittals.
  - b. Purchase of materials.
  - c. Delivery.
  - d. Fabrication.
  - e. Installation.
2. Processing: Process data to produce output data or a computer-drawn, timescaled network. Revise data, reorganize activity sequences, and reproduce as often as necessary to produce the CPM schedule within the limitations of the Contract Time.
- E. Initial Issue of Schedule: Prepare initial network diagram from a list of straight "early start-total float" sort. Identify critical activities. Prepare tabulated reports showing the following:
1. Contractor or subcontractor and the Work or activity.
  2. Description of activity.
  3. Principal events of activity.
  4. Immediate preceding and succeeding activities.
  5. Early and late start dates.
  6. Early and late finish dates.
  7. Activity duration in workdays.
  8. Total float or slack time.
  9. Average size of workforce.
  10. Dollar value of activity (coordinated with the Schedule of Values).
- F. Schedule Updating: Concurrent with making revisions to schedule, prepare tabulated reports showing the following:
1. Identification of activities that have changed.
  2. Changes in early and late start dates.
  3. Changes in early and late finish dates.
  4. Changes in activity durations in workdays.
  5. Changes in the critical path.
  6. Changes in total float or slack time.
  7. Changes in the Contract Time.

## 2.4 REPORTS

- A. Material Location Reports: At Owner's request prepare a comprehensive list of materials delivered to and stored at Project site. List shall be cumulative, showing materials previously reported plus items recently delivered. Include with list a statement of progress on and delivery dates for materials or items of equipment fabricated or stored away from Project site.
- B. Field Condition Reports: Immediately on discovery of a difference between field conditions and the Contract Documents, prepare a detailed report. Submit with a request for information on CSI Form 13.2A. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

## 2.5 SPECIAL REPORTS

- A. General: Submit special reports directly to Owner within one day of an occurrence. Distribute copies of report to parties affected by the occurrence.

- B. Reporting Unusual Events: When an event of an unusual and significant nature occurs at Project site, whether or not related directly to the Work, prepare and submit a special report. List chain of events, persons participating, response by Contractor's personnel, evaluation of results or effects, and similar pertinent information. Advise Owner in advance when these events are known or predictable.

### PART 3 - EXECUTION

#### 3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.
  - 1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
  - 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
  - 3. As the Work progresses, indicate Actual Completion percentage for each activity.
- B. Distribution: Distribute copies of approved schedule to Architect, Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
  - 1. Post copies in Project meeting rooms and temporary field offices.
  - 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION 013200

## SECTION 013233 - PHOTOGRAPHIC DOCUMENTATION

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for the following:
  - 1. Preconstruction photographs.
  - 2. Final completion construction photographs.
- B. Related Requirements:
  - 1. Section 013300 "Submittal Procedures" for submitting photographic documentation.
  - 2. Section 017700 "Closeout Procedures" for submitting photographic documentation as project record documents at Project closeout.
  - 3. Section 024119 "Selective Structure Demolition" for photographic documentation before selective demolition operations commence.

#### 1.3 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For photographer.
- B. Key Plan: Submit key plan of Project site and building with notation of vantage points marked for location and direction of each photograph. Indicate elevation or story of construction. Include same information as corresponding photographic documentation.
- C. Digital Photographs: Submit image files within three days of taking photographs.
  - 1. Digital Camera: Minimum sensor resolution of 8 megapixels.
  - 2. Format: Minimum 3200 by 2400 pixels, in unaltered original files, with same aspect ratio as the sensor, uncropped, date and time stamped, in folder named by date of photograph, accompanied by key plan file.
  - 3. Identification: Provide the following information with each image description in file metadata tag:
    - a. Name of Project.
    - b. Name of Contractor.
    - c. Date photograph was taken.
    - d. Description of vantage point, indicating location, direction (by compass point), and elevation or story of construction.

1.4 QUALITY ASSURANCE

- A. Photographer Qualifications: An individual who has been regularly engaged as a professional photographer of construction projects for not less than three years.

1.5 USAGE RIGHTS

- A. Obtain and transfer copyright usage rights from photographer to Owner for unlimited reproduction of photographic documentation.

PART 2 - PRODUCTS

2.1 PHOTOGRAPHIC MEDIA

- A. Digital Images: Provide images in JPG format, produced by a digital camera with minimum sensor size of 8 megapixels, and at an image resolution of not less than 3200 by 2400 pixels.

PART 3 - EXECUTION

3.1 CONSTRUCTION PHOTOGRAPHS

- A. Photographer: Engage a qualified photographer to take construction photographs.
- B. General: Take photographs using the maximum range of depth of field, and that are in focus, to clearly show the Work. Photographs with blurry or out-of-focus areas will not be accepted.
  - 1. Maintain key plan with each set of construction photographs that identifies each photographic location.
- C. Digital Images: Submit digital images exactly as originally recorded in the digital camera, without alteration, manipulation, editing, or modifications using image-editing software.
  - 1. Date and Time: Include date and time in file name for each image.
  - 2. Field Office Images: Maintain one set of images accessible in the field office at Project site, available at all times for reference. Identify images in the same manner as those submitted to Architect.
- D. Preconstruction Photographs: Before starting construction, take photographs of Project site and surrounding properties, including existing items to remain during construction, from different vantage points, as directed by Owner.
  - 1. Take 20 photographs to show existing conditions adjacent to property before starting the Work.
- E. Final Completion Construction Photographs: Take 20 color photographs after date of Substantial Completion for submission as project record documents. Architect will inform photographer of desired vantage points.

1. Include date stamp.

END OF SECTION 013233

## SECTION 013300 - SUBMITTAL PROCEDURES

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other miscellaneous submittals.

#### 1.2 DEFINITIONS

- A. Action Submittals: Written and graphic information that requires Architect's responsive action.
- B. Informational Submittals: Written information that does not require Architect's approval. Submittals may be rejected for not complying with requirements.

#### 1.3 SUBMITTAL PROCEDURES

- A. General: One electronic copy of CAD Drawings of the Contract Drawings will be provided by Architect, with appropriate disclaimers, for Contractor's use in preparing submittals.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
  - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
  - 2. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
    - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- C. Submittals Schedule: Comply with requirements in Division 1 Section "Construction Progress Documentation" for list of submittals and time requirements for scheduled performance of related construction activities.
- D. Processing Time: Allow sufficient time for submittal review, including time for resubmittals, so that installation will not be delayed as a result of the time required to process submittals. Time for review shall commence on Architect's receipt of submittal.
  - 1. Initial Review: Allow two weeks for initial review of each submittal. Allow additional time if processing must be delayed to permit coordination with subsequent submittals. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
  - 2. If intermediate submittal is necessary, process it in same manner as initial submittal.
  - 3. Allow two weeks for processing each resubmittal.

4. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing.
- E. Identification: Place a permanent label or title block on each submittal for identification.
1. Indicate name of firm or entity that prepared each submittal on label or title block.
  2. Provide two spaces approximately 4 by 5 inches on label or beside the title block to record Architect and Contractor's review and approval markings and action taken.
  3. Include the following information on label for processing and recording action taken:
    - a. Project name.
    - b. Date.
    - c. Name and address of Architect.
    - d. Name and address of Contractor.
    - e. Name and address of subcontractor.
    - f. Name and address of supplier.
    - g. Name of manufacturer.
    - h. Number and title of appropriate Specification Section.
    - i. Drawing number and detail references, as appropriate.
    - j. Contractor/ Architect's log number.
      - 1) Example: 03000-1A-B
    - k. Other necessary identification.
- F. Deviations: Highlight, encircle, or otherwise identify deviations from the Contract Documents on submittals.
- G. Transmittal Form: Submit transmittal form to the Architect for review. The Architect will make revisions if necessary.
1. Process transmittal forms to provide a record of activity.
- H. Transmittal: Package each submittal individually and appropriately for transmittal and handling. Transmit each submittal from Contractor to Architect using a transmittal form. Submittals received from sources other than the Contractor will be returned without action.
1. On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Architect on previous submittals, and deviations from requirements of the Contract Documents, including minor variations and limitations. Include the same label information as the related submittal.
  2. Include Contractor's certification stating that information submitted complies with requirements of the Contract Documents.
- I. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
1. Do not proceed with installation until an applicable copy of Product Data applicable is in the installer's possession.

- J. Use for Construction: Use only final submittals with mark indicating action taken by Architect in connection with construction.

## PART 2 - PRODUCTS

### 2.1 ACTION SUBMITTALS

- A. General: Prepare and submit Action Submittals required by individual Specification Sections.
  - 1. Number of Copies: Submit copies of each submittal, as follows, unless otherwise indicated:
    - a. Initial Submittal: Submit two preliminary copies of each submittal where selection of options, color, pattern, texture, or similar characteristics is required. Architect will return one submittal with options selected.
    - b. Final Submittal: Submit three copies, unless copies are required for operation and maintenance manuals. Submit five copies where copies are required for operation and maintenance manuals. Architect will retain two copies; remainder will be returned. Mark up and retain one returned copy as a Project Record Document.
- B. Product Data: Collect information into a single submittal for each element of construction or system.
  - 1. If information must be specially prepared for submittal because standard printed data are not suitable for use, submit as Shop Drawings, not as Product Data.
  - 2. Mark each copy of each submittal to show which products and options are applicable. Where printed Product Data includes information on several products, some of which are not required, mark copies to indicate the applicable information.
  - 3. Include the following information, as applicable:
    - a. Manufacturer's written recommendations.
    - b. Manufacturer's product specifications.
    - c. Manufacturer's installation instructions.
    - d. Standard color charts.
    - e. Manufacturer's catalog cuts.
    - f. Wiring diagrams showing factory-installed wiring.
    - g. Printed performance curves.
    - h. Operational range diagrams.
    - i. Mill reports.
    - j. Standard product operating and maintenance manuals.
    - k. Compliance with recognized trade association standards.
    - l. Compliance with recognized testing agency standards.
    - m. Application of testing agency labels and seals.
    - n. Notation of dimensions verified by field measurement.
    - o. Notation of coordination requirements.
  - 4. Do not submit Product Data until compliance with requirements of the Contract Documents has been confirmed.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data. Do not



use Shop Drawings without an appropriate final stamp indicating action taken in connection with construction.

1. Preparation: Include the following information, as applicable:
    - a. Dimensions.
    - b. Identification of products and materials.
    - c. Fabrication and installation drawings.
    - d. Roughing-in and setting diagrams.
    - e. Wiring diagrams showing field-installed wiring, including power, signal, and control wiring.
    - f. Shopwork manufacturing instructions.
    - g. Templates and patterns.
    - h. Schedules.
    - i. Design calculations.
    - j. Signed and sealed specialty engineering documents.
    - k. Compliance with specified standards.
    - l. Notation of coordination requirements.
    - m. Notation of dimensions established by field measurement.
  2. Wiring Diagrams: Differentiate between manufacturer-installed and field-installed wiring.
  3. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches but no larger than 30 by 40 inches.
  4. Number of Copies: Submit copies of each submittal, as follows:
    - a. Initial Submittal: Submit one correctable, translucent, reproducible print and one blue- or black-line print. Architect will return the reproducible print.
    - b. Final Submittal: Submit three blue- or black-line prints, unless prints are required for operation and maintenance manuals. Submit five prints where prints are required for operation and maintenance manuals. Architect will retain two prints; remainder will be returned.
      - 1) Maintain one of the returned prints as a Record Document.
- D. Coordination Drawings: Comply with requirements in Division 1 Section "Project Management and Coordination."
- E. Samples: Prepare physical units of materials or products, including the following:
1. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
  2. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from the same material to be used for the Work, cured and finished in manner specified, and physically identical with the product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
  3. Preparation: Mount, display, or package Samples in manner specified to facilitate review of qualities indicated. Prepare Samples to match Architect's sample where so indicated. Attach label on unexposed side that includes the following:
    - a. Generic description of Sample.

- b. Product name or name of manufacturer.
    - c. Sample source.
  4. Additional Information: On an attached separate sheet, prepared on Contractor's letterhead, provide the following:
    - a. Size limitations.
    - b. Compliance with recognized standards.
    - c. Availability.
    - d. Delivery time.
  5. Submit Samples for review of kind, color, pattern, and texture for a final check of these characteristics with other elements and for a comparison of these characteristics between final submittal and actual component as delivered and installed.
    - a. If variation in color, pattern, texture, or other characteristic is inherent in the product represented by a Sample, submit multiple units (not less than 3) that show approximate limits of the variations.
    - b. Refer to individual Specification Sections for requirements for Samples that illustrate workmanship, fabrication techniques, details of assembly, connections, operation, and similar construction characteristics.
  6. Number of Samples for Initial Selection: Submit two full sets of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return one set with options selected.
  7. Number of Samples for Verification: Submit three sets of Samples. Architect will retain two Sample sets; remainder will be returned.
    - a. Submit a single Sample where assembly details, workmanship, fabrication techniques, connections, operation, and other similar characteristics are to be demonstrated.
  8. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
    - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
    - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
  9. Distribution of Samples: Prepare and distribute additional sets to subcontractors, manufacturers, fabricators, suppliers, and installers, and others as required for performance of the Work. Show distribution on transmittal forms.
    - a. Field samples specified in individual Sections are special types of samples. Field samples are full-size examples erected on site to illustrate finishes, coatings, or finish materials and to establish the standard by which the Work will be judged.
- F. Delegated-Design Submittal: Comply with requirements in Division 01 Section "Quality Requirements."

- G. Submittals Schedule: Comply with requirements in Division 01 Section "Construction Progress Documentation."
- H. Application for Payment: Comply with requirements in Division 01 Section "Payment Procedures."
- I. Schedule of Values: Comply with requirements in Division 01 Section "Payment Procedures."
- J. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
  - 1. Name, address, and telephone number of entity performing subcontract or supplying products.
  - 2. Number and title of related Specification Section(s) covered by subcontract.
  - 3. Drawing number and detail references, as appropriate, covered by subcontract.

## 2.2 INFORMATIONAL SUBMITTALS

- A. General: Prepare and submit Informational Submittals required by other Specification Sections.
  - 1. Number of Copies: Submit two copies of each submittal, unless otherwise indicated. Architect will not return copies.
  - 2. Certificates and Certifications: Provide a notarized statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.
  - 3. Test and Inspection Reports: Comply with requirements in Division 1 Section "Quality Requirements."
- B. Contractor's Construction Schedule: Comply with requirements in Division 1 Section "Construction Progress Documentation."
- C. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- D. Product Certificates: Prepare written statements on manufacturer's letterhead certifying that product complies with requirements.
- E. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements. Submit record of Welding Procedure Specification (WPS) and Procedure Qualification Record (PQR) on AWS forms. Include names of firms and personnel certified.
- F. Installer Certificates: Prepare written statements on manufacturer's letterhead certifying that Installer complies with requirements and, where required, is authorized for this specific Project.
- G. Manufacturer Certificates: Prepare written statements on manufacturer's letterhead certifying that manufacturer complies with requirements. Include evidence of manufacturing experience where required.

- H. Material Certificates: Prepare written statements on manufacturer's letterhead certifying that material complies with requirements.
- I. Material Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements.
- J. Preconstruction Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements.
- K. Compatibility Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
- L. Field Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements.
- M. Product Test Reports: For individual Specification Sections requiring Test Reports prepare written reports indicating current product produced by manufacturer complies with requirements. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- N. Research/Evaluation Reports: For individual Specification Sections requiring Research/Evaluation Reports prepare written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
  - 1. Name of evaluation organization.
  - 2. Date of evaluation.
  - 3. Time period when report is in effect.
  - 4. Product and manufacturers' names.
  - 5. Description of product.
  - 6. Test procedures and results.
  - 7. Limitations of use.
- O. Maintenance Data: Prepare written and graphic instructions and procedures for operation and normal maintenance of products and equipment. Comply with requirements in Division 1 Section "Closeout Procedures."
- P. Manufacturer's Instructions: Prepare written or published information that documents manufacturer's recommendations, guidelines, and procedures for installing or operating a product or equipment. Include name of product and name, address, and telephone number of manufacturer. Include the following, as applicable:
  - 1. Preparation of substrates.
  - 2. Required substrate tolerances.
  - 3. Sequence of installation or erection.
  - 4. Required installation tolerances.
  - 5. Required adjustments.
  - 6. Recommendations for cleaning and protection.

- Q. Manufacturer's Field Reports: Prepare written information documenting factory authorized service representative's tests and inspections. Include the following, as applicable:
1. Name, address, and telephone number of factory-authorized service representative making report.
  2. Statement on condition of substrates and their acceptability for installation of product.
  3. Statement that products at Project site comply with requirements.
  4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
  5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
  6. Statement whether conditions, products, and installation will affect warranty.
  7. Other required items indicated in individual Specification Sections.
- R. Construction Photographs: Comply with requirements in Division 1 Section "Construction Progress Documentation."

### PART 3 - EXECUTION

#### 3.1 CONTRACTOR'S REVIEW

- A. Review each submittal and check for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

#### 3.2 ARCHITECT'S ACTION

- A. General: Architect will not review submittals that do not bear Contractor's approval stamp and will return them without action.
- B. Action Submittals: Architect will review each submittal, make marks to indicate corrections or modifications required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action taken, as follows:
1. Final Unrestricted Release: When submittals are marked "Accepted", that part of the Work covered by the submittal may proceed provided it complies with requirements of the Contract Documents; final acceptance will depend upon that compliance.
  2. Final-But-Restricted Release: When submittals are marked "Accepted as Noted", that part of the Work covered by the submittal may proceed provided it complies with notations or corrections on the submittal and with requirements of the Contract Documents; final acceptance will depend upon that compliance
  3. Returned for Resubmittal: When submittal is marked "Revise and Resubmit as Requested", do not proceed with that part of the Work covered by the submittal, including purchasing, fabrication, delivery, or other activity. Revise or prepare a new submittal in accordance with the notations; resubmit without delay. Repeat if necessary to obtain a different action mark.

4. Rejected: When submittal is marked "Not Accepted", do not proceed with that part of the work covered by the submittal, including purchasing, fabrication, delivery, or other activity. Revise or prepare a new submittal in accordance in accordance with the notations, resubmit without delay.
  5. Other Action: Where a submittal is primarily for information or record purposes, special processing or other activity, the submittal will be returned, marked "No Action Taken" or similar identifier.
- C. Informational Submittals: Architect will review each submittal and will not return it, or will reject and return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- D. Other Submittals: Submittals not required by the Contract Documents will not be reviewed and may be discarded.

END OF SECTION 013300

## SECTION 013516 - ALTERATION PROJECT PROCEDURES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes special procedures for alteration work.

#### 1.3 DEFINITIONS

- A. Alteration Work: This term includes remodeling, renovation, repair, and maintenance work performed within existing spaces or on existing surfaces as part of the Project.
- B. Consolidate: To strengthen loose or deteriorated materials in place.
- C. Design Reference Sample: A sample that represents the Architect's prebid selection of work to be matched; it may be existing work or work specially produced for the Project.
- D. Dismantle: To remove by disassembling or detaching an item from a surface, using gentle methods and equipment to prevent damage to the item and surfaces; disposing of items unless indicated to be salvaged or reinstalled.
- E. Match: To blend with adjacent construction and manifest no apparent difference in material type, species, cut, form, detail, color, grain, texture, or finish; as approved by Architect.
- F. Refinish: To remove existing finishes to base material and apply new finish to match original, or as otherwise indicated.
- G. Repair: To correct damage and defects, retaining existing materials, features, and finishes. This includes patching, piecing-in, splicing, consolidating, or otherwise reinforcing or upgrading materials.
- H. Replace: To remove, duplicate, and reinstall entire item with new material. The original item is the pattern for creating duplicates unless otherwise indicated.
- I. Replicate: To reproduce in exact detail, materials, and finish unless otherwise indicated.
- J. Reproduce: To fabricate a new item, accurate in detail to the original, and from either the same or a similar material as the original, unless otherwise indicated.
- K. Retain: To keep existing items that are not to be removed or dismantled.
- L. Strip: To remove existing finish down to base material unless otherwise indicated.

#### 1.4 COORDINATION

- A. Alteration Work Subschedule: A construction schedule coordinating the sequencing and scheduling of alteration work for entire Project, including each activity to be performed, and based on Contractor's Construction Schedule. Secure time commitments for performing critical construction activities from separate entities responsible for alteration work.
1. Schedule construction operations in sequence required to obtain best Work results.
  2. Coordinate sequence of alteration work activities to accommodate the following:
    - a. Owner's continuing occupancy of portions of existing building.
  3. Detail sequence of alteration work, with start and end dates.
  4. Utility Services: Indicate how long utility services will be interrupted. Coordinate shutoff, capping, and continuation of utility services.

#### 1.5 PROJECT MEETINGS FOR ALTERATION WORK

- A. Preliminary Conference for Alteration Work: Before starting alteration work, conduct conference at Owner's office.
1. Attendees: In addition to representatives of Owner, Architect, and Contractor, testing service representative, specialists, and chemical-cleaner manufacturer(s) shall be represented at the meeting.
  2. Agenda: Discuss items of significance that could affect progress of alteration work, including review of the following:
    - a. Areas where existing construction is to remain and the required protection.
    - b. Hauling routes.
    - c. Sequence of alteration work operations.
    - d. Storage, protection, and accounting for salvaged and specially fabricated items.
    - e. Existing conditions, staging, and structural loading limitations of areas where materials are stored.
  3. Reporting: Record conference results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from conference.

#### 1.6 QUALITY ASSURANCE

- A. Safety and Health Standard: Comply with ANSI/ASSE A10.6.

#### 1.7 STORAGE AND HANDLING OF SALVAGED MATERIALS

- A. Salvaged Materials for Reinstallation:
1. Repair and clean items for reuse as indicated.
  2. Pack or crate items after cleaning and repairing; cushion against damage during handling. Label contents of containers.
  3. Protect items from damage during transport and storage.



4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment unless otherwise indicated. Provide connections, supports, and miscellaneous materials to make items functional for use indicated.
- B. Existing Materials to Remain: Protect construction indicated to remain against damage and soiling from construction work. Where permitted by Architect, items may be dismantled and taken to a suitable, protected storage location during construction work and reinstalled in their original locations after alteration and other construction work in the vicinity is complete.
- C. Storage: Catalog and store items within a weathertight enclosure where they are protected from moisture, weather, condensation, and freezing temperatures.
  1. Identify each item for reinstallation with a nonpermanent mark to document its original location. Indicate original locations on plans, elevations, sections, or photographs by annotating the identifying marks.
  2. Secure stored materials to protect from theft.
  3. Control humidity so that it does not exceed 85 percent. Maintain temperatures 5 deg F (3 deg C) or more above the dew point.
- D. Storage Space:
  1. Owner will arrange for limited on-site location(s) for free storage of salvaged material. This storage space does not include security for stored material.

#### 1.8 FIELD CONDITIONS

- A. Survey of Existing Conditions: Record existing conditions that affect the Work by use of preconstruction photographs.
  1. Comply with requirements specified in Section 013233 "Photographic Documentation."
- B. Discrepancies: Notify Architect of discrepancies between existing conditions and Drawings before proceeding with removal and dismantling work.
- C. Owner's Removals: Before beginning alteration work, verify in correspondence with Owner that the following items have been removed:
  1. See Drawings for reference.
- D. Size Limitations in Existing Spaces: Materials, products, and equipment used for performing the Work and for transporting debris, materials, and products shall be of sizes that clear surfaces within existing spaces, areas, rooms, and openings, including temporary protection, by 12 inches (300 mm) or more.

PART 2 - PRODUCTS - (Not Used)

PART 3 - EXECUTION

3.1 PROTECTION

- A. Temporary Protection of Materials to Remain:
  - 1. Protect existing materials with temporary protections and construction. Do not remove existing materials unless otherwise indicated.
- B. Comply with each product manufacturer's written instructions for protections and precautions. Protect against adverse effects of products and procedures on people and adjacent materials, components, and vegetation.
- C. Utility and Communications Services:
  - 1. Notify Owner, Architect, authorities having jurisdiction, and entities owning or controlling wires, conduits, pipes, and other services affected by alteration work before commencing operations.
  - 2. Disconnect and cap pipes and services as required by authorities having jurisdiction, as required for alteration work.
  - 3. Maintain existing services unless otherwise indicated; keep in service, and protect against damage during operations. Provide temporary services during interruptions to existing utilities.

3.2 GENERAL ALTERATION WORK

- A. Have specialty work performed only by qualified specialists.
- B. Ensure that supervisory personnel are present when work begins and during its progress.
- C. Record existing work before each procedure (preconstruction), and record progress during the work. Use digital preconstruction documentation photographs. Comply with requirements in Section 013233 "Photographic Documentation."
- D. Perform surveys of Project site as the Work progresses to detect hazards resulting from alterations.
- E. Notify Architect of visible changes in the integrity of material or components whether from environmental causes including biological attack, UV degradation, freezing, or thawing or from structural defects including cracks, movement, or distortion.
  - 1. Do not proceed with the work in question until directed by Architect.

END OF SECTION 013156

## SECTION 014000 - QUALITY REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
  - 1. Specific quality-assurance and -control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
  - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
  - 3. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.
  - 4. Specific test and inspection requirements are not specified in this Section.

#### 1.2 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.
- C. Mockups: Full-size physical assemblies that are constructed on-site. Mockups are constructed to verify selections made under Sample submittals; to demonstrate aesthetic effects and, where indicated, qualities of materials and execution; to review coordination, testing, or operation; to show interface between dissimilar materials; and to demonstrate compliance with specified installation tolerances. Mockups are not Samples. Unless otherwise indicated, approved mockups establish the standard by which the Work will be judged.
  - 1. Integrated Exterior Mockups: Mockups of the exterior envelope erected separately from the building but on Project site, consisting of multiple products, assemblies, and subassemblies.
  - 2. Room Mockups: Mockups of typical interior spaces complete with wall, floor, and ceiling finishes, doors, windows, millwork, casework, specialties, furnishings and equipment, and lighting.

- D. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.
- E. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- F. Source Quality-Control Testing: Tests and inspections that are performed at the source, e.g., plant, mill, factory, or shop.
- G. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- H. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- I. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
  - 1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).
- J. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

### 1.3 CONFLICTING REQUIREMENTS

- A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

### 1.4 ACTION SUBMITTALS

- A. Shop Drawings: For integrated exterior mockups, provide plans, sections, and elevations, indicating materials and size of mockup construction.
  - 1. Indicate manufacturer and model number of individual components.
  - 2. Provide axonometric drawings for conditions difficult to illustrate in two dimensions.

1.5 INFORMATIONAL SUBMITTALS

- A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.
- B. Qualification Data: For Contractor's quality-control personnel.
- C. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- D. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
  - 1. Specification Section number and title.
  - 2. Entity responsible for performing tests and inspections.
  - 3. Description of test and inspection.
  - 4. Identification of applicable standards.
  - 5. Identification of test and inspection methods.
  - 6. Number of tests and inspections required.
  - 7. Time schedule or time span for tests and inspections.
  - 8. Requirements for obtaining samples.
  - 9. Unique characteristics of each quality-control service.

1.6 CONTRACTOR'S QUALITY-CONTROL PLAN

- A. Quality-Control Plan, General: Submit quality-control plan within 10 days of Notice of Award, and not less than five days prior to preconstruction conference. Submit in format acceptable to Architect. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities. Coordinate with Contractor's construction schedule.
- B. Quality-Control Personnel Qualifications: Engage qualified full-time personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.
  - 1. Project quality-control manager may also serve as Project superintendent.
- C. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.
- D. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:
  - 1. Contractor-performed tests and inspections including subcontractor-performed tests and inspections. Include required tests and inspections and Contractor elected tests and inspections.
  - 2. Special inspections required by authorities having jurisdiction and indicated on the "Statement of Special Inspections."
  - 3. Owner-performed tests and inspections indicated in the Contract Documents.

- E. Continuous Inspection of Workmanship: Describe process for continuous inspection during construction to identify and correct deficiencies in workmanship in addition to testing and inspection specified. Indicate types of corrective actions to be required to bring work into compliance with standards of workmanship established by Contract requirements and approved mockups.
- F. Monitoring and Documentation: Maintain testing and inspection reports including log of approved and rejected results. Include work Architect has indicated as nonconforming or defective. Indicate corrective actions taken to bring nonconforming work into compliance with requirements. Comply with requirements of authorities having jurisdiction.

#### 1.7 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
  - 1. Date of issue.
  - 2. Project title and number.
  - 3. Name, address, and telephone number of testing agency.
  - 4. Dates and locations of samples and tests or inspections.
  - 5. Names of individuals making tests and inspections.
  - 6. Description of the Work and test and inspection method.
  - 7. Identification of product and Specification Section.
  - 8. Complete test or inspection data.
  - 9. Test and inspection results and an interpretation of test results.
  - 10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
  - 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
  - 12. Name and signature of laboratory inspector.
  - 13. Recommendations on retesting and reinspecting.
- B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:
  - 1. Name, address, and telephone number of technical representative making report.
  - 2. Statement on condition of substrates and their acceptability for installation of product.
  - 3. Statement that products at Project site comply with requirements.
  - 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
  - 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
  - 6. Statement whether conditions, products, and installation will affect warranty.
  - 7. Other required items indicated in individual Specification Sections.
- C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:
  - 1. Name, address, and telephone number of factory-authorized service representative making report.
  - 2. Statement that equipment complies with requirements.

3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
4. Statement whether conditions, products, and installation will affect warranty.
5. Other required items indicated in individual Specification Sections.

D. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

## 1.8 QUALITY ASSURANCE

A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.

B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

D. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.

E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar in material, design, and extent to those indicated for this Project.

F. Specialists: Certain Specification Sections require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.

1. Requirements of authorities having jurisdiction shall supersede requirements for specialists.

G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according to ASTM E 329; and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.

1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.

H. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation

of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.

- I. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- J. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:
  1. Contractor responsibilities include the following:
    - a. Provide test specimens representative of proposed products and construction.
    - b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
    - c. Provide sizes and configurations of test assemblies, mockups, and laboratory mockups to adequately demonstrate capability of products to comply with performance requirements.
    - d. Build site-assembled test assemblies and mockups using installers who will perform same tasks for Project.
    - e. Build laboratory mockups at testing facility using personnel, products, and methods of construction indicated for the completed Work.  
When testing is complete, remove test specimens, assemblies, and mockups; do not reuse products on Project.
  2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect, with copy to Contractor. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.
- K. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:
  1. Build mockups in location and of size indicated or, if not indicated, as directed by Architect.
  2. Notify Architect seven days in advance of dates and times when mockups will be constructed.
  3. Employ supervisory personnel who will oversee mockup construction. Employ workers that will be employed during the construction at Project.
  4. Demonstrate the proposed range of aesthetic effects and workmanship.
  5. Obtain Architect's approval of mockups before starting work, fabrication, or construction.
    - a. Allow seven days for initial review and each re-review of each mockup.
  6. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
  7. Demolish and remove mockups when directed unless otherwise indicated.
- L. Integrated Exterior Mockups: Construct integrated exterior mockup according to approved Shop Drawings. Coordinate installation of exterior envelope materials and products for which mockups are required in individual Specification Sections, along with supporting materials.



- M. Room Mockups: Construct room mockups incorporating required materials and assemblies, finished according to requirements. Provide required lighting and additional lighting where required to enable Architect to evaluate quality of the Work. Provide room mockups of the following rooms:

1. Where indicated on the Drawings.

#### 1.9 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
  2. Payment for these services will be made from testing and inspecting allowances, as authorized by Change Orders.
  3. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.
- B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.
1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
  2. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.
    - a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
  3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
  4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
  5. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
  6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Section 013300 "Submittal Procedures."
- D. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.

- E. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.
  - F. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
    - 1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
    - 2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
    - 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
    - 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
    - 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
    - 6. Do not perform any duties of Contractor.
  - G. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
    - 1. Access to the Work.
    - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
    - 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
    - 4. Facilities for storage and field curing of test samples.
    - 5. Preliminary design mix proposed for use for material mixes that require control by testing agency.
    - 6. Security and protection for samples and for testing and inspecting equipment at Project site.
  - H. Coordination: Coordinate sequence of activities to accommodate required quality assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
    - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.
  - I. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar quality-control services required by the Contract Documents. Coordinate and submit concurrently with Contractor's construction schedule. Update as the Work progresses.
    - 1. Distribution: Distribute schedule to Owner, Architect, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.
- 1.10 SPECIAL TESTS AND INSPECTIONS
- A. Special Tests and Inspections: Conducted by a qualified testing agency or special inspector as required by authorities having jurisdiction, as indicated in individual Specification Sections, and as follows:

1. Verifying that manufacturer maintains detailed fabrication and quality-control procedures and reviews the completeness and adequacy of those procedures to perform the Work.
2. Notifying Architect and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
3. Submitting a certified written report of each test, inspection, and similar quality control service to Architect with copy to Contractor and to authorities having jurisdiction.
4. Submitting a final report of special tests and inspections at Substantial Completion, which includes a list of unresolved deficiencies.
5. Interpreting tests and inspections and stating in each report whether tested and inspected work complies with or deviates from the Contract Documents.
6. Retesting and reinspecting corrected work.

## PART 2 - PRODUCTS (Not Used)

## PART 3 - EXECUTION

### 3.1 TEST AND INSPECTION LOG

- A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:
  1. Date test or inspection was conducted.
  2. Description of the Work tested or inspected.
  3. Date test or inspection results were transmitted to Architect.
  4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

### 3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
  1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 014000

## SECTION 014000 - QUALITY REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
  - 1. Specific quality-assurance and -control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
  - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
  - 3. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.
  - 4. Specific test and inspection requirements are not specified in this Section.

#### 1.2 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.
- C. Mockups: Full-size physical assemblies that are constructed on-site. Mockups are constructed to verify selections made under Sample submittals; to demonstrate aesthetic effects and, where indicated, qualities of materials and execution; to review coordination, testing, or operation; to show interface between dissimilar materials; and to demonstrate compliance with specified installation tolerances. Mockups are not Samples. Unless otherwise indicated, approved mockups establish the standard by which the Work will be judged.
  - 1. Integrated Exterior Mockups: Mockups of the exterior envelope erected separately from the building but on Project site, consisting of multiple products, assemblies, and subassemblies.
  - 2. Room Mockups: Mockups of typical interior spaces complete with wall, floor, and ceiling finishes, doors, windows, millwork, casework, specialties, furnishings and equipment, and lighting.

- D. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.
- E. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- F. Source Quality-Control Testing: Tests and inspections that are performed at the source, e.g., plant, mill, factory, or shop.
- G. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- H. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- I. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
  - 1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).
- J. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

### 1.3 CONFLICTING REQUIREMENTS

- A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

### 1.4 ACTION SUBMITTALS

- A. Shop Drawings: For integrated exterior mockups, provide plans, sections, and elevations, indicating materials and size of mockup construction.
  - 1. Indicate manufacturer and model number of individual components.
  - 2. Provide axonometric drawings for conditions difficult to illustrate in two dimensions.

1.5 INFORMATIONAL SUBMITTALS

- A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.
- B. Qualification Data: For Contractor's quality-control personnel.
- C. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- D. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
  - 1. Specification Section number and title.
  - 2. Entity responsible for performing tests and inspections.
  - 3. Description of test and inspection.
  - 4. Identification of applicable standards.
  - 5. Identification of test and inspection methods.
  - 6. Number of tests and inspections required.
  - 7. Time schedule or time span for tests and inspections.
  - 8. Requirements for obtaining samples.
  - 9. Unique characteristics of each quality-control service.

1.6 CONTRACTOR'S QUALITY-CONTROL PLAN

- A. Quality-Control Plan, General: Submit quality-control plan within 10 days of Notice of Award, and not less than five days prior to preconstruction conference. Submit in format acceptable to Architect. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities. Coordinate with Contractor's construction schedule.
- B. Quality-Control Personnel Qualifications: Engage qualified full-time personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.
  - 1. Project quality-control manager may also serve as Project superintendent.
- C. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.
- D. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:
  - 1. Contractor-performed tests and inspections including subcontractor-performed tests and inspections. Include required tests and inspections and Contractor elected tests and inspections.
  - 2. Special inspections required by authorities having jurisdiction and indicated on the "Statement of Special Inspections."
  - 3. Owner-performed tests and inspections indicated in the Contract Documents.

- E. Continuous Inspection of Workmanship: Describe process for continuous inspection during construction to identify and correct deficiencies in workmanship in addition to testing and inspection specified. Indicate types of corrective actions to be required to bring work into compliance with standards of workmanship established by Contract requirements and approved mockups.
- F. Monitoring and Documentation: Maintain testing and inspection reports including log of approved and rejected results. Include work Architect has indicated as nonconforming or defective. Indicate corrective actions taken to bring nonconforming work into compliance with requirements. Comply with requirements of authorities having jurisdiction.

#### 1.7 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
  - 1. Date of issue.
  - 2. Project title and number.
  - 3. Name, address, and telephone number of testing agency.
  - 4. Dates and locations of samples and tests or inspections.
  - 5. Names of individuals making tests and inspections.
  - 6. Description of the Work and test and inspection method.
  - 7. Identification of product and Specification Section.
  - 8. Complete test or inspection data.
  - 9. Test and inspection results and an interpretation of test results.
  - 10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
  - 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
  - 12. Name and signature of laboratory inspector.
  - 13. Recommendations on retesting and reinspecting.
- B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:
  - 1. Name, address, and telephone number of technical representative making report.
  - 2. Statement on condition of substrates and their acceptability for installation of product.
  - 3. Statement that products at Project site comply with requirements.
  - 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
  - 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
  - 6. Statement whether conditions, products, and installation will affect warranty.
  - 7. Other required items indicated in individual Specification Sections.
- C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:
  - 1. Name, address, and telephone number of factory-authorized service representative making report.
  - 2. Statement that equipment complies with requirements.

3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
4. Statement whether conditions, products, and installation will affect warranty.
5. Other required items indicated in individual Specification Sections.

D. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

## 1.8 QUALITY ASSURANCE

A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.

B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

D. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.

E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar in material, design, and extent to those indicated for this Project.

F. Specialists: Certain Specification Sections require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.

1. Requirements of authorities having jurisdiction shall supersede requirements for specialists.

G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according to ASTM E 329; and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.

1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.

H. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation



of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.

- I. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- J. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:
  1. Contractor responsibilities include the following:
    - a. Provide test specimens representative of proposed products and construction.
    - b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
    - c. Provide sizes and configurations of test assemblies, mockups, and laboratory mockups to adequately demonstrate capability of products to comply with performance requirements.
    - d. Build site-assembled test assemblies and mockups using installers who will perform same tasks for Project.
    - e. Build laboratory mockups at testing facility using personnel, products, and methods of construction indicated for the completed Work.  
When testing is complete, remove test specimens, assemblies, and mockups; do not reuse products on Project.
  2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect, with copy to Contractor. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.
- K. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:
  1. Build mockups in location and of size indicated or, if not indicated, as directed by Architect.
  2. Notify Architect seven days in advance of dates and times when mockups will be constructed.
  3. Employ supervisory personnel who will oversee mockup construction. Employ workers that will be employed during the construction at Project.
  4. Demonstrate the proposed range of aesthetic effects and workmanship.
  5. Obtain Architect's approval of mockups before starting work, fabrication, or construction.
    - a. Allow seven days for initial review and each re-review of each mockup.
  6. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
  7. Demolish and remove mockups when directed unless otherwise indicated.
- L. Integrated Exterior Mockups: Construct integrated exterior mockup according to approved Shop Drawings. Coordinate installation of exterior envelope materials and products for which mockups are required in individual Specification Sections, along with supporting materials.

- M. Room Mockups: Construct room mockups incorporating required materials and assemblies, finished according to requirements. Provide required lighting and additional lighting where required to enable Architect to evaluate quality of the Work. Provide room mockups of the following rooms:

1. Where indicated on the Drawings.

#### 1.9 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
  2. Payment for these services will be made from testing and inspecting allowances, as authorized by Change Orders.
  3. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.
- B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.
1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
  2. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.
    - a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
  3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
  4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
  5. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
  6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Section 013300 "Submittal Procedures."
- D. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.

- E. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.
  - F. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
    - 1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
    - 2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
    - 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
    - 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
    - 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
    - 6. Do not perform any duties of Contractor.
  - G. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
    - 1. Access to the Work.
    - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
    - 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
    - 4. Facilities for storage and field curing of test samples.
    - 5. Preliminary design mix proposed for use for material mixes that require control by testing agency.
    - 6. Security and protection for samples and for testing and inspecting equipment at Project site.
  - H. Coordination: Coordinate sequence of activities to accommodate required quality assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
    - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.
  - I. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar quality-control services required by the Contract Documents. Coordinate and submit concurrently with Contractor's construction schedule. Update as the Work progresses.
    - 1. Distribution: Distribute schedule to Owner, Architect, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.
- 1.10 SPECIAL TESTS AND INSPECTIONS
- A. Special Tests and Inspections: Conducted by a qualified testing agency or special inspector as required by authorities having jurisdiction, as indicated in individual Specification Sections, and as follows:

1. Verifying that manufacturer maintains detailed fabrication and quality-control procedures and reviews the completeness and adequacy of those procedures to perform the Work.
2. Notifying Architect and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
3. Submitting a certified written report of each test, inspection, and similar quality control service to Architect with copy to Contractor and to authorities having jurisdiction.
4. Submitting a final report of special tests and inspections at Substantial Completion, which includes a list of unresolved deficiencies.
5. Interpreting tests and inspections and stating in each report whether tested and inspected work complies with or deviates from the Contract Documents.
6. Retesting and reinspecting corrected work.

## PART 2 - PRODUCTS (Not Used)

## PART 3 - EXECUTION

### 3.1 TEST AND INSPECTION LOG

- A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:
  1. Date test or inspection was conducted.
  2. Description of the Work tested or inspected.
  3. Date test or inspection results were transmitted to Architect.
  4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

### 3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
  1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 014000

## SECTION 014200 - REFERENCES

### PART 1 - GENERAL

#### 1.1 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Operations at Project site including unloading, temporarily storing, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

#### 1.2 INDUSTRY STANDARDS

- A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.
- B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.
- C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.

1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

### 1.3 ABBREVIATIONS AND ACRONYMS

- A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities indicated in Thomson Gale's "Encyclopedia of Associations" or in Columbia Books' "National Trade & Professional Associations of the U.S."

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 014200

## SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes requirements for temporary facilities and controls, including temporary utilities, support facilities, and security and protection facilities.
- B. Temporary utilities include, but are not limited to, the following:
  - 1. Water service and distribution.
  - 2. Electric power service.
  - 3. Lighting.
  - 4. Telephone service.
  - 5. Storm and sanitary sewer.
  - 6. Storm water run-off control.
- C. Support facilities include, but are not limited to, the following:
  - 1. Temporary roads and paving.
  - 2. Dewatering facilities and drains.
  - 3. Project identification and temporary signs.
  - 4. Waste disposal facilities.
  - 5. Field offices.
  - 6. Storage and fabrication sheds.
  - 7. Lifts and hoists.
  - 8. Construction aids and miscellaneous services and facilities.
  - 9. Sanitary facilities, including drinking water.
  - 10. Temporary heat.
- D. Security and protection facilities include, but are not limited to, the following:
  - 1. Environmental protection.
  - 2. Stormwater control.
  - 3. Tree and plant protection.
  - 4. Pest control.
  - 5. Barricades, warning signs, and lights.
  - 6. Sidewalk bridge or enclosure fence for the site.
  - 7. Temporary enclosures.
  - 8. Temporary partitions.
  - 9. Fire protection.

#### 1.2 DEFINITIONS

- A. Permanent Enclosure: As determined by Architect, permanent or temporary roofing is complete, insulated, and weathertight; exterior walls are insulated and weathertight; and all openings are closed with permanent construction or substantial temporary closures.

### 1.3 USE CHARGES

- A. General: Cost or use charges for temporary facilities are not chargeable to Owner or Architect and shall be included in the Contract Sum. Allow other entities to use temporary services and facilities without cost, including, but not limited to, the following:
  - 1. Architect.
  - 2. Testing agencies.
  - 3. Personnel of authorities having jurisdiction.
- B. Sewer Service: Pay sewer service use charges for sewer usage, by all parties engaged in construction, at Project site.
- C. Water Service: Pay water service use charges, whether metered or otherwise, for water used by all entities engaged in construction activities at Project site.
- D. Electric Power Service: Pay electric power service use charges, whether metered or otherwise, for electricity used by all entities engaged in construction activities at Project site.

### 1.4 SUBMITTALS

- A. Temporary Utility Reports: Submit reports of tests, inspections, meter readings, and similar procedures performed on temporary utilities.
- B. Implementation and Termination Schedule: Within 15 days of date established for submittal of Contractor's Construction Schedule, submit a schedule indicating implementation and termination of each temporary utility.

### 1.5 QUALITY ASSURANCE

- A. Regulations: Comply with industry standards and applicable laws and regulations of authorities having jurisdiction, including but not limited to:
  - 1. Building Code requirements.
  - 2. Health and safety regulations.
  - 3. Utility company regulations.
  - 4. Police, Fire Department, and Rescue Squad rules.
  - 5. Environmental protection regulations.
- B. Standards: Comply with ANSI A10.6, NECA's "Temporary Electrical Facilities," and NFPA 241.
  - 1. Trade Jurisdictions: Assigned responsibilities for installation and operation of temporary utilities are not intended to interfere with trade regulations and union jurisdictions.
  - 2. Industry Recommendations: Refer to "Guidelines for Bid Conditions for Temporary Job Utilities and Services", prepared jointly by AGC and ASC, for industry recommendations.
  - 3. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- C. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.



## 1.6 PROJECT CONDITIONS

- A. Temporary Utilities: Prepare a schedule indicating dates for implementation and termination of each temporary utility. At earliest feasible time, when acceptable to Owner, change over from use of temporary service to use of permanent service.
  - 1. Temporary Use of Permanent Facilities: Installer of each permanent service shall assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.
- B. Conditions of Use: The following conditions apply to use of temporary services and facilities by all parties engaged in the Work:
  - 1. Keep temporary services and facilities clean and neat.
  - 2. Relocate temporary services and facilities as required by progress of the Work.

## PART 2 - PRODUCTS

### 2.1 MATERIALS

- A. General: Provide new materials. Undamaged, previously used materials in serviceable condition may be used if approved by Architect. Provide materials suitable for use intended.
- B. Lumber and Plywood: Comply with requirements in Division 6 Section "Rough Carpentry."
  - 1. For job-built temporary offices, shops and sheds within the construction area provide UL labeled, fire treated lumber and plywood for framing, sheathing and siding.
  - 2. For signs and directory boards, provide exterior type, Grade B-B High Density Concrete Form Overlay Plywood conforming to PS-1, of sizes and thickness indicated.
  - 3. For fences and vision barriers, provide exterior type, minimum 3/8" thick plywood. 4. For safety barriers, sidewalk bridges and similar uses, provide minimum 5/8" thick exterior plywood.
- C. Roofing: UL Class A, Standard-weight, mineral-surfaced, asphalt shingles or asphalt impregnated and -coated, mineral-surfaced, roll-roofing sheet.
- D. Gypsum Board: Minimum 1/2 inch thick by 48 inches wide by maximum available lengths; regular-type panels with tapered edges. Comply with ASTM C 36.
- E. Insulation: Unfaced mineral-fiber blanket, manufactured from glass, slag wool, or rock wool; with maximum flame-spread and smoke-developed indices of 25 and 50, respectively.
- F. Paint: Comply with requirements in Division 9 Section "Painting."
- G. Tarpaulins: Fire-resistive labeled with flame-spread rating of 15 or less.
- H. Water: Potable.

## 2.2 EQUIPMENT

- A. General: Provide new equipment, if acceptable to the Architect, undamaged, previously used equipment in serviceable condition may be used. Provide equipment suitable for use intended.
- B. Field Offices: Prefabricated or mobile units or similar job-built construction with lockable entrances, operable windows, and serviceable finishes; heated and air conditioned; on foundations adequate for normal loading. Provide the following for jobbuilt construction:
  - 1. Exposed Lumber and Plywood: Paint with exterior-grade, acrylic-latex emulsion over exterior primer.
  - 2. Interior Walls: Paint with two coats of interior latex-flat wall paint.
  - 3. Roofs: Asphalt shingles or roll roofing.
- C. Fire Extinguishers: Hand carried, portable, UL rated. Provide class and extinguishing agent as indicated or a combination of extinguishers of NFPA-recommended classes for exposures.
  - 1. Comply with NFPA 10 and NFPA 241 for classification, extinguishing agent, and size required by location and class of fire exposure.
- D. Self-Contained Toilet Units: Single-occupant units of chemical, aerated recirculation, or combustion type; vented; fully enclosed with a glass-fiber-reinforced polyester shell or similar nonabsorbent material.
- E. Heating Equipment: Provide self-contained heaters with individual space thermostatic control.
  - 1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
  - 2. Heating Units: Listed and labeled, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use for type of fuel being consumed.
- F. Electrical Outlets: Properly configured, NEMA-polarized outlets to prevent insertion of 110- to 120-V plugs into higher-voltage outlets; equipped with ground-fault circuit interrupters, reset button, and pilot light.

## PART 3 - EXECUTION

### 3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required.
- B. Provide each facility ready for use when needed to avoid delay. Maintain and modify as required. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

### 3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Engage appropriate local utility company to install temporary service or connect to existing service. Where utility company provides only part of the service, provide the remainder

with matching, compatible materials and equipment. Comply with utility company recommendations.

1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.
  2. Provide adequate capacity at each stage of construction. Before temporary utility is available, provide trucked-in services.
  3. Obtain easements to bring temporary utilities to Project site where Owner's easements cannot be used for that purpose.
- B. Sewers and Drainage: If sewers are available, provide temporary connections to remove effluent that can be discharged lawfully. If sewers are not available or cannot be used, provide drainage ditches, dry wells, stabilization ponds, and similar facilities. If neither sewers nor drainage facilities can be lawfully used for discharge of effluent, provide containers to remove and dispose of effluent off-site in a lawful manner.
1. Filter out excessive soil, construction debris, chemicals, oils, and similar contaminants that might clog sewers or pollute waterways before discharge.
  2. Connect temporary sewers to municipal system as directed by sewer department officials.
  3. Maintain temporary sewers and drainage facilities in a clean, sanitary condition. After heavy use, restore normal conditions promptly.
- C. Water Service: Install water service and distribution piping in sizes and pressures adequate for construction until permanent water service is in use. Sterilize temporary water piping before use.
- D. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking-water fixtures. Comply with regulations and health codes for type, number, location, operation, and maintenance of fixtures and facilities.
1. Disposable Supplies: Provide toilet tissue, paper towels, paper cups, and similar disposable materials for each facility. Maintain adequate supply. Provide covered waste containers for disposal of used material.
  2. Toilets: Install self-contained toilet units. Shield toilets to ensure privacy.
  3. Wash Facilities: Install wash facilities supplied with potable water at convenient locations for personnel who handle materials that require wash up. Dispose of drainage properly. Supply cleaning compounds appropriate for each type of material handled.
    - a. Provide safety showers, eyewash fountains, and similar facilities for convenience, safety, and sanitation of personnel.
  4. Drinking-Water Facilities: Provide bottled-water, drinking-water units; include paper supply.
- E. Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment from that specified that will not have a harmful effect on completed installations or elements being installed.
- F. Ventilation and Humidity Control: Provide temporary ventilation required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of high humidity. Select equipment from that specified that will not have a

harmful effect on completed installations or elements being installed. Coordinate ventilation requirements to produce ambient condition required and minimize energy consumption.

- G. Electric Power Service: Provide weatherproof, grounded electric power service and distribution system of sufficient size, capacity, and power characteristics during construction period. Include meters, transformers, overload-protected disconnecting means, automatic ground-fault interrupters, and main distribution switchgear.
  - 1. Install electric power service underground, unless overhead service must be used.
  - 2. Install power distribution wiring overhead and rise vertically where least exposed to damage.
- H. Electric Distribution: Provide receptacle outlets adequate for connection of power tools and equipment.
  - 1. Provide waterproof connectors to connect separate lengths of electrical power cords if single lengths will not reach areas where construction activities are in progress. Do not exceed safe length-voltage ratio.
- I. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations and traffic conditions.
  - 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.
- J. Telephone Service: Provide temporary telephone service throughout construction period for common-use facilities used by all personnel engaged in construction activities. Install separate telephone line for each field office and first-aid station.
  - 1. Provide additional telephone lines for the following: a. In field office with more than two occupants, install a telephone for each additional occupant or pair of occupants.
  - 2. At each telephone, post a list of important telephone numbers.

### 3.3 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:
  - 1. Locate field offices, storage sheds, sanitary facilities, and other temporary construction and support facilities for easy access.
  - 2. Provide incombustible construction for offices, shops, and sheds located within construction area or within 30 feet of building lines. Comply with NFPA 241.
- B. Temporary Roads and Paved Areas: Construct and maintain temporary roads and paved areas adequate to support loads and to withstand exposure to traffic during construction period. Locate temporary roads and paved areas in same location as permanent roads and paved areas. Review proposed modifications to permanent paving with the Architect. Extend temporary roads and paved areas, within construction limits indicated, as necessary for construction operations.
  - 1. Coordinate elevations of temporary roads and paved areas with permanent roads and paved areas.

2. Coordinate temporary paving development with subgrade grading, compaction, installation and stabilization of subbase, and installation of base and finish courses of permanent paving.
  3. Prepare subgrade and install subbase and base for temporary roads and paved areas according to Division 2 Section "Earthwork."
  4. Install temporary paving to minimize the need to rework the installations as to result in permanent roads and paved areas that are without damage or deterioration when occupied by the Owner.
  5. Recondition base after temporary use, including removing contaminated material, regrading, proofrolling, compacting, and testing.
  6. Delay installation of final course of permanent hot-mix asphalt pavement until immediately before Substantial Completion. Repair hot-mix asphalt base-course pavement before installation of final course according to Division 2 Section "Asphalt Paving." Coordinate with weather conditions to avoid unsatisfactory results.
- C. Dewatering Facilities and Drains: Comply with requirements in applicable Division 2 Sections for temporary drainage and dewatering facilities and operations not directly associated with construction activities included in individual Sections. Where feasible, use same facilities. Maintain Project site, excavations, and construction free of water.
1. Dispose of rainwater in a lawful manner that will not result in flooding Project or adjoining property nor endanger permanent Work or temporary facilities.
- D. Project Identification and Temporary Signs: Prepare Project identification and other signs in sizes indicated. Install signs where indicated to inform public and persons seeking entrance to Project. Do not permit installation of unauthorized signs.
1. Engage an experienced sign painter to apply graphics for Project identification signs. Comply with details indicated.
  2. Prepare temporary signs to provide directional information to construction personnel and visitors.
  3. Construct signs of exterior-type Grade B-B high-density concrete form overlay plywood in sizes and thickness indicated. Support on posts or framing of preservative-treated wood or steel.
  4. Paint sign panel and applied graphics with exterior-grade alkyd gloss enamel over exterior primer.
- E. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Containerize and clearly label hazardous, dangerous, or unsanitary waste materials separately from other waste. Comply with Division 1 Section "Execution Requirements" for progress cleaning requirements.
1. If required by authorities having jurisdiction, provide separate containers, clearly labeled, for each type of waste material to be deposited.
  2. Develop a waste management plan for Work performed on Project. Indicate types of waste materials Project will produce and estimate quantities of each type. Provide detailed information for on-site waste storage and separation of recyclable materials. Provide information on destination of each type of waste material and means to be used to dispose of all waste materials.
- F. Janitorial Services: Provide janitorial services on a daily basis for temporary offices, toilets, wash facilities, and similar areas.

- G. General Contractor's Field Office: Provide an insulated, weathertight, air-conditioned field office for use as a common facility by personnel engaged in construction activities; of sufficient size to accommodate required office personnel and meetings of 10 persons at Project site. Keep office clean and orderly.
  - 1. Furnish and equip offices as follows:
    - a. Desk and four chairs, four-drawer file cabinet, a plan table, a plan rack, and bookcase.
    - b. Water cooler and private toilet complete with water closet, lavatory, and medicine cabinet with mirror.
- H. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment involved, including temporary utility services. Sheds may be open shelters or fully enclosed spaces within building or elsewhere onsite.
  - 1. Construct framing, sheathing, and siding using fire-retardant-treated lumber and plywood.
  - 2. Paint exposed lumber and plywood with exterior-grade acrylic-latex emulsion over exterior primer.
- I. Lifts and Hoists: Provide facilities for hoisting materials and personnel. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.

#### 3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction in ways and by methods that comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects. Avoid using tools and equipment that produce harmful noise. Restrict use of noisemaking tools and equipment to hours that will minimize complaints from persons or firms near Project site.
- B. Stormwater Control: Provide earthen embankments and similar barriers in and around excavations and subgrade construction, sufficient to prevent flooding by runoff of stormwater from heavy rains.
- C. Tree and Plant Protection: Install temporary fencing located as indicated or outside the drip line of trees to protect vegetation from construction damage. Protect tree root systems from damage, flooding, and erosion.
- D. Site Enclosure Fence: When excavation begins, install chain-link fence with lockable entrance gates. Locate where indicated, or enclose entire Project site or portion determined sufficient to accommodate construction operations. Install in a manner that will prevent people, dogs, and other animals from easily entering site except by entrance gates.
  - 1. Set fence posts in compacted mixture of gravel and earth.
  - 2. Provide gates in sizes and at locations necessary to accommodate delivery vehicles and other construction operations.

- E. Security Enclosure and Lockup: Install substantial temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security.
- F. Temporary Exterior Lighting: Install exterior yard and sign lights so that signs are visible when Work is being performed.
- G. Barricades, Warning Signs, and Lights: Comply with standards and code requirements for erecting structurally adequate barricades. Paint with appropriate colors, graphics, and warning signs to inform personnel and public of possible hazard. Where appropriate and needed, provide lighting, including flashing red or amber lights.
- H. Covered Walkway: Erect a structurally adequate, protective, covered walkway for passage of persons along adjacent public street. Coordinate with entrance gates, other facilities, and obstructions. Comply with regulations of authorities having jurisdiction.
  - 1. Construct covered walkways using scaffold or shoring framing.
  - 2. Provide wood-plank overhead decking, protective plywood enclosure walls, handrails, barricades, warning signs, lights, safe and well-drained walkways, and similar provisions for protection and safe passage.
  - 3. Extend back wall beyond the structure to complete enclosure fence.
  - 4. Paint and maintain in a manner approved by Owner and Architect.
  - 5. For safety barriers, sidewalk bridges, and similar uses, provide minimum 5/8- inch- thick exterior plywood.
- I. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.
  - 1. Where heating or cooling is needed and permanent enclosure is not complete, provide insulated temporary enclosures. Coordinate enclosure with ventilating and material drying or curing requirements to avoid dangerous conditions and effects.
  - 2. Horizontal Openings: Close openings in floor or roof decks and horizontal surfaces with load-bearing, wood-framed construction.
  - 3. Install tarpaulins securely using fire-retardant-treated wood framing and other materials.
  - 4. Where temporary wood or plywood enclosure exceeds 100 sq. ft. in area, use fire-retardant-treated material for framing and main sheathing.
- J. Temporary Fire Protection: Until fire-protection needs are supplied by permanent facilities, install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241.
  - 1. Provide fire extinguishers, installed on walls on mounting brackets, visible and accessible from space being served, with sign mounted above.
    - a. Field Offices: Class A stored-pressure water-type extinguishers.
    - b. Other Locations: Class ABC dry-chemical extinguishers or a combination of extinguishers of NFPA-recommended classes for exposures.
    - c. Locate fire extinguishers where convenient and effective for their intended purpose; provide not less than one extinguisher on each floor at or near each usable stairwell.
  - 2. Store combustible materials in containers in fire-safe locations.

3. Maintain unobstructed access to fire extinguishers, fire hydrants, temporary fireprotection facilities, stairways, and other access routes for firefighting. Prohibit smoking in hazardous fire-exposure areas.
4. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition.
5. Permanent Fire Protection: At earliest feasible date in each area of Project, complete installation of permanent fire-protection facility, including connected services, and place into operation and use. Instruct key personnel on use of facilities.
6. Develop and supervise an overall fire-prevention and first-aid fire-protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.

### 3.5 OPERATION, TERMINATION, AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Maintenance: Maintain facilities in good operating condition until removal. Protect from damage caused by freezing temperatures and similar elements.
  1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.
  2. Prevent water-filled piping from freezing. Maintain markers for underground lines. Protect from damage during excavation operations.
- C. Operate Project-identification-sign lighting daily from dusk until 12:00 midnight.
- D. Termination and Removal: Unless the Architect requests that temporary facilities be maintained longer, remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
  1. Materials and facilities that constitute temporary facilities are the property of Contractor. Owner reserves right to take possession of Project identification signs.
  2. Remove temporary paving not intended for or acceptable for integration into permanent paving. Where area is intended for landscape development, remove soil and aggregate fill that do not comply with requirements for fill or subsoil. Remove materials contaminated with road oil, asphalt and other petrochemical compounds, and other substances that might impair growth of plant materials or lawns. Repair or replace street paving, curbs, and sidewalks at temporary entrances, as required by authorities having jurisdiction.
  3. At Substantial Completion, clean and renovate permanent facilities used during construction period. Comply with final cleaning requirements in Division 1 Section "Closeout Procedures".

END OF SECTION 015000



## SECTION 016000 - PRODUCT REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.

#### 1.2 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
  - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
  - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
  - 3. Comparable Product: Product that is demonstrated and approved through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a specific manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of other manufacturers.

#### 1.3 ACTION SUBMITTALS

- A. Comparable Product Requests: Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
  - 1. Include data to indicate compliance with the requirements specified in "Comparable Products" Article.
  - 2. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
    - a. Form of Approval: As specified in Division 01 Section "Submittal Procedures."

- b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.

- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Division 01 Section "Submittal Procedures." Show compliance with requirements.

#### 1.4 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.
  - 1. Each contractor is responsible for providing products and construction methods compatible with products and construction methods of other contractors.
  - 2. If a dispute arises between contractors over concurrently selectable but incompatible products, Architect will determine which products shall be used.

#### 1.5 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

#### 1.6 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
  - 1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
  - 2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.
  - 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
  - 2. Specified Form: When specified forms are included with the Specifications, prepare a written document using indicated form properly executed.
  - 3. Refer to Divisions 02 through 49. Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Division 01 Section "Closeout Procedures."

## PART 2 - PRODUCTS

### 2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.
1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
  2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
  3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
  4. Where products are accompanied by the term "as selected," Architect will make selection.
  5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
  6. Or Equal: For products specified by name and accompanied by the term "or equal," or "or approved equal," or "or approved," comply with requirements in "Comparable Products" Article to obtain approval for use of an unnamed product.
- B. Product Selection Procedures:
1. Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
  2. Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
  3. Products:
    - a. Restricted List: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will be considered, unless otherwise indicated.
    - b. Nonrestricted List: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed, or an unnamed product, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product.
  4. Manufacturers:
    - a. Restricted List: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will be considered, unless otherwise indicated.
    - b. Nonrestricted List: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed, or a product by an unnamed manufacturer, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed manufacturer's product.

5. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.
- C. Visual Matching Specification: Where Specifications require "match Architect's sample", provide a product that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches.
1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Division 01 Section "Substitution Procedures" for proposal of product.
- D. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

## 2.2 COMPARABLE PRODUCTS

- A. Conditions for Consideration: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:
1. Evidence that the proposed product does not require revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
  2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
  3. Evidence that proposed product provides specified warranty.
  4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
  5. Samples, if requested.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

SECTION 017300 - EXECUTION

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes general procedural requirements governing execution of the Work including, but not limited to, the following:
  - 1. Construction layout.
  - 2. Field engineering and surveying.
  - 3. General installation of products.
  - 4. Coordination of Owner-installed products.
  - 5. Progress cleaning.
  - 6. Starting and adjusting.
  - 7. Protection of installed construction.
  - 8. Correction of the Work.

1.2 SUBMITTALS

- A. Qualification Data: For professional engineer to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- B. Certificates: Submit certificate signed by professional engineer certifying that location and elevation of improvements comply with requirements.
- C. Landfill Receipts: Submit copy of receipts issued by a landfill facility, licensed to accept hazardous materials, for hazardous waste disposal.
- D. Certified Surveys: Submit two copies signed by professional engineer.
- E. Final Property Survey: Submit 10 copies showing the Work performed and record survey data.

1.3 QUALITY ASSURANCE

- A. Land Surveyor Qualifications: A professional land surveyor who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing land-surveying services of the kind indicated.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Existing Conditions: The existence and location of site improvements, utilities, and other construction indicated as existing are not guaranteed. Before beginning work, investigate and verify the existence and location of mechanical and electrical systems and other construction affecting the Work.
  - 1. Before construction, verify the location and points of connection of utility services.
- B. Existing Utilities: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities and other construction affecting the Work.
  - 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; and underground electrical services.
  - 2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- C. Acceptance of Conditions: Examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
  - 1. Written Report: Where a written report listing conditions detrimental to performance of the Work is required by other Sections, include the following:
    - a. Description of the Work.
    - b. List of detrimental conditions, including substrates.
    - c. List of unacceptable installation tolerances.
    - d. Recommended corrections.
  - 2. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
  - 3. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
  - 4. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
  - 5. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Existing Utility Information: Furnish information to local utility and the Owner that is necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or other utility appurtenances located in or affected by construction. Coordinate with authorities having jurisdiction.

- B. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
  - 1. Notify Owner not less than two days in advance of proposed utility interruptions.
  - 2. Do not proceed with utility interruptions without Architect's written permission.
- C. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- D. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- E. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents, submit a request for information to Architect. Include a detailed description of problem encountered, together with recommendations for changing the Contract Documents.

### 3.3 CONSTRUCTION LAYOUT

- A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks. If discrepancies are discovered, notify Architect promptly.
- B. General: Engage a professional engineer to lay out the Work using accepted surveying practices.
  - 1. Establish benchmarks and control points to set lines and levels at each story of construction and elsewhere as needed to locate each element of Project.
  - 2. Establish dimensions within tolerances indicated. Do not scale Drawings to obtain required dimensions.
  - 3. Inform installers of lines and levels to which they must comply.
  - 4. Notify Architect when deviations from required lines and levels exceed allowable tolerances.
  - 5. Close site surveys with an error of closure equal to or less than the standard established by authorities having jurisdiction.
- C. Site Improvements: Locate and lay out site improvements, including pavements, grading, fill and topsoil placement, utility slopes, and invert elevations.
- D. Building Lines and Levels: Locate and lay out control lines and levels for structures, building foundations, column grids, and floor levels, including those required for mechanical and electrical work. Transfer survey markings and elevations for use with control lines and levels. Level foundations and piers from two or more locations.
- E. Record Log: Maintain a log of layout control work. Record deviations from required lines and levels. Include beginning and ending dates and times of surveys, weather conditions, name and duty of each survey party member, and types of instruments and tapes used. Make the log available for reference by Architect.

### 3.4 FIELD ENGINEERING

- A. Identification: Owner will identify existing benchmarks, control points, and property corners.
- B. Reference Points: Locate existing permanent benchmarks, control points, and similar reference points before beginning the Work. Preserve and protect permanent benchmarks and control points during construction operations.
  - 1. Do not change or relocate existing benchmarks or control points without prior written approval of Architect. Report lost or destroyed permanent benchmarks or control points promptly. Report the need to relocate permanent benchmarks or control points to Architect before proceeding.
  - 2. Replace lost or destroyed permanent benchmarks and control points promptly. Base replacements on the original survey control points.
- C. Benchmarks: Establish and maintain a minimum of two permanent benchmarks on Project site, referenced to data established by survey control points. Comply with authorities having jurisdiction for type and size of benchmark.
  - 1. Record benchmark locations, with horizontal and vertical data, on Project Record Documents.
  - 2. Where the actual location or elevation of layout points cannot be marked, provide temporary reference points sufficient to locate the Work.
  - 3. Remove temporary reference points when no longer needed. Restore marked construction to its original condition.
- D. Certified Survey: On completion of foundation walls, major site improvements, and other work requiring field-engineering services, prepare a certified survey showing dimensions, locations, angles, and elevations of construction and sitework.
- E. Final Property Survey: Prepare a final property survey showing significant features (real property) for Project. Include on the survey a certification, signed by professional engineer, that principal metes, bounds, lines, and levels of Project are accurately positioned as shown on the survey.
  - 1. Show boundary lines, monuments, streets, site improvements and utilities, existing improvements and significant vegetation, adjoining properties, acreage, grade contours, and the distance and bearing from a site corner to a legal point.
  - 2. Recording: At Substantial Completion, have the final property survey recorded by or with authorities having jurisdiction as the official "property survey."

### 3.5 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
  - 1. Make vertical work plumb and make horizontal work level.
  - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
  - 3. Conceal pipes, ducts, and wiring in finished areas, unless otherwise indicated.
  - 4. Maintain minimum headroom clearance of indicated in spaces without a suspended ceiling.



- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- F. Anchors and Fasteners: Provide anchors and fasteners as required to anchor each component securely in place, accurately located and aligned with other portions of the Work.
  - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
  - 2. Allow for building movement, including thermal expansion and contraction.
- G. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
- H. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

### 3.6 OWNER-INSTALLED PRODUCTS

- A. Site Access: Provide access to Project site for Owner's construction forces.
- B. Coordination: Coordinate construction and operations of the Work with work performed by Owner's construction forces.
  - 1. Construction Schedule: Inform Owner of Contractor's preferred construction schedule for Owner's portion of the Work. Adjust construction schedule based on a mutually agreeable timetable. Notify Owner if changes to schedule are required due to differences in actual construction progress.
  - 2. Preinstallation Conferences: Include Owner's construction forces at preinstallation conferences covering portions of the Work that are to receive Owner's work. Attend preinstallation conferences conducted by Owner's construction forces if portions of the Work depend on Owner's construction.

### 3.7 PROGRESS CLEANING

- A. General: Clean Project site and work areas daily, including common areas. Coordinate progress cleaning for joint-use areas where more than one installer has worked. Enforce requirements strictly. Dispose of materials lawfully.
  - 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
  - 2. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.

- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
  - 1. Remove liquid spills promptly.
  - 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.
- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.
- F. Exposed Surfaces: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- G. Cutting and Patching: Clean areas and spaces where cutting and patching are performed. Completely remove paint, mortar, oils, putty, and similar materials.
  - 1. Thoroughly clean piping, conduit, and similar features before applying paint or other finishing materials. Restore damaged pipe covering to its original condition.
- H. Waste Disposal: Burying or burning waste materials on-site will not be permitted. Washing waste materials down sewers or into waterways will not be permitted.
- I. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- J. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- K. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

### 3.8 STARTING AND ADJUSTING

- A. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- B. Adjust operating components for proper operation without binding. Adjust equipment for proper operation.
- C. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

- D. Manufacturer's Field Service: If a factory-authorized service representative is required to inspect field-assembled components and equipment installation, comply with qualification requirements in Division 1 Section "Quality Requirements."

### 3.9 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.

### 3.10 CORRECTION OF THEWORK

- A. Repair or remove and replace defective construction. Restore damaged substrates and finishes. Comply with requirements in Division 1 Section "Cutting and Patching."
  - 1. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment.
- B. Restore permanent facilities used during construction to their specified condition.
- C. Remove and replace damaged surfaces that are exposed to view if surfaces cannot be repaired without visible evidence of repair.
- D. Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.
- E. Remove and replace chipped, scratched, and broken glass or reflective surfaces.

END OF SECTION 017300

## SECTION 017700 - CLOSEOUT PROCEDURES

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
1. Inspection procedures.
  2. Warranties.
  3. Instruction of Owner's personnel.
  4. Final cleaning.

#### 1.2 SUBSTANTIAL COMPLETION

- A. Preliminary Procedures: Before requesting inspection for determining date of Substantial Completion, complete the following. List items below that are incomplete in request.
1. Prepare a list of items to be completed and corrected (punch list), the value of items on the list, and reasons why the Work is not complete.
  2. Advise Owner of pending insurance changeover requirements.
  3. Submit specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
  4. Obtain and submit releases permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
  5. Deliver tools, spare parts, extra materials, and similar items to location designated by Owner. Label with manufacturer's name and model number where applicable.
  6. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
  7. Complete startup testing of systems.
  8. Submit test/adjust/balance records.
  9. Terminate and remove temporary facilities from Project site, construction tools, and similar elements.
  10. Advise Owner of changeover in heat and other utilities.
  11. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
  12. Complete final cleaning requirements, including touchup painting.
  13. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.

- B. Inspection: Submit a written request for inspection for Substantial Completion. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.
  - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
  - 2. Results of completed inspection will form the basis of requirements for Final Completion.

### 1.3 FINAL COMPLETION

- A. Preliminary Procedures: Before requesting final inspection for determining date of Final Completion, complete the following:
  - 1. Prepare and submit Project Record Documents, operation and maintenance manuals, Final Completion construction photographs and photographic negatives, damage or settlement surveys, property surveys, and similar final record information.
  - 2. Submit a final Application for Payment according to Division 1 Section "Payment Procedures."
  - 3. Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. The certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
  - 4. Submit evidence of final, continuing insurance coverage complying with insurance requirements.
  - 5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems. Submit demonstration and training videotapes.
- B. Inspection: Submit a written request for final inspection for acceptance. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
  - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

### 1.4 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Preparation: Submit three copies of list. Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
  - 1. Organize list of spaces in sequential order.
  - 2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.

3. Include the following information at the top of each page:
  - a. Project name.
  - b. Date.
  - c. Name of Architect.
  - d. Name of Contractor.
  - e. Page number.

#### 1.5 PROJECT RECORD DOCUMENTS

- A. General: Do not use Project Record Documents for construction purposes. Protect Project Record Documents from deterioration and loss. Provide access to Project Record Documents for Architect's reference during normal working hours.

#### 1.6 OPERATION AND MAINTENANCE MANUALS

- A. General: Assemble a complete set of operation and maintenance data indicating the operation and maintenance of each system, subsystem, and piece of equipment not part of a system. Include operation and maintenance data required in individual Specification Sections and as follows:

#### 1.7 WARRANTIES

- A. Submittal Time: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated.
- B. Partial Occupancy: Submit properly executed warranties within 15 days of completion of designated portions of the Work that are completed and occupied or used by Owner during construction period by separate agreement with Contractor.
- C. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.
  1. Bind warranties and bonds in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
  2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
  3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
- D. Provide additional copies of each warranty to include in operation and maintenance manuals.

## PART 2 - PRODUCTS

### 2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

## PART 3 - EXECUTION

### 3.1 DEMONSTRATION AND TRAINING

- A. Instruction: Instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
  - 1. Provide instructors experienced in operation and maintenance procedures.
  - 2. Provide instruction at mutually agreed-on times. For equipment that requires seasonal operation, provide similar instruction at the start of each season.
  - 3. Schedule training with Owner with at least seven days' advance notice.
  - 4. Coordinate instructors, including providing notification of dates, times, length of instruction, and course content.
- B. Program Structure: Develop an instruction program that includes individual training modules for each system and equipment not part of a system, as required by individual Specification Sections. For each training module, develop a learning objective and teaching outline. Include instruction for the following:
  - 1. System design and operational philosophy.
  - 2. Review of documentation.
  - 3. Operations.
  - 4. Adjustments.
  - 5. Troubleshooting.
  - 6. Maintenance.
  - 7. Repair.

### 3.2 FINAL CLEANING

- A. General: Provide final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
  - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a portion of Project:

- a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
  - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
  - c. Rake grounds that are neither planted nor paved to a smooth, eventextured surface.
  - d. Remove tools, construction equipment, machinery, and surplus material from Project site.
  - e. Remove snow and ice to provide safe access to building.
  - f. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
  - g. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
  - h. Sweep concrete floors broom clean in unoccupied spaces.
  - i. Vacuum carpet and similar soft surfaces, removing debris and excess nap; shampoo if visible soil or stains remain.
  - j. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, visionobscuring materials. Replace chipped or broken glass and other damaged transparent materials. Polish mirrors and glass, taking care not to scratch surfaces.
  - k. Remove labels that are not permanent.
  - l. Touch up and otherwise repair and restore marred, exposed finishes and surfaces. Replace finishes and surfaces that cannot be satisfactorily repaired or restored or that already show evidence of repair or restoration.
    - 1) Do not paint over "UL" and similar labels, including mechanical and electrical nameplates.
  - m. Wipe surfaces of mechanical and electrical equipment, elevator equipment, and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
  - n. Replace parts subject to unusual operating conditions.
  - o. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
  - p. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
  - q. Clean ducts, blowers, and coils if units were operated without filters during construction.
  - r. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency. Replace burned-out bulbs, and those noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.
  - s. Leave Project clean and ready for occupancy.
2. Comply with safety standards for cleaning. Do not burn waste materials. Do not bury debris or excess materials on Owner's property. Do not discharge volatile, harmful, or dangerous materials into drainage systems. Remove waste materials from Project site and dispose of lawfully.

END OF SECTION 017700



## SECTION 024119 - SELECTIVE DEMOLITION

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for removing selective portions of the building to accommodate new construction
  - 1. Remodeling construction work and patching are included within the respective sections of specifications, including removal of materials for reuse and incorporation into remodeling or new construction.

#### 1.2 MATERIALS OWNERSHIP

- A. Unless otherwise indicated, demolition waste becomes property of Contractor.
- B. Historic items, relics, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, antiques, and other items of interest or value to Owner that may be encountered during selective demolition remain Owner's property.
  - 1. Carefully salvage in a manner to prevent damage and deliver promptly return to Owner.

#### 1.3 SUBMITTALS

- A. Pre-demolition Conference: Conduct conference at Project site.
  - 1. Inspect and discuss condition of construction to be selectively demolished.
  - 2. Review structural load limitations of existing structure.
  - 3. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
  - 4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
  - 5. Review areas where existing construction is to remain and requires protection.
  - 6. Contractor to coordinate protection of envelope and finishes until final completion.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For refrigerant recovery technician.
- B. Proposed Protection Measures: Submit report, including drawings, that indicates the measures proposed for protecting individuals and property, for environmental protection, for dust control and, for noise control. Indicate proposed locations and construction of barriers. .

- C. Schedule of Selective Demolition Activities: Indicate the following:
1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's on-site operations are uninterrupted.
  2. Interruption of utility services. Indicate how long utility services will be interrupted.
  3. Coordination for shutoff, capping, and continuation of utility services.
  4. Use of stairs.
  5. Coordination of Owner's continuing occupancy of portions of existing building and of Owner's partial occupancy of completed Work.
- D. Inventory: Submit a list of items to be removed and salvaged and deliver to Owner prior to start of demolition. See salvage schedule of demolition plans.
- E. Pre-demolition Photographs or Video: Submit before Work begins.
1. Submit digital photographs in JPEG format of existing conditions of structure surfaces, equipment, and adjacent improvements that might be misconstrued as damage related to removal operations. File with Architect prior to start of work.
- F. This is in addition to the requirements for the pre-construction photos required.
- G. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician responsible for recovering refrigerant, stating that all refrigerant that was present is identified in pounds, the total amount of refrigerant which is recovered is identified in pounds, and that recovery was performed according to EPA regulations. Include name and address of technician and date refrigerant was recovered.

#### 1.5 QUALITY ASSURANCE

- A. Refrigerant Recovery Technician Qualifications: Certified by an EPA-approved certification program.
- B. Demolition Firm Qualifications: An experienced firm that has specialized in demolition work similar in material and extent to that indicated for this Project.
- C. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition, including but not limited to, the ten day notification. Comply with hauling and disposal regulations of authorities having jurisdiction.
- D. Standards: Comply with ANSI A10.6 and NFPA 241.
- E. Pre-demolition Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination."
- F. Pre-demolition Conference: Conduct conference at Project site to comply with requirements in Division 01 Section "Project Management and Coordination." Review methods and procedures related to selective demolition including, but not limited to, the following:
1. Inspect and discuss condition of construction to be selectively demolished.
  2. Review structural load limitations of existing structure.

3. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
5. Review areas where existing construction is to remain and requires protection.

#### 1.6 PROJECT CONDITIONS

- A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.
- B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
  1. Owner assumes no responsibility for actual condition of items or structures to be demolished.
- C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- D. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.
  1. If materials suspected of containing hazardous materials are encountered, do not disturb; immediately notify Architect and Owner. Owner will remove hazardous materials under a separate contract.
- E. Storage or sale of removed items or materials on-site is not permitted.
- F. Items indicated to be removed but of salvageable value to Contractor may be removed from structure as work progresses. Transport salvaged items from site as they are removed.
  1. Storage or sale of removed items or materials on-site is not permitted.
- G. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
  1. Do not interrupt utilities serving occupied facilities, except when authorized in writing by Owner. Provide temporary services during interruptions to existing utilities, as acceptable to Owner.
  2. Maintain fire-protection facilities in service during selective demolition operations.

#### 1.7 WARRANTY

- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties. Notify warrantor before proceeding.
  1. Use original installer to the greatest extent possible

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ANSI/ASSE A10.6 and NFPA 241.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped before starting selective demolition operations.
- B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
  - 1. Record existing conditions by use of preconstruction photographs. Comply with requirements specified in Division 01.
- C. Verify that hazardous materials and hazardous building components have been removed before proceeding with building demolition operations.
- D. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Architect.
- E. Engage a professional engineer to survey condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective demolition operations.
  - 1. Perform surveys as the Work progresses to detect hazards resulting from selective demolition activities.
- F. Survey of Existing Conditions: Record existing conditions by use of measured drawings, preconstruction photographs, preconstruction videotapes and templates.
  - 1. Inventory and record the condition of items to be removed and salvaged. Provide photographs or video of conditions that might be misconstrued as damage caused by salvage operations.
  - 2. Before selective demolition or removal of existing building elements that will be reproduced or duplicated in final Work, make permanent record of measurements, materials, and construction details required to make exact reproduction.
- G. Perform surveys as the Work progresses to detect hazards resulting from selective demolition activities.

### 3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage during selective demolition operations.
- B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off indicated utility services and mechanical/electrical systems serving areas to be selectively demolished.
  - 1. Owner will arrange to shut off indicated services/systems when requested by Contractor.
- C. Refrigerant: Remove refrigerant from mechanical equipment to be selectively demolished according to 40 CFR 82 and regulations of authorities having jurisdiction.

### 3.3 PREPARATION

- A. Temporary Facilities: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
  - 1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
  - 2. Erect temporary covered passageways as required by authorities having jurisdiction.
  - 3. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
  - 4. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
  - 5. Cover and protect furniture, furnishings, and equipment that have not been removed.
- B. Temporary Shoring: Provide and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.
  - 1. Strengthen or add new supports when required during progress of selective demolition.
  - 2. Cease operations and notify Architect immediately if safety of structure appears to be endangered. Take precautions to support structure until determination is made for continuing operations.

### 3.4 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
  - 1. Proceed with selective demolition systematically, from higher to lower level. Complete selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.

2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.
  3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
  4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain fire watch and portable fire-suppression devices during flame-cutting operations.
  5. Maintain adequate ventilation when using cutting torches.
  6. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
  7. Provide services for effective air and water pollution controls as required by local authorities having jurisdiction.
- B. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and reinstalled in their original locations after selective demolition operations are complete.
- C. If unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure both nature and extent of the conflict. Submit report to Architect in written, accurate detail. Pending receipt of directive from Architect, rearrange selective demolition schedule as necessary to continue overall job progress without undue delay.

### 3.5 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Except for items or materials indicated to be reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, remove demolished materials from Site and legally dispose in an EPA-approved landfill.
1. Do not allow demolished materials to accumulate on-site.
  2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
- B. Burning: Do not burn demolished materials.
- C. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

### 3.6 CLEANING

- A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 024119

SECTION 055213 - PIPE AND TUBE RAILINGS

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes the following:
  - 1. Aluminum pipe and tube railings.

1.2 SUBMITTALS

- A. Product Data: For the following:
  - 1. Manufacturer's product lines of mechanically connected railings.
  - 2. Railing brackets.
  - 3. Grout, anchoring cement, and paint products.
- B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.
- C. Samples: For each type of exposed finish required.
  - 1. Sections of each distinctly different linear railing member, including handrails, top rails, posts, and balusters.
  - 2. Fittings and brackets.
  - 3. Assembled Sample of railing system, made from full-size components, including top rail, post, handrail, and infill. Sample need not be full height.
    - a. Show method of connecting and finishing members at intersections.
- D. Delegated-Design Submittal: For railings, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
- E. Qualification Data: For firms and persons specified in the "Quality Assurance" Article to demonstrate their capabilities and experience. Include a list of completed projects with project name, addresses, names of architects and owners, and other information specified.

### 1.3 QUALITY ASSURANCE

- A. Contractor's Qualifications: Employ only experienced Contractors (Installers) skilled in the successful installation of the specified materials and assemblies on similar projects for not less than five (5) years.
- B. Manufacturer's Qualifications: Employ only manufacturers with not less than five (5) years of successful experience making the specified materials as a current catalog and regular production item.
- C. Welding Standards: Comply with applicable provisions of AWS D1.2 "Structural Welding Code-- Aluminum".
  - 1. Certify that each welder has satisfactorily passed AWS qualification tests for welding processes involved and, if pertinent, has undergone re-certification.
- D. Inserts and Anchorages: Furnish inserts and anchoring devices which must be set in concrete or built into masonry for installation of stair work. Provide setting drawings, templates, instructions, and directions for installation of anchorage devices. Coordinate delivery with other work to avoid delay.
  - 1. See Concrete and Masonry Sections of these Specifications for installation of inserts and anchorage devices.
- A. Shop Assembly: Pre-assemble items in shop to greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Clearly mark units for field welded re-assembly and coordinated installation. Bolted connections are no allowed, except to structure.
- B. Single Source Responsibility: Unless otherwise indicated, provide handrails through a single source and from one manufacturer for each indicated type of unit Specified.

### 1.4 DELIVERY, STORAGE, AND HANDLING

- A. General: Deliver, store and handle units in strict accordance with manufacturer's written recommendations.
- B. Shop Assembly: As much as possible, assemble handrail units in shop and ship to job site when construction schedule and conditions are ready for immediate installation.
  - 1. Handrails shall not be stored at the job site.

### 1.5 WARRANTY

- A. Warranty: Material and workmanship including finish.
  - 1. One (10) year warranty.



## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design railings, including attachment to building construction.
- B. Structural Performance: Railings, including attachment to building construction, shall withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated:
  - 1. Handrails and Top Rails of Guards:
    - a. Uniform load of 50 lbf/ ft. applied in any direction.
    - b. Concentrated load of 200 lbf applied in any direction.
    - c. Uniform and concentrated loads need not be assumed to act concurrently.
  - 2. Infill of Guards:
    - a. Concentrated load of 50 lbf applied horizontally on an area of 1 sq. ft.
    - b. Infill load and other loads need not be assumed to act concurrently.
- C. General: Handrails and railings shall conform with applicable requirements of the following:
  - 1. Accessibility Requirements Manual from the Florida Department of Community Affairs, Florida Board of Building Codes and Standards.
  - 2. NFPA 101, Life Safety Code.
  - 3. Florida Building Code.

### 2.2 METALS, GENERAL

- A. Brackets, Flanges, and Anchors: Cast or formed metal of same type of material and finish as supported rails unless otherwise indicated.
  - 1. Provide brackets of type indicated; provide type with concealed fasteners.

### 2.3 ALUMINUM

- A. Aluminum, General: Provide alloy and temper recommended by aluminum producer and finisher for type of use and finish indicated, and with not less than the strength and durability properties of alloy and temper designated below for each aluminum form required.
- B. Extruded Bars and Tubing: ASTM B 221, Alloy 6063-T5/T52.
- C. Extruded Structural Pipe and Round Tubing: ASTM B 429, Alloy 6063-T6.
- D. Drawn Seamless Tubing: ASTM B 210, Alloy 6063-T832.
- E. Plate and Sheet: ASTM B 209, Alloy 6061-T6.

- F. Die and Hand Forgings: ASTM B 247, Alloy 6061-T6.
- G. Castings: ASTM B 26, Alloy A356.0-T6.
- H. ASTM E98: Standard Test Method for Anchorage of Permanent Metal Railing Systems and Rails for Buildings.

#### 2.4 FASTENERS

- A. General: Provide zinc-coated fasteners for exterior use or where built into exterior walls. Select fasteners for the type, grade, and class required.
- B. Masonry Anchorage Devices: Expansion shields, FS FF--325.
- C. Toggle Bolts: Tumble-wing type, FS FF-B-588, type, class, and style as required.
- D. Concrete Anchor Bolts: Hexagon head "Kwik Bolt" by Hilti Fastening System, Tulsa, OK.
- E. Post-Installed Anchors: Torque-controlled expansion anchors or chemical anchors capable of sustaining, without failure, a load equal to 6 times the load imposed when installed in unit masonry and 4 times the load imposed when installed in concrete, as determined by testing according to ASTM E 488/E 488M, conducted by a qualified independent testing agency.
  - 1. Material for Interior Locations: Carbon-steel components zinc-plated to comply with ASTM B 633 or ASTM F 1941, Class Fe/Zn 5, unless otherwise indicated.
  - 2. Material for Exterior Locations and Where Stainless Steel Is Indicated: Alloy Group 1 stainless-steel bolts, ASTM F 593, and nuts, ASTM F 594.

#### 2.5 MISCELLANEOUS MATERIALS

- A. Welding Rods and Bare Electrodes: Select according to AWS specifications for metal alloy welded.
- B. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D 1187/D 1187M.
- C. Nonshrink, Nonmetallic Grout: Factory-packaged, nonstaining, noncorrosive, nongaseous grout complying with ASTM C 1107/C 1107M. Provide grout specifically recommended by manufacturer for interior and exterior applications.

#### 2.6 FABRICATION

- A. Assemble handrails in the shop and ship to the jobsite when construction conditions allow immediate installation. Do not store handrails at the jobsite.
- B. Cut, drill, and punch metals cleanly and accurately. Remove burrs and ease edges to a radius of approximately 1/32 inch unless otherwise indicated. Remove sharp or rough areas on exposed surfaces.
- C. Form work true to line and level with accurate angles and surfaces.

- D. Welded Connections: Cope components at connections to provide close fit, or use fittings designed for this purpose. Weld all around at connections, including at fittings.
  - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
  - 2. Obtain fusion without undercut or overlap.
  - 3. Remove flux immediately.
  - 4. At exposed connections, finish exposed surfaces smooth and blended so no roughness shows after finishing and welded surface matches contours of adjoining surfaces.
  - 5. Use of Bondo type fillers or putty is prohibited.
- E. Welded Connections for Aluminum Pipe: Fabricate railings to interconnect members with concealed internal welds that eliminate surface grinding, using manufacturer's standard system of sleeve and socket fittings.
- F. Form changes in direction by bending.
- G. For changes in direction made by bending, use jigs to produce uniform curvature for each repetitive configuration required. Maintain cross section of member throughout entire bend without buckling, twisting, cracking, or otherwise deforming exposed surfaces of components.
- H. Close exposed ends of railing members with prefabricated end fittings.
- I. Provide wall returns at ends of wall-mounted handrails unless otherwise indicated.
- J. Brackets, Flanges, Fittings, and Anchors: Provide wall brackets, flanges, miscellaneous fittings, and anchors to interconnect railing members to other work unless otherwise indicated.
  - 1. At brackets and fittings fastened to plaster or gypsum board partitions, provide crush-resistant fillers or other means to transfer loads through wall finishes to structural supports and prevent bracket or fitting rotation and crushing of substrate.

## 2.7 ALUMINUM FINISHES

- A. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are unacceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.
- B. Clear Anodic Finish: AAMA 611, AA-M12C22A41.

## PART 3 - EXECUTION

### 3.1 INSTALLATION, GENERAL

- A. Secure handrails to wall with wall brackets and end fittings. Provide bracket with not less than 1-1/2-inch clearance from inside face of handrail and finished wall surface. Locate brackets as

indicated or, if not indicated, at spacing required for design loading. Secure wall brackets and wall return fittings to building construction as follows:

1. Use type of bracket with predrilled hole for exposed bolt anchorage.
  2. For concrete and solid masonry anchorage, use drilled-in expansion shield and either concealed hanger bolt or exposed lag bolt, as applicable.
  3. For hollow masonry anchorage, use toggle bolts having square heads.
- B. Set railings accurately in location, alignment, and elevation; measured from established lines and levels and free of rack.
1. Do not weld, cut, or abrade surfaces of railing components that are coated or finished after fabrication and that are intended for field connection by mechanical or other means without further cutting or fitting.
  2. Set posts plumb within a tolerance of 1/16 inch in 3 feet.
  3. Align rails so variations from level for horizontal members and variations from parallel with rake of steps and ramps for sloping members do not exceed 1/4 inch in 12 feet.
- C. Control of Corrosion: Prevent galvanic action and other forms of corrosion by insulating metals and other materials from direct contact with incompatible materials.
1. Coat, with a heavy coat of bituminous paint, concealed surfaces of aluminum that are in contact with grout, concrete, masonry, wood, or dissimilar metals.

### 3.2 ANCHORING POSTS

- A. Use cast aluminum pipe sleeves preset and anchored into concrete for installing exterior railing. After posts are inserted into sleeves, fill annular space between post and sleeve with nonshrink, nonmetallic grout or anchoring cement, mixed and placed to comply with anchoring material manufacturer's written instructions.

### 3.3 ATTACHING RAILINGS

- A. Attach railings to wall with wall brackets and concealed fasteners. Locate brackets as indicated or, if not indicated, at spacing required to support structural loads.
- B. Secure wall brackets and railing end flanges to building construction as indicated.

### 3.4 PROTECTION AND CLEANING

- A. Protect finishes of railings from damage during construction with manufacture's protective covering.
- B. Clean aluminum surfaces in accordance with manufacturer's instructions and recommendations. Remove dirt, grime, and other contaminates completely.

END OF SECTION 055213

SECTION 062023 - INTERIOR FINISH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
1. Interior wood wall caps.

1.2 SUBMITTALS

- A. Shop Drawings: Show location of each item, dimensioned plans and elevations.
- B. Samples:
1. Shop-applied transparent finishes.

1.3 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install interior finish carpentry materials until building is enclosed and weatherproof, wet work in space is completed and nominally dry, and HVAC system is operating and maintaining temperature and relative humidity at occupancy levels during the remainder of the construction period.

PART 2 - PRODUCTS

2.1 INTERIOR TRIM

- A. Hardwood Lumber Trim for Transparent Finish (Stain or Clear Finish):
1. Species and Grade: White maple.
  2. Maximum Moisture Content: 9 percent.
  3. Finger Jointing: Not allowed.
  4. Gluing for Width: Not allowed.
  5. Face Surface: Surfaced (smooth).
  6. Matching: Selected for compatible grain and color.

2.2 MISCELLANEOUS MATERIALS

- A. Fasteners for Interior Finish Carpentry: Nails, screws, and other anchoring devices of type, size, material, and finish required for application indicated to provide secure attachment, concealed where possible.

- B. Glue: Aliphatic-resin, polyurethane, or resorcinol wood glue recommended by manufacturer for general carpentry use.
- C. Multipurpose Construction Adhesive: Formulation complying with ASTM D 3498 that is recommended for indicated use by adhesive manufacturer.

### 2.3 FABRICATION

- A. Ease edges of lumber less than 1 inch in nominal thickness to 1/16-inch radius and edges of lumber 1 inch or more in nominal thickness to 1/8-inch radius.

### 2.4 SHOP FINISHING

- A. General: Finish wood stair treads at fabrication shop as specified in this Section. Defer only final touchup, cleaning, and polishing until after installation.
- B. Preparation for Finishing: Comply with referenced quality standard for sanding, filling countersunk fasteners, sealing concealed surfaces, and similar preparations for finishing architectural woodwork, as applicable to each unit of work.
  - 1. Backpriming: Apply one coat of sealer or primer, compatible with finish coats, to concealed surfaces of woodwork.
- C. Transparent Finish:
  - 1. Grade: Premium.
  - 2. Finish: water-based polyurethane.
  - 3. Staining: Match Architect's sample.
  - 4. Sheen: Match Architect's sample.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine finish carpentry materials before installation. Reject materials that are wet, moisture damaged, and mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Clean substrates of projections and substances detrimental to application.
- B. Before installation, condition wood to average prevailing humidity conditions in installation areas.

3.3 INSTALLATION, GENERAL

- A. Do not use materials that are unsound; warped; improperly treated or finished; inadequately seasoned; too small to fabricate with proper jointing arrangements; or with defective surfaces, sizes, or patterns.
- B. Install interior finish carpentry level, plumb, true, and aligned with adjacent materials. Use concealed shims where necessary for alignment.

3.4 ADJUSTING

- A. Replace interior finish carpentry that is damaged or does not comply with requirements. Interior finish carpentry may be repaired or refinished if work complies with requirements and shows no evidence of repair or refinishing. Adjust joinery for uniform appearance.

3.5 CLEANING

- A. Clean interior finish carpentry on exposed and semiexposed surfaces. Restore damaged or soiled areas and touch up factory-applied finishes if any.

3.6 PROTECTION

- A. Protect installed products from damage from weather and other causes during construction.

END OF SECTION 062023

## SECTION 064116 - PLASTIC-LAMINATE-FACED ARCHITECTURAL CABINETS

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Section Includes:

1. Plastic-laminate-faced architectural cabinets.
1. Wood furring, blocking, shims, and hanging strips for installing plastic-laminate faced architectural counter unless concealed within other construction before installation.

#### 1.2 SUBMITTALS

A. Product Data: For each type of product, including high-pressure decorative laminate and cabinet hardware and accessories.

B. Shop Drawings: Show location of each item, dimensioned plans and elevations, large-scale details, attachment devices, and other components.

1. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement specified in other Sections.
2. Show locations and sizes of cutouts and holes for electrical switches and outlets and other items installed in architectural plastic-laminate cabinets.

C. Samples for Verification:

1. Plastic laminates, 8 by 10 inches, for each color, pattern, and surface finish, with one sample applied to core material.
2. PVC edge material

#### 1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

#### 1.4 QUALITY ASSURANCE

A. Fabricator Qualifications: Shop that employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful in-service performance. Shop is a certified participant in AWI's Quality Certification Program.



1.5 DELIVERY, STORAGE, AND HANDLING

- A. Do not deliver casework until painting and similar operations that could damage woodwork have been completed in installation areas. If cabinets must be stored in other than installation areas, store only in areas where environmental conditions comply with requirements specified in Field Conditions Article.

1.6 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install cabinets until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature and relative humidity at occupancy levels during the remainder of the construction period.
- B. Field Measurements: Where cabinets are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
  - 1. Locate concealed framing, blocking, and reinforcements that support cabinets by field measurements before being enclosed, and indicate measurements on Shop Drawings.
- C. Established Dimensions: Where cabinets are indicated to fit to other construction, establish dimensions for areas where cabinets are to fit. Provide allowance for trimming at site, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

1.7 COORDINATION

- A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to ensure that cabinets can be supported and installed as indicated.

PART 2 - PRODUCTS

2.1 PLASTIC-LAMINATE-FACED ARCHITECTURAL CABINETS

- A. Quality Standard: Unless otherwise indicated, comply with the "Architectural Woodwork Standards" for grades of architectural plastic-laminate cabinets indicated for construction, finishes, installation, and other requirements.
- B. Grade: Custom.
- C. Type of Construction: As Indicated.
- D. Counter Style: As Indicated.
- E. Cabinet, Door, and Drawer Front Interface Style: As indicated.

- F. High-Pressure Decorative Laminate: NEMA LD 3, grades as indicated or if not indicated, as required by woodwork quality standard.
  - 1. Colors, Patterns, and Finishes: As indicated on the in the finsh lsits, Or Equal.
- G. Laminate Cladding for Exposed Surfaces:
  - 1. Horizontal Surfaces: Grade HGS.
  - 2. Vertical Surfaces: Grade VGS.
  - 3. Edges: Grade HGS.
- H. Materials for Semiexposed Surfaces:
  - 1. Surfaces Other Than Drawer Bodies: High-pressure decorative laminate, NEMA LD 3, Grade CLS.
    - a. For semiexposed backs of panels with exposed plastic-laminate surfaces, provide surface of high-pressure decorative laminate, NEMA LD 3, Grade CLS.
  - 2. Sides and Backs: White Birch or White Maple plywood; not less than 3/8-inch thick; clear finish.
  - 3. Bottoms: White Birch or White Maple plywood; not less than 1/4-inch thick; clear finish.
- I. Concealed Backs of Panels with Exposed Plastic-Laminate Surfaces: High-pressure decorative laminate, NEMA LD 3, Grade BKL.
- J. Drawer Construction: Fabricate with exposed fronts fastened to subfront with mounting screws from interior of body.
  - 1. Drawer Sides and Backs: Refer to Millwork Notes on the Drawings.
  - 2. Drawer Bottoms: White Birch or White Maple plywood; not less than 1/4-inch thick.
- K. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed laminate surfaces complying with the following requirements:
  - 1. Match Existing – As indicated on Drawings

## 2.2 WOOD MATERIALS

- A. Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of woodwork and quality grade specified unless otherwise indicated.
  - 1. Medium-Density Fiberboard: ANSI A208.2, made with binder containing no urea formaldehyde.
  - 2. Plywood: APA Grade A-C; HPVA HP-1, made with adhesive containing no urea formaldehyde.
    - a. Thickness: 3/4-inch unless otherwise indicated.

### 2.3 CABINET HARDWARE AND ACCESSORIES

- A. General: Provide cabinet hardware and accessory materials associated with architectural cabinets.
- B. Hinges:
  - 1. Product and Manufacturer – Basis of Design: A-Series hinge, 110-degree swing; Hafele America Co., or Equal.
- C. Pulls: Steel Bar Pulls, Match Architects sample.
- D. Adjustable Shelf Supports/ Shelf Rests: plastic two-pin type with shelf hold-down clip.
  - 1. Product and Manufacturer – Basis of Design: Item No. 282.47.402 Shelf Support, Double Pin, transparent plastic; Hafele America, Archdale, NC, or Equal.
- E. Drawer Slides:
  - 1. Product and Manufacturer – Basis of Design: Series 3832 AA Action Assist, full extension drawer slide; 100 pound rating; Accuride International, or Equal.
- F. Door and Drawer Silencers: BHMA A156.16, L03011.
  - 1. Color: To be selected from manufacturer's standard color selections.
- G. PVC Edge Banding: Polyethylene molding strip for counter edges; PVC edge banding for all counter doors, and drawers.
  - 1. Products and Manufacturer: Subject to compliance with requirements, available products and manufacturers that may be incorporated into the Work include, but are not limited to, the following:
    - a. 3M and Charter Industries, Grand Rapids, MI, or Equal.
      - 1) Colors: To be selected by the Architect.
      - 2) Thickness: 3mm.
      - 3) Width: Full width of edge.

### 2.4 MISCELLANEOUS MATERIALS

- A. Furring, Blocking, Shims, and Hanging Strips: Softwood or hardwood lumber, kiln dried to less than 15 percent moisture content.
- B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide metal expansion sleeves or expansion bolts for post-installed anchors. Use nonferrous-metal or hot-dip galvanized anchors and inserts at inside face of exterior walls and at floors.
- C. Adhesives: Do not use adhesives that contain urea formaldehyde.

## 2.5 FABRICATION

- A. General: Fabricate cabinets and shelves to dimensions, profiles, and details indicated.
  - 1. Complete fabrication, including assembly and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.
  - 2. Shop-cut openings to maximum extent possible to receive hardware, appliances, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.
- B. Countertops: Provide plastic-laminate backer sheet, Grade BKL, on underside of countertop substrates.
- C. Shelves: 3/4-inch plywood core with high pressure laminate all sides and edges.

## PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Before installation, condition cabinets to average prevailing humidity conditions in installation areas.
- B. Before installing cabinets, examine shop-fabricated work for completion and complete work as required.

### 3.2 INSTALLATION

- A. Assemble cabinets and complete fabrication at Project site to the extent that it was not completed in the shop.
- B. Install cabinets level, plumb, true, and straight. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches.
- C. Scribe and cut cabinets to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.
- D. Anchor cabinets to anchors or blocking built in or directly attached to substrates. Secure with countersunk, concealed fasteners and blind nailing. Use fine finishing nails or finishing screws for exposed fastening, countersunk and filled flush with woodwork.
  - 1. Use filler matching finish of items being installed.

- E. Cabinets: Install without distortion so doors and drawers fit openings properly and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.
  - 1. Install cabinets with no more than 1/8 inch in 96-inch sag, bow, or other variation from a straight line.

### 3.3 ADJUSTING AND CLEANING

- A. Repair damaged and defective cabinets, where possible, to eliminate functional and visual defects; where not possible to repair, replace woodwork. Adjust joinery for uniform appearance.
- B. Clean, lubricate, and adjust hardware.
- C. Clean cabinets on exposed and semiexposed surfaces.

END OF SECTION 064116

## SECTION 072100 - BUILDING INSULATION

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section Includes:
1. Sound attenuation blanket insulation.

#### 1.2 SUBMITTALS

- A. Product Data: Each type of insulation product specified.
- B. Product Test Reports: From and based on tests performed by a qualified independent testing agency evidencing compliance of insulation products with specified requirements, based on comprehensive testing of current products.

#### 1.3 QUALITY ASSURANCE

- A. Fire-Test-Response Characteristics: Provide insulation and related materials with the fire-test-response characteristics indicated on Drawings or specified elsewhere in this Section as determined by testing identical products per test method indicated below by UL or another testing and inspecting agency acceptable to authorities having jurisdiction. Identify materials with appropriate markings of applicable testing and inspecting agency.
1. Surface-Burning Characteristics: ASTM E 84.
  2. Fire-Resistance Ratings: ASTM E 119.
  3. Combustion Characteristics: ASTM E 136.

#### 1.4 DELIVERY, STORAGE, AND HANDLING

- A. Protect insulation materials from physical damage and from deterioration by moisture, soiling, and other sources. Store inside and in a dry location. Comply with manufacturer's written instructions for handling, storing, and protecting during installation.

### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Insulation shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

- B. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Sound Attenuation Blanket Insulation:
  - a. CertainTeed Corporation.
  - b. Knauf Fiber Glass GmbH.
  - c. Owens-Corning Fiberglas Corporation.
  - d. Schuller International, Inc.

## 2.2 INSULATING MATERIALS

- A. General: Provide insulating materials that comply with requirements and with referenced standards.

1. Preformed Units: Sizes to fit applications indicated; selected from manufacturer's standard thickness, widths, and lengths.

## 2.3 SOUND ATTENUATION BLANKET INSULATION

- A. Sound Attenuation Blanket Insulation: ASTM C 665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.

1. Thickness: To match cavity space indicated; provide single thickness blanket.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and conditions, to determine if conditions affecting performance of insulation are satisfactory. Do not proceed with installation until unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION, GENERAL

- A. Comply with insulation manufacturer's written instructions applicable to products and application indicated.
- B. Install insulation that is undamaged, dry, and unsoiled
- C. Extend insulation in thickness indicated to envelop entire area to be insulated. Cut and fit tightly around obstructions and fill voids with insulation. Remove projections that interfere with placement.
- D. Apply single layer of insulation to produce thickness indicated, unless multiple layers are otherwise shown or required to make up total thickness.

### 3.3 INSTALLATION OF INSULATION

- A. Apply insulation units to substrates, complying with manufacturer's written instructions.
- B. Install insulation in cavities formed by framing members according to the following requirements:
  - 1. Use insulation widths and lengths that fill the cavities formed by framing members. If more than one length is required to fill cavity, provide lengths that will produce a snug fit between ends.
  - 2. Place insulation in cavities formed by framing members to produce a friction fit between edges of insulation and adjoining framing members.
  - 3. Do not force or compact insulation into stud cavity.

### 3.4 PROTECTION

- A. General: Protect installed insulation from damage due to harmful weather exposures, physical abuse, and other causes. Provide temporary coverings or enclosures where insulation is subject to abuse and cannot be concealed and protected by permanent construction immediately after installation.

END OF SECTION 072100



## SECTION 078413 - PENETRATION FIRESTOPPING

### PART 1 - GENERAL

#### 1.1 SUMMARY

##### A. Section Includes:

1. Through-penetration firestop systems for penetrations through the following fire-resistance-rated assemblies, including both empty openings and openings containing penetrating items:
  - a. Walls and partitions.
  - b. Floors and ceilings.
  - c. Smoke barriers.

#### 1.2 PERFORMANCE REQUIREMENTS

- A. General: For the following constructions, provide through-penetration firestop systems that are produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of assembly penetrated.
  1. Fire-resistance-rated load-bearing walls, including partitions, with fire-protection-rated openings.
  2. Fire-resistance-rated non-load-bearing walls, including partitions, with fire-protection-rated openings.
- B. F-Rated Systems: Provide through-penetration firestop systems with F-ratings indicated, as determined per ASTM E 814, but not less than that equaling or exceeding fire-resistance rating of constructions penetrated.
- C. For through-penetration firestop systems exposed to view, traffic, moisture, and physical damage, provide products that after curing do not deteriorate when exposed to these conditions both during and after construction.
  1. For piping penetrations for plumbing and wet-pipe sprinkler systems, provide moisture-resistant through-penetration firestop systems.
  2. For penetrations involving insulated piping, provide through-penetration firestop systems not requiring removal of insulation.
- D. For through-penetration firestop systems exposed to view, provide products with flame-spread ratings of less than 25 and smoke-developed ratings of less than 450, as determined per  
ASTM E 84.

### 1.3 SUBMITTALS

- A. Product Data: For each type of through-penetration firestop system product indicated.
- B. Shop Drawings: For each through-penetration firestop system, show each kind of construction condition penetrated, relationships to adjoining construction, and kind of penetrating item. Include firestop design designation of testing and inspecting agency acceptable to authorities having jurisdiction that evidences compliance with requirements for each condition indicated.
  - 1. Submit documentation, including illustrations, from a qualified testing and inspecting agency that is applicable to each through-penetration firestop system configuration for construction and penetrating items.
  - 2. Where Project conditions require modification of qualified testing and inspecting agency's illustration to suit a particular through-penetration firestop condition, submit illustration, with modifications marked, approved by through-penetration firestop system manufacturer's fire-protection engineer.
- C. Qualification Data: For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and Owners, and other information specified.
- D. Product Certificates: Signed by manufacturers of through-penetration firestop system products certifying that products furnished comply with requirements.
- E. Product Test Reports: From a qualified testing agency indicating through-penetration firestop system complies with requirements, based on comprehensive testing of current products.

### 1.4 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who has completed through-penetration firestop systems similar in material, design, and extent to that indicated for this Project and whose work has resulted in construction with a record of successful in-service performance.
- B. Installer Qualifications: An experienced installer who is qualified by having the necessary experience, staff, and training to install manufacturer's products per specified requirements. A manufacturer's willingness to sell its through-penetration firestop system products to Contractor or to an installer engaged by Contractor does not in itself confer qualification on buyer.
- C. Source Limitations: Obtain through-penetration firestop systems, for each kind of penetration and construction condition indicated, from a single manufacturer.

- D. Fire-Test-Response Characteristics: Provide through-penetration firestop systems that comply with the following requirements and those specified in "Performance Requirements" Article:
1. Firestopping tests are performed by a qualified testing and inspecting agency. A qualified testing and inspecting agency is UL or another agency performing testing and follow-up inspection services for firestop systems acceptable to authorities having jurisdiction.
  2. Through-penetration firestop systems are identical to those tested per ASTM E 814. Provide rated systems complying with the following requirements:
    - a. Through-penetration firestop system products bear classification marking of qualified testing and inspecting agency.
    - b. Through-penetration firestop systems correspond to those indicated by reference to through-penetration firestop system designations listed by the following:
      - 1) UL in "Fire Resistance Directory."
- E. Preinstallation Conference: Conduct conference at Project site.

#### 1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver through-penetration firestop system products to Project site in original, unopened containers or packages with intact and legible manufacturers' labels identifying product and manufacturer; date of manufacture; lot number; shelf life, if applicable; qualified testing and inspecting agency's classification marking applicable to Project; curing time; and mixing instructions for multicomponent materials.
- B. Store and handle materials for through-penetration firestop systems to prevent their deterioration or damage due to moisture, temperature changes, contaminants, or other causes.

#### 1.6 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install through-penetration firestop systems when ambient or substrate temperatures are outside limits permitted by through-penetration firestop system manufacturers or when substrates are wet due to rain, frost, condensation, or other causes.
- B. Ventilate through-penetration firestop systems per manufacturer's written instructions by natural means or, where this is inadequate, forced-air circulation.

#### 1.7 COORDINATION

- A. Coordinate construction of openings and penetrating items to ensure that through-penetration firestop systems are installed according to specified requirements.
- B. Coordinate sizing of sleeves, openings, core-drilled holes, or cut openings to accommodate through-penetration firestop systems.
- C. Notify Owner's inspecting agency at least seven days in advance of through-penetration firestop system installations; confirm dates and times on days preceding each series of installations.

- D. Do not cover up through-penetration firestop system installations that will become concealed behind other construction until Owner's inspecting agency and building inspector, if required by authorities having jurisdiction, have examined each installation.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Hilti, Inc.
  - 2. 3M Fire Protection Products
  - 3. Tremco, Inc.

### 2.2 FIRESTOPPING, GENERAL

- A. Compatibility: Provide through-penetration firestop systems that are compatible with one another, with the substrates forming openings, and with the items, if any, penetrating through-penetration firestop systems, under conditions of service and application, as demonstrated by through-penetration firestop system manufacturer based on testing and field experience.
- B. Exposed Penetration Firestopping Systems: Flame-spread and smoke-developed indexes of less than 25 and 450, respectively, per ASTM E 84.
- C. Accessories: Provide components for each through-penetration firestop system that are needed to install fill materials and to comply with "Performance Requirements" Article. Use only components specified by through-penetration firestop system manufacturer and approved by the qualified testing and inspecting agency for firestop systems indicated. Accessories include, but are not limited to, the following items:
  - 1. Permanent forming/damming/backing materials, including the following:
    - a. Slag-/rock-wool-fiber insulation.
    - b. Sealants used in combination with other forming/damming/backing materials to prevent leakage of fill materials in liquid state.
    - c. Fire-rated form board.
    - d. Fillers for sealants.
  - 2. Temporary forming materials.
  - 3. Substrate primers.
  - 4. Collars.
  - 5. Steel sleeves.

### 2.3 FILL MATERIALS

- A. General: Provide through-penetration firestop systems containing the types of fill materials indicated by reference to the types of materials described in this Article. Fill materials are those

referred to in directories of the referenced testing and inspecting agencies as fill, void, or cavity materials.

- B. Latex Sealants: Single-component latex formulations that after cure do not re-emulsify during exposure to moisture.
- C. Firestop Devices: Factory-assembled collars formed from galvanized steel and lined with intumescent material sized to fit specific diameter of penetrant.
- D. Intumescent Composite Sheets: Rigid panels consisting of aluminum-foil-faced elastomeric sheet bonded to galvanized steel sheet.
- E. Intumescent Putties: Nonhardening dielectric, water-resistant putties containing no solvents, inorganic fibers, or silicone compounds.
- F. Intumescent Wrap Strips: Single-component intumescent elastomeric sheets with aluminum foil on one side.
- G. Mortars: Prepackaged, dry mixes consisting of a blend of inorganic binders, hydraulic cement, fillers, and lightweight aggregate formulated for mixing with water at Project site to form a nonshrinking, homogeneous mortar.
- H. Pillows/Bags: Reusable, heat-expanding pillows/bags consisting of glass-fiber cloth cases filled with a combination of mineral-fiber, water-insoluble expansion agents and fire-retardant additives.
- I. Silicone Foams: Multicomponent, silicone-based liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.
- J. Silicone Sealants: Moisture-curing, single-component, silicone-based, neutral-curing elastomeric sealants of grade indicated below:
  - 1. Grade: Pourable (self-leveling) formulation for openings in horizontal surfaces and nonsag formulation for openings in vertical and other surfaces requiring a nonslumping, gunnable sealant, unless indicated firestop system limits use to nonsag grade for both opening conditions.
  - 2. Grade for Horizontal Surfaces: Pourable (self-leveling) formulation for openings in other horizontal surfaces.
  - 3. Grade for Vertical Surfaces: Nonsag formulation for openings in vertical and other surfaces.

## 2.4 MIXING

- A. For those products requiring mixing before application, comply with through-penetration firestop system manufacturer's written instructions for accurate proportioning of materials, water (if required), type of mixing equipment, selection of mixer speeds, mixing containers, mixing time, and other items or procedures needed to produce products of uniform quality with optimum performance characteristics for application indicated.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for opening configurations, penetrating items, substrates, and other conditions affecting performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 PREPARATION

- A. Surface Cleaning: Clean out openings immediately before installing through-penetration firestop systems to comply with written recommendations of firestop system manufacturer and the following requirements:
  - 1. Remove from surfaces of opening substrates and from penetrating items foreign materials that could interfere with adhesion of through-penetration firestop systems.
  - 2. Clean opening substrates and penetrating items to produce clean, sound surfaces capable of developing optimum bond with through-penetration firestop systems. Remove loose particles remaining from cleaning operation.
  - 3. Remove laitance and form-release agents from concrete.
- B. Priming: Prime substrates where recommended in writing by through-penetration firestop system manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.
- C. Masking Tape: Use masking tape to prevent through-penetration firestop systems from contacting adjoining surfaces that will remain exposed on completion of Work and that would otherwise be permanently stained or damaged by such contact or by cleaning methods used to remove smears from firestop system materials. Remove tape as soon as possible without disturbing firestop system's seal with substrates.

#### 3.3 THROUGH-PENETRATION FIRESTOP SYSTEM INSTALLATION

- A. General: Install through-penetration firestop systems to comply with "Performance Requirements" Article and firestop system manufacturer's written installation instructions and published drawings for products and applications indicated.
- B. Install forming/damming/backing materials and other accessories of types required to support fill materials during their application and in the position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.
  - 1. After installing fill materials, remove combustible forming materials and other accessories not indicated as permanent components of firestop systems.

- C. Install fill materials for firestop systems by proven techniques to produce the following results:
1. Fill voids and cavities formed by openings, forming materials, accessories, and penetrating items as required to achieve fire-resistance ratings indicated.
  2. Apply materials so they contact and adhere to substrates formed by openings and penetrating items.
  3. For fill materials that will remain exposed after completing Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

### 3.4 FIELD QUALITY CONTROL

- A. Proceed with enclosing through-penetration firestop systems with other construction only after inspection reports are issued.
- B. Where deficiencies are found, repair or replace through-penetration firestop systems so they comply with requirements.

### 3.5 IDENTIFICATION

- A. Identify through-penetration firestop systems with pressure-sensitive, self-adhesive, preprinted vinyl labels. Attach labels permanently to surfaces of penetrated construction on both sides of each firestop system installation where labels will be visible to anyone seeking to remove penetrating items or firestop systems. Include the following information on labels:
1. The words: "Warning--Through-Penetration Firestop System--Do Not Disturb. Notify Building Management of Any Damage."
  2. Contractor's name, address, and phone number.
  3. Through-penetration firestop system designation of applicable testing and inspecting agency.
  4. Date of installation.
  5. Through-penetration firestop system manufacturer's name.
  6. Installer's name.

### 3.6 CLEANING AND PROTECTION

- A. Clean off excess fill materials adjacent to openings as Work progresses by methods and with cleaning materials that are approved in writing by through-penetration firestop system manufacturers and that do not damage materials in which openings occur.
- B. Provide final protection and maintain conditions during and after installation that ensure through-penetration firestop systems are without damage or deterioration at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated through-penetration firestop systems immediately and install new materials to produce through-penetration firestop systems complying with specified requirements.

END OF SECTION 078413

SECTION 081213 - HOLLOW METAL FRAMES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes hollow-metal frames.

1.2 DEFINITIONS

- A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or SDI A250.8.

1.3 COORDINATION

- A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.

1.4 SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, fire-resistance ratings, and finishes.
- B. Shop Drawings: Include the following:
  - 1. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
  - 2. Locations of reinforcement and preparations for hardware.
  - 3. Details of each different wall opening condition.
  - 4. Details of anchorages, joints, field splices, and connections.
  - 5. Details of moldings, removable stops, and glazing.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver hollow-metal work palletized, packaged, or crated to provide protection during transit and Project-site storage. Do not use nonvented plastic.
  - 1. Provide additional protection to prevent damage to factory-finished units.
- B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.
- C. Store hollow-metal work vertically under cover at Project site with head up. Place on minimum 4-inch-high wood blocking. Provide minimum 1/4-inch space between each unit to permit air circulation.



## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
1. Amweld International, LLC.
  2. Ceco Door; ASSA ABLOY.
  3. Curries Company; ASSA ABLOY.
  4. Republic Doors and Frames.
  5. Steelcraft; an Allegion brand.
- B. Source Limitations: Obtain hollow-metal work from single source from single manufacturer.

### 2.2 REGULATORY REQUIREMENTS

- A. Fire-Rated Assemblies: Complying with NFPA 80 and listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction for fire-protection ratings indicated, based on testing at positive pressure according to NFPA 252 or UL 10C.

### 2.3 INTERIOR FRAMES

- A. Construct interior frames to comply with the standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.
- B. Heavy-Duty Frames: SDI A250.8, Level 2.
1. Physical Performance: Level B according to SDI A250.4.
  2. Materials: Uncoated steel sheet, minimum thickness of 0.053 inch.
  3. Frames: Fabricated from same thickness material as adjacent door frame.
  4. Construction: Knocked down or slip on frames.
  5. Exposed Finish: Factory.

### 2.4 FRAME ANCHORS

- A. Jamb Anchors:
1. Stud-Wall Type: Designed to engage stud, welded to back of frames; not less than 0.042 inch thick.
- B. Floor Anchors: Formed from same material as frames, minimum thickness of 0.042 inch, and as follows:
1. Monolithic Concrete Slabs: Clip-type anchors, with two holes to receive fasteners.

## 2.5 MATERIALS

- A. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B; suitable for exposed applications.
- B. Hot-Rolled Steel Sheet: ASTM A 1011/A 1011M, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.
- C. Frame Anchors: ASTM A 879/A 879M, Commercial Steel (CS), 04Z coating designation; mill phosphatized.
- D. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A 153/A 153M.
- E. Bituminous Coating: Cold-applied asphalt mastic, compounded for 15-mil dry film thickness per coat. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.

## 2.6 FABRICATION

- A. Fabricate hollow-metal work to be rigid and free of defects, warp, or buckle. Accurately form metal to required sizes and profiles, with minimum radius for metal thickness. Where practical, fit and assemble units in manufacturer's plant. To ensure proper assembly at Project site, clearly identify work that cannot be permanently factory assembled before shipment.
- B. Hollow-Metal Frames: Where frames are fabricated in sections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of same thickness metal as frames.
  - 1. Frames: Provide closed tubular members with no visible face seams or joints, fabricated from same material as door frame. Fasten members at crossings and to jambs by butt welding.
  - 2. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
  - 3. Floor Anchors: Weld anchors to bottoms of jambs with at least four spot welds per anchor; however, for slip-on drywall frames, provide anchor clips or countersunk holes at bottoms of jambs.
  - 4. Jamb Anchors: Provide number and spacing of anchors as follows:
    - a. Stud-Wall Type: Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:
      - 1) Three anchors per jamb up to 60 inches high.
      - 2) Four anchors per jamb from 60 to 90 inches high.
      - 3) Five anchors per jamb from 90 to 96 inches high.
  - 5. Head Anchors: Two anchors per head for frames more than 42 inches wide and mounted in metal-stud partitions.
  - 6. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers as follows. Keep holes clear during construction.
    - a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
    - b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.

- C. Hardware Preparation: Factory prepare hollow-metal work to receive templated mortised hardware; include cutouts, reinforcement, mortising, drilling, and tapping according to SDI A250.6, the Door Hardware Schedule, and templates.
  - 1. Reinforce frames to receive nontemplated, mortised, and surface-mounted hardware.
  - 2. Comply with applicable requirements in SDI A250.6 and BHMA A156.115 for preparation of hollow-metal work for hardware.

## 2.7 STEEL FINISHES

- A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.
  - 1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Drill and tap frames to receive nontemplated, mortised, and surface-mounted hardware.

### 3.3 INSTALLATION

- A. General: Install hollow-metal work plumb, rigid, properly aligned, and securely fastened in place. Comply with Drawings and manufacturer's written instructions.
- B. Hollow-Metal Frames: Install hollow-metal frames for doors, transoms, sidelites, borrowed lites, and other openings, of size and profile indicated. Comply with SDI A250.11 or NAAMM-HMMA 840 as required by standards specified.
  - 1. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces, leaving surfaces smooth and undamaged.
    - a. At fire-rated openings, install frames according to NFPA 80.

- b. Where frames are fabricated in sections because of shipping or handling limitations, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces.
    - c. Remove temporary braces necessary for installation only after frames have been properly set and secured.
    - d. Check plumb, square, and twist of frames as walls are constructed. Shim as necessary to comply with installation tolerances.
  2. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor, and secure with postinstalled expansion anchors.
    - a. Floor anchors may be set with power-actuated fasteners instead of postinstalled expansion anchors if so indicated and approved on Shop Drawings.
  3. Metal-Stud Partitions: Solidly pack mineral-fiber insulation inside frames.
  4. In-Place Metal or Wood-Stud Partitions: Secure slip-on drywall frames in place according to manufacturer's written instructions.
  5. Installation Tolerances: Adjust hollow-metal door frames for squareness, alignment, twist, and plumb to the following tolerances:
    - a. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
    - b. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.
    - c. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
    - d. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.
- C. Glazing: Comply with installation requirements in Section 088000 "Glazing" and with hollow-metal manufacturer's written instructions.
  1. Secure stops with countersunk flat- or oval-head machine screws spaced uniformly not more than 9 inches o.c. and not more than 2 inches o.c. from each corner.

### 3.4 ADJUSTING AND CLEANING

- A. Final Adjustments: Remove and replace defective work, including hollow-metal work that is warped, bowed, or otherwise unacceptable.
- B. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.
- C. Touchup Painting: Cleaning and touchup painting of abraded areas of paint are specified in painting Sections.

END OF SECTION 081213

## SECTION 081416 - FLUSH WOOD DOORS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section Includes:
  - 1. Solid-core doors.
  - 2. Factory machining for hardware.

#### 1.2 SUBMITTALS

- A. Product Data: For each type of door and pocket door frame. Include details of core and edge construction, and trim for openings. Include factory-finishing specifications.
- B. Shop Drawings: For wood doors. Indicate location, size, and hand of each door; elevation of each kind of door; construction details not covered in Product Data, and other pertinent data, including the following:
  - 1. Undercuts.
  - 2. Fire-protection ratings for fire-rated doors.
- C. Samples for Verification:
  - 1. Factory finishes applied to actual door face materials, approximately 8 by 10 inches, for each material and finish. For each wood species and transparent finish, provide set of three Samples showing typical range of color and grain to be expected in finished Work.

#### 1.3 QUALITY ASSURANCE

- A. Source Limitations: Obtain flush wood doors through one source from a single manufacturer.

#### 1.4 DELIVERY, STORAGE, AND HANDLING

- A. Comply with requirements of referenced standard and manufacturer's written instructions.
- B. Mark each door on top and bottom rail with opening number used on Shop Drawings.

## 1.5 PROJECT CONDITIONS

- A. Environmental Limitations: Do not deliver or install doors until building is enclosed, wet work is complete.

## 1.6 WARRANTY

- A. Special Warranty: Manufacturer's standard form, signed by manufacturer, Installer, and Contractor, in which manufacturer agrees to repair or replace doors that are defective in materials or workmanship, have warped (bow, cup, or twist), or show telegraphing of core construction in face veneers.
  - 1. Warranty shall also include installation and finishing that may be required due to repair or replacement of defective doors.
  - 2. Warranty shall be in effect during the following period of time from date of Certificate of Occupancy.
    - a. Solid-Core Interior Doors: Manufacturer's standard warranty.

## PART 2 - PRODUCTS

### 2.1 SOLID-CORE WOOD DOORS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Flush Wood Doors:
    - a. Algoma Hardwoods Inc.
    - b. Eggers Industries; Architectural Door Division.
    - c. Marshfield DoorSystems, Inc.
    - d. VT Industries, Inc.

### 2.2 DOOR CONSTRUCTION, GENERAL

- A. Urea-Formaldehyde: Wood materials shall contain no added urea-formaldehyde.

### 2.3 VENEERED-FACED DOORS FOR TRANSPARENT FINISH

- A. Interior Solid-Core Doors:
  - 1. Grade: Premium.
  - 2. Finish: Match Architect's samples.
  - 3. Wood Species: White birch.

4. Cut: Rotary cut.
5. Construction: Five plies. Stiles and rails bonded to core; entire unit abrasive planed before veneering.
6. Vertical and Top Edges: Same species as faces.
7. Bottom Edge: Manufacturer's option.
8. Top and Bottom: Provide veneer to match door faces or compatible veneer matching door faces.

## 2.4 DOORS FOR OPAQUE FINISH

### A. Interior Solid-Core Doors:

1. Grade: Premium.
2. Finish: Factory primed.
3. Faces: Any paint-grade closed-grain hardwood of mill option.
4. Construction: Manufacturer's standard.
5. Vertical and Top Edges: Same species as faces.
6. Bottom Edge: Fabricator's option.
7. Top and Bottom: Provide veneer to match door faces or compatible veneer matching door faces.

## 2.5 LIGHT FRAMES

### A. Metal Frames for Light Openings: Manufacturer's standard frame formed of 0.0478-inch-thick, cold-rolled steel sheet; factory primed.

1. Jamb: Split jamb with zinc coated steel sides and back.

## 2.6 FABRICATION

### A. General: Fabricate doors in sizes indicated for Project-site fitting.

1. Factory fit doors to suit frame-opening sizes indicated, with the following uniform clearances and bevels, unless otherwise indicated:

### B. Clearances: Additional means of gap covering shall be provided where either code required or the room use dictates privacy.

1. Non-Fire-Rated Doors: Not more than 1/8 inch at jambs and heads, and not more than 1/8 inch between meeting stiles of pairs of doors; 3/4 inch at bottom unless otherwise indicated.

### C. Machining: Factory machine doors for hardware that is not surface applied. Locate hardware to comply with DHI-WDHS-3. Comply with final hardware schedules, door frame Shop Drawings, DHI A115-W series standards, and hardware templates.

1. Coordinate measurements of hardware mortises in metal frames to verify dimensions and alignment before factory machining.
- D. Openings: Cut and trim openings through doors to comply with applicable requirements of referenced standards for kind(s) of door(s) required.
1. Light Openings: Trim openings with moldings of material and profile indicated.
- E. Fire-Rated Wood Doors: Doors complying with NFPA 80 that are listed and labeled by a qualified testing agency, for fire-protection ratings indicated, based on testing at positive pressure according to NFPA 252 or UL 10C.
1. Provide screw-attached metal labels.
  2. Cores: Provide core specified or mineral core as needed to provide fire-protection rating indicated.
  3. Edge Construction: Provide edge construction with intumescent seals concealed by outer stile. Comply with specified requirements for exposed edges.
  4. Pairs: Provide fire-retardant stiles that are listed and labeled for applications indicated without formed-steel edges and astragals. Provide stiles with concealed intumescent seals. Comply with specified requirements for exposed edges.
- F. Particleboard-Core Doors:
1. Particleboard: ANSI A208.1, Grade LD-1 or Grade LD-2, made with binder containing no urea-formaldehyde.
  2. Blocking: Provide wood blocking in particleboard-core doors as needed to eliminate through-bolting hardware.
  3. Edge Construction: At hinge stiles, provide laminated-edge construction with improved screw-holding capability and split resistance. Comply with specified requirements for exposed edges.
    - a. Screw-Holding Capability: Minimum 550 lbf per WDMA T.M.-10.
- G. Mineral-Core Doors:
1. Core: Noncombustible mineral product complying with requirements of referenced quality standard and testing and inspecting agency for fire-protection rating indicated.
  2. Blocking: Provide composite blocking with improved screw-holding capability approved for use in doors of fire-protection ratings indicated as needed to eliminate through-bolting hardware.
    - a. 5-inch top-rail blocking.
    - b. 5-inch bottom-rail blocking, in doors indicated to have protection plates.
    - c. 5-inch midrail blocking, in doors indicated to have armor plates.
    - d. Provide lock blocks, as required, in doors indicated to have exit devices.



3. Edge Construction: At hinge stiles, provide laminated-edge construction with improved screw-holding capability and split resistance. Comply with specified requirements for exposed edges.
  - a. Screw-Holding Capability: Minimum 550 lbf per WDMA T.M.-10.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine doors and installed door frames before hanging doors.
  1. Verify that frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
  2. Reject doors with defects.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 INSTALLATION

- A. Hardware: For installation, see Division 08 Section "Door Hardware."
- B. Manufacturer's Written Instructions: Install doors to comply with manufacturer's written instructions, referenced quality standard, and as indicated.
- C. Job-Fitted Doors: Align and fit doors in frames with uniform clearances and bevels as indicated below; do not trim stiles and rails in excess of limits set by manufacturer. Machine doors for hardware. Seal cut surfaces after fitting and machining.
  1. Clearances: Provide 1/8 inch at heads, jambs, and between pairs of doors. Provide 1/8 inch from bottom of door to top of decorative floor finish or covering. Where threshold is shown or scheduled, provide 1/4 inch from bottom of door to top of threshold.
  2. Bevel non-fire-rated doors 1/8 inch in 2 inches at lock and hinge edges.
- D. Factory-Finished Doors: Restore finish before installation if fitting or machining is required at Project site.

#### 3.3 ADJUSTING

- A. Operation: Rehang or replace doors that do not swing or operate freely.
- B. Finished Doors: Replace doors that are damaged or do not comply with requirements. Doors may be repaired or refinished if work complies with requirements and shows no evidence of repair or refinishing.

ORANGE COUNTY SHERIFF'S OFFICE  
CENTRAL OPERATIONS CENTER -  
SHERIFF'S OFFICE COMMAND AND MONITOR CENTER  
ORANGE COUNTY, FLORIDA

FLUSH WOOD DOORS  
SECTION 081416

END OF SECTION 081416

## SECTION 084126 - ALL-GLASS STOREFRONTS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section Includes:
  - 1. Interior all-glass storefronts.

#### 1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.3 SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for all-glass system.
  - 2. Product Data: For sealants, indicating VOC content.
- B. Shop Drawings: For all-glass storefronts.
  - 1. Include plans, elevations, and sections.
  - 2. Include details of fittings and glazing.
- C. Samples for Initial Selection: For each type of exposed finish indicated.

#### 1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.
- B. Product Options: Information on Drawings and in Specifications establishes requirements for aesthetic effects and performance characteristics of assemblies. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction.
  - 1. Do not change intended aesthetic effects, as judged solely by Architect, except with Architect's approval. If changes are proposed, submit comprehensive explanatory data to Architect for review.

## 1.5 WARRANTY

- A. Special Warranty: Installer agrees to repair or replace components of all-glass systems that do not comply with requirements or that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
  - 2. Warranty Period: Two years from date of Substantial Completion.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. General Performance: Comply with performance requirements specified, as determined by testing of all-glass storefronts representing those indicated for this Project without failure due to defective manufacture, fabrication, installation, or other defects in construction.

### 2.2 MANUFACTURERS

- A. Basis of Design Manufacturer; ; C.R. Laurence Co, in compliance with requirements, other available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. Blumcraft of Pittsburgh
  - 2. Trulite Glass & Aluminum Solutions, LLC.
  - 3. Virginia Glass Products Corporation.

### 2.3 METAL COMPONENTS

- A. Fitting Configuration:
  - 1. All-Glass Storefronts: Continuous rail fitting at top and bottom. Patch fitting for lock at latch side.

B. Rail Fittings:

1. Material: Aluminum.
2. Height:
  - a. Top Rail: As indicated.
  - b. Bottom Rail: As indicated.
3. Profile: As indicated.
4. End Caps: Manufacturer's standard precision-fit end caps for rail fittings.

C. Anchors and Fastenings: Concealed.

D. Materials:

1. Aluminum: ASTM B 221, with strength and durability characteristics of not less than Alloy 6063-T5.
  - a. Color and finish: Clear anodized.

2.4 GLASS

A. Glass: ASTM C 1048, Kind FT (fully tempered), Condition A (uncoated surfaces), Type I (transparent), tested for surface and edge compression per ASTM C 1048 and for impact strength per 16 CFR 1201 for Category II materials.

1. Clear monolithic.
  - a. Thickness: As Indicated.
2. Exposed Edges: Machine ground and flat polished.
3. Butt Edges: Flat ground.

2.5 BUTT-GLAZING SEALANTS

A. Single-Component, Nonsag, Acid-Curing Silicone Joint Sealant: ASTM C 920, Type S, Grade NS, Class 25, for Uses NT, G, and A.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - a. Dow Corning Corporation.
  - b. GE Construction Sealants; Momentive Performance Materials Inc.
  - c. Pecora Corporation.

## 2.6 FABRICATION

- A. Provide holes and cutouts in glass to receive hardware, fittings, and accessory fittings before tempering glass. Do not cut, drill, or make other alterations to glass after tempering.
  - 1. Fully temper glass using horizontal (roller-hearth) process, and fabricate so that when glass is installed, roll-wave distortion is parallel with the floor.
- B. Factory assemble components and factory install hardware and fittings to greatest extent possible.

## 2.7 ALUMINUM FINISHES

- A. Clear Anodic Finish: AAMA 611, AA-M12C22A31, Class II, 0.010 mm or thicker.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine areas and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Install all-glass systems and associated components according to manufacturer's written instructions.
- B. Set units level, plumb, and true to line, with uniform joints.
- C. Maintain uniform clearances between adjacent components.
- D. Install butt-joint sealants according to manufacturer's instructions.

### 3.3 ADJUSTING AND CLEANING

- A. Remove excess sealant and glazing compounds and dirt from surfaces.

END OF SECTION 084126

SECTION 085113 - ALUMINUM WINDOWS

PART 1 - GENERAL

1.1 SUMMARY

A. This Section includes the following:

1. Aluminum windows.

1.2 CODE COMPLIANCE

A. Windows shall meet the requirements of the Florida Building Code.

1. Provide product evaluations and installation requirements indicating compliance.

1.3 TESTING AND PERFORMANCE REQUIREMENTS

A. Test Units:

1. Air, water, and structural test unit shall conform to requirements set forth in ANSI/AAMA/NWDA 101/I.S.2-97.

B. Test Procedures and Performances:

1. Windows shall conform to ANSI/AAMA/NWDA 101/I.S.2-97 requirements for the window type referenced. In addition, the following specific performance requirements shall be met.
  - a. Performance Class: HC.
  - b. Performance Grade: 65.
2. Provide AAMA-certified aluminum windows with an attached label.
3. Life Cycle Testing: Test in accordance with AAMA 910. There shall be no damage to fasteners, hardware parts, support arms, activating mechanisms, or any other damage that would cause the window to be inoperable. Air infiltration and water resistance tests shall not exceed specified requirements.
4. Air Infiltration: Maximum rate not more than indicated when tested according to AAMA/WDMA 101/I.S.2/NAFS, Air Infiltration Test.
  - a. Maximum Rate: 0.3 cfm/sq. ft. (5 cu. m/h x sq. m) of area at an inward test pressure of 6.24 lbf/sq. ft. (300 Pa).

5. Water Resistance: No water leakage as defined in AAMA/WDMA referenced test methods at a water test pressure equaling that indicated, when tested according to AAMA/WDMA 101/I.S.2/NAFS, Water Resistance Test.
  - a. Test Pressure: 15 percent of positive design pressure, but not less than 12 lbf/sq. ft. (720 Pa).
6. Uniform Load Deflection Test: With window sash and ventilators closed and locked, test unit in accordance with ASTM E 330 at a static air pressure difference (positive and negative) of 60 psf.
  - a. During the course of the test no member shall deflect over L/175 of its span.
7. Uniform Load Structural Test: With window sash and ventilators closed and locked, test unit in accordance with ASTM E 330 at a static air pressure difference of 60 psf.
  - a. At conclusion of test there shall be no glass breakage, permanent damage to fasteners, hardware parts, support arms or actuating mechanisms, nor any other damage that would cause the window to be inoperable.
8. Thermal Movements: Provide aluminum windows, including anchorage, that accommodate thermal movements of units resulting from the following maximum change (range) in ambient and surface temperatures without buckling, distortion, opening of joints, failure of joint sealants, damaging loads and stresses on glazing and connections, and other detrimental effects. Base engineering calculation on actual surface temperatures of materials due to solar heat gain and nighttime-sky heat loss. 1)
  - a. Temperature Change (Range): 120 deg F (67 deg C), ambient; 180 deg F (100 deg C) material surfaces.

#### 1.4 SUBMITTALS

- A. Product Approval: Submit current Product Approval documentation in accordance with the Florida Building Code.
- B. Engineering Responsibility: Prepare engineering data for curtain wall systems, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project as prepared by a professional engineer registered in the state of Florida.
- C. Product Data: Include construction details, material descriptions, fabrication methods, dimensions of individual components and profiles, hardware, finishes, and operating instructions for each type of aluminum window indicated.



- D. Shop Drawings: Prepared by or under the supervision of a qualified professional engineer.
  - 1. Include plans, elevations, sections, details, hardware, attachments to other Work, and operational clearances, detailing fabrication and assembly of aluminum windows.
    - a. Submit evidence of meeting performance requirements. Include Engineering Calculations signed and sealed by the qualified professional engineer who was responsible for their preparation.
    - b. Demonstrate adequacy of receptor system.
  - 2. Provide Engineer's Computations and a P.E. Stamp from a Florida Licensed Engineer. Calculations are to be project specific and provide certification of structural adequacy for anchors, glass, mullions, meeting rails and window frames.
- E. Samples for Initial Selection: For units with factory-applied finishes.
  - 1. Include Samples of hardware and accessories involving color selection.
  - 2. Include Samples of glazing with privacy film.
- F. Samples for Verification: For aluminum windows and components required, showing full range of color variations for finishes, and prepared on Samples of size indicated below:
  - 1. Exposed Finishes: 2 by 4 inches.
  - 2. Exposed Hardware: Full-size units.
  - 3. Include Samples of glazing with privacy film.
- G. Qualification Data: For Installer, professional engineer and testing agency.
- H. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency.
- I. Field Quality-Control Test Reports: From a qualified testing and inspecting agency engaged by Contractor.
- J. Test Reports: Test reports shall be accompanied by the window manufacturer's letter of certification, stating the tested window meets or exceeds the referenced criteria for the appropriate AAMA/NWWDA 101/I.S.2 - 97 window type.
- K. Product Test Reports: Based on evaluation of comprehensive tests performed within the last four years by a qualified testing agency, for each type, grade, and size of aluminum window. Test results based on use of down-sized test units will not be accepted.
- L. Maintenance Data: For operable window sash, operating hardware, weather stripping, window system operators, and finishes to include in maintenance manuals.

## 1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Experienced Installers skilled in the successful installation of the specified materials and assemblies on similar projects for a minimum of five (5) years.
  - 1. Engineering Responsibility: Preparation of data for window systems including the following:
    - a. Shop Drawings based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project.
    - b. Shop Drawings, pre-construction testing program development, and comprehensive engineering analysis by a qualified professional engineer.
- B. Test Reports: Provide test reports from AAMA accredited laboratories certifying the performance as specified.
  - 1. Test reports shall be accompanied by the window manufacturer's letter of certification, stating the tested window meets or exceeds the referenced criteria for the appropriate ANSI/AAMA/NWWDA 101/I.S.2/NAFS-02 window type.
- C. Source Limitations: Obtain aluminum windows through one source from a single manufacturer.
- D. Glazing Publications: Comply with published recommendations of glass manufacturers and GANA's "Glazing Manual" unless more stringent requirements are indicated.
- E. Preinstallation Conference: Conduct conference at Project site.
  - 1. Inspect and discuss condition of substrate and other preparatory work performed by other trades.
  - 2. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
  - 3. Review required testing and inspecting procedures.
- F. Source Limitations for Glass: Obtain glass from one source from a single manufacturer for each glass type.
- G. Welding Standards: Comply with applicable provisions of AWS D1.2, "Structural Welding Code-Aluminum."

## 1.6 PROJECT CONDITIONS

- A. Field Measurements: Verify dimensions by field measurements before fabrication and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

## 1.7 WARRANTY

- A. **Manufacturer's Warranty:** Manufacturer agrees to repair or replace components of aluminum-framed entrances and storefronts that do not comply with requirements or that fail in materials or workmanship within specified warranty period.
1. Failures include, but are not limited to, the following:
    - a. Structural failures including, but not limited to, excessive deflection.
    - b. Noise or vibration created by wind and thermal and structural movements.
    - c. Deterioration of metals and other materials beyond normal weathering.
    - d. Water penetration through fixed glazing and framing areas.
    - e. Failure of operating components.
  2. Warranty Period: 10 years from date of Final Completion.
- B. **Finish Warranty:** Manufacturer's standard form in which manufacturer agrees to repair or replace components on which finishes do not comply with requirements or that fail in materials or workmanship within specified warranty period. Warranty does not include normal weathering.
1. Warranty Period: 10 years from date of Final Completion.

## PART 2 - PRODUCTS

### 2.1 ALUMINUM WINDOWS

- A. **Basis-of-Design Product:** AA900 Fixed Window, Kawneer an Alcoa Company or a comparable product by one of the following:
1. Glass: 1-inch thick; spandrel, insulated, impact resistant
    - a. Exterior Lite: Black silicone coated Spandrel Glass #2 surface, Fully tempered, 3/16-inch thick.
    - b. 3/8-inch airspace
    - c. Interior Lite: Laminated; 0.090 PVB interlayer; 3/16-inch heat strengthened bonded to 3/16-inch heat strengthened glass.
- B. Products of the following manufacturers are acceptable, providing their products equal or exceed the quality specified; and they can provide products of the type, size, function, and arrangement required.
1. EFCO, Corporation.
  2. YKK AP America Inc;

## 2.2 MATERIALS

- A. Aluminum: Alloy and temper recommended by manufacturer for type of use and finish indicated, complying with the requirements of standards indicated below.
  - 1. Sheet and Plate: ASTM B 209.
  - 2. Extruded Bars, Rods, Shapes, and Tubes: ASTM B 221.
  - 3. Extruded Structural Pipe and Tubes: ASTM B 429.
  - 4. Bars, Rods, and Wire: ASTM B 211.
  - 5. Welding Rods and Bare Electrodes: AWS A5.10.
- B. Steel Reinforcement: Complying with ASTM A 36 for structural shapes, plates, and bars; ASTM A 611 for cold-rolled sheet and strip; or ASTM A 570 for hot-rolled sheet and strip.
- C. Glazing Gaskets: As required to comply with system performance requirements. Provide gasket assemblies that have corners sealed with sealant recommended by gasket manufacturer.
- D. Spacers, Setting Blocks, Gaskets, and Bond Breakers: Manufacturer's standard permanent, nonmigrating types in hardness recommended by manufacturer, compatible with sealants, and suitable for system performance requirements.
- E. Framing system gaskets, sealants, and joint fillers as recommended by manufacturer for joint type.
- F. Compression Glazing Strips and Weather-Stripping: Provide compressible weather stripping designed for permanently resilient sealing under bumper or wiper action, and completely concealed when aluminum window is closed.
  - 1. Weather-Stripping Material: Elastomeric cellular preformed gaskets complying with ASTM C 509.
  - 2. Weather-Stripping Material: Dense elastomeric gaskets complying with ASTM C 864
  - 3. Weather-Stripping Material: Manufacturer's standard system and materials complying with AAMA/NWWDA 101/I.S.2.

## 2.3 INSECT SCREENS

- A. General: Fabricate insect screens to integrate with window frame. Provide screen for each operable exterior sash. Screen wickets are not permitted.
  - 1. Type and Location: Full, inside for project-out sashes.
- B. Aluminum Frames: Manufacturer's standard aluminum alloy complying with SMA 1004 or SMA 1201. Fabricate frames with mitered or coped joints or corner extrusions, concealed fasteners, and removable PVC spline/anchor concealing edge of frame.
  - 1. Tubular Framing Sections and Cross Braces: Roll formed from aluminum sheet.

- C. Glass-Fiber Mesh Fabric: 18-by-14 or 18-by-16 mesh of PVC-coated, glass-fiber threads; woven and fused to form a fabric mesh resistant to corrosion, shrinkage, stretch, impact damage, and weather deterioration. Comply with ASTM D 3656/D 3656M.
  - 1. Mesh Color: Manufacturer's standard.

## 2.4 COMPONENTS

- A. Fasteners and Accessories: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding fasteners and accessories compatible with adjacent materials.
  - 1. Reinforce members as required to retain fastener threads.
  - 2. Do not use exposed fasteners, except for hardware application. For hardware application, use countersunk Phillips flat-head machine screws finished to match framing members or hardware being fastened, unless otherwise indicated.
- B. Concrete and Masonry Inserts: Hot-dip galvanized cast-iron, malleable-iron, or steel inserts complying with ASTM A 123 or ASTM A 153 requirements.

## 2.5 GLAZING

- A. Tinted privacy glazing, Match Architects Sample.
- B. Ballistic Resistance: Level 3 according to UL 752.

## 2.6 HARDWARE

- A. General: Provide manufacturer's standard hardware fabricated from aluminum, stainless steel, carbon steel complying with AAMA 907, or other corrosion-resistant material compatible with aluminum; designed to smoothly operate, tightly close, and securely lock aluminum windows and sized to accommodate sash or ventilator weight and dimensions. Cadmium-plated hardware is not permitted. Do not use aluminum in frictional contact with other metals. Where exposed, provide solid clear anodized, extruded, cast, or wrought aluminum, die-cast zinc with special coating finish, or nonmagnetic stainless steel.
- B. Projected Windows: Provide the following operating hardware:
  - 1. Operator: Push-bar operator designed to open and close ventilators.
  - 2. Hinge: Concealed four-bar hinges with nylon bushings finished to match window.
  - 3. Lock: Cam-action, sweep lock handle with strike or combination lever handle and cam action lock with concealed pawl and keeper.
    - a. Provide two or more locks on units over 40 to 45 inches (1015 to 1140 mm) wide or high.
  - 4. Limit Device: Concealed limit device; located on jamb of each ventilator. (A/E will determine amount of the opening permitted.)

## 2.7 ACCESSORIES

- A. General: Provide manufacturer's standard accessories that comply with indicated standards, unless otherwise indicated.
- B. Sill treatment shall be by an extruded sill receptor or 0.062-inch thick sill flashing finished to match windows. Sill profile shall be properly end dammed and sealed to the substrate.

## 2.8 FABRICATION

- A. General: Manufacturer's standard fabrication that complies with the indicated standards. Include a complete system for assembling components and anchoring windows.
  - 1. Fabricate aluminum windows that are reglazable without dismantling sash or ventilator framing.
  - 2. Fabricate aluminum windows, in sizes indicated.

## 2.9 ALUMINUM FINISH

- A. Clear Anodic Finish: AAMA 611, AA-M12C22A41, Class I, 0.018 mm or thicker.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine areas, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of work.
  - 1. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. General: Comply with manufacturer's written instructions for installing windows, hardware, accessories, and other components; Drawings; and Shop Drawings.
  - 1. Do not install damaged components.
  - 2. Seal joints watertight.
- B. Install windows level, plumb, square, true to line, without distortion or impeding thermal movement, anchored securely in place to structural support, and in proper relation to wall flashing and other adjacent construction.
- C. Set sill members in bed of sealant or with gaskets, as indicated, for weathertight construction.
- D. Install glazing as specified Division 08 Section "Glazing."
- E. Install sealants as specified in Division 07 Section "Joint Sealants."

- F. Install components to drain water passing joints, condensation occurring within framing members, and moisture migrating within the system to exterior.
- G. Metal Protection:
  - 1. Where aluminum will contact dissimilar metals, protect against galvanic action by painting contact surfaces with primer or by applying sealant or tape or installing nonconductive spacers as recommended by manufacturer for this purpose.
  - 2. Where aluminum will contact concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint.
- H. Connections: Connect automatic operators to building electrical system.

### 3.3 ADJUSTING

- A. Adjust operating ventilators, hardware, operators, and accessories for a tight fit at contact points and weather stripping for smooth operation and weathertight closure. Lubricate hardware and moving parts.
- B. Remove excess sealant and glazing compounds, and dirt from surfaces.

### 3.4 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports.
  - 1. Testing and inspecting agency will interpret tests and state in each report whether tested work complies with or deviates from requirements.
- B. Field Testing and Performance Requirements: Windows shall be field tested in accordance with AAMA 502, "Voluntary Specification for Field Testing of Windows and Sliding Glass Doors," using Test Method A.
  - 1. Test one additional window or two percent of the window installation, whichever is greater, for air infiltration and water penetration as specified.
  - 2. Cost for all successful tests, both original and retest shall be paid by the Contractor. All unsuccessful tests, both original and retest, shall be paid by the Contractor.
  - 3. Testing shall be by an AAMA accredited testing agency selected by the architect and window manufacturer and employed by the responsible contractor.

4. Air infiltration field tests shall be conducted at the same uniform static test pressure as the laboratory test unit. The Maximum allowable rate of air leakage shall not exceed 1.5 times the laboratory test unit for hardware and glazing types consistent with the laboratory test unit. Performance values may be reduced due to deviations from the laboratory test unit such as product size, configuration, hardware selected, and glazing configuration. The field test air leakage rate shall not exceed 1.5 times the maximum allowable laboratory performance specified in the testing criteria listed in Section 1.05.A.1 for any configuration.
  5. Water penetration field tests shall be conducted at a static test pressure of 2/3 of the laboratory test performance values for hardware and glazing types consistent with the laboratory test unit. Performance values may be reduced due to deviations from the laboratory test unit such as product size, configuration, hardware selected, and glazing variations. The field test water test pressure shall not be less than 2/3 of the minimum allowable laboratory performance specified in the testing criteria listed in Section 1.05.A.1 for any configuration.
- C. Repair or remove work where test results and inspections indicate that it does not comply with specified requirements.
- D. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

### 3.5 PROTECTION AND CLEANING

- A. All windows shall use positive graphic identification showing that there is glazing in the frame while the window is being installed. Remove graphic identification when the window is cleaned.
- B. Protect window surfaces from contact with contaminating substances resulting from construction operations. In addition, monitor window surfaces adjacent to and below exterior concrete and masonry surfaces during construction for presence of dirt, scum, alkaline deposits, stains, or other contaminants. If contaminating substances do contact window surfaces, remove contaminants immediately according to manufacturer's written recommendations.
- C. Clean aluminum surfaces immediately after installing windows. Avoid damaging protective coatings and finishes. Remove excess sealants, glazing materials, dirt, and other substances.
- D. Clean glass immediately after installation. Comply with manufacturer's written recommendations for final cleaning and maintenance. Remove nonpermanent labels and clean surfaces.
- E. Remove and replace glass that has been broken, chipped, cracked, abraded, or damaged during construction period.

END OF SECTION 08 51 13



SECTION 087100 – DOOR HARDWARE

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes commercial door hardware for the following:
1. Hollow Metal Door and Frames,
  2. Aluminum Door and Frames,
  3. Wood Doors and Frames.
  4. Other doors to the extent indicated.
- B. Door hardware includes, but is not necessarily limited to, the following:
1. Mechanical door hardware.
  2. Electromechanical door hardware.
  3. Cylinders specified for doors in other sections.
- C. Codes and References: Comply with the version year adopted by the Authority Having Jurisdiction.
1. ANSI A117.1 - Accessible and Usable Buildings and Facilities.
  2. ICC/IBC - International Building Code.
  3. NFPA 70 - National Electrical Code.
  4. NFPA 80 - Fire Doors and Windows.
  5. NFPA 101 - Life Safety Code.
  6. NFPA 105 - Installation of Smoke Door Assemblies.
  7. State Building Codes, Local Amendments.
- D. Standards: All hardware specified herein shall comply with the following industry standards:
1. ANSI/BHMA Certified Product Standards - A156 Series
  2. UL10C – Positive Pressure Fire Tests of Door Assemblies

1.2 SUBMITTALS

- A. Product Data: Manufacturer's product data sheets including installation details, material descriptions, dimensions of individual components and profiles, operational descriptions and finishes.

- B. Door Hardware Schedule: Prepared by or under the supervision of supplier, detailing fabrication and assembly of door hardware, as well as procedures and diagrams. Coordinate the final Door Hardware Schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of door hardware.
1. Format: Comply with scheduling sequence and vertical format in DHI's "Sequence and Format for the Hardware Schedule."
  2. Organization: Organize the Door Hardware Schedule into door hardware sets indicating complete designations of every item required for each door or opening. Organize door hardware sets in same order as in the Door Hardware Sets at the end of Part 3. Submittals that do not follow the same format and order as the Door Hardware Sets will be rejected and subject to resubmission.
  3. Content: Include the following information:
    - a. Type, style, function, size, label, hand, and finish of each door hardware item.
    - b. Manufacturer of each item.
    - c. Fastenings and other pertinent information.
    - d. Location of door hardware set, cross-referenced to Drawings, both on floor plans and in door and frame schedule.
    - e. Explanation of abbreviations, symbols, and codes contained in schedule.
    - f. Mounting locations for door hardware.
    - g. Door and frame sizes and materials.
    - h. Warranty information for each product.
  4. Submittal Sequence: Submit the final Door Hardware Schedule at earliest possible date, particularly where approval of the Door Hardware Schedule must precede fabrication of other work that is critical in the Project construction schedule. Include Product Data, Samples, Shop Drawings of other work affected by door hardware, and other information essential to the coordinated review of the Door Hardware Schedule.
- C. Shop Drawings: Details of electrified access control hardware indicating the following:
1. Wiring Diagrams: Upon receipt of approved schedules, submit detailed system wiring diagrams for power, signaling, monitoring, communication, and control of the access control system electrified hardware. Differentiate between manufacturer-installed and field-installed wiring. Include the following:
    - a. Elevation diagram of each unique access controlled opening showing location and interconnection of major system components with respect to their placement in the respective door openings.
    - b. Complete (risers, point-to-point) access control system block wiring diagrams.
    - c. Wiring instructions for each electronic component scheduled herein.
  2. Electrical Coordination: Coordinate with related sections the voltages and wiring details required at electrically controlled and operated hardware openings.
- D. Proof of Certification: Provide copy of manufacturer(s) official certification or accreditation document indicating proof of status as a qualified installer of Windstorm assemblies.

- E. Keying Schedule: After a keying meeting with the owner has taken place prepare a separate keying schedule detailing final instructions. Submit the keying schedule in electronic format. Include keying system explanation, door numbers, key set symbols, hardware set numbers and special instructions. Owner must approve submitted keying schedule prior to the ordering of permanent cylinders/cores.
- F. Informational Submittals:
  - 1. Product Test Reports: Indicating compliance with cycle testing requirements, based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified independent testing agency.
- G. Operating and Maintenance Manuals: Provide manufacturers operating and maintenance manuals for each item comprising the complete door hardware installation in quantity as required in Division 01, Closeout Submittals.

### 1.3 QUALITY ASSURANCE

- A. Manufacturers Qualifications: Engage qualified manufacturers with a minimum 5 years of documented experience in producing hardware and equipment similar to that indicated for this Project and that have a proven record of successful in-service performance.
- B. Installer Qualifications: A minimum 3 years documented experience installing both standard and electrified door hardware similar in material, design, and extent to that indicated for this Project and whose work has resulted in construction with a record of successful in-service performance.
- C. Door Hardware Supplier Qualifications: Experienced commercial door hardware distributors with a minimum 5 years documented experience supplying both mechanical and electromechanical hardware installations comparable in material, design, and extent to that indicated for this Project. Supplier recognized as a factory direct distributor by the manufacturers of the primary materials with a warehousing facility in Project's vicinity. Supplier to have on staff a certified Architectural Hardware Consultant (AHC) available during the course of the Work to consult with Contractor, Architect, and Owner concerning both standard and electromechanical door hardware and keying.
- D. Source Limitations: Obtain each type and variety of door hardware specified in this section from a single source unless otherwise indicated.
  - 1. Electrified modifications or enhancements made to a source manufacturer's product line by a secondary or third party source will not be accepted.
  - 2. Provide electromechanical door hardware from the same manufacturer as mechanical door hardware, unless otherwise indicated.
- E. Each unit to bear third party permanent label demonstrating compliance with the referenced standards.

- F. Keying Conference: Conduct conference to comply with requirements in Division 01 Section "Project Meetings." Keying conference to incorporate the following criteria into the final keying schedule document:
1. Function of building, purpose of each area and degree of security required.
  2. Plans for existing and future key system expansion.
  3. Requirements for key control storage and software.
  4. Installation of permanent keys, cylinder cores and software.
  5. Address and requirements for delivery of keys.
- G. Pre-Submittal Conference: Conduct coordination conference in compliance with requirements in Division 01 Section "Project Meetings" with attendance by representatives of Supplier(s), Installer(s), and Contractor(s) to review proper methods and the procedures for receiving, handling, and installing door hardware.
1. Prior to installation of door hardware, conduct a project specific training meeting to instruct the installing contractors' personnel on the proper installation and adjustment of their respective products. Product training to be attended by installers of door hardware (including electromechanical hardware) for aluminum, hollow metal and wood doors. Training will include the use of installation manuals, hardware schedules, templates and physical product samples as required.
  2. Inspect and discuss electrical roughing-in, power supply connections, and other preparatory work performed by other trades.
  3. Review sequence of operation narratives for each unique access controlled opening.
  4. Review and finalize construction schedule and verify availability of materials.
  5. Review the required inspecting, testing, commissioning, and demonstration procedures
- H. At completion of installation, provide written documentation that components were applied to manufacturer's instructions and recommendations and according to approved schedule.

#### 1.4 DELIVERY, STORAGE, AND HANDLING

- A. Inventory door hardware on receipt and provide secure lock-up and shelving for door hardware delivered to Project site. Do not store electronic access control hardware, software or accessories at Project site without prior authorization.
- B. Tag each item or package separately with identification related to the final Door Hardware Schedule, and include basic installation instructions with each item or package.
- C. Deliver, as applicable, permanent keys, cylinders, cores, access control credentials, software and related accessories directly to Owner via registered mail or overnight package service. Instructions for delivery to the Owner shall be established at the "Keying Conference".

#### 1.5 COORDINATION

- A. Templates: Obtain and distribute to the parties involved templates for doors, frames, and other work specified to be factory prepared for installing standard and electrified hardware. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing hardware to comply with indicated requirements.

- B. Door Hardware and Electrical Connections: Coordinate the layout and installation of scheduled electrified door hardware and related access control equipment with required connections to source power junction boxes, low voltage power supplies, detection and monitoring hardware, and fire and detection alarm systems.
- C. Door and Frame Preparation: Doors and corresponding frames are to be prepared, reinforced and pre-wired (if applicable) to receive the installation of the specified electrified, monitoring, signaling and access control system hardware without additional in-field modifications.

## 1.6 WARRANTY

- A. General Warranty: Reference Division 01, General Requirements. Special warranties specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Warranty Period: Written warranty, executed by manufacturer(s), agreeing to repair or replace components of standard and electrified door hardware that fails in materials or workmanship within specified warranty period after final acceptance by the Owner. Failures include, but are not limited to, the following:
  - 1. Structural failures including excessive deflection, cracking, or breakage.
  - 2. Faulty operation of the hardware.
  - 3. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
  - 4. Electrical component defects and failures within the systems operation.
- C. Standard Warranty Period: One year from date of Substantial Completion, unless otherwise indicated.
- D. Special Warranty Periods:
  - 1. Five years for standard duty cylindrical (bored) locks and latches.
  - 2. Five years for exit hardware.
  - 3. Twenty five years for manual surface door closer bodies.
  - 4. Two years for electromechanical door hardware.

## 1.7 MAINTENANCE SERVICE

- A. Maintenance Tools and Instructions: Furnish a complete set of specialized tools and maintenance instructions as needed for Owner's continued adjustment, maintenance, and removal and replacement of door hardware.

## PART 2 - PRODUCTS

### 2.1 SCHEDULED DOOR HARDWARE

- A. General: Provide door hardware for each door to comply with requirements in Door Hardware Sets and each referenced section that products are to be supplied under.

- B. Designations: Requirements for quantity, item, size, finish or color, grade, function, and other distinctive qualities of each type of door hardware are indicated in the Door Hardware Sets at the end of Part 3. Products are identified by using door hardware designations, as follows:
- C. Named Manufacturer's Products: Product designation and manufacturer are listed for each door hardware type required for the purpose of establishing requirements. Manufacturers' names are abbreviated in the Door Hardware Schedule.
- D. Substitutions: Requests for substitution and product approval for inclusive mechanical and electromechanical door hardware in compliance with the specifications must be submitted in writing and in accordance with the procedures and time frames outlined in Division 01, Substitution Procedures. Approval of requests is at the discretion of the architect, owner, and their designated consultants.

## 2.2 HANGING DEVICES

- A. Hinges: ANSI/BHMA A156.1 certified butt hinges with number of hinge knuckles as specified in the Door Hardware Sets.
  - 1. Quantity: Provide the following hinge quantity, unless otherwise indicated:
    - a. Two Hinges: For doors with heights up to 60 inches.
    - b. Three Hinges: For doors with heights 61 to 90 inches.
    - c. Four Hinges: For doors with heights 91 to 120 inches.
    - d. For doors with heights more than 120 inches, provide 4 hinges, plus 1 hinge for every 30 inches of door height greater than 120 inches.
  - 2. Hinge Size: Provide the following, unless otherwise indicated, with hinge widths sized for door thickness and clearances required:
    - a. Widths up to 3'0": 4-1/2" standard or heavy weight as specified.
    - b. Sizes from 3'1" to 4'0": 5" standard or heavy weight as specified.
  - 3. Hinge Weight and Base Material: Unless otherwise indicated, provide the following:
    - a. Exterior Doors: Heavy weight, non-ferrous, ball bearing or oil impregnated bearing hinges unless Hardware Sets indicate standard weight.
    - b. Interior Doors: Standard weight, steel, ball bearing or oil impregnated bearing hinges unless Hardware Sets indicate heavy weight.
  - 4. Hinge Options: Comply with the following where indicated in the Hardware Sets or on Drawings:
    - a. Non-removable Pins: Provide set screw in hinge barrel that, when tightened into a groove in hinge pin, prevents removal of pin while door is closed; for the all out-swinging lockable doors.
  - 5. Acceptable Manufacturers:
    - a. Ives (IVE)
    - b. Hager Companies (HA).
    - c. Bommer (BO)

- B. Continuous Geared Hinges: ANSI/BHMA A156.26 Grade 1-600 certified continuous geared hinge. with minimum 0.120-inch thick extruded 6060 T6 aluminum alloy hinge leaves and a minimum overall width of 4 inches. Hinges are non-handed, reversible and fabricated to template screw locations. Factory trim hinges to suit door height and prepare for electrical cut-outs.

1. Acceptable Manufacturers or Equal:

- a. Ives (IVE)
- b. Stanley (ST)
- c. Select (SE)

## 2.3 POWER TRANSFER DEVICES

- A. Electrified Quick Connect Continuous Geared Transfer Hinges: Provide electrified transfer continuous geared hinges with a 12" removable service panel cutout accessible without de-mounting door from the frame. Furnish with Molex™ standardized plug connectors with sufficient number of concealed wires (up to 12) to accommodate the electrified functions specified in the Door Hardware Sets. Connectors plug directly to through-door wiring harnesses for connection to electric locking devices and power supplies. Wire nut connections are not acceptable.

1. Acceptable Manufacturers or Equal:

- a. McKinney Products (MK) - SER-QC (# wires) Option.
- b. Pemko Manufacturing (PE) - SER-QC (# wires) Option.

- B. Electric Door Wire Harnesses: Provide electric/data transfer wiring harnesses with standardized plug connectors to accommodate up to twelve (12) wires. Connectors plug directly to through-door wiring harnesses for connection to electric locking devices and power supplies. Provide sufficient number and type of concealed wires to accommodate electric function of specified hardware. Provide a connector for through-door electronic locking devices and from hinge to junction box above the opening. Wire nut connections are not acceptable. Determine the length required for each electrified hardware component for the door type, size and construction, minimum of two per electrified opening.

1. Provide one each of the following tools as part of the base bid contract:

- a. McKinney Products (MK) - Electrical Connecting Kit: QC-R001.
- b. McKinney Products (MK) - Connector Hand Tool: QC-R003.

2. Acceptable Manufacturers or Equal:

- a. McKinney Products (MK) – QC-C Series.

## 2.4 DOOR OPERATING TRIM

- A. Flush Bolts and Surface Bolts: ANSI/BHMA A156.3 and A156.16, Grade 1, certified.

1. Manual flush bolts to be furnished with top rod of sufficient length to allow bolt location approximately six feet from the floor.
  2. Furnish dust proof strikes for bottom bolts.
  3. Surface bolts to be minimum 8" in length and U.L. listed for labeled fire doors and U.L. listed for windstorm components where applicable.
  4. Provide related accessories (mounting brackets, strikes, coordinators, etc.) as required for appropriate installation and operation.
  5. Acceptable Manufacturers:
    - a. Door Controls International (DC).
    - b. Rockwood Manufacturing (RO).
    - c. Trimco (TC).
- B. Door Push Plates and Pulls: ANS/BHMA A156.6 certified door pushes and pulls of type and design specified in the Hardware Sets. Coordinate and provide proper width and height as required where conflicting hardware dictates.
1. Push/Pull Plates: Minimum .050 inch thick, size as indicated in hardware sets, with beveled edges, secured with exposed screws unless otherwise indicated.
  2. Door Pull and Push Bar Design: Size, shape, and material as indicated in the hardware sets. Minimum clearance of 2 1/2-inches from face of door unless otherwise indicated.
  3. Offset Pull Design: Size, shape, and material as indicated in the hardware sets. Minimum clearance of 2 1/2-inches from face of door and offset of 90 degrees unless otherwise indicated.
  4. Fasteners: Provide manufacturer's designated fastener type as indicated in Hardware Sets.
  5. Acceptable Manufacturers or Equal:
    - a. Rockwood Manufacturing (RO).
    - b. Trimco (TC).

## 2.5 CYLINDERS AND KEYING

- A. General: Cylinder manufacturer to have minimum (10) years experience designing secured master key systems and have on record a published security keying system policy.
- B. Source Limitations: Obtain each type of keyed cylinder and keys from the same source manufacturer as locksets and exit devices, unless otherwise indicated.
1. Acceptable Manufacturers or Equal:
    - a. Schlage Primus (SC)
    - b. Rockwood (RO)
    - c. Corbin Russin Hardware (RU)
- C. Cylinders: Original manufacturer cylinders complying with the following:
1. Keyway: Manufacturer's Standard.
- D. Keying System: Each type of lock and cylinders to be factory keyed.



1. Conduct specified "Keying Conference" to define and document keying system instructions and requirements.
2. Furnish factory cut, nickel-silver large bow permanently inscribed with a visual key control number as directed by Owner.
3. New System: Key locks to a new key system as directed by the Owner.

E. Key Quantity: Provide the following minimum number of keys:

1. Change Keys per Cylinder: Two (2)
2. Master Keys (per Master Key Level/Group): Five (5).
3. Construction Keys (where required): Ten (10).

F. Construction Keying: Provide construction master keyed cylinders.

## 2.6 MECHANICAL LOCKS AND LATCHING DEVICES

A. Cylindrical Locksets, Grade 2 (Standard Duty): ANSI/BHMA A156.2, Series 4000, Grade 2 certified.

1. Locks are to be non-handed and fully field reversible.
2. Acceptable Manufacturers or Equal:
  - a. Corbin Russwin Hardware (RU) - CL3800 Series.
  - b. Sargent Manufacturing (SA) - 7-Line.
  - c. Schlage (SC) - AL Series.
  - d. Yale Locks and Hardware (YA) - 5300LN Series.

## 2.7 AUXILIARY LOCKS

- A. Mortise Deadlocks, Small Case: ANSI/BHMA A156.5, Grade 1, certified small case mortise type deadlocks constructed of heavy gauge wrought corrosion resistant steel. Steel or stainless steel bolts with a 1" throw and hardened steel roller pins. Deadlocks to be products of the same source manufacturer and keyway as other specified locksets.
1. Acceptable Manufacturers or Equal:
    - a. Corbin Russwin Hardware (RU) - DL4100 Series.
    - b. Sargent Manufacturing (SA) - 4870 Series.
    - c. Schlage (SC) - L460 Series.
    - d. Yale Locks and Hardware (YA) - 350 Series.

## 2.8 CONVENTIONAL EXIT DEVICES

- A. General Requirements: All exit devices specified herein shall meet or exceed the following criteria:
1. At doors not requiring a fire rating, provide devices complying with NFPA 101 and listed and labeled for "Panic Hardware" according to UL305. Provide proper fasteners as required by manufacturer including sex nuts and bolts at openings specified in the Hardware Sets.
  2. Where exit devices are required on fire rated doors, provide devices complying with NFPA 80 and with UL labeling indicating "Fire Exit Hardware". Provide devices with the proper fasteners for installation as tested and listed by UL. Consult manufacturer's catalog and template book for specific requirements.
  3. Electromechanical Options: Subject to same compliance standards and requirements as mechanical exit devices, electrified devices to be of type and design as specified in hardware sets. Include any specific controllers when conventional power supplies are not sufficient to provide the proper inrush current.
  4. Vertical Rod Exit Devices: Where surface or concealed vertical rod exit devices are used at interior openings, provide as less bottom rod (LBR) unless otherwise indicated. Provide dust proof strikes where thermal pins are required to project into the floor.
  5. Rail Sizing: Provide exit device rails factory sized for proper door width application.
  6. Through Bolt Installation: For exit devices and trim as indicated in Door Hardware Sets.
  7. Hurricane and Tornado Resistance Compliance: Conventional exit devices are to be U.L. listed for windstorm components where applicable. Provide the appropriate hurricane or tornado resistant products that have been independent third party tested, certified, and labeled to meet state and local windstorm building codes applicable to project.

- B. Conventional Push Rail Exit Devices (Heavy Duty): ANSI/BHMA A156.3, Grade 1 certified panic and fire exit hardware devices furnished in the functions specified in the Hardware Sets. Exit device latch to be stainless steel, pullman type, with deadlock feature.

1. Acceptable Manufacturers or Equal:
  - a. Corbin Russwin Hardware (RU) - ED4000 / ED5000 Series.
  - b. Sargent Manufacturing (SA) - 80 Series.
  - c. Von Duprin (VD) – 98A Series

## 2.9 DOOR CLOSERS

- A. All door closers specified herein shall meet or exceed the following criteria:

1. General: Door closers to be from one manufacturer, matching in design and style, with the same type door preparations and templates regardless of application or spring size. Closers to be non-handed with full sized covers including installation and adjusting information on inside of cover.
2. Standards: Closers to comply with UL-10C for Positive Pressure Fire Test and be U.L. listed for use of fire rated doors.
3. Cycle Testing: Provide closers which have surpassed 15 million cycles in a test witnessed and verified by UL.
4. Size of Units: Comply with manufacturer's written recommendations for sizing of door closers depending on size of door, exposure to weather, and anticipated frequency of use. Where closers are indicated for doors required to be accessible to the physically handicapped, provide units complying with ANSI ICC/A117.1.
5. Closer Arms: Provide heavy duty, forged steel closer arms unless otherwise indicated in Hardware Sets.
6. Closers shall not be installed on exterior or corridor side of doors; where possible install closers on door for optimum aesthetics.
7. Closer Accessories: Provide door closer accessories including custom templates, special mounting brackets, spacers and drop plates, and through-bolt and security type fasteners as required for proper installation.

- B. Door Closers, Surface Mounted (Commercial Duty): ANSI/BHMA 156.4, Grade 1 certified surface mounted, institutional grade door closers with complete spring power adjustment, sizes 1 thru 6; and fully operational adjustable according to door size, frequency of use, and opening force. Closers to be rack and pinion type, one piece cast iron or aluminum alloy body construction, with adjustable backcheck, closing sweep, and latch speed control valves. Provide non-handed units standard.

1. Acceptable Manufacturers or Equal:
  - a. Corbin Russwin Hardware (RU) - DC6000 Series.
  - b. LCN Closers (LC) – 404/4041XP Series.
  - c. Yale Locks and Hardware (YA) - 3500 Series.

## 2.10 ARCHITECTURAL TRIM

### A. Door Protective Trim

1. General: Door protective trim units to be of type and design as specified below or in the Hardware Sets.
2. Size: Fabricate protection plates (kick, armor, or mop) not more than 2" less than door width (LDW) on stop side of single doors and 1" LDW on stop side of pairs of doors, and not more than 1" less than door width on pull side. Coordinate and provide proper width and height as required where conflicting hardware dictates. Height to be as specified in the Hardware Sets.
3. Protection Plates: ANSI/BHMA A156.6 certified protection plates (kick, armor, or mop), fabricated from the following:
  - a. Stainless Steel: 300 grade, 050-inch thick.
4. Options and fasteners: Provide manufacturer's designated fastener type as specified in the Hardware Sets. Provide countersunk screw holes.
5. Acceptable Manufacturers or Equal:
  - a. Rockwood Manufacturing (RO).
  - b. Trimco (TC).

## 2.11 DOOR STOPS AND HOLDERS

- A. General: Door stops and holders to be of type and design as specified below or in the Hardware Sets.

- B. Door Stops and Bumpers: ANSI/BHMA A156.16, Grade 1 certified door stops and wall bumpers. Provide wall bumpers, either convex or concave types with anchorage as indicated, unless floor or other types of door stops are specified in Hardware Sets. Do not mount floor stops where they will impede traffic. Where floor or wall bumpers are not appropriate, provide overhead type stops and holders.

1. Acceptable Manufacturers or Equal:

- a. Ives (IVE)
- b. Rockwood Manufacturing (RO).

- C. Overhead Door Stops and Holders: ANSI/BHMA A156.6, Grade 1 certified overhead stops and holders to be surface or concealed types as indicated in Hardware Sets. Track, slide, arm and jamb bracket to be constructed of extruded bronze and shock absorber spring of heavy tempered steel. Provide non-handed design with mounting brackets as required for proper operation and function.

1. Acceptable Manufacturers or Equal:

- a. Rixson Door Controls (RF).
- b. Rockwood Manufacturing (RO).
- c. Glynn Johnson (GJ).

## 2.12 ARCHITECTURAL SEALS

- A. General: Thresholds, weatherstripping, and gasket seals to be of type and design as specified below or in the Hardware Sets. Provide continuous weatherstrip gasketing on exterior doors and provide smoke, light, or sound gasketing on interior doors where indicated. At exterior applications provide non-corrosive fasteners and elsewhere where indicated.

- B. Smoke Labeled Gasketing: Assemblies complying with NFPA 105 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for smoke control ratings indicated, based on testing according to UL 1784.

1. Provide smoke labeled perimeter gasketing at all smoke labeled openings.

- C. Fire Labeled Gasketing: Assemblies complying with NFPA 80 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire ratings indicated, based on testing according to UL-10C.

1. Provide intumescent seals as indicated to meet UL10C Standard for Positive Pressure Fire Tests of Door Assemblies, and UBC 7-2, Fire Tests of Door Assemblies.

- D. Sound-Rated Gasketing: Assemblies that are listed and labeled by a testing and inspecting agency, for sound ratings indicated.

- E. Replaceable Seal Strips: Provide only those units where resilient or flexible seal strips are easily replaceable and readily available from stocks maintained by manufacturer.

1. Acceptable Manufacturers or Equal:
  - a. Pemko Manufacturing (PE).
  - b. National Guard Products (NG)
  - c. Zero (ZER)

## 2.13 ELECTRONIC ACCESSORIES

- A. Door Position Switches: Door position magnetic reed contact switches specifically designed for use in commercial door applications. On recessed models the contact and magnetic housing snap-lock into a 1" diameter hole. Surface mounted models include wide gap distance design complete with armored flex cabling. Provide SPDT, N/O switches with optional Rare Earth Magnet installation on steel doors with flush top channels.

1. Acceptable Manufacturers or Equal:
  - a. Sargent Manufacturing (SA) – 3280 Series.
  - b. Schlage (SCH).
  - c. LCN

- B. Power Supplies: Provide Nationally Recognized Testing Laboratory Listed 12VDC or 24VDC (field selectable) filtered and regulated power supplies. Include battery backup option with integral battery charging capability in addition to operating the DC load in event of line voltage failure. Provide the least number of units, at the appropriate amperage level, sufficient to exceed the required total draw for the specified electrified hardware and access control equipment.

1. Acceptable Manufacturers or Equal:
  - a. Securitron (SU) - BPS Series.

## 2.14 FABRICATION

- A. Fasteners: Provide door hardware manufactured to comply with published templates generally prepared for machine, wood, and sheet metal screws. Provide screws according to manufacturers recognized installation standards for application intended.

## 2.15 FINISHES

- A. Standard: Designations used in the Hardware Sets and elsewhere indicate hardware finishes complying with ANSI/BHMA A156.18, including coordination with traditional U.S. finishes indicated by certain manufacturers for their products.
- B. Provide quality of finish, including thickness of plating or coating (if any), composition, hardness, and other qualities complying with manufacturer's standards, but in no case less than specified by referenced standards for the applicable units of hardware.
- C. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine scheduled openings, with Installer present, for compliance with requirements for installation tolerances, labeled fire door assembly construction, wall and floor construction, and other conditions affecting performance.
- B. Notify architect of any discrepancies or conflicts between the door schedule, door types, drawings and scheduled hardware. Proceed only after such discrepancies or conflicts have been resolved in writing.

#### 3.2 PREPARATION

- A. Hollow Metal Doors and Frames: Comply with ANSI/DHI A115 series.
- B. Wood Doors: Comply with ANSI/DHI A115-W series.

#### 3.3 INSTALLATION

- A. Install each item of mechanical and electromechanical hardware and access control equipment to comply with manufacturer's written instructions and according to specifications.
  - 1. Installers are to be trained and certified by the manufacturer on the proper installation and adjustment of fire, life safety, and security products including: hanging devices; locking devices; closing devices; and seals.
- B. Mounting Heights: Mount door hardware units at heights indicated in following applicable publications, unless specifically indicated or required to comply with governing regulations:
  - 1. Standard Steel Doors and Frames: DHI's "Recommended Locations for Architectural Hardware for Standard Steel Doors and Frames."
  - 2. Wood Doors: DHI WDHS.3, "Recommended Locations for Architectural Hardware for Wood Flush Doors."
  - 3. Where indicated to comply with accessibility requirements, comply with ANSI A117.1 "Accessibility Guidelines for Buildings and Facilities."
  - 4. Provide blocking in drywall partitions where wall stops or other wall mounted hardware is located.
- C. Retrofitting: Install door hardware to comply with manufacturer's published templates and written instructions. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be painted or finished in another way, coordinate removal, storage, and reinstallation of surface protective trim units with finishing work specified in Division 9 Sections. Do not install surface-mounted items until finishes have been completed on substrates involved.
- D. Thresholds: Set thresholds for exterior and acoustical doors in full bed of sealant complying with requirements specified in Division 7 Section "Joint Sealants."

- E. Storage: Provide a secure lock up for hardware delivered to the project but not yet installed. Control the handling and installation of hardware items so that the completion of the work will not be delayed by hardware losses before and after installation.

### 3.4 CLEANING AND PROTECTION

- A. Protect all hardware stored on construction site in a covered and dry place. Protect exposed hardware installed on doors during the construction phase. Install any and all hardware at the latest possible time frame.
- B. Clean adjacent surfaces soiled by door hardware installation.
- C. Clean operating items as necessary to restore proper finish. Provide final protection and maintain conditions that ensure door hardware is without damage or deterioration at time of owner occupancy.

### 3.5 DEMONSTRATION

- A. Instruct Owner's maintenance personnel to adjust, operate, and maintain mechanical and electromechanical door hardware.

### 3.6 DOOR HARDWARE SETS

- A. The hardware sets represent the design intent and direction of the owner and architect. They are a guideline only and should not be considered a detailed hardware schedule. Discrepancies, conflicting hardware and missing items should be brought to the attention of the architect with corrections made prior to the bidding process. Omitted items not included in a hardware set should be scheduled with the appropriate additional hardware required for proper application and functionality.

- B. Manufacturer's Abbreviations:

BM	Bommer
DM	Dor-O-Matic
GJ	Glynn Johnson
HA	Hager
IVE	Ives Architectural Hardware Products
LCN	LCN
NG	National Guard Products
PE	Penko
QU	Quality
RF	Rixson
RO	Rockwood
SCH	Schlage, Schlage Electronics, Schlage Primus
SE	Select Products Limited
ST	Stanley
VON	Von Duprin
ZER	Zero



**Hardware Schedule**

Hardware Set No. 01

Door: 113A

Provide each SGL door(s) with the following:

Qty		Description	Catalog Number	Finish	Mfr
4	EA	HW HINGE	3CB1HW 5 X 4.5 NRP	652	IVE
1	EA	STOREROOM LOCK	L9080T 17A	626	SCH
1	EA	PRIMUS CORE	20-740-XP	626	SCH
1	EA	ELECTRIC STRIKE	6211 FSE	630	VON
1	EA	SURFACE CLOSER	4040XP	689	LCN
1	EA	KICK PLATE	8400 10" X 2" LDW B4E	630	IVE
1	EA	WALL STOP	WS406/407CCV	630	IVE
1	EA	GASKETING	188S-BK	S-Bk	ZER

Card reader to unlock electric strike by security supplier  
Wiring Diagram by Hardware Supplier

Hardware Set No. 02

Door: 115A

Provide each PR door(s) with the following:

Qty		Description	Catalog Number	Finish	Mfr
8	EA	HINGE	3CB1 4.5 X 4.5	652	IVE
1	EA	FIRE EXIT HARDWARE	9827-EO-F-LBR-ER36-499F-SNB	626	VON
1	EA	FIRE EXIT HARDWARE	9827-L-NL-F-LBR-ER36-17-499F-SNB	626	VON
1	EA	RIM CYLINDER	20-057-ICX	626	SCH
1	EA	PRIMUS CORE	20-740-XP	626	SCH
2	EA	SURFACE CLOSER	4040XP SCUSH	689	LCN
2	EA	KICK PLATE	8400 10" X 1" LDW B4E	630	IVE
1	EA	GASKETING	188S-BK	S-Bk	ZER
2	EA	MEETING STILE	8193AA	AA	ZER

Hardware Set No. 03

Doors: 110A, 111A, 112A, 112B and 116A.

Provide each SGL door(s) with the following:

Qty		Description	Catalog Number	Finish	Mfr
4	EA	HINGE	3CB1 4.5 X 4.5 NRP	652	IVE
1	EA	STOREROOM LOCK	L9080T 17A	626	SCH
1	EA	PRIMUS CORE	20-740-XP	626	SCH
1	EA	ELECTRIC STRIKE	6211 FSE	630	VON
1	EA	SURFACE CLOSER	4040XP	689	LCN
1	EA	KICK PLATE	8400 10" X 2" LDW B4E	630	IVE
1	EA	WALL STOP	WS406/407CCV	630	IVE
1	EA	GASKETING	188S-BK	S-Bk	ZER

Card reader to unlock electric strike by security supplier  
Wiring Diagram by Hardware Supplier

Hardware Set No. 04

Door: 108A.

Provide each SGL door(s) with the following:

Qty		Description	Catalog Number	Finish	Mfr
4	EA	HINGE	3CB1 4.5 X 4.5	652	IVE
1	EA	STOREROOM LOCK	L9080T 17A	626	SCH
1	EA	PRIMUS CORE	20-740-XP	626	SCH
1	EA	SURFACE CLOSER	4040XP	689	LCN
1	EA	KICK PLATE	8400 10" X 2" LDW B4E	630	IVE
1	EA	WALL STOP	WS406/407CCV	630	IVE
1	EA	GASKETING	188S-BK	S-Bk	ZER

Hardware Set No. 05

Doors: 106A and 107A.

Provide each SGL door(s) with the following:

Qty		Description	Catalog Number	Finish	Mfr
4	EA	HINGE	3PB1 4.5 X 4.5	652	IVE
1	EA	OFFICE W/SIM RETRACT	L9056T 17A	626	SCH
1	EA	PRIMUS CORE	20-740-XP	626	SCH
1	EA	WALL STOP	WS406/407CCV	630	IVE
3	EA	SILENCER	SR64	GRY	IVE

Hardware Set No. 06

Doors: 105A and 109A.

Provide each SGL door(s) with the following:

Qty		Description	Catalog Number	Finish	Mfr
4	EA	HINGE	3CB1 4.5 X 4.5	652	IVE
1	EA	PASSAGE SET	L9010 17A	626	SCH
1	EA	SURFACE CLOSER	4040XP	689	LCN
1	EA	KICK PLATE	8400 10" X 2" LDW B4E	630	IVE
1	EA	WALL STOP	WS406/407CCV	630	IVE
3	EA	SILENCER	SR64	GRY	IVE

Notes: -Weather seals to be provided by door manufacturer

-Provide necessary drop plates and fillers for proper installation of door closers

-Exterior doors and hardware to comply with FBC windstorm requirements.

-Operation: presenting valid credential to reader temporarily retracts latchbolt, permitting entry. Trim is fail secure with key override outside trim. Inside pushbar always permits egress. Request to exit (Rx) allows authorized egress

END OF SECTION 087100

## SECTION 088000 - GLAZING

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Section Includes:

1. Glass.

#### 1.2 DEFINITIONS

- A. Manufacturer: A firm that produces primary glass or fabricated glass as defined in referenced glazing publications.

#### 1.3 PERFORMANCE REQUIREMENTS

- A. General: Provide glazing systems capable of withstanding normal thermal movement and wind and impact loads (where applicable) without failure, including loss or glass breakage attributable to the following: defective manufacture, fabrication, and installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; or other defects in construction.
- B. Glass Design: Glass thickness indicated is minimums and is for detailing only. Confirm glass thickness by analyzing Project wind loads for exterior glass and in-service conditions for exterior and interior glass.
- C. Thermal Movements: Provide glazing that allows for thermal movements resulting from the maximum change (range) in ambient and surface temperatures acting on glass framing members and glazing components.

#### 1.4 SUBMITTALS

- A. Product Data: For each glass product and glazing material indicated.
- B. Samples: For the following products, in the form of 12-inch- square Samples for glass.
1. Each glass type indicated.
- C. Warranties: For glass types indicated.

#### 1.5 QUALITY ASSURANCE

- A. Source Limitations for Glazing Accessories: Obtain glazing accessories from one source for each product and installation method indicated.
- B. Safety Glass: Category II materials complying with testing requirements in 16 CFR 1201 and ANSI Z97.1.
  - 1. Subject to compliance with requirements, permanently mark safety glass with certification label of Safety Glazing Certification Council or another certification agency acceptable to authorities having jurisdiction.
- C. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below, unless more stringent requirements are indicated. Refer to these publications for glazing terms not otherwise defined in this Section or in referenced standards.
  - 1. GANA Publications: GANA'S "Glazing Manual".
- D. Insulating-Glass Certification Program: Permanently marked either on spacers or on at least one component lite of units with appropriate certification label of IGCC.

#### 1.6 DELIVERY, STORAGE, AND HANDLING

- A. Protect glazing materials according to manufacturer's written instructions and as needed to prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.

#### 1.7 PROJECT CONDITIONS

- A. Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.
  - 1. Do not install liquid glazing sealants when ambient and substrate temperature conditions are outside limits permitted by glazing sealant manufacturer or below 40 degrees F.

#### 1.8 WARRANTY

- A. Manufacturer's Warranty on Insulating Glass: Manufacturer's standard form in which insulating-glass manufacturer agrees to replace insulating-glass units that deteriorate within specified warranty period.
  - 1. Warranty Period: 10 years from date of Substantial Completion.

## PART 2 - PRODUCTS

### 2.1 HEAT TREATED FLOAT GLASS:

- A. Fabrication Process: By vertical (tong-held) or horizontal (roller-hearth) process, at manufacturer's option, except provide horizontal process where indicated as tongless or free of tong marks.
- B. Heat-Treated Float Glass: ASTM C 1048; Type I (transparent glass, flat); Quality q3 (glazing select); class, kind, and condition as indicated.

### 2.2 TEMPERED GLASS

- A. Tempered Glass: Clear fully tempered float glass.
  - 1. Thickness: 1/4-inch, minimum.
  - 2. Labeling: Provide safety glazing labeling.

### 2.3 LAMINATED GLASS

- A. Laminated Glass: ASTM C 1172. Use materials that have a proven record of no tendency to bubble, discolor, or lose physical and mechanical properties after fabrication and installation.
  - 1. Construction: Laminate glass with polyvinyl butyral interlayer to comply with interlayer manufacturer's written instructions.
  - 2. Interlayer Thickness: Provide thickness not less than that indicated and as needed to comply with requirements.
  - 3. Interlayer Color: Clear unless otherwise indicated.
- B. Windborne-Debris-Impact-Resistant Laminated Glass: Comply with requirements specified above for laminated glass except laminate glass with the following to comply with interlayer manufacturer's written instructions:
  - 1. Polyvinyl butyral interlayer.

### 2.4 SPANDREL GLAZING

- A. Silicone-Coated Spandrel Glass: ASTM C 1048, Type I, Condition C, Quality-Q3.

## 2.5 INSULATING GLASS

- A. Insulating-Glass Units: Factory-assembled units consisting of sealed lites of glass separated by a dehydrated interspace, qualified according to ASTM E 2190, and complying with other requirements specified.
1. Sealing System: Dual seal.
  2. Spacer: Manufacturer's standard spacer material and construction.

## 2.6 ELASTOMERIC GLAZING SEALANTS

- A. General: Provide products of type indicated, complying with the following requirements:
1. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.
  2. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range for this characteristic.
- B. Elastomeric Glazing Sealant Standard: Comply with ASTM C 920 and other requirements indicated for each liquid-applied, chemically curing sealant in the Glazing Sealant Schedule at the end of Part 3, including those referencing ASTM C 920 classifications for type, grade, class, and uses.
1. Additional Movement Capability: Where additional movement capability is specified in the Glazing Sealant Schedule, provide products with the capability, when tested for adhesion and cohesion under maximum cyclic movement per ASTM C 719, to withstand the specified percentage change in the joint width existing at time of installation and remain in compliance with other requirements in ASTM C 920 for uses indicated.

## 2.7 MISCELLANEOUS GLAZING MATERIALS

- A. General: Provide products of material, size, and shape complying with referenced glazing standard, requirements of manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.
- B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.
- C. Setting Blocks: Elastomeric material with a Shore A durometer hardness of 85, plus or minus 5.

- D. Spacers: Elastomeric blocks or continuous extrusions with a Shore A durometer hardness required by glass manufacturer to maintain glass lites in place for installation indicated.
- E. Edge Blocks: Elastomeric material of hardness needed to limit glass lateral movement (side walking).
- F. Cylindrical Glazing Sealant Backing: ASTM C 1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

## 2.8 FABRICATION OF GLASS AND OTHER GLAZING PRODUCTS

- A. Fabricate glass and other glazing products in sizes required to glaze openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing standard, to comply with system performance requirements.
- B. Clean-cut or flat-grind vertical edges of butt-glazed monolithic lites in a manner that produces square edges with slight kerfs at junctions with indoor and outdoor faces.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine framing glazing, with Installer present, for compliance with the following:
  - 1. Manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
  - 2. Presence and functioning of weep system.
  - 3. Minimum required face or edge clearances.
  - 4. Effective sealing between joints of glass-framing members.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings not firmly bonded to substrates.

### 3.3 GLAZING, GENERAL

- A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.



- B. Glazing channel dimensions, as indicated on Drawings, provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances. Adjust as required by Project conditions during installation.
- C. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass is glass with edge damage or other imperfections that, when installed, could weaken glass and impair performance and appearance.
- D. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction sealant-substrate testing.
- E. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.
- F. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.
- G. Provide spacers for glass lites where the length plus width is larger than 50 inches as follows:
  - 1. Locate spacers directly opposite each other on both inside and outside faces of glass. Install correct size and spacing to preserve required face clearances, unless gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and to comply with system performance requirements.
  - 2. Provide 1/8-inch minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.
- H. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and according to requirements in referenced glazing publications.
- I. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.
- J. Where wedge-shaped gaskets are driven into one side of channel to pressurize sealant or gasket on opposite side, provide adequate anchorage so gasket cannot walk out when installation is subjected to movement.
- K. Square cut wedge-shaped gaskets at corners and install gaskets in a manner recommended by gasket manufacturer to prevent corners from pulling away; seal corner joints and butt joints with sealant recommended by gasket manufacturer.

### 3.4 SEALANT GLAZING (WET)

- A. Install continuous spacers, or spacers combined with cylindrical sealant backing, between glass lites and glazing stops to maintain glass face clearances and to prevent sealant from extruding into glass channel and blocking weep systems until sealants cure. Secure spacers or spacers and backings in place and in position to control depth of installed sealant relative to edge clearance for optimum sealant performance.
- B. Force sealants into glazing channels to eliminate voids and to ensure complete wetting or bond of sealant to glass and channel surfaces.
- C. Tool exposed surfaces of sealants to provide a substantial wash away from glass.

### 3.5 PROTECTION AND CLEANING

- A. Protect exterior glass from damage immediately after installation by attaching crossed streamers to framing held away from glass. Do not apply markers to glass surface. Remove nonpermanent labels, and clean surfaces.
- B. Protect glass from contact with contaminating substances resulting from construction operations, including weld splatter. If, despite such protection, contaminating substances do come into contact with glass, remove them immediately as recommended by glass manufacturer.
- C. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for build-up of dirt, scum, alkaline deposits, or stains; remove as recommended by glass manufacturer.
- D. Remove and replace glass that is broken, chipped, cracked, abraded, or damaged in any way, including natural causes, accidents, and vandalism, during construction period.
- E. Wash glass on both exposed surfaces in each area of Project not more than four days before date scheduled for inspections that establish date of Substantial Completion.

END OF SECTION 088000

SECTION 092216 - NON-STRUCTURAL METAL FRAMING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Non-load-bearing steel framing systems for interior gypsum board assemblies.

1.2 SUBMITTALS

A. Product Data: For each type of product.

1. Studs and Runners: Provide documentation that framing members' certification is according to SFIA's "Code Compliance Certification Program for Cold-Formed Steel Structural and Non-Structural Framing Members". SFIA's program certifies that studs and runners comply with the IBC, ASTM C 645, AISI S100, and AISI S220. Mechanical properties, coatings, dimensions, and labeling are checked.
2. Manufacturers' limiting tables indicating products provided.
3. Manufacturer's Certification: Submit manufacturer's certification of product compliance with codes and standards along with product literature and data sheets for specified products.
4. Evaluation Reports: For Metal Framing, from ICC-ES or other qualified testing agency acceptable to authorities having jurisdiction.

- B. Delegated-Design by Specialty Structural Engineer (SSE) Delegated-Design Submittal: For steel framing, fasteners, accessories and support. The design professional, individual or organization having responsibility for the design of the specialty items. This responsibility shall be in accordance with the state's statues and regulations governing the professional registration and certification of architects or engineers.

1.3 QUALITY ASSURANCE

- A. Fire-Test-Response Characteristics: For fire-resistance-rated assemblies that incorporate non-load-bearing steel framing, provide materials and construction identical to those tested in assembly indicated according to ASTM E 119 by an independent testing agency.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 01 40 00 "Quality Requirements," to design steel framing systems.
  - 1. Design framing systems in accordance with American Iron and Steel Institute Publication S220 "North American Specification for the Design of Cold-Formed Steel Framing – Non-Structural Members", except as otherwise shown or specified.
  - 2. Design loads: As indicated on the Architectural Drawings or 5 PSF minimum as required by the Building Code.
  - 3. Design framing systems to accommodate deflection of primary building structure and construction tolerances and to withstand design loads with a maximum deflection of 1/240 inches and including finish material.
- B. Fire-Test-Response Characteristics: Provide materials and construction identical to those tested according to ASTM E 119.
- C. STC-Rated Assemblies: Provide materials and construction identical to those tested in assembly indicated according to ASTM E 90 and classified according to ASTM E 413.

### 2.2 NON-LOAD-BEARING STEEL FRAMING, GENERAL

- A. Framing Members, General: Comply with ASTM C 754 for conditions indicated.
  - 1. Steel Sheet Components: Comply with ASTM C 645 requirements for metal, unless otherwise indicated.
  - 2. Protective Coating: ASTM A 653/A 653M, G60, hot-dip galvanized.
  - 3. Depth: As indicated on Drawings.
  - 4. Minimum Base-Metal Thickness: 0.0188 inch (25 gauge), except as indicated below.
    - a. Provide 3-5/8-inch, 20 DW gauge metal studs at 16 inches on center for walls between 10 to 12 feet in height.
    - b. Provide 3-5/8-inch, 20 STR gauge metal studs at 16 inches on center for walls between 12 to 16 feet in height.
    - c. Provide 0.0312-inch thick studs for framing supporting ceramic tile substrates.
- B. Cold-Rolled Channel Bridging: Steel, 0.053-inch minimum base-metal thickness, with minimum 1/2-inch- wide flanges.
  - 1. Depth: As indicated on Drawings.
  - 2. Clip Angle: Not less than 1-1/2 by 1-1/2 inches, 0.068-inch- thick, galvanized steel.
- C. Hat-Shaped, Rigid Furring Channels: ASTM C 645.
  - 1. Depth: As indicated on Drawings.

- D. Resilient Furring Channels: 1/2-inch- deep, steel sheet members designed to reduce sound transmission.
  - 1. Configuration: Asymmetrical or hat shaped.
- E. Z-Shaped Furring: With slotted or nonslotted web, face flange of Insert depth, wall attachment flange of 7/8 inch, minimum uncoated-metal thickness of 0.018 inch, and depth required to fit insulation thickness indicated.
- F. Furring Channels (Furring Members):
  - 1. Cold-Rolled Channels: 0.0538-inch bare-steel thickness, with minimum 1/2-inch- wide flanges, 3/4 inch deep.
  - 2. Steel Studs: ASTM C 645.
    - a. Minimum Base-Metal Thickness: 0.0179 inch.
    - b. Depth: As indicated on Drawings.
  - 3. Hat-Shaped, Rigid Furring Channels: ASTM C 645, 7/8 inch deep.
    - a. Minimum Base Metal Thickness: 0.0312 inch.

### 2.3 AUXILIARY MATERIALS

- A. Fasteners for Metal Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.
- B. Isolation Strip at Exterior Walls: Provide one of the following:
  - 1. Asphalt-Saturated Organic Felt: ASTM D 226, Type I (No. 15 asphalt felt), nonperforated.
  - 2. Foam Gasket: Adhesive-backed, closed-cell vinyl foam strips that allow fastener penetration without foam displacement, 1/8 inch thick, in width to suit steel stud size.

## PART 3 - EXECUTION

### 3.1 INSTALLATION, GENERAL

- A. Installation Standard: ASTM C 754.
  - 1. Gypsum Plaster Assemblies: Also comply with requirements in ASTM C 841 that apply to framing installation.
  - 2. Portland Cement Plaster Assemblies: Also comply with requirements in ASTM C 1063 that apply to framing installation.
  - 3. Gypsum Board Assemblies: Also comply with requirements in ASTM C 840 that apply to framing installation.
- B. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.

- C. Install bracing at terminations in assemblies.
- D. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.

### 3.2 INSTALLING FRAMED ASSEMBLIES

- A. Install framing system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types and other assembly components indicated.
- B. Where studs are installed directly against exterior masonry walls or dissimilar metals at exterior walls, install isolation strip between studs and exterior wall.
- C. Install studs so flanges within framing system point in same direction.
- D. Stud Spacing: 16-inches on center unless otherwise indicated.
- E. Install tracks (runners) at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings, except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts penetrating partitions above ceiling.
  - 1. Slip-Type Head Joints: Where framing extends to overhead structural supports, install to produce joints at tops of framing systems that prevent axial loading of finished assemblies.
  - 2. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install runner track section (for cripple studs) at head and secure to jamb studs.
    - a. Install two studs at each jamb unless otherwise indicated.
    - b. Install cripple studs at head adjacent to each jamb stud, with a minimum 1/2-inch clearance from jamb stud to allow for installation of control joint in finished assembly.
    - c. Extend jamb studs through suspended ceilings and attach to underside of overhead structure.
  - 3. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.
  - 4. Fire-Resistance-Rated Partitions: Install framing to comply with fire-resistance-rated assembly indicated and support closures and to make partitions continuous from floor to underside of solid structure.
    - a. Firestop Track: Where indicated, install to maintain continuity of fire-resistance-rated assembly indicated.
  - 5. Sound-Rated Partitions: Install framing to comply with sound-rated assembly indicated.

F. Direct Furring:

1. Attach to concrete or masonry with stub nails, screws designed for masonry attachment, or powder-driven fasteners spaced 24 inches o.c.

G. Z-Furring Members:

1. Erect insulation vertically and hold in place with Z-furring members spaced 24 inches o.c.
2. Except at exterior corners, securely attach narrow flanges of furring members to wall with concrete stub nails, screws designed for masonry attachment, or powder-driven fasteners spaced 24 inches o.c.
3. At exterior corners, attach wide flange of furring members to wall with short flange extending beyond corner; on adjacent wall surface, screw-attach short flange of furring channel to web of attached channel. At interior corners, space second member no more than 12 inches from corner and cut insulation to fit.

H. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch from the plane formed by faces of adjacent framing.

END OF SECTION 092216

SECTION 092900 - GYP SUM BOARD

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior gypsum board.
2. Tile backer board.

1.2 SUBMITTALS

- A. Product Data: For each type of product indicated.

1.3 QUALITY ASSURANCE

- A. Fire-Resistance-Rated Assemblies: For fire-resistance-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 119 by an independent testing agency.
- B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 90 and classified according to ASTM E 413 by an independent testing agency.
- C. Protected Openings Identification: All fire-resistive construction including fire barriers, fire walls, and smoke barriers shall be permanently stenciled on the partition as follows.
1. Provide the following wording: FIRE AND SMOKE BARRIER - PROTECT ALL OPENINGS.
    - a. Letter Size: 6-inches high
    - b. Spacing: 4 feet on center, maximum.
    - c. Letter Font: Helvetica Regular
    - d. Letter Color: Red.
  2. Also provide a 3-inch wide painted red line below the identification signage to identify the direction and extent/length of the rated wall. Extend the painted line the full length of the wall; identify directional changes and where rated walls end.

1.4 STORAGE AND HANDLING

- A. Store materials inside under cover and keep them dry and protected against damage from weather, condensation, direct sunlight, construction traffic, and other causes. Stack panels flat to prevent sagging.



1.5 PROJECT CONDITIONS

- A. Environmental Limitations: Comply with ASTM C 840 requirements or gypsum board manufacturer's written recommendations, whichever are more stringent.
- B. Do not install interior products until installation areas are enclosed and conditioned.
- C. Do not install panels that are wet, those that are moisture damaged, and those that are mold damaged.
  - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
  - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

PART 2 - PRODUCTS

2.1 INTERIOR GYPSUM BOARD

- A. General: Complying with ASTM C 36 or ASTM C 1396, as applicable to type of gypsum board indicated and whichever is more stringent.
  - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
    - a. G-P Gypsum.
    - b. Lafarge North America Inc.
    - c. National Gypsum Company.
    - d. USG Corporation.
- B. Regular Type and Type X (fire rated):
  - 1. Thickness: As indicated.
  - 2. Long Edges: Tapered.

2.2 TRIM ACCESSORIES

- A. Interior Trim: ASTM C 1047.
  - 1. Material: Paper-faced galvanized steel sheet.
  - 2. Shapes: As indicated.

### 2.3 JOINT TREATMENT MATERIALS

- A. General: Comply with ASTM C 475.
- B. Joint Tape:
  - 1. Interior Gypsum Wallboard: Paper.
  - 2. Backer Board: As recommended by panel manufacturer.
- C. Joint Compound for Interior Gypsum Wallboard: For each coat use formulation that is compatible with other compounds applied on previous or for successive coats.
- D. Joint Compound for Backer Board: As recommended by backer unit manufacturer.

### 2.4 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards and manufacturer's written recommendations.
- B. Steel Drill Screws: ASTM C 1002, unless otherwise indicated.
  - 1. Use screws complying with ASTM C 954 for fastening panels to steel members from 0.033 to 0.112 inch thick.
  - 2. For fastening backer board, use screws of type and size recommended by panel manufacturer.
- C. Acoustic Sealant: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834. Product effectively reduces airborne sound transmission through perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.
  - 1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Grabber Construction Products; Acoustical Sealant GSC.
    - b. Pecora Corporation; AC-20 FTR or AIS-919.
    - c. Specified Technologies, Inc.; Smoke N Sound Acoustical Sealant.
    - d. USG Corporation; SHEETROCK Acoustical Sealant.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine areas and substrates, with Installer present, and including welded hollow-metal frames and framing, for compliance with requirements and other conditions affecting performance.
- B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 APPLYING AND FINISHING PANELS

- A. General: Comply with ASTM C 840.
- B. Examine panels before installation. Reject panels that are wet or moisture damaged.
- C. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments, except floors. Provide 1/4- to 1/2-inch- wide spaces at these locations, and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.
- D. Tile Backer Board Units: Comply with manufacture's instructions and recommendations.
  - 1. Where backer board units abut other types of panels in same plane, shim surfaces to produce a uniform plane across panel surfaces.
- E. Penetrations:
  - 1. Refer to Section 07 84 13 Penetration Firestopping regarding sealing of wall and ceiling penetrations.
  - 2. Seal around all non-fire rated penetrations of gypsum panel walls and ceilings completely to minimum of Smoketight requirements.

#### 3.3 INSTALLING TRIM ACCESSORIES

- A. General: Attach trim according to manufacturer's written instructions.

- B. Control Joints: Install control joints according to ASTM C 840 in specific locations identified, where approved by Architect, as indicated on the Drawings, and as follows:
  - 1. Ceilings: Unless otherwise indicated install control joints as follows:
    - a. Install control joints in areas exceeding 2500 sq. ft.
    - b. Space control joints not more than 50 feet on center.
    - c. Install control joints where ceiling framing or furring changes direction.
  - 2. Partitions and Furring: Unless otherwise indicated install control joints as follows:
    - a. Install control joints in partitions and wall furring runs exceeding 30 feet.
    - b. Space control joints not more than 30 feet on center.
    - c. Install control joints in furred assemblies where control joints occur in base exterior wall.

### 3.4 FINISHING GYPSUM BOARD

- A. General: Treat gypsum board joints, interior angles, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare gypsum board surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.
- B. Prefill open joints and damaged surface areas.
- C. Apply joint tape over gypsum board joints, except those with trim having flanges not intended for tape.
- D. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C 840:
  - 1. Level 3: Ceiling plenum areas, concealed areas, and where indicated.
  - 2. Level 4: All other locations.
  - 3. Level 5: Locations indicated on the Drawings.
- E. Tile Backer Board Units: Finish according to manufacturer's written instructions.

### 3.5 PROTECTION

- A. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.
- B. Remove and replace panels that are wet or moisture damaged.
  - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.

END OF SECTION 09 29 00

SECTION 095113 - ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
1. Acoustical ceiling tile.
  2. Exposed grid suspension systems.
  3. Perimeter and trim Accessories.

1.2 SUBMITTALS

- A. Product Data: For products indicated.
- B. Samples for Verification: For each component indicated and for each exposed finish required, prepared on Samples of size indicated below.
1. Ceiling Panels: Set of 12-inch- square Samples of each type, color, pattern, and texture.
  2. Exposed Suspension System Members, Moldings, and Trim: Set of 12-inch- long Samples of each type, finish, and color.
- C. Maintenance Data: For ceiling panels and grid.

1.3 QUALITY ASSURANCE

- A. Source Limitations:
1. Ceiling Panels: Obtain through one source from a single manufacturer.
  2. Suspension System: Obtain each type through one source from a single manufacturer.
- B. Fire-Test-Response Characteristics: Provide acoustical panel ceilings that comply with the following requirements:
1. Surface-Burning Characteristics: Provide acoustical panels with the following surface-burning characteristics complying with ASTM E 1264 for Class A materials as determined by testing identical products per ASTM E 84:
    - a. Smoke-Developed Index: 450 or less.
- C. Preinstallation Conference: Conduct conference at Project site.

#### 1.4 DELIVERY, STORAGE, AND HANDLING

- A. Deliver acoustical panels, suspension system components, and accessories to Project site in original, unopened packages and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.
- B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.
- C. Handle acoustical panels carefully to avoid chipping edges or damaging units in any way.

#### 1.5 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install acoustical panel ceilings until spaces are enclosed and weatherproof, wet work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

#### 1.6 COORDINATION

- A. Coordinate layout and installation of acoustical panels and suspension system with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, fire-suppression system, and partition assemblies.

### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Source Limitations: Obtain each type of acoustical ceiling panel and its supporting suspension system from single source from single manufacturer.

#### 2.2 PERFORMANCE REQUIREMENTS

- A. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  - 1. Flame-Spread Index: Class A according to ASTM E 1264.
  - 2. Smoke-Developed Index: 50 or less.

### 2.3 ACOUSTICAL PANELS

- A. Basis-of-Design Product: As Indicated on the Finish List.

### 2.4 METAL SUSPENSION SYSTEM

- A. Basis-of-Design Product: As Indicated on the Finish List.
- B. Suspension systems shall meet or exceed the requirements of ASTM C 635 for dimensional tolerances, coatings and finishes, and load carrying capabilities. Individual component deflection shall not exceed 1/360 of the span.
- C. Finishes and Colors: Provide hot-dipped galvanized finish G-60 on all ceiling suspension components. Exposed surfaces of suspension system components shall receive white baked-on enamel paint.
- D. Attachment Devices: Size for five times the design load indicated in ASTM C 635, Table 1, "Direct Hung," unless otherwise indicated.
  - 1. Anchors in Concrete: Anchors of type and material indicated below, with holes or loops for attaching hangers of type indicated and with capability to sustain, without failure, a load equal to five times that imposed by ceiling construction, as determined by testing per ASTM E 488 or ASTM E 1512 as applicable, conducted by a qualified testing and inspecting agency.
    - a. Type: Postinstalled expansion anchors.
    - b. Corrosion Protection: Carbon-steel components zinc plated to comply with ASTM B 633, Class Fe/Zn 5 (0.005 mm) for Class SC 1 service condition.
  - 2. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hangers of type indicated, and with capability to sustain, without failure, a load equal to 10 times that imposed by ceiling construction, as determined by testing per ASTM E 1190, conducted by a qualified testing and inspecting agency.
- E. Wire Hangers, Braces, and Ties: Provide wires complying with the following requirements:
  - 1. Zinc-Coated Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
  - 2. Size: Select wire diameter so its stress at three times hanger design load (ASTM C 635, Table 1, "Direct Hung") will be less than yield stress of wire, but provide not less than 0.106-inch- diameter wire.

### 2.5 MISCELLANEOUS MATERIALS

- A. Concealed Acoustical Sealant: Nondrying, nonhardening, nonskinning, nonstaining, non-bleeding gunnable sealant complying with requirement specified in Section 07 92 00, Sealants and Caulking.

## 2.6 METAL EDGE MOLDINGS AND TRIM

- A. Roll-Formed Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations that fit acoustical panel edge details and suspension systems indicated; formed from sheet metal of same material, finish, and color as that used for exposed flanges of suspension system runners.
  - 1. For lay-in panels with reveal edge details, provide stepped edge molding that forms reveal of same depth and width as that formed between edge of panel and flange at exposed suspension member.

## 2.7 ACOUSTICAL SEALANT

- A. Products:
  - 1. Acoustical Sealant for Exposed and Concealed Joints:
    - a. Pecora Corp; AC-20 FTR Acoustical and Insulation Sealant.
    - b. United States Gypsum Co.; SHEETROCK Acoustical Sealant.
- B. Acoustical Sealant for Exposed and Concealed Joints: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834 and effective in reducing airborne sound transmission through perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders, and comply with layout shown on reflected ceiling plans.

### 3.3 INSTALLATION, GENERAL

- A. General: Install acoustical panel ceilings to comply with ASTM C 636 per manufacturer's written instructions and CISCA's "Ceiling Systems Handbook."



- B. Suspend ceiling hangers from building's structural members and as follows:
1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
  2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
  3. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards and publications.
  4. Secure wire hangers to ceiling suspension members and to supports above with a minimum of three tight turns. Connect hangers directly either to structures or to inserts, eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
  5. Do not attach hangers to steel roof deck. Attach hangers to structural members.
  6. Space hangers not more than 48 inches o.c. along each member supported directly from hangers, unless otherwise indicated; provide hangers not more than 8 inches from ends of each member.
- C. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
  2. Screw attach moldings to substrate at intervals not more than 16 inches o.c. and not more than 3 inches from ends, leveling with ceiling suspension system to a tolerance of 1/8 inch in 12 feet. Miter corners accurately and connect securely.
  3. Do not use exposed fasteners, including pop rivets, on moldings and trim.
- D. Install suspension system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- E. Install acoustical panels with undamaged edges and fit accurately into suspension system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide a neat, precise fit.
1. For square-edged panels, install panels with edges fully hidden from view by flanges of suspension system runners and moldings.
  2. For reveal-edged panels on suspension system runners, install panels with bottom of reveal in firm contact with top surface of runner flanges.
  3. Paint cut edges of panel remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.

### 3.4 CLEANING

- A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

ORANGE COUNTY SHERIFF'S OFFICE  
CENTRAL OPERATIONS CENTER -  
SHERIFF'S OFFICE COMMAND AND MONITOR CENTER  
ORANGE COUNTY, FLORIDA

ACOUSTICAL PANEL CEILINGS  
SECTION 095113

END OF SECTION 095113

SECTION 095113 - ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
1. Acoustical ceiling tile.
  2. Exposed grid suspension systems.
  3. Perimeter and trim Accessories.

1.2 SUBMITTALS

- A. Product Data: For products indicated.
- B. Samples for Verification: For each component indicated and for each exposed finish required, prepared on Samples of size indicated below.
1. Ceiling Panels: Set of 12-inch- square Samples of each type, color, pattern, and texture.
  2. Exposed Suspension System Members, Moldings, and Trim: Set of 12-inch- long Samples of each type, finish, and color.
- C. Maintenance Data: For ceiling panels and grid.

1.3 QUALITY ASSURANCE

- A. Source Limitations:
1. Ceiling Panels: Obtain through one source from a single manufacturer.
  2. Suspension System: Obtain each type through one source from a single manufacturer.
- B. Fire-Test-Response Characteristics: Provide acoustical panel ceilings that comply with the following requirements:
1. Surface-Burning Characteristics: Provide acoustical panels with the following surface-burning characteristics complying with ASTM E 1264 for Class A materials as determined by testing identical products per ASTM E 84:
    - a. Smoke-Developed Index: 450 or less.
- C. Preinstallation Conference: Conduct conference at Project site.

#### 1.4 DELIVERY, STORAGE, AND HANDLING

- A. Deliver acoustical panels, suspension system components, and accessories to Project site in original, unopened packages and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.
- B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.
- C. Handle acoustical panels carefully to avoid chipping edges or damaging units in any way.

#### 1.5 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install acoustical panel ceilings until spaces are enclosed and weatherproof, wet work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

#### 1.6 COORDINATION

- A. Coordinate layout and installation of acoustical panels and suspension system with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, fire-suppression system, and partition assemblies.

### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Source Limitations: Obtain each type of acoustical ceiling panel and its supporting suspension system from single source from single manufacturer.

#### 2.2 PERFORMANCE REQUIREMENTS

- A. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  - 1. Flame-Spread Index: Class A according to ASTM E 1264.
  - 2. Smoke-Developed Index: 50 or less.

## 2.3 ACOUSTICAL PANELS

- A. Basis-of-Design Product: As Indicated on the Finish List, Or Equal.
- B. Products of the following manufacturers are acceptable, providing their products equal or exceed the quality specified; and they can provide products of the type, size, function, and arrangement required.
  - 1. Armstrong World Industries, Inc.
  - 2. Chicago Metallic Corporation.
  - 3. United States Gypsum Company.

## 2.4 METAL SUSPENSION SYSTEM

- A. Basis-of-Design Product: As Indicated on the Finish List.
- B. Suspension systems shall meet or exceed the requirements of ASTM C 635 for dimensional tolerances, coatings and finishes, and load carrying capabilities. Individual component deflection shall not exceed 1/360 of the span.
- C. Finishes and Colors: Provide hot-dipped galvanized finish G-60 on all ceiling suspension components. Exposed surfaces of suspension system components shall receive white baked-on enamel paint.
- D. Attachment Devices: Size for five times the design load indicated in ASTM C 635, Table 1, "Direct Hung," unless otherwise indicated.
  - 1. Anchors in Concrete: Anchors of type and material indicated below, with holes or loops for attaching hangers of type indicated and with capability to sustain, without failure, a load equal to five times that imposed by ceiling construction, as determined by testing per ASTM E 488 or ASTM E 1512 as applicable, conducted by a qualified testing and inspecting agency.
    - a. Type: Postinstalled expansion anchors.
    - b. Corrosion Protection: Carbon-steel components zinc plated to comply with ASTM B 633, Class Fe/Zn 5 (0.005 mm) for Class SC 1 service condition.
  - 2. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hangers of type indicated, and with capability to sustain, without failure, a load equal to 10 times that imposed by ceiling construction, as determined by testing per ASTM E 1190, conducted by a qualified testing and inspecting agency.
- E. Wire Hangers, Braces, and Ties: Provide wires complying with the following requirements:
  - 1. Zinc-Coated Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
  - 2. Size: Select wire diameter so its stress at three times hanger design load (ASTM C 635, Table 1, "Direct Hung") will be less than yield stress of wire, but provide not less than 0.106-inch- diameter wire.

## 2.5 MISCELLANEOUS MATERIALS

- A. Concealed Acoustical Sealant: Nondrying, nonhardening, nonskinning, nonstaining, non-bleeding gunnable sealant complying with requirement specified in Section 07 92 00, Sealants and Caulking.

## 2.6 METAL EDGE MOLDINGS AND TRIM

- A. Roll-Formed Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations that fit acoustical panel edge details and suspension systems indicated; formed from sheet metal of same material, finish, and color as that used for exposed flanges of suspension system runners.
  - 1. For lay-in panels with reveal edge details, provide stepped edge molding that forms reveal of same depth and width as that formed between edge of panel and flange at exposed suspension member.

## 2.7 ACOUSTICAL SEALANT

- A. Products:
  - 1. Acoustical Sealant for Exposed and Concealed Joints:
    - a. Pecora Corp; AC-20 FTR Acoustical and Insulation Sealant.
    - b. United States Gypsum Co.; SHEETROCK Acoustical Sealant.
    - c. Tremco Quart Acoustical Sealant 333.
- B. Acoustical Sealant for Exposed and Concealed Joints: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834 and effective in reducing airborne sound transmission through perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders, and comply with layout shown on reflected ceiling plans.

### 3.3 INSTALLATION, GENERAL

- A. General: Install acoustical panel ceilings to comply with ASTM C 636 per manufacturer's written instructions and CISCA's "Ceiling Systems Handbook."
- B. Suspend ceiling hangers from building's structural members and as follows:
  - 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
  - 2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
  - 3. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards and publications.
  - 4. Secure wire hangers to ceiling suspension members and to supports above with a minimum of three tight turns. Connect hangers directly either to structures or to inserts, eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
  - 5. Do not attach hangers to steel roof deck. Attach hangers to structural members.
  - 6. Space hangers not more than 48 inches o.c. along each member supported directly from hangers, unless otherwise indicated; provide hangers not more than 8 inches from ends of each member.
- C. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
  - 1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
  - 2. Screw attach moldings to substrate at intervals not more than 16 inches o.c. and not more than 3 inches from ends, leveling with ceiling suspension system to a tolerance of 1/8 inch in 12 feet. Miter corners accurately and connect securely.
  - 3. Do not use exposed fasteners, including pop rivets, on moldings and trim.
- D. Install suspension system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- E. Install acoustical panels with undamaged edges and fit accurately into suspension system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide a neat, precise fit.
  - 1. For square-edged panels, install panels with edges fully hidden from view by flanges of suspension system runners and moldings.
  - 2. For reveal-edged panels on suspension system runners, install panels with bottom of reveal in firm contact with top surface of runner flanges.

3. Paint cut edges of panel remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.

#### 3.4 CLEANING

- A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 095113



SECTION 096513 - RESILIENT BASE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Resilient base.

1.2 SUBMITTALS

A. Product Data: For each type of product.

B. Samples: For each exposed product and for each color and texture specified, not less than 12 inches long.

C. Samples for Initial Selection: For each type of product indicated.

D. Samples for Verification: For each type of product indicated and for each color, texture, and pattern required in manufacturer's standard-size Samples, but not less than 12 inches long.

E. Product Schedule: For resilient base.

1.3 DELIVERY, STORAGE, AND HANDLING

A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F.

1.4 FIELD CONDITIONS

A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive resilient products during the following time periods:

1. 48 hours before installation.
2. During installation.
3. 48 hours after installation.

B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 95 deg F.

C. Install resilient products after other finishing operations, including painting, have been completed.

## PART 2 - PRODUCTS

### 2.1 RUBBER BASE

- A. Basis-of-Design Product: As Indicated on the Finish List.

### 2.2 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.
- C. Metal Edge Strips: Extruded aluminum with mill finish of width shown, of height required to protect exposed edges of flooring, and in maximum available lengths to minimize running joints.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
  - 1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
  - 1. Installation of resilient products indicates acceptance of surfaces and conditions.

### 3.2 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.
- B. Do not install resilient products until they are the same temperature as the space where they are to be installed.
  - 1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.

### 3.3 RESILIENT BASE INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient base.

- B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.
- C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.
- D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
- E. Do not stretch resilient base during installation.
- F. Preformed Corners: Install preformed corners before installing straight pieces.

#### 3.4 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.
- B. Perform the following operations immediately after completing resilient-product installation:
  - 1. Remove adhesive and other blemishes from exposed surfaces.
- C. Protect resilient products from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

END OF SECTION 096513

## SECTION 096540 – VINYL PLANK FLOORING

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes the following:
  - 1. Solid vinyl plank flooring.

#### 1.2 SUBMITTALS

- A. Product Data: For each type of product
- B. Shop Drawings: For each type of floor plank. Include floor plank layouts, edges, columns, doorways, enclosing partitions, built-in furniture, cabinets, and cutouts.
  - 1. Show details of special patterns.
- C. Samples: Full-size units of each color and pattern of floor plank required.

#### 1.3 WARRANTY

- A. Manufacturer's Standard warranty to begin at date of Substantial Completion.

### PART 2 - PRODUCTS

#### 2.1 VINYL PLANK FLOORING

- A. Basis of Design Product; As Indicated on the Finish List, Or Equal.

#### 2.2 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by floor plank manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by floor plank and adhesive manufacturers to suit floor plank and substrate conditions indicated.
- C. Floor Polish: Provide protective, liquid floor-polish products recommended by floor plank manufacturer.

## 2.3 ACOUSTIC UNDERLAYMENT

- A. General: Provide underlayment to achieve an assembly rating of 50 STC and 50 IIC for apartments.

## PART 3 - EXECUTION

- A. Prepare substrates according to floor plank manufacturer's written instructions to ensure adhesion of resilient products.
- B. Concrete Substrates: Prepare according to ASTM F 710.
  - 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
  - 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by floor plank manufacturer. Do not use solvents.
  - 3. Alkalinity and Adhesion Testing: Perform tests recommended by floor plank manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing.
  - 4. Moisture Testing: Proceed with installation only after substrates pass testing according to floor plank manufacturer's written recommendations, but not less stringent than the following:
    - a. Perform anhydrous calcium chloride test according to ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
    - b. Perform relative humidity test using in situ probes according to ASTM F 2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level.
- C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- D. Do not install floor planks until they are the same temperature as the space where they are to be installed.
- E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient floor plank.

## 3.2 FLOOR PLANK INSTALLATION

- A. Comply with manufacturer's written instructions for installing floor plank.
- B. Lay out floor planks from center marks established with principal walls, discounting minor offsets, so planks at opposite edges of room are of equal width. Adjust as necessary to avoid using cut widths that equal less than one-half plank at perimeter.
  - 1. Lay planks in pattern indicated.

- C. Match floor planks for color and pattern by selecting planks from cartons in the same sequence as manufactured and packaged, if so numbered. Discard broken, cracked, chipped, or deformed planks.
  - 1. Lay planks in pattern of colors and sizes indicated.
- D. Scribe, cut, and fit floor planks to butt neatly and tightly to vertical surfaces and permanent fixtures including built-in furniture, cabinets, pipes, outlets, and door frames.
- E. Extend floor planks into toe spaces, door reveals, closets, and similar openings. Extend floor planks to center of door openings.
- F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on floor planks as marked on substrates. Use chalk or other nonpermanent marking device.
- G. Install floor planks on covers for telephone and electrical ducts, building expansion-joint covers, and similar items in finished floor areas. Maintain overall continuity of color and pattern between pieces of plank installed on covers and adjoining planks. Tightly adhere plank edges to substrates that abut covers and to cover perimeters.
- H. Adhere floor planks to flooring substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.

### 3.3 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting floor plank.
- B. Floor Polish: Remove soil, adhesive, and blemishes from floor plank surfaces before applying liquid floor polish in accordance with manufacturer's recommendations.

END OF SECTION 096540

SECTION 096813 - TILE CARPETING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Carpet tile.

1.2 SUBMITTALS

A. Product Data: Submit product data for each carpet material and installation accessory required. Submit written data on physical characteristics, durability, resistance to fading, and flame resistance characteristics.

B. Shop Drawings: Show the following:

1. Columns, doorways, enclosing walls or partitions, built-in cabinets, and locations where cutouts are required in carpet tiles.
2. Carpet tile type, color, and dye lot.
3. Type of subfloor.
4. Type of installation.
5. Pattern of installation.
6. Pattern type, location, and direction.
7. Pile direction.
8. Type, color, and location of insets and borders.
9. Type, color, and location of edge, transition, and other accessory strips.
10. Transition details to other flooring materials.

C. Samples: For each of the following products and for each color and texture required. Label each Sample with manufacturer's name, material description, color, pattern, and designation indicated on Drawings and in schedules.

1. Carpet Tile: Full-size Sample.

D. Product Schedule: For carpet tile. Use same designations indicated on Drawings.

E. Qualification Data: For Installer.

F. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency.

G. Maintenance Data: For carpet tiles to include in maintenance manuals. Include the following:

1. Methods for maintaining carpet tile, including cleaning and stain-removal products and procedures and manufacturer's recommended maintenance schedule.
2. Precautions for cleaning materials and methods that could be detrimental to carpet tile.

- H. Warranty: Special warranty specified in this Section.

### 1.3 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who is certified by the Floor Covering Installation Board or who can demonstrate compliance with its certification program requirements.
- B. Fire-Test-Response Characteristics: Provide products with the critical radiant flux classification determined by testing identical products per ASTM E 648 by an independent testing and inspecting agency acceptable to authorities having jurisdiction.
  - 1. Flammability:
    - a. Methenamine Pill: Meets CGSB 4-GP-129/DOC FF-1-70
    - b. Radiant Panel: Class 1 (direct gluedown)
    - c. Smoke Density: ASTM E-662 less than 450.
- C. Preinstallation Conference: Conduct conference at Project site.

### 1.4 DELIVERY, STORAGE, AND HANDLING

- A. Comply with CRI 104.

### 1.5 PROJECT CONDITIONS

- A. Comply with CRI 104 for temperature, humidity, and ventilation limitations.
- B. Comply with manufacturer's requirements for temperature and humidity.
- C. Environmental Limitations: Do not deliver or install carpet tiles until spaces are enclosed and weathertight, wet work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at occupancy levels during the remainder of the construction period.
- D. Do not install carpet tiles until wet work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.
- E. Do not install carpet tiles over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive and concrete slabs have pH range recommended by carpet tile manufacturer.



1.6 WARRANTY

- A. Warranty for Carpet Tiles: Manufacturer agrees to repair or replace components of carpet tile installation that fail in materials or workmanship within specified warranty period.
1. Warranty does not include deterioration or failure of carpet tile due to unusual traffic, failure of substrate, vandalism, or abuse.
  2. Failures include, but are not limited to, more than 10 percent edge raveling, snags, runs, dimensional stability, excess static discharge, loss of tuft bind strength, loss of face fiber, and delamination.
  3. Warranty Period: Minimum 10 years from date of Substantial Completion.

1.7 EXTRA MATERIALS

- A. At the time of building acceptance, deliver to the Owner the following extra materials. Deliver in original unopened cartons or containers with each item properly identified.
1. Furnish extra materials described below that match products installed, are packaged with protective covering for storage, and are identified with labels describing contents.
    - a. Carpet Tile: Full-size units equal to 5 percent of amount installed for each type indicated, but not less than 10 sq. yd.

PART 2 - PRODUCTS

2.1 CARPET TILE

- A. Product and Manufacturer: Refer to the Finish List. Or Equal.

2.2 INSTALLATION ACCESSORIES

- A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided or recommended by carpet tile manufacturer.
- B. Adhesives: Water-resistant, mildew-resistant, nonstaining, pressure-sensitive type to suit products and subfloor conditions indicated, that complies with flammability requirements for installed carpet tile and is recommended by carpet tile manufacturer for releasable installation.
1. VOC Limits: Provide adhesives with VOC content not more than 50 g/L when calculated according to 40 CFR 59, Subpart D (EPA method 24).

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet tile performance. Examine carpet tile for type, color, pattern, and potential defects.
- B. Concrete Subfloors: Verify that concrete slabs comply with ASTM F 710 and the following:
  - 1. Slab substrates are dry and free of curing compounds, sealers, hardeners, and other materials that may interfere with adhesive bond. Determine adhesion and dryness characteristics by performing bond and moisture tests recommended by carpet tile manufacturer.
  - 2. Subfloor finishes comply with requirements specified in Division 3 Section "Cast-in-Place Concrete" for slabs receiving carpet tile.
  - 3. Subfloors are free of cracks, ridges, depressions, scale, and foreign deposits.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 PREPARATION

- A. General: Comply with CRI 104, Section "Site Conditions; Floor Preparation," and with carpet tile manufacturer's written installation instructions for preparing substrates indicated to receive carpet tile installation.
- B. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, depressions, and protrusions in substrates. Fill or level cracks, holes and depressions 1/8 inch wide or wider and protrusions more than 1/32 inch, unless more stringent requirements are required by manufacturer's written instructions.
- C. Remove coatings, including curing compounds, and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, without using solvents. Use mechanical methods recommended in writing by carpet tile manufacturer.
- D. Broom and vacuum clean substrates to be covered immediately before installing carpet tile.

#### 3.3 INSTALLATION

- A. General: Comply with manufacturer's instructions and recommendations for carpet installation.
- B. Maintain dye lot integrity. Do not mix dye lots in same area.
- C. Cut and fit carpet tile to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended by carpet tile manufacturer.

- D. Extend carpet tile into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.
- E. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on finish flooring as marked on subfloor. Use nonpermanent, nonstaining marking device.
- F. Install pattern parallel to walls and borders.
- G. Stagger joints of carpet tiles so carpet tile grid is offset from access flooring panel grid. Do not fill seams of access flooring panels with carpet adhesive; keep seams free of adhesive.

### 3.4 CLEANING AND PROTECTION

- A. Perform the following operations immediately after installing carpet tile:
  - 1. Remove excess adhesive, seam sealer, and other surface blemishes using cleaner recommended by carpet tile manufacturer.
  - 2. Remove yarns that protrude from carpet tile surface.
  - 3. Vacuum carpet tile using commercial machine with face-beater element.
- B. Protect installed carpet tile to comply with CRI 104 "Protection of Indoor Installations."
- C. Protect carpet tile against damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by carpet tile manufacturer.

END OF SECTION 096813

SECTION 096900 - ACCESS FLOORING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Cementitious-core steel panel access flooring.

1.2 COORDINATION

- A. Coordinate location of mechanical and electrical work in underfloor cavity to prevent interference with access flooring.
- B. Mark pedestal locations on subfloor to enable mechanical and electrical work to proceed without interfering with access-flooring pedestals installed after mechanical and electrical work.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review connections between access flooring and mechanical and electrical systems.
2. Review procedures for keeping underfloor space clean.

1.4 SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for access flooring.
2. Include loading capacities.

B. Shop Drawings: For access flooring:

1. Include layout of access flooring and relationship to adjoining Work based on field-verified dimensions.
2. Details and sections with descriptive notes indicating materials, finishes, fasteners, typical and special edge conditions, accessories, and understructures.

C. Samples: For the following products:

1. Floor Coverings: Full-size units for each color and texture specified.
2. Exposed Metal Accessories: Approximately 10 inches in length.
3. One full-size floor panel, pedestal, and understructure unit for each type of access flooring required.

1.5 INFORMATIONAL SUBMITTALS.

- A. Qualification Data: For Installer.
- B. Product Certificates: For each type of access flooring.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Panels: 10 square feet.
  - 2. Pedestals: 10 square feet.
  - 3. Stringers: 10 square feet.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

1.8 DESIGN REQUIREMENTS

- A. Access floor system, where indicated on the design documents, shall consist of modular and removable fully encased cementitious filled welded steel panels fastened onto, and supported by, adjustable height pedestal assemblies. Pedestal head and panel corner design must provide a positive location and lateral engagement of the panel to the understructure support system without the use of fasteners.
- B. Panel shall be easily removed by one person with a suction cup lifting device and shall be interchangeable.

1.9 FIELD CONDITIONS

- A. Area to receive and store access floor materials shall be enclosed and maintained at ambient temperatures between 35° to 95° F and relative humidity levels between 20 to 80%. All floor panels shall be stored at ambient temperatures between 50° to 90° F for at least 24 hours before installation begins. All areas of installation shall be enclosed and maintained at ambient temperature between 50° to 90° F and at relative humidity levels between 20% to 80% and shall remain within these environmental limits throughout occupancy.

1.10 REFERENCES

- A. CISCA (Ceilings & Interior Systems Construction Association) - "Recommended Test Procedures for Access Floors" shall be used as a guideline when presenting load performance product information.

#### 1.11 PERFORMANCE CERTIFICATION

- A. Product tests shall be witnessed and certified by independent engineering and testing laboratory based in the U.S. with a minimum of five years experience testing access floor components in accordance CISCA "Recommended Test Procedures for Access Floors".

### PART 2 - PRODUCTS

#### 2.1 PERFORMANCE REQUIREMENTS

- A. Design Load: Panel supported on actual understructure system shall be capable of supporting a point load of 1250 lbs applied on a one square inch area at any location on the panel without experiencing permanent set as defined by CISCA. The loading method used to determine design (allowable) load shall be in conformance with CISCA Concentrated Load test method but with panel tested on actual understructure instead of steel blocks.
- B. Safety Factor: Panel supported on actual understructure system shall withstand a point load of no less than (2) two times the design load rating on a one square inch area anywhere on the panel without failure when tested in accordance with CISCA A/F, Section 2 "Ultimate Loading". Failure is defined as the point at which the system will no longer accept the load.
- C. Ultimate Load: Panel supported on actual understructure system shall be capable of supporting a point load of at least 2500 lbs applied through a load indenter on a one square inch area at any location on the panel without failure (i.e. minimum safety factor of 2) when tested in accordance with CISCA A/F, Section 2, "Ultimate Loading".
- D. Rolling Load: Panel supported on actual understructure system shall be able to withstand the following rolling loads at any location on the panel without developing a local and overall surface deformation greater than 0.040 inches when tested in accordance with CISCA A/F, Section 3, "Rolling Loads". Note: wheel 1 and wheel 2 tests shall be performed on two separate panels.
1. CISCA Wheel 1: Size: 3" dia x 1 13/16" wide Load: 1125 lbs. Passes:10
  2. CISCA Wheel 2: Size: 6" dia x 2" wide Load: 875 lbs. Passes:10,000
- E. Impact Load: Panel supported on actual understructure (the system) shall be capable of supporting an impact load of 150 lbs. dropped from a height of 36 inches onto a one square inch area (using a round or square indenter) at any location on the panel when tested in accordance with CISCA A/F Section 8, "Drop Impact Load Test".
- F. Panel Drop Test: Panel shall be capable of being dropped face up onto to a concrete slab from a height of 36", after which it shall continue to meet all load performance requirements as previously defined.
- G. Panel Cutout: Panel with an 8" diameter interior cutout supported on actual understructure shall be capable of maintaining its design load strength with a minimum safety factor of 2 anywhere on the panel without the use of additional supports.
- H. Flammability: System shall meet *Class A* Flame spread requirements for flame spread and smoke development. Tests shall be performed in accordance with ASTM-E84-1998, Standard Test Method for Surface Burning Characteristics for Building Materials.

- I. Combustibility: All components of the access floor system shall qualify as noncombustible by demonstrating compliance with requirements of ASTM E 136, Standard Test Method for Behavior of Materials in a Vertical Tube Furnace at 750 deg C.
- J. Axial Load: Pedestal support assembly shall provide a minimum 6000 lb. axial load without permanent deformation when tested in accordance with CISCA A/F, Section 5, "Pedestal Axial Load Test."
- K. Overturning Moment: Pedestal support assembly shall provide an average overturning moment of 1000 in-lbs. when glued to a clean, sound, uncoated concrete surface when tested in accordance with CISCA A/F, Section 6, "Pedestal Overturning Moment Test". ICBO number for the specific system or structural calculations shall be required attesting to the lateral stability of the system under seismic conditions.

## 2.2 CEMENTITIOUS-CORE STEEL PANEL ACCESS FLOORING

- A. Fabricate panels from cold-rolled steel sheet, with die-cut flat top sheet and die-formed and stiffened bottom pan welded together. Protect metal surfaces against corrosion using manufacturer's standard factory-applied finish. Fully grout internal spaces of completed units with manufacturer's standard cementitious fill.
  - 1. Basis-of-Design Product: Subject to compliance with requirements, provide Tate Access Floors, Inc; Concore or a comparable product by one of the following:
    - a. ASM Modular Systems, Inc.
    - b. Camino Modular Systems, Inc.
  - 2. Configuration: Provide modular panels with nominal size of 24 by 24 inches, interchangeable with other field panels without disturbing adjacent panels or understructure.
  - 3. Attachment to Understructure: Manufacturers Standard.
  - 4. Finish: Manufacturer's standard.
- B. Pedestal System Understructure: System consisting of base, column with provisions for height adjustment, and head (cap); made of steel.
  - 1. Base: Square or circular base with not less than 16 sq. in. of bearing area.
  - 2. Column: Of height required to bring finished floor to elevations indicated. Weld column to base plate.
  - 3. Provide vibration-proof leveling mechanism for making and holding fine adjustments in height over a range of not less than +/- 1-inch and for locking at a selected height, so deliberate action is required to change height setting and prevent vibratory displacement.
  - 4. Head: Designed to support the floor panel indicated.
    - a. Bolted Assemblies: Provide head with four holes aligned with holes in floor panels for bolting of panels to pedestals.

## 2.3 ACCESSORIES

- A. Provide manufacturer's standard steps, ramps, fascia plate, perimeter support, and grommets where indicated on the contract drawings.

## 2.4 FINISHES

- A. Carpet tile: Access floor system shall be designed to accommodate a modular carpet tile that precisely matches one carpet tile to one panel, by utilizing four positioning buttons on the carpet tile which engage into four positioning location holes within the top surface of the access floor panel. Adhesives shall not be permitted except where the carpet is cut and more than two positioners are removed.
- B. Fabrication Tolerances
  - 1. Floor panel flatness measured on a diagonal:  $\pm 0.035''$
  - 2. Floor panel flatness measured along edges:  $\pm 0.025''$
  - 3. Floor panel width or length of required size:  $\pm 0.010''$
  - 4. Floor panel squareness tolerance:  $\pm 0.015''$

## 2.5 FABRICATION

- A. Panel Markings: Clearly and permanently mark floor panels on their underside with panel type and concentrated-load rating.
- B. Bolted Panels: Provide panels with holes drilled in corners to align precisely with threaded holes in pedestal heads and to accept countersunk screws with heads flush with top of panel.
  - 1. Captive Fasteners: Provide fasteners held captive to panels.
- C. Cutouts: Fabricate cutouts in floor panels for cable penetrations and service outlets. Provide reinforcement or additional support, if needed, to make panels with cutouts comply with structural performance requirements.
  - 1. Grommets: Where indicated, fit cutouts with manufacturer's standard grommets; or, if size of cutouts exceeds maximum grommet size available, trim edge of cutouts with manufacturer's standard plastic molding with tapered top flange. Furnish removable covers for grommets.

## 2.6 ACCESSORIES

- A. Adhesives: Manufacturer's standard adhesive for bonding pedestal bases to subfloor.
- B. Ramps: Manufacturer's standard ramp construction of width and slope indicated, but not steeper than 1:12, with raised-disc or textured rubber or vinyl-tile floor coverings, and of same materials, performance, and construction requirements as access flooring.



- C. Panel Lifting Device: Provide (2) Panel manufacturer's standard portable lifting device for each type of panel required.
- D. Perimeter Support: Where indicated, provide manufacturer's standard method for supporting panel edge and forming transition between access flooring and adjoining floor coverings at same level as access flooring.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates, with Installer and manufacturer's authorized representative present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
  - 1. Verify that substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of conditions and deleterious substances that might interfere with attachment of pedestals.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 PREPARATION

- A. Lay out floor panel installation to keep the number of cut panels at floor perimeter to a minimum. Avoid using panels cut to less than 6 inches.
- B. Locate each pedestal, complete any necessary subfloor preparation, and vacuum subfloor to remove dust, dirt, and construction debris before beginning installation.
- C. Slab shall be broom swept clean prior to installation.

#### 3.3 INSTALLATION

- A. Install access flooring and accessories under supervision of access-flooring manufacturer's authorized representative to produce a rigid, firm installation that complies with performance requirements and is free of instability, rocking, rattles, and squeaks.
- B. Adhesive Attachment of Pedestals: Set pedestals in adhesive, according to access-flooring manufacturer's written instructions, to provide full bearing of pedestal base on subfloor.
- C. Adjust pedestals so installed panels are flat, level, and at the proper height.
- D. Install flooring panels securely in place, leaving them properly seated with panel edges flush. Do not force panels into place.
- E. Scribe perimeter panels to provide a close fit, with adjoining construction having no voids greater than 1/8 inch where panels abut vertical surfaces.
- F. Finished floor shall be level, not varying more than 0.062" in 10 feet or 0.125" overall.

- G. Inspect system prior to application of floor covering and replace any floor panels that are cracked, broken and structurally damaged and do not comply with specified requirements.
- H. Installed panels shall be straight and square and spaced so that the distance from one end to the other of any line of 12 panels is not less than 24 feet and does not exceed 24' 1/8".
- I. Acceptance: General contractor shall accept floor in whole or in part prior to allowing use by other trades.
- J. All cable and wire openings shall be sealed with manufacturer's removable cable cutout seal or grommets.
- K. Install access flooring without change in elevation between adjacent panels and within the following tolerances:
  - 1. Plus or minus 1/16 inch in any 10-foot distance.
  - 2. Plus or minus 1/8 inch from a level plane over entire access flooring area.

#### 3.4 PROTECTION

- A. Prohibit traffic on access flooring for 24 hours and removal of floor panels for 72 hours after installation, to allow pedestal adhesive to set.
- B. Replace access-flooring panels that are stained, scratched, or otherwise damaged or that do not comply with specified requirements.

END OF SECTION 096900

## SECTION 099100 - PAINTING

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section Includes:
1. Exposed interior items and surfaces.
  2. Surface preparation, priming, and finish coats specified in this Section are in addition to shop priming and surface treatment specified in other Sections.
- B. Paint exposed surfaces, except where the paint schedules indicate that a surface or material is not to be painted or is to remain natural. If the paint schedules do not specifically mention an item or a surface, paint the item or surface the same as similar adjacent materials or surfaces whether or not schedules indicate colors. If the schedules do not indicate color or finish, the Architect will select from standard colors and finishes available. Painting includes field painting of exposed bare and covered pipes and ducts (including color coding), hangers, exposed steel and iron work, and primed metal surfaces of mechanical and electrical equipment installed and application of paint coats to all finish coated mechanical and electrical equipment, except as otherwise indicated.
- C. Do not paint prefinished items, concealed surfaces, finished metal surfaces, operating parts, and labels.
- D. Do not paint over Underwriters Laboratories (UL), Factory Mutual (FM), or other code-required labels or equipment name, identification, performance rating, or nomenclature plates.

#### 1.2 SUBMITTALS

- A. Product Data: For each paint system specified. Include primers.
1. Material List: Provide an inclusive list of required coating materials. Indicate each material and cross-reference specific coating, finish system, and application. Identify each material by manufacturer's catalog number and general classification.
  2. Manufacturer's Information: Provide manufacturer's technical information, including label analysis and instructions for handling, storing, and applying each coating material proposed for use.

- B. Samples for Initial Selection: Manufacturer's color charts showing the full range of colors available for each type of finish-coat material indicated.
  - 1. After color selection, the Architect will furnish color chips for surfaces to be coated.
- C. Samples for Verification: Of each color and material to be applied, with texture to simulate actual conditions, on representative Samples of the actual substrate.
  - 1. Provide stepped Samples, defining each separate coat, including primers. Use representative colors when preparing Samples for review. Resubmit until required sheen, color, and texture are achieved.
  - 2. Provide a list of materials and applications for each coat of each sample. Label each sample for location and application.
  - 3. On actual wall surfaces and interior building components, duplicate painted finishes of prepared samples. On at least 100 square feet of surface, as directed, provide full-coat finish samples until required sheen level., color and texture is obtained; simulate finished lighting conditions for review of in-place work.
- D. Qualification Data: For firms and persons specified in the "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.

### 1.3 QUALITY ASSURANCE

- A. Applicator Qualifications: Engage an experienced applicator who has completed painting system applications similar in material and extent to that indicated for this Project with a record of successful in-service performance.
- B. Source Limitations: Obtain primers, and undercoat materials for each coating system from the same manufacturer as the finish coats.

### 1.4 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials to the Project Site in manufacturer's original, unopened packages and containers bearing manufacturer's name and label, and the following information:
  - 1. Product name or title of material.
  - 2. Product description (generic classification or binder type).
  - 3. Manufacturer's stock number and date of manufacture.
  - 4. Contents by volume, for pigment and vehicle constituents.
  - 5. Thinning instructions.
  - 6. Application instructions.
  - 7. Color name and number.
  - 8. VOC content.

- B. Store materials not in use in tightly covered containers in a well-ventilated area at a minimum ambient temperature of 45 deg F. Maintain containers used in storage in a clean condition, free of foreign materials and residue.
  - 1. Protect from freezing. Keep storage area neat and orderly. Remove oily rags and waste daily. Take necessary measures to ensure that workers and work areas are protected from fire and health hazards resulting from handling, mixing, and application.

## 1.5 PROJECT CONDITIONS

- A. Apply water-based paints only when the temperature of surfaces to be painted and surrounding air temperatures are between 50 and 90 degrees F.
- B. Apply solvent-thinned paints only when the temperature of surfaces to be painted and surrounding air temperatures are between 45 and 95 degrees F.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Products and Manufacturers: Subject to compliance with requirements, products and manufacturers specified include, but are not limited to, the following:
  - 1. The Sherwin-Williams Company
- B. Other Products and Manufacturers: Subject to compliance with requirements, available products and manufacturers that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Benjamin Moore & Company (Moore)
  - 2. Glidden Professional
  - 3. PPG Industries, Inc. (PPG)

### 2.2 PAINT MATERIALS, GENERAL

- A. Material Compatibility: Provide primers, and finish-coat materials that are compatible with one another and the substrates indicated under conditions of service and application, as demonstrated by manufacturer based on testing and field experience.

- B. Material Quality: Provide manufacturer's best-quality paint material of the various coating types specified. Paint-material containers not displaying manufacturer's product identification will not be acceptable.
  - 1. Proprietary Names: Use of manufacturer's proprietary product names to designate colors or materials is not intended to imply that products named are required to be used to the exclusion of equivalent products of other manufacturers. Furnish manufacturer's material data and certificates of performance for proposed substitutions.
- C. Colors: Provide color selections made by the Architect.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with the Applicator present, under which painting will be performed for compliance with paint application requirements.
  - 1. Do not begin to apply paint until unsatisfactory conditions have been corrected and surfaces receiving paint are thoroughly dry.
  - 2. Start of painting will be construed as the Applicator's acceptance of surfaces and conditions within a particular area.
- B. Coordination of Work: Review other Sections in which primers are provided to ensure compatibility of the total system for various substrates. On request, furnish information on characteristics of finish materials to ensure use of compatible primers.
  - 1. Notify the Architect about anticipated problems using the materials specified over substrates primed by others.

#### 3.2 PREPARATION

- A. General: Remove hardware and hardware accessories, plates, machined surfaces, lighting fixtures, and similar items already installed that are not to be painted. If removal is impractical or impossible because of the size or weight of the item, provide surface-applied protection before surface preparation and painting.
  - 1. After completing painting operations in each space or area, reinstall items removed using workers skilled in the trades involved.
- B. Cleaning: Before applying paint or other surface treatments, clean the substrates of substances that could impair the bond of the various coatings. Remove oil and grease before cleaning.

1. Schedule cleaning and painting so dust and other contaminants from the cleaning process will not fall on wet, newly painted surfaces.

C. Surface Preparation: Clean and prepare surfaces to be painted according to manufacturer's written instructions for each particular substrate condition and as specified.

D. Materials Preparation: Mix and prepare paint materials according to manufacturer's written instructions.

E. Tinting: Tint each undercoat a lighter shade to simplify identification of each coat when multiple coats of the same material are applied. Tint undercoats to match the color of the finish coat, but provide sufficient differences in shade of undercoats to distinguish each separate coat.

### 3.3 APPLICATION

A. General: Apply paint according to manufacturer's written instructions. Use applicators and techniques best suited for substrate and type of material being applied.

### 3.4 CLEANING

A. Cleanup: At the end of each workday, remove empty cans, rags, rubbish, and other discarded paint materials from the site.

1. After completing painting, clean glass and paint-spattered surfaces. Remove spattered paint by washing and scraping. Be careful not to scratch or damage adjacent finished surfaces.

### 3.5 PROTECTION

A. Protect work of other trades, whether being painted or not, against damage by painting. Correct damage by cleaning, repairing or replacing, and repainting, as approved by Architect.

B. Provide "Wet Paint" signs to protect newly painted finishes. Remove temporary protective wrappings provided by others to protect their work after completing painting operations.

1. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces. Comply with procedures specified in PDCA P1.

### 3.6 INTERIOR PAINT SCHEDULE

#### A. Gypsum Drywall – Walls:

1. Paint System, Application and Finish: Latex; two Finish Coats over Primer.
  - a. Primer: Promar 200 Zero VOC Latex Primer
  - b. Finish Coats: Promar 200 Zero VOC Interior Latex
  - c. Sheen Level: Refer to the Finish Legend.

#### B. Ferrous Metal: Includes steel doors and frames, handrails and railings.

1. Paint System, Application and Finish:
  - a. Primer: Kem Kromik Universal Metal Primer
  - b. Finish Coats: ProIndustrial Urethane Alkyd Enamel
  - c. Sheen Level: Refer to the Finish Legend.

### 3.7 EXTERIOR PAINT

- A. For touch-up, match existing.

END OF SECTION 099100



## SECTION 134715 - BULLET RESISTANT PANELS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section Includes
  - 1. Bullet Resistant Panels.

#### 1.2 SUBMITTALS

- A. Product Data: Manufacturer's data sheets on each product to be used, including:
  - 1. Preparation instructions and recommendations.
  - 2. Storage and handling requirements and recommendations.
  - 3. Installation methods.
- B. Shop Drawings:
  - 1. Submit shop drawings prepared by the manufacturer showing plans, sections, elevations, layouts, profiles and product component locations, including anchorage, fasteners, and accessories.
- C. Design Data: Bullet resistance analysis design calculations for specific project conditions, certifying system conformance to specified performance requirements.
- D. Test Reports: Certified test reports showing compliance with specified performance characteristics and physical properties.

#### 1.3 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing products of the type specified with a minimum documented experience of five years.
- B. Installer Qualifications: Company specializing in installation of products specified with minimum three years documented experience.
- C. Pre-installation Meetings: Conduct pre-installation meeting to verify project requirements, substrate conditions, and manufacturer's installation instructions.
- D. Coordination of Work: Coordinate layout and installation of components with other construction supported by, or penetrating through, ceilings, including light fixtures, HVAC equipment, fire-suppression system, and partitions.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials in manufacturer's unopened, undamaged packaging, with manufacturer's labels intact.
- B. Store products in manufacturer's unopened packaging until ready for installation.
- C. Store assemblies, off the ground and on end, to prevent damage to face corners and edges.
- D. Store assemblies covered to protect them from damage but permitting air circulation.

1.5 PROJECT CONDITIONS

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Basis of Design product and Manufacturer; ArmorCo. Kevlar Ballistic Panel NIJ IIIA.
  - 1. UL-752 Level 3.
- B. Other Acceptable Manufacturers which may be incorporated into the work are but not limited to the following:
  - 1. Total Security Solutions.
  - 2. Bulldog Direct Protective Systems, Inc.

2.2 APPLICATIONS/SCOPE

- A. Bullet resistant protection shall be provided in the sizes and in the configuration indicated on the Drawings.
- B. Provide components complete with adhesive, fasteners, and other devices required for complete assembly.

### 2.3 BULLET RESISTANT PANELS

- A. Bullet Protection Panels. Kevlar composite panel manufactured using multiple layers of ballistic grade Kevlar impregnated with resin and compressed into flat rigid sheets.
  - 1. Panels shall be of the "non ricochet type" intended to permit the encapture and retention of an attacking projectile lessening the potential of lateral penetration.
  - 2. Panels conforming to UL 752 Rating level as follows:
    - a. UL Level 3.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Do not begin installation until openings and installing surfaces have been properly prepared.
- B. Verify openings are in accordance with approved shop drawings

#### 3.2 PREPARATION

- A. Clean surfaces thoroughly prior to installation.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

#### 3.3 INSTALLATION

- A. Install in accordance with manufacturer's instructions and requirements of UL 752.
- B. Install all equipment plumb, level, rigid and in true alignment.
- C. Set equipment in accordance with the manufacturer's printed recommendations. Use proper anchoring devices for the material to be anchored to. All exposed anchor holes shall be used for anchoring.
- D. Bullet Resistant panels can be installed using an industrial adhesive, mastic, screws or bolts. Method of application shall maintain the bullet resistive rating at junctures with the concrete floor slab, concrete roof slab, bullet resistive door frames, bullet resistive window frames, and all required penetrations.
  - 1. All joints reinforced by a back-up layer of bullet resistive material.
  - 2. Bullet resistance of the joint, as reinforced, shall be at least equal to that of the panel.
  - 3. Minimum width of reinforcing layer at joint shall be 4 inches (2 inches on each panel or a 2 inch minimum overlap).

END OF SECTION 134715

SECTION 211313 - WET-PIPE SPRINKLER SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes wet-pipe sprinkler system, system design, installation, and certification. The entire system shall be installed in conformance with NFPA 13.
- B. Section Includes:
  - 1. Pipes, fittings, and specialties.
  - 2. Sprinklers.

1.3 DEFINITIONS

- A. Standard-Pressure Sprinkler Piping: Wet-pipe sprinkler system piping designed to operate at working pressure of 175 psig maximum.

1.4 REFERENCES

- A. Florida Building Code, 2014
- B. Florida Building Code, Existing Building Code, 2014
- C. Florida Fire Prevention Code, 2014
- D. NFPA 13 (National Fire Protection Association) - Installation of Sprinkler Systems
- E. NFPA 25 (National Fire Protection Association) – Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection System
- F. NFPA 72 (National Fire Protection Association) – National Fire Alarm Code
- G. 2016 Underwriters Laboratories, Inc. (UL) Fire Protection Equipment Directory
- H. Requirements of Owner Insurance Underwriter and Other Authorities Having Jurisdiction as applicable.

#### 1.5 SYSTEM DESCRIPTIONS

- A. Wet-Pipe Sprinkler System: Automatic sprinklers are attached to piping containing water that is connected to the water supply through an alarm valve. Water discharges immediately from sprinklers when they are opened. Sprinklers open when heat melts the fusible link or destroys the frangible device. Hose connections are included if indicated. System to provide coverage for all areas in the building except those noted on the contract documents.
- B. Provide hydraulically designed system to NFPA 13 occupancy requirements. Provide all sprinkler risers with hydraulic data plate with system design information. Mount to respective riser. This data plate shall include the location of the design area or areas, discharge densities over the design area or areas, required flow and residual pressure demand at the base of the riser, occupancy classification or commodity classification and maximum permitted storage height/configuration, and hose stream demand included in addition to the sprinkler demand.
- C. Contactor shall perform flow test per NFPA 291 to verify available supply.
- D. Sprinkler system shall be hydraulically calculated. Pipe sizes shown on drawings shall be maintained and used in calculations.
- E. Light Hazard Design Criteria: 0.10 gpm/ft<sup>2</sup> over 1500 ft<sup>2</sup> design area with an outside hose stream demand of 100 gpm for a duration of 30 minutes.
- F. Ordinary Hazard Group 1 Design Criteria: 0.15 gpm/ft<sup>2</sup> over 1500 ft<sup>2</sup> design area with an outside hose stream demand of 250 gpm for a duration of 60-90 minutes.
- G. Sprinkler spacing shall not exceed 196 ft<sup>2</sup> for Light Hazard, 130 ft<sup>2</sup> for Ordinary Hazard
- H. Sprinkler spacing shall not exceed 196 ft<sup>2</sup> for Light Hazard
- I. A 10% safety factor should be incorporated into all hydraulic calculations.
- J. Maximum 20 fps system flow velocity and 15 fps in mains with paddle water flow switches.

#### 1.6 PERFORMANCE REQUIREMENTS

- A. Standard-Pressure Piping System Component: Listed for 175-psig minimum working pressure.
- B. Sprinkler system design shall be approved by authorities having jurisdiction.
  - 1. Sprinkler Occupancy Hazard Classifications:
    - a. Building Service Areas: Ordinary Hazard, Group 1.
    - b. Electrical Equipment Rooms: Ordinary Hazard, Group 1.
    - c. General Storage Areas: Ordinary Hazard, Group 1.
    - d. Mechanical Equipment Rooms: Ordinary Hazard, Group 1.
    - e. Office and Public Areas: Light Hazard.

#### 1.7 SUBMITTALS

- A. Submittal Procedures: Submittal procedures as indicated in Division 1 of these specifications.

- B. Shop Drawings: NFPA 13 drawings, hydraulic calculations for each design area with cross reference to applicable drawings, water supply data, and equipment schedule. Indicate layout of finished ceiling areas indicating sprinkler locations coordinated with ceiling installation. Indicate detailed pipe layout, hangers and supports, sprinklers, components and accessories. Indicate system controls. Provide coordination drawings indicating the work of other trades.
  - 1. Sprinklers shall be referred to on drawings, submittals and other documentation, by the sprinkler identification or Model number as specifically published in the appropriate agency listing or approval. Trade names or other abbreviated designations shall not be allowed.
- C. Product Data: Submit data on sprinklers, valves, and specialties, including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.
- D. Fire Hydrant Flow Test Report: Prior to system layout, submit detailed fire flow test data per NFPA 291. Include scaled/dimensioned drawing showing flow/pressure locations/elevations; number/size/coefficient for orifices; pitot/static/residual pressures; test time/date; main sizes.
- E. Approved sprinkler drawings: working plans, prepared according to NFPA 13, that have been approved by authorities having jurisdiction and owner's representative, including hydraulic calculations.

#### 1.8 CLOSEOUT SUBMITTALS

- A. Execution Requirements: Closeout procedures as indicated in division 1 of these specifications.
- B. Project Record Documents: Record actual locations of sprinklers and deviations of piping from drawings. Indicate drain and test locations.
- C. Operation and Maintenance Data: Submit components of system, servicing requirements, record drawings, inspection data, replacement part numbers and availability, and location and numbers of service depot.
- D. Submit the latest edition of NFPA 25 "Standard for the Inspection, Testing, and Maintenance of Water Based Fire Protection System" to the owner upon completion of project.
- E. Field Test Reports and Certificates: Indicate and interpret test results for compliance with performance requirements and as described in NFPA 13. Include "Contractor's Material and Test Certificate for Above Ground Piping".
- F. Schedule of preventative maintenance inspections/testing and outline of what inspections/testing shall occur.

#### 1.9 QUALITY ASSURANCE

- A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum three years documented experience, and with service facilities within 100 miles of project.

- B. Installer: Company specializing and licensed in performing work of this section with minimum five years documented experience and NICET (National Institute for Certification in Engineering Technologies) certified.
- C. System shall be designed and installed under the direct supervision of a NICET Level IV certified designer in Fire Protection/Automatic Sprinkler System Layout.
- D. Firestop Installer Qualifications: FM 4991, UL, or proof of certified training.
- E. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

1.10 MAINTENANCE SERVICE

- A. Furnish service and maintenance of the system components for one year from the Date of Substantial Completion as outlined in Division 21 specifications.

1.11 PROJECT CONDITIONS

- A. Interruption of Existing Sprinkler Service: Do not interrupt sprinkler service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary sprinkler service according to requirements indicated:
  - 1. Notify Owner no fewer than two days in advance of proposed interruption of sprinkler service.
  - 2. Do not proceed with interruption of sprinkler service without Owner's written permission.
  - 3. Fire safety during construction and/or demolition shall be performed in accordance with the Florida Building Code..

1.12 COORDINATION

- A. Coordinate layout and installation of sprinklers with other construction that penetrates ceilings, including light fixtures, HVAC equipment, and partition assemblies.

1.13 EXTRA MATERIALS

- A. Provide extra sprinklers as required by NFPA 13.
- B. Provide suitable wrenches for each sprinkler type.
- C. Provide all manufacturer special tools for maintenance of system.

1.14 ADDITIONAL SPRINKLERS AND GUARDS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

## PART 2 - PRODUCTS

### 2.1 PIPING MATERIALS

- A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, and fitting materials, and for joining methods for specific services, service locations, and pipe sizes.

### 2.2 STEEL PIPE AND FITTINGS

- A. Standard Weight, Black Steel Pipe: ASTM A 53/A 53M, or ASTM A 135, ASTM A 795, Schedule 40 for NPS 2 and smaller. Pipe ends may be factory or field formed to match joining method.
- B. Standard Weight, Black Steel Pipe: ASTM A 53/A 53M, or ASTM A 135, ASTM A 795, Schedule 10 for NPS 2.5 and larger. Pipe ends may be factory or field formed to match joining method
- C. BlackSteel Pipe Nipples: ASTM A 733, made of ASTM A 53/A 53M, standard-weight, seamless steel pipe with threaded ends.
- D. Uncoated, Steel Couplings: ASTM A 865, threaded.
- E. Uncoated, Gray-Iron Threaded Fittings: ASME B16.4, Class 125, standard pattern.
- F. Malleable- or Ductile-Iron Unions: UL 860.
- G. Cast-Iron Flanges: ASME 16.1, Class 125.
- H. Steel Flanges and Flanged Fittings: ASME B16.5, Class 150.
- I. Steel Welding Fittings: ASTM A 234/A 234M and ASME B16.9.
- J. Grooved-Joint, Steel-Pipe Appurtenances:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Anvil International, Inc.
    - b. Tyco Fire & Building Products LP.
    - c. Victaulic Company.
  - 2. Pressure Rating: 175 psigminimum.
  - 3. Uncoated, Grooved-End Fittings for Steel Piping: ASTM A 47/A 47M, malleable-iron casting or ASTM A 536, ductile-iron casting; with dimensions matching steel pipe.
  - 4. Grooved-End-Pipe Couplings for Steel Piping: AWWA C606 and UL 213, rigid pattern, unless otherwise indicated, for steel-pipe dimensions. Include ferrous housing sections, EPDM-rubber gasket, and bolts and nuts.



## 2.3 PIPING JOINING MATERIALS

- A. Pipe-Flange Gasket Materials: AWWA C110, rubber, flat face, 1/8 inch.
  - 1. Class 125, Cast-Iron Flanges and Class 150, Bronze Flat-Face Flanges: Full-face gaskets.
  - 2. Class 250, Cast-Iron Flanges and Class 300, Steel Raised-Face Flanges: Ring-type gaskets.
- B. Metal, Pipe-Flange Bolts and Nuts: ASME B18.2.1, carbon steel unless otherwise indicated.

## 2.4 SPRINKLERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Reliable Automatic Sprinkler Co., Inc.
  - 2. Tyco Fire & Building Products LP.
  - 3. Victaulic Company.
  - 4. Viking Corporation.
- B. General Requirements:
  - 1. Standard: UL's "Fire Protection Equipment Directory" listing or "Approval Guide," published by FM Global, listing.
  - 2. Pressure Rating for Automatic Sprinklers: 175 psig minimum.
- C. Automatic Sprinklers with Heat-Responsive Element:
  - 1. Nonresidential Applications: UL 199.
  - 2. Characteristics: Nominal 1/2-inch orifice with Discharge Coefficient K of 5.6, and for "Ordinary" temperature classification rating unless otherwise indicated or required by application.
- D. Sprinkler Finishes:
  - 1. Chrome plated.
  - 2. Painted.
- E. Sprinkler Escutcheons: Materials, types, and finishes for the following sprinkler mounting applications. Escutcheons for concealed, flush, and recessed-type sprinklers are specified with sprinklers.
  - 1. Ceiling Mounting: Chrome-plated steel, two piece, with 1-inch vertical adjustment.
- F. Sprinkler Guards:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Reliable Automatic Sprinkler Co., Inc.
    - b. Tyco Fire & Building Products LP.
    - c. Victaulic Company.
    - d. Viking Corporation.

2. Standard: UL 199.
3. Type: Wire cage with fastening device for attaching to sprinkler.

### PART 3 - EXECUTION

#### 3.1 PREPARATION

- A. Perform fire-hydrant flow test according to NFPA 13 and NFPA 291. Use results for system design calculations required in "Systems Description" Article.
- B. Report test results promptly and in writing.

#### 3.2 PIPING INSTALLATION

- A. Locations and Arrangements: Drawing plans, schematics, and diagrams indicate general location and arrangement of piping. Install piping as indicated, as far as practical.
  1. Deviations from approved working plans for piping require written approval from authorities having jurisdiction. File written approval with Architect before deviating from approved working plans.
  2. Install piping to minimize obstructions to other trades.
  3. Install piping concealed above finished ceilings unless noted otherwise.
  4. Pipe size called for shall be maintained. Pipe size changes made only as reviewed by owner's representative. Where discrepancy in size occurs, the larger size shall be provided.
- B. Piping Standard: Comply with requirements for installation of sprinkler piping in NFPA 13.
- C. Use listed fittings to make changes in direction, branch takeoffs from mains, and reductions in pipe sizes.
- D. Install unions adjacent to each valve in pipes NPS 2 and smaller.
- E. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.
- F. Install sprinkler piping with drains for complete system drainage.
- G. Install hangers and supports for sprinkler system piping according to NFPA 13. Comply with requirements for hanger materials in NFPA 13.
- H. Fill sprinkler system piping with water.
- I. Install escutcheons for piping penetrations of walls, ceilings, and floors.

### 3.3 JOINT CONSTRUCTION

- A. Install couplings, flanges, flanged fittings, unions, nipples, and transition and special fittings that have finish and pressure ratings same as or higher than system's pressure rating for aboveground applications unless otherwise indicated.
- B. Install unions adjacent to each valve in pipes NPS 2 and smaller.
- C. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.
- D. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- E. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.
- F. Flanged Joints: Select appropriate gasket material in size, type, and thickness suitable for water service. Join flanges with gasket and bolts according to ASME B31.9.
- G. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
  - 1. Apply appropriate tape or thread compound to external pipe threads.
  - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
- H. Steel-Piping, Roll-Grooved Joints: Roll rounded-edge groove in end of pipe according to AWWA C606. Assemble coupling with housing, gasket, lubricant, and bolts. Join steel pipe and grooved-end fittings according to AWWA C606 for steel-pipe grooved joints.
- I. Dissimilar-Material Piping Joints: Make joints using adapters compatible with materials of both piping systems.

### 3.4 SPRINKLER INSTALLATION

- A. Install sprinklers in suspended ceilings in center of narrow dimension of acoustical ceiling panels.
- B. Install dry-type sprinklers with water supply from heated space. Do not install pendent or sidewall, wet-type sprinklers in areas subject to freezing.
- C. The sprinkler bulb protector must remain in place until the sprinkler is completely installed and before the system is placed in service. Failure to follow this instruction could cause damage to the glass bulb, resulting in improper sprinkler operation, serious personal injury and property damage. Remove bulb protectors carefully by hand after installation. Do not use any tools to remove bulb protectors.
- D. Do not install sprinklers that have been dropped, damaged, or show a visible loss of fluid. Never install sprinklers with cracked bulbs.

- E. Provide protection in electric, telephone, elevator equipment, and electronic equipment spaces. Piping shall not pass directly over electric panel boards, switchboards, motor control centers, elevator rooms/hoist ways, controllers, and similar electric/telephone equipment.
- F. Provide guards for sprinklers in mechanical, storage, closet, and similar spaces than 8'-0" above finished floor.
- G. Provide protection under ductwork, groups of ductwork, and other obstructions to water spray distribution. Use intermediate level sprinklers if subject to water spray from above.
- H. Provide sprinklers within combustible concealed spaces in accordance with NFPA 13.

### 3.5 IDENTIFICATION

- A. Install labeling and pipe markers on equipment and piping according to requirements in NFPA 13.
- B. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."
- C. Provide sign at or near fire department connection a minimum of an 36" by 36" reflective diagrammatic sign meeting NFPA 170 requirements. The sign shall also indicate the building name and address in which it services, systems within the building in which it serves, and the pressure required at the inlets to deliver the greatest system demand.
- D. Valve Signage:
  - 1. All main and sectional system control valves, including water supply control valves, shall have a sign indicating the portion of the system that is controlled by the valve.
  - 2. All control, drain, and test connection valves shall be provided with signs indicating their purpose.
  - 3. Where a main or section control valve is located in a closed room or concealed space, the location of the valve shall be indicated by a sign in an approved location on the outside of the door or near the opening to the concealed space.

### 3.6 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Final Acceptance/Commissioning Test: The system will be accepted only after satisfactory test of the entire system has been accomplished by the Contractor at the direction of the C&S Engineers, Inc. Fire Protection Engineer, in the presence of the Authority Having Jurisdiction and the Owner. The Contractor shall notify the above witnesses, in writing, 72 hours prior to the commencement of testing. Failure to contact the above parties will require the Contractor to conduct tests a second time at the Contractor's expense in the presence of the above parties. The C&S Engineers, Inc. Fire Protection Engineer shall have complete direction over the final acceptance/commissioning test of the system.

- C. Water flow detecting devices including the associated alarm circuits shall be flow tested through the inspector's test connection and shall result in an audible alarm on the premises within 5 minutes after such flow begins and until such flow stops.
- D. The main drain valve shall be opened and remain open until the system pressure stabilizes. Static and residual pressures shall be recorded.
- E. Tests and Inspections:
  - 1. Leak Test: After installation, charge systems and test for leaks. Repair leaks and retest until no leaks exist.
  - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
  - 3. Flush, test, and inspect sprinkler systems according to NFPA 13, "Systems Acceptance" Chapter.
  - 4. Energize circuits to electrical equipment and devices.
- F. Sprinkler piping system will be considered defective if it does not pass tests and inspections.
- G. Prepare test and inspection reports.
- H. Test backflow preventer in accordance with NFPA 13, "Systems Acceptance" chapter.

### 3.7 INTERFACE WITH OTHER PRODUCTS

- A. Verify signal devices are installed and connected to fire alarm system.

### 3.8 PROTECTION OF INSTALLED CONSTRUCTION

- A. Apply masking tape or paper cover to protect concealed sprinklers, cover plates, and sprinkler escutcheons not receiving field paint finish. Remove after painting. Replace painted sprinklers with new.

### 3.9 CLEANING

- A. Clean dirt and debris from sprinklers.
- B. Remove and replace sprinklers with paint other than factory finish.

### 3.10 DEMONSTRATION AND TRAINING

- A. The Contractor shall provide a minimum of 2 hours of instruction and operation, and maintenance of all elements of the materials and methods specified above for "non-technician" personnel prior to the commissioning of the building fire suppression system. All training shall take place prior to final acceptance testing of the system. All demonstration and training provided to Owner personnel shall be witnessed by the C&S Engineers, Inc. Fire Protection Engineer and the Authority Having Jurisdiction. The Contractor shall notify the above witnesses, in writing, 72 hours prior to the commencement of testing. Failure to contact the

above parties will require the Contractor to conduct training a second time at the contractor's expense in the presence of the above parties.

- B. Instruction shall be provided by a material or system manufacturer's certified representative familiar with the equipment and special operating requirements of the system provided and the Owner's operating procedures.
- C. Instructions shall include classroom training as well as hands on training of all components of the system and their operation.
- D. Instruction shall be made available on a schedule acceptable to the Owner and the availability of the operating personnel. Instructions shall be in two separate groupings with the last instruction time frame 30 days after the second grouping. This is to allow the operating personnel to familiarize themselves with the equipment and get follow-up training as required. The last training session shall be a minimum of 1 hour(s).
- E. Contractor shall be responsible for providing sufficient training materials for all present at the training session, (minimum 15 personnel). Coordinate actual requirements with the Owner at time of training.
- F. The Contractor shall be responsible for providing videotaped training sessions, which will be submitted to the owner for future employee training. All of the training sessions conducted shall be videotaped.

### 3.11 PIPING SCHEDULE

- A. Sprinkler specialty fittings may be used, downstream of control valves, instead of specified fittings.
- B. Standard-pressure, wet-pipe sprinkler system, NPS 2 and smaller, shall be one of the following:
  - 1. Standard-weight, Schedule 40, black-steel pipe with threaded ends; uncoated, gray-iron threaded fittings; and threaded joints.
- C. Standard-pressure, wet-pipe sprinkler system, NPS 2-1/2 to 6, shall be one of the following:
  - 1. Standard-weight, Schedule 10, black-steel pipe with roll grooved ends; uncoated, grooved-end fittings for steel piping; grooved-end-pipe couplings for steel piping; and grooved joints.

### 3.12 SPRINKLER SCHEDULE

- A. Use sprinkler types in subparagraphs below for the following applications:
  - 1. Rooms without Ceilings: Upright sprinklers.
  - 2. Rooms with Suspended Ceilings: Semi-recessed pendent sprinklers .
  - 3. Wall Mounting: Sidewall sprinklers.
  - 4. Spaces Subject to Freezing: Upright, pendent, dry sprinklers; and sidewall, dry sprinklers as indicated.
- B. Provide sprinkler types in subparagraphs below with finishes indicated.

ORANGE COUNTY SHERIFF'S OFFICE  
CENTRAL OPERATIONS CENTER -  
SHERIFF'S OFFICE COMMAND AND MONITOR CENTER  
ORANGE COUNTY, FLORIDA

WET-PIPE SPRINKLER SYSTEMS  
SECTION 211313

1. Recessed Sprinklers: Bright chrome, with bright chrome escutcheon. Coordinate sprinkler finish with surrounding architectural finishes.

END OF SECTION 211313

## SECTION 220719 - PLUMBING PIPING INSULATION

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes insulating the following plumbing piping services:
  - 1. Domestic hot-water piping.
  - 2. Domestic recirculating hot-water piping.
  - 3. Sanitary waste piping exposed to freezing conditions.
  - 4. Storm-water piping exposed to freezing conditions.
  - 5. Roof drains and rainwater leaders.
  - 6. Supplies and drains for handicap-accessible lavatories and sinks.

#### 1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

#### 1.3 QUALITY ASSURANCE

- A. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84 by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
  - 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.

### PART 2 - PRODUCTS

#### 2.1 INSULATION MATERIALS

- A. All domestic hot water plumbing shall be insulated.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Mineral-Fiber, Preformed Pipe Insulation:
  - 1. Type I, 850 Deg F Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A, with factory-applied ASJ. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

#### 2.2 INSULATING CEMENTS

- A. Mineral-Fiber, Hydraulic-Setting Insulating and Finishing Cement: Comply with ASTM C 449.



2.3 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated, unless otherwise indicated.
- B. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.
- C. ASJ Adhesive, and FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.

2.4 MASTICS

- A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.
- B. Breather Mastic: Water based; suitable for indoor and outdoor use on above-ambient services.
  - 1. Water-Vapor Permeance: ASTM F 1249, 1.8 perms at 0.0625-inch dry film thickness.
  - 2. Service Temperature Range: Minus 20 to plus 180 deg F.
  - 3. Solids Content: 60 percent by volume and 66 percent by weight.
  - 4. Color: White.

2.5 SEALANTS

- A. ASJ Flashing Sealants, and Vinyl, PVDC, and PVC Jacket Flashing Sealants:
  - 1. Materials shall be compatible with insulation materials, jackets, and substrates.
  - 2. Fire- and water-resistant, flexible, elastomeric sealant.
  - 3. Service Temperature Range: Minus 40 to plus 250 deg F.
  - 4. Color: White.

2.6 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
  - 1. ASJ: White, kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C 1136, Type I.

2.7 FIELD-APPLIED FABRIC-REINFORCING MESH

- A. Woven Polyester Fabric: Approximately 1 oz./sq. yd. with a thread count of 10 strands by 10 strands/sq. in., in a Leno weave, for pipe.

2.8 FIELD-APPLIED JACKETS

- A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.

- B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
  - 1. Adhesive: As recommended by jacket material manufacturer.
  - 2. Color: White.
  - 3. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
    - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.

## 2.9 TAPES

- A. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C 1136.
  - 1. Width: 3 inches.
  - 2. Thickness: 11.5 mils.
  - 3. Adhesion: 90 ounces force/inch in width.
  - 4. Elongation: 2 percent.
  - 5. Tensile Strength: 40 lbf/inch in width.
  - 6. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.

## 2.10 SECUREMENTS

- A. Aluminum Bands: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 1/2 inch wide with wing seal.
- B. Staples: Outward-clinching insulation staples, nominal 3/4-inch-wide, stainless steel or Monel.

## PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

### 3.2 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping including fittings, valves, and specialties.
- B. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- C. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- D. Keep insulation materials dry during application and finishing.

- E. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- F. Install insulation with least number of joints practical.
- G. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
  - 1. Install insulation continuously through hangers and around anchor attachments.
  - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
  - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
  - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.
- H. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- I. Install insulation with factory-applied jackets as follows:
  - 1. Draw jacket tight and smooth.
  - 2. Cover circumferential joints with 3-inch-wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
  - 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 2 inches o.c.
  - 4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
  - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to pipe flanges and fittings.
- J. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- K. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- L. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.
- M. For above-ambient services, do not install insulation to the following:
  - 1. Vibration-control devices.
  - 2. Testing agency labels and stamps.
  - 3. Nameplates and data plates.

### 3.3 PENETRATIONS

- A. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- B. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.
  - 1. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping and fire-resistive joint sealers.

### 3.4 GENERAL PIPE INSULATION INSTALLATION

- A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.
- B. Install removable insulation covers at locations indicated. Installation shall conform to the following:
  - 1. Make removable flange and union insulation from sectional pipe insulation of same thickness as that on adjoining pipe. Install same insulation jacket as adjoining pipe insulation.
  - 2. When flange and union covers are made from sectional pipe insulation, extend insulation from flanges or union long at least two times the insulation thickness over adjacent pipe insulation on each side of flange or union. Secure flange cover in place with stainless-steel or aluminum bands. Select band material compatible with insulation and jacket.
  - 3. Construct removable valve insulation covers in same manner as for flanges, except divide the two-part section on the vertical center line of valve body.
  - 4. When covers are made from block insulation, make two halves, each consisting of mitered blocks wired to stainless-steel fabric. Secure this wire frame, with its attached insulation, to flanges with tie wire. Extend insulation at least 2 inches over adjacent pipe insulation on each side of valve. Fill space between flange or union cover and pipe insulation with insulating cement. Finish cover assembly with insulating cement applied in two coats. After first coat is dry, apply and trowel second coat to a smooth finish.
  - 5. Unless a PVC jacket is indicated in field-applied jacket schedules, finish exposed surfaces with a metal jacket.

### 3.5 INSTALLATION OF MINERAL-FIBER PREFORMED PIPE INSULATION

- A. Insulation Installation on Straight Pipes and Tubes:
  - 1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
  - 2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
  - 3. For insulation with factory-applied jackets on above-ambient surfaces, secure laps with outward clinched staples at 6 inches o.c.
  - 4. For insulation with factory-applied jackets on below-ambient surfaces, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.

B. Insulation Installation on Pipe Flanges:

1. Install preformed pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch, and seal joints with flashing sealant.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
4. Install insulation to flanges as specified for flange insulation application.

### 3.6 FIELD-APPLIED JACKET INSTALLATION

A. Where FSK jackets are indicated, install as follows:

1. Draw jacket material smooth and tight.
2. Install lap or joint strips with same material as jacket.
3. Secure jacket to insulation with manufacturer's recommended adhesive.
4. Install jacket with 1-1/2-inch laps at longitudinal seams and 3-inch-wide joint strips at end joints.
5. Seal openings, punctures, and breaks in vapor-retarder jackets and exposed insulation with vapor-barrier mastic.

B. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints. Seal with manufacturers recommended adhesive.

1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

C. Where metal jackets are indicated, install with 2-inch overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel bands 12 inches o.c. and at end joints.

3.7 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

3.8 INDOOR PIPING INSULATION SCHEDULE

- A. Domestic Hot and Recirculated Hot Water: Insulation shall be the following:
  - 1. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1-1/2 inch thick.

3.9 INDOOR, FIELD-APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Piping, Exposed:
  - 1. None.
  - 2. PVC: 20 mils thick.

END OF SECTION 220719

SECTION 221116 - DOMESTIC WATER PIPING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
  - 1. Copper tube and fittings.

1.2 ACTION SUBMITTALS

- A. Product Data: For transition fittings and dielectric fittings.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

- A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.
- B. Potable-water piping and components shall comply with NSF 14 and NSF 61 Annex G. Plastic piping components shall be marked with "NSF-pw."
- C. Comply with NSF Standard 372 for low lead.

2.2 COPPER TUBE AND FITTINGS

- A. Hard Copper Tube: ASTM B 88, Type L water tube, drawn temper.
- B. Wrought-Copper, Solder-Joint Fittings: ASME B16.22, wrought-copper pressure fittings.
- C. Copper Unions:
  - 1. MSS SP-123.
  - 2. Cast-copper-alloy, hexagonal-stock body.
  - 3. Ball-and-socket, metal-to-metal seating surfaces.
  - 4. Solder-joint or threaded ends.
- D. Copper Pressure-Seal-Joint Fittings:
  - 1. Fittings for NPS 2 and Smaller: Wrought-copper fitting with EPDM-rubber, O-ring seal in each end.
  - 2. Fittings for NPS 2-1/2 to NPS 4: Cast-bronze or wrought-copper fitting with EPDM-rubber, O-ring seal in each end.

- E. Copper Push-on-Joint Fittings:
  - 1. Cast-copper fitting complying with ASME B16.18 or wrought-copper fitting complying with ASME B 16.22.
  - 2. Stainless-steel teeth and EPDM-rubber, O-ring seal in each end instead of solder-joint ends.

### PART 3 - EXECUTION

#### 3.1 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of domestic water piping. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Install copper tubing under building slab according to CDA's "Copper Tube Handbook."
- C. Install shutoff valve, hose-end drain valve, strainer, pressure gage, and test tee with valve inside the building at each domestic water-service entrance. Comply with requirements for pressure gages in Section 220519 "Meters and Gages for Plumbing Piping" and with requirements for drain valves and strainers in Section 221119 "Domestic Water Piping Specialties."
- D. Install domestic water piping level without pitch and plumb.
- E. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- F. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- G. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.
- H. Install piping to permit valve servicing.
- I. Install nipples, unions, special fittings, and valves with pressure ratings the same as or higher than the system pressure rating used in applications below unless otherwise indicated.
- J. Install piping free of sags and bends.
- K. Install fittings for changes in direction and branch connections.
- L. Install unions in copper tubing at final connection to each piece of equipment, machine, and specialty.



### 3.2 JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.
- C. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
  - 1. Apply appropriate tape or thread compound to external pipe threads.
  - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
- D. Soldered Joints for Copper Tubing: Apply ASTM B 813, water-flushable flux to end of tube. Join copper tube and fittings according to ASTM B 828 or CDA's "Copper Tube Handbook."
- E. Pressure-Sealed Joints for Copper Tubing: Join copper tube and pressure-seal fittings with tools recommended by fitting manufacturer.
- F. Joints for Dissimilar-Material Piping: Make joints using adapters compatible with materials of both piping systems.

### 3.3 TRANSITION FITTING INSTALLATION

- A. Install transition couplings at joints of dissimilar piping.
- B. Transition Fittings in Underground Domestic Water Piping:
  - 1. Fittings for NPS 1-1/2 and Smaller: Fitting-type coupling.
  - 2. Fittings for NPS 2 and Larger: Sleeve-type coupling.

### 3.4 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements for seismic-restraint devices in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."

### 3.5 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. When installing piping adjacent to equipment and machines, allow space for service and maintenance.
- C. Connect domestic water piping to exterior water-service piping. Use transition fitting to join dissimilar piping materials.

3.6 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Piping Inspections:

- a. Do not enclose, cover, or put piping into operation until it has been inspected and approved by authorities having jurisdiction.
- b. During installation, notify authorities having jurisdiction at least one day before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:
  - 1) Roughing-in Inspection: Arrange for inspection of piping before concealing or closing in after roughing in and before setting fixtures.
  - 2) Final Inspection: Arrange for authorities having jurisdiction to observe tests specified in "Piping Tests" Subparagraph below and to ensure compliance with requirements.
- c. Reinspection: If authorities having jurisdiction find that piping will not pass tests or inspections, make required corrections and arrange for reinspection.
- d. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

3.7 PIPING SCHEDULE

- A. All domestic water piping shall be hard drawn type L copper at sizes indicated on plans

END OF SECTION 221116

SECTION 221316 - SANITARY WASTE AND VENT PIPING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
  - 1. Pipe, tube, and fittings.
  - 2. Specialty pipe fittings.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 HUB-AND-SPIGOT, CAST-IRON SOIL PIPE AND FITTINGS

- A. Pipe and Fittings: ASTM A 74, Service class.
- B. Gaskets: ASTM C 564, rubber.
- C. Calking Materials: ASTM B 29, pure lead and oakum or hemp fiber.

2.2 PVC PIPE AND FITTINGS

- A. Comply with NSF 14, "Plastics Piping Systems Components and Related Materials," for plastic piping components. Include marking with "NSF-dwv" for plastic drain, waste, and vent piping and "NSF-sewer" for plastic sewer piping.
- B. Solid-Wall PVC Pipe: ASTM D 2665, drain, waste, and vent.
- C. Cellular-Core PVC Pipe: ASTM F 891, Schedule 40.
- D. PVC Socket Fittings: ASTM D 2665, made to ASTM D 3311, drain, waste, and vent patterns and to fit Schedule 40 pipe.
- E. Adhesive Primer: ASTM F 656.
- F. Solvent Cement: ASTM D 2564.

### PART 3 - EXECUTION

#### 3.1 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems.
  - 1. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations.
  - 2. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- E. Install piping at indicated slopes.
- F. Install piping free of sags and bends.
- G. Install fittings for changes in direction and branch connections.
- H. Install piping to allow application of insulation.
- I. Lay buried building waste piping beginning at low point of each system.
  - 1. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream.
  - 2. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements.
  - 3. Maintain swab in piping and pull past each joint as completed.
- J. Install soil and waste and vent piping at the following minimum slopes unless otherwise indicated:
  - 1. Building Sanitary Waste: 2 percent downward in direction of flow for piping NPS 3 and smaller; 2 percent downward in direction of flow for piping NPS 4 and larger.
  - 2. Horizontal Sanitary Waste Piping: 2 percent downward in direction of flow.
  - 3. Vent Piping: 1 percent down toward vertical fixture vent or toward vent stack.
- K. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
- L. Install aboveground PVC piping according to ASTM D 2665.

### 3.2 JOINT CONSTRUCTION

- A. Join hub-and-spigot, cast-iron soil piping with gasket joints according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for compression joints.
- B. Plastic, Nonpressure-Piping, Solvent-Cement Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:
  - 1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
  - 2. ABS Piping: Join according to ASTM D 2235 and ASTM D 2661 appendixes.
  - 3. PVC Piping: Join according to ASTM D 2855 and ASTM D 2665 appendixes.

### 3.3 HANGER AND SUPPORT INSTALLATION

- A. Support horizontal piping and tubing within 12 inches of each fitting
- B. Support vertical piping and tubing at base and at each floor.
- C. Rod diameter may be reduced one size for double-rod hangers, with 3/8-inch minimum rods.
- D. Install hangers for cast-iron soil piping with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 1-1/2 and NPS 2: 60 inches with 3/8-inch rod.
  - 2. NPS 3: 60 inches with 1/2-inch rod.
  - 3. NPS 4 and NPS 5: 60 inches with 5/8-inch rod.
  - 4. NPS 6 and NPS 8: 60 inches with 3/4-inch rod.
  - 5. NPS 10 and NPS 12: 60 inches with 7/8-inch rod.
  - 6. Spacing for 10-foot lengths may be increased to 10 feet. Spacing for fittings is limited to 60 inches.
- E. Install supports for vertical cast-iron soil piping every 15 feet.
- F. Install hangers for steel piping with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 1-1/4: 84 inches with 3/8-inch rod.
  - 2. NPS 1-1/2: 108 inches with 3/8-inch rod.
  - 3. NPS 2: 10 feet with 3/8-inch rod.
  - 4. NPS 2-1/2: 11 feet with 1/2-inch rod.
  - 5. NPS 3: 12 feet with 1/2-inch rod.
  - 6. NPS 4 and NPS 5: 12 feet with 5/8-inch rod.
  - 7. NPS 6 and NPS 8: 12 feet with 3/4-inch rod.
  - 8. NPS 10 and NPS 12: 12 feet with 7/8-inch rod.
- G. Install hangers for PVC piping with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 1-1/2 and NPS 2: 48 inches with 3/8-inch rod.
  - 2. NPS 3: 48 inches with 1/2-inch rod.
  - 3. NPS 4 and NPS 5: 48 inches with 5/8-inch rod.

4. NPS 6 and NPS 8: 48 inches with 3/4-inch rod.
  5. NPS 10 and NPS 12: 48 inches with 7/8-inch rod.
- H. Install supports for vertical PVC piping every 48 inches.
- I. Support piping and tubing not listed above according to MSS SP-58 and manufacturer's written instructions.

END OF SECTION 221316

SECTION 224213 - COMMERCIAL PLUMBING FIXTURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:  
1. Sink

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 LAV-1

- A. Counter-mounted Sink
- a. 20 gauge stainless steel single bowl sink
  - b. (2) faucet mounting holes, 4" centers
  - c. Provide Moen Commercial (2) handle faucet
    - 1) 0.5 gpm
    - 2) ADA compliant lever handles
    - 3) 4" spacing
    - 4) Chrome finish
  - d. Basis of design shall be Kohler, Elkay or approved equal

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Sink Installation
- 1. Install sinks level and plumb according to roughing-in drawings.
  - 2. Install supports, affixed to building substrate, for wall-mounted lavatories
  - 3. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Use deep-pattern escutcheons if required to conceal protruding fittings.
  - 4. Seal joints between lavatories and counters and walls using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to fixture color.
- B. Joint Sealing:
- 1. Match sealant color to water-closet color.

3.2 CONNECTIONS

- A. Comply with water piping requirements specified in Section 221116 "Domestic Water Piping."
- B. Comply with soil and waste piping requirements specified in Section 221316 "Sanitary Waste and Vent Piping."
- C. Where installing piping adjacent to water closets, allow space for service and maintenance.

3.3 ADJUSTING

- A. Operate and adjust water closets and controls. Replace damaged and malfunctioning water closets, fittings, and controls.
- B. Adjust water pressure at flushometer valves to produce proper flow.

3.4 CLEANING AND PROTECTION

- A. Clean water closets and fittings with manufacturers' recommended cleaning methods and materials.
- B. Install protective covering for installed water closets and fittings.
- C. Do not allow use of water closets for temporary facilities unless approved in writing by Owner.

END OF SECTION 224213.13



SECTION 230593 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
  - 1. Balancing Air Systems:
    - a. Variable-air-volume systems.
  - 2. Balancing Hydronic Piping Systems:
    - a. Constant-flow hydronic systems.

1.2 DEFINITIONS

- A. AABC: Associated Air Balance Council.
- B. NEBB: National Environmental Balancing Bureau.
- C. TAB: Testing, adjusting, and balancing.
- D. TABB: Testing, Adjusting, and Balancing Bureau.
- E. TAB Specialist: An independent entity meeting qualifications to perform TAB work.
- F. TDH: Total dynamic head.

1.3 INFORMATIONAL SUBMITTALS

- A. Certified TAB reports.

1.4 QUALITY ASSURANCE

- A. TAB Specialists Qualifications: Certified by AABC, NEBB, or TABB.
  - 1. TAB Field Supervisor: Employee of the TAB specialist and certified by AABC, NEBB, or TABB.
  - 2. TAB Technician: Employee of the TAB specialist and certified by AABC, NEBB, or TABB as a TAB technician.
- B. Instrumentation Type, Quantity, Accuracy, and Calibration: Comply with requirements in ASHRAE 111, Section 4, "Instrumentation."
- C. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 7.2.2 - "Air Balancing."

- D. ASHRAE/IESNA Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6.7.2.3 - "System Balancing."

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems designs that may preclude proper TAB of systems and equipment.
- B. Examine installed systems for balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are applicable for intended purpose and are accessible.
- C. Examine the approved submittals for HVAC systems and equipment.
- D. Examine design data including HVAC system descriptions, statements of design assumptions for environmental conditions and systems output, and statements of philosophies and assumptions about HVAC system and equipment controls.
- E. Examine ceiling plenums and underfloor air plenums used for supply, return, or relief air to verify that they are properly separated from adjacent areas. Verify that penetrations in plenum walls are sealed and fire-stopped if required.
- F. Examine equipment performance data including fan and pump curves.
  - 1. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
  - 2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems - Duct Design." Compare results with the design data and installed conditions.
- G. Examine system and equipment installations and verify that field quality-control testing, cleaning, and adjusting specified in individual Sections have been performed.
- H. Examine test reports specified in individual system and equipment Sections.
- I. Examine HVAC equipment and verify that bearings are greased, belts are aligned and tight, filters are clean, and equipment with functioning controls is ready for operation.
- J. Examine terminal units, such as variable-air-volume boxes, and verify that they are accessible and their controls are connected and functioning.

- K. Examine strainers. Verify that startup screens have been replaced by permanent screens with indicated perforations.
- L. Examine control valves for proper installation for their intended function of throttling, diverting, or mixing fluid flows.
- M. Examine heat-transfer coils for correct piping connections and for clean and straight fins.
- N. Examine system pumps to ensure absence of entrained air in the suction piping.
- O. Examine operating safety interlocks and controls on HVAC equipment.
- P. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

### 3.2 PREPARATION

- A. Prepare a TAB plan that includes strategies and step-by-step procedures for balancing the systems.
- B. Perform system-readiness checks of HVAC systems and equipment to verify system readiness for TAB work. Include, at a minimum, the following:
  - 1. Airside:
    - a. Duct systems are complete with terminals installed.
    - b. Volume, smoke, and fire dampers are open and functional.
    - c. Clean filters are installed.
    - d. Fans are operating, free of vibration, and rotating in correct direction.
    - e. Variable-frequency controllers' startup is complete and safeties are verified.
    - f. Automatic temperature-control systems are operational.
    - g. Ceilings are installed.
    - h. Windows and doors are installed.
    - i. Suitable access to balancing devices and equipment is provided.
  - 2. Hydronics:
    - a. Verify leakage and pressure tests on water distribution systems have been satisfactorily completed.
    - b. Piping is complete with terminals installed.
    - c. Water treatment is complete.
    - d. Systems are flushed, filled, and air purged.
    - e. Strainers are pulled and cleaned.
    - f. Control valves are functioning per the sequence of operation.
    - g. Shutoff and balance valves have been verified to be 100 percent open.
    - h. Suitable access to balancing devices and equipment is provided.

### 3.3 GENERAL PROCEDURES FOR TESTING AND BALANCING

- A. Perform testing and balancing procedures on each system according to the procedures contained in SMACNA's "HVAC Systems - Testing, Adjusting, and Balancing" and in this Section.
- B. Cut insulation, ducts, pipes, and equipment cabinets for installation of test probes to the minimum extent necessary for TAB procedures.
  - 1. After testing and balancing, patch probe holes in ducts with same material and thickness as used to construct ducts.
  - 2. After testing and balancing, install test ports and duct access doors that comply with requirements in Section 233300 "Air Duct Accessories."
  - 3. Install and join new insulation that matches removed materials. Restore insulation, coverings, vapor barrier, and finish according to Section 230713 "Duct Insulation," Section 230716 "HVAC Equipment Insulation," and Section 230719 "HVAC Piping Insulation."
- C. Mark equipment and balancing devices, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, with paint or other suitable, permanent identification material to show final settings.
- D. Take and report testing and balancing measurements in inch-pound (IP) units.

### 3.4 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

- A. Prepare test reports for both fans and outlets. Obtain manufacturer's outlet factors and recommended testing procedures. Cross-check the summation of required outlet volumes with required fan volumes.
- B. Prepare schematic diagrams of systems' "as-built" duct layouts.
- C. For variable-air-volume systems, develop a plan to simulate diversity.
- D. Determine the best locations in main and branch ducts for accurate duct-airflow measurements.
- E. Check airflow patterns from the outdoor-air louvers and dampers and the return- and exhaust-air dampers through the supply-fan discharge and mixing dampers.
- F. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.
- G. Verify that motor starters are equipped with properly sized thermal protection.
- H. Check dampers for proper position to achieve desired airflow path.
- I. Check for airflow blockages.
- J. Check condensate drains for proper connections and functioning.
- K. Check for proper sealing of air-handling-unit components.
- L. Verify that air duct system is sealed as specified in Section 233113 "Metal Ducts."

### 3.5 PROCEDURES FOR VARIABLE-AIR-VOLUME SYSTEMS

- A. Adjust the variable-air-volume systems as follows:
1. Verify that the system static pressure sensor is located two-thirds of the distance down the duct from the fan discharge.
  2. Verify that the system is under static pressure control.
  3. Select the terminal unit that is most critical to the supply-fan airflow. Measure inlet static pressure, and adjust system static pressure control set point so the entering static pressure for the critical terminal unit is not less than the sum of the terminal-unit manufacturer's recommended minimum inlet static pressure plus the static pressure needed to overcome terminal-unit discharge system losses.
  4. Calibrate and balance each terminal unit for maximum and minimum design airflow as follows:
    - a. Adjust controls so that terminal is calling for maximum airflow. Some controllers require starting with minimum airflow. Verify calibration procedure for specific project.
    - b. Measure airflow and adjust calibration factor as required for design maximum airflow. Record calibration factor.
    - c. When maximum airflow is correct, balance the air outlets downstream from terminal units.
    - d. Adjust controls so that terminal is calling for minimum airflow.
    - e. Measure airflow and adjust calibration factor as required for design minimum airflow. Record calibration factor. If no minimum calibration is available, note any deviation from design airflow.
    - f. When in full cooling or full heating, ensure that there is no mixing of hot-deck and cold-deck airstreams unless so designed.
    - g. On constant volume terminals, in critical areas where room pressure is to be maintained, verify that the airflow remains constant over the full range of full cooling to full heating. Note any deviation from design airflow or room pressure.
  5. After terminals have been calibrated and balanced, test and adjust system for total airflow. Adjust fans to deliver total design airflows within the maximum allowable fan speed listed by fan manufacturer.
    - a. Set outside-air, return-air, and relief-air dampers for proper position that simulates minimum outdoor-air conditions.
    - b. Set terminals for maximum airflow. If system design includes diversity, adjust terminals for maximum and minimum airflow so that connected total matches fan selection and simulates actual load in the building.
    - c. Where duct conditions allow, measure airflow by Pitot-tube traverse. If necessary, perform multiple Pitot-tube traverses to obtain total airflow.
    - d. Where duct conditions are not suitable for Pitot-tube traverse measurements, a coil traverse may be acceptable.
    - e. If a reliable Pitot-tube traverse or coil traverse is not possible, measure airflow at terminals and calculate the total airflow.
  6. Measure fan static pressures as follows:
    - a. Measure static pressure directly at the fan outlet or through the flexible connection.
    - b. Measure static pressure directly at the fan inlet or through the flexible connection.
    - c. Measure static pressure across each component that makes up the air-handling system.

- d. Report any artificial loading of filters at the time static pressures are measured.
7. Set final return and outside airflow to the fan while operating at maximum return airflow and minimum outdoor airflow.
  - a. Balance the return-air ducts and inlets the same as described for constant-volume air systems.
  - b. Verify that terminal units are meeting design airflow under system maximum flow.
8. Re-measure the inlet static pressure at the most critical terminal unit and adjust the system static pressure set point to the most energy-efficient set point to maintain the optimum system static pressure. Record set point and give to controls contractor.
9. Verify final system conditions as follows:
  - a. Re-measure and confirm that minimum outdoor, return, and relief airflows are within design. Readjust to match design if necessary.
  - b. Re-measure and confirm that total airflow is within design.
  - c. Re-measure final fan operating data, rpms, volts, amps, and static profile.
  - d. Mark final settings.
  - e. Test system in economizer mode. Verify proper operation and adjust if necessary. Measure and record all operating data.
  - f. Verify tracking between supply and return fans.

### 3.6 GENERAL PROCEDURES FOR HYDRONIC SYSTEMS

- A. Prepare test reports for pumps, coils, and heat exchangers. Obtain approved submittals and manufacturer-recommended testing procedures. Crosscheck the summation of required coil and heat exchanger flow rates with pump design flow rate.
- B. Prepare schematic diagrams of systems' "as-built" piping layouts.
- C. In addition to requirements in "Preparation" Article, prepare hydronic systems for testing and balancing as follows:
  1. Check liquid level in expansion tank.
  2. Check highest vent for adequate pressure.
  3. Check flow-control valves for proper position.
  4. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.
  5. Verify that motor starters are equipped with properly sized thermal protection.
  6. Check that air has been purged from the system.

### 3.7 PROCEDURES FOR VARIABLE-FLOW HYDRONIC SYSTEMS

- A. Balance systems with automatic two- and three-way control valves by setting systems at maximum flow through heat-exchange terminals, and proceed as specified above for hydronic systems.
- B. Adjust the variable-flow hydronic system as follows:
  1. Verify that the differential-pressure sensor is located as indicated.
  2. Determine whether there is diversity in the system.

- C. For systems with no diversity:
1. Adjust pumps to deliver total design gpm.
    - a. Measure total water flow.
      - 1) Position valves for full flow through coils.
      - 2) Measure flow by main flow meter, if installed.
      - 3) If main flow meter is not installed, determine flow by pump TDH or exchanger pressure drop.
    - b. Measure pump TDH as follows:
      - 1) Measure discharge pressure directly at the pump outlet flange or in discharge pipe prior to any valves.
      - 2) Measure inlet pressure directly at the pump inlet flange or in suction pipe prior to any valves or strainers.
      - 3) Convert pressure to head and correct for differences in gage heights.
      - 4) Verify pump impeller size by measuring the TDH with the discharge valve closed. Note the point on manufacturer's pump curve at zero flow and verify that the pump has the intended impeller size.
      - 5) With valves open, read pump TDH. Adjust pump discharge valve until design water flow is achieved.
    - c. Monitor motor performance during procedures and do not operate motor in an overloaded condition.
  2. Adjust flow-measuring devices installed in mains and branches to design water flows.
    - a. Measure flow in main and branch pipes.
    - b. Adjust main and branch balance valves for design flow.
    - c. Re-measure each main and branch after all have been adjusted.
  3. Adjust flow-measuring devices installed at terminals for each space to design water flows.
    - a. Measure flow at terminals.
    - b. Adjust each terminal to design flow.
    - c. Re-measure each terminal after it is adjusted.
    - d. Position control valves to bypass the coil and adjust the bypass valve to maintain design flow.
    - e. Perform temperature tests after flows have been balanced.
  4. For systems with pressure-independent valves at terminals:
    - a. Measure differential pressure and verify that it is within manufacturer's specified range.
    - b. Perform temperature tests after flows have been verified.
  5. For systems without pressure-independent valves or flow-measuring devices at terminals:
    - a. Measure and balance coils by either coil pressure drop or temperature method.

- b. If balanced by coil pressure drop, perform temperature tests after flows have been verified.
  6. Prior to verifying final system conditions, determine the system differential-pressure set point.
  7. If the pump discharge valve was used to set total system flow with variable-frequency controller at 60 Hz, at completion open discharge valve 100 percent and allow variable-frequency controller to control system differential-pressure set point. Record pump data under both conditions.
  8. Mark final settings and verify that all memory stops have been set.
  9. Verify final system conditions as follows:
    - a. Re-measure and confirm that total water flow is within design.
    - b. Re-measure final pumps' operating data, TDH, volts, amps, and static profile.
    - c. Mark final settings.
  10. Verify that memory stops have been set.
- D. For systems with diversity:
  1. Determine diversity factor.
  2. Simulate system diversity by closing required number of control valves, as approved by the design engineer.
  3. Adjust pumps to deliver total design gpm.
    - a. Measure total water flow.
      - 1) Position valves for full flow through coils.
      - 2) Measure flow by main flow meter, if installed.
      - 3) If main flow meter is not installed, determine flow by pump TDH or exchanger pressure drop.
    - b. Measure pump TDH as follows:
      - 1) Measure discharge pressure directly at the pump outlet flange or in discharge pipe prior to any valves.
      - 2) Measure inlet pressure directly at the pump inlet flange or in suction pipe prior to any valves or strainers.
      - 3) Convert pressure to head and correct for differences in gage heights.
      - 4) Verify pump impeller size by measuring the TDH with the discharge valve closed. Note the point on manufacturer's pump curve at zero flow and verify that the pump has the intended impeller size.
      - 5) With valves open, read pump TDH. Adjust pump discharge valve until design water flow is achieved.
    - c. Monitor motor performance during procedures and do not operate motor in an overloaded condition.
  4. Adjust flow-measuring devices installed in mains and branches to design water flows.
    - a. Measure flow in main and branch pipes.
    - b. Adjust main and branch balance valves for design flow.
    - c. Re-measure each main and branch after all have been adjusted.



5. Adjust flow-measuring devices installed at terminals for each space to design water flows.
  - a. Measure flow at terminals.
  - b. Adjust each terminal to design flow.
  - c. Re-measure each terminal after it is adjusted.
  - d. Position control valves to bypass the coil, and adjust the bypass valve to maintain design flow.
  - e. Perform temperature tests after flows have been balanced.
6. For systems with pressure-independent valves at terminals:
  - a. Measure differential pressure, and verify that it is within manufacturer's specified range.
  - b. Perform temperature tests after flows have been verified.
7. For systems without pressure-independent valves or flow-measuring devices at terminals:
  - a. Measure and balance coils by either coil pressure drop or temperature method.
  - b. If balanced by coil pressure drop, perform temperature tests after flows have been verified.
8. Open control valves that were shut. Close a sufficient number of control valves that were previously open to maintain diversity, and balance terminals that were just opened.
9. Prior to verifying final system conditions, determine system differential-pressure set point.
10. If the pump discharge valve was used to set total system flow with variable-frequency controller at 60 Hz, at completion open discharge valve 100 percent and allow variable-frequency controller to control system differential-pressure set point. Record pump data under both conditions.
11. Mark final settings and verify that memory stops have been set.
12. Verify final system conditions as follows:
  - a. Re-measure and confirm that total water flow is within design.
  - b. Re-measure final pumps' operating data, TDH, volts, amps, and static profile.
  - c. Mark final settings.
13. Verify that memory stops have been set.

### 3.8 TOLERANCES

- A. Set HVAC system's airflow rates and water flow rates within the following tolerances:
  1. Supply, Return, and Exhaust Fans and Equipment with Fans: Plus or minus 10 percent.
  2. Air Outlets and Inlets: Plus or minus 10 percent.
  3. Condenser Water Flow Rate: Plus or minus 10 percent.
- B. Maintaining pressure relationships as designed shall have priority over the tolerances specified above.

### 3.9 FINAL REPORT

- A. General: Prepare a certified written report; tabulate and divide the report into separate sections for tested systems and balanced systems.
1. Include a certification sheet at the front of the report's binder, signed and sealed by the certified testing and balancing engineer.
  2. Include a list of instruments used for procedures, along with proof of calibration.
  3. Certify validity and accuracy of field data.
- B. General Report Data: In addition to form titles and entries, include the following data:
1. Title page.
  2. Name and address of the TAB specialist.
  3. Project name.
  4. Project location.
  5. Architect's name and address.
  6. Engineer's name and address.
  7. Contractor's name and address.
  8. Report date.
  9. Signature of TAB supervisor who certifies the report.
  10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.
  11. Summary of contents including the following:
    - a. Indicated versus final performance.
    - b. Notable characteristics of systems.
    - c. Description of system operation sequence if it varies from the Contract Documents.
  12. Nomenclature sheets for each item of equipment.
  13. Data for terminal units, including manufacturer's name, type, size, and fittings.
  14. Notes to explain why certain final data in the body of reports vary from indicated values.
  15. Test conditions for fans and pump performance forms including the following:
    - a. Settings for outdoor-, return-, and exhaust-air dampers.
    - b. Conditions of filters.
    - c. Cooling coil, wet- and dry-bulb conditions.
    - d. Face and bypass damper settings at coils.
    - e. Fan drive settings including settings and percentage of maximum pitch diameter.
    - f. Inlet vane settings for variable-air-volume systems.
    - g. Settings for supply-air, static-pressure controller.
    - h. Other system operating conditions that affect performance.
- C. Air-Handling-Unit Test Reports: For air-handling units with coils, include the following:
1. Unit Data:
    - a. Unit identification.
    - b. Location.
    - c. Make and type.
    - d. Model number and unit size.
    - e. Manufacturer's serial number.

- f. Unit arrangement and class.
    - g. Discharge arrangement.
  2. Motor Data:
    - a. Motor make, and frame type and size.
    - b. Horsepower and rpm.
    - c. Volts, phase, and hertz.
    - d. Full-load amperage and service factor.
  3. Test Data (Indicated and Actual Values):
    - a. Total airflow rate in cfm.
    - b. Total system static pressure in inches wg.
    - c. Fan rpm.
    - d. Discharge static pressure in inches wg.
    - e. Filter static-pressure differential in inches wg.
    - f. Cooling-coil static-pressure differential in inches wg.
    - g.
- D. Electric-Coil Test Reports: For electric furnaces, duct coils, and electric coils installed in central-station air-handling units, include the following:
  1. Unit Data:
    - a. System identification.
    - b. Location.
    - c. Coil identification.
    - d. Capacity in Btu/h.
    - e. Number of stages.
    - f. Connected volts, phase, and hertz.
    - g. Rated amperage.
    - h. Airflow rate in cfm.
    - i. Face area in sq. ft..
    - j. Minimum face velocity in fpm.
  2. Test Data (Indicated and Actual Values):
    - a. Heat output in Btu/h.
    - b. Airflow rate in cfm.
    - c. Air velocity in fpm.
    - d. Entering-air temperature in deg F.
    - e. Leaving-air temperature in deg F.
    - f. Voltage at each connection.
    - g. Amperage for each phase.
- E. Fan Test Reports: For supply, return, and exhaust fans, include the following:
  1. Fan Data:
    - a. System identification.
    - b. Location.
    - c. Make and type.

- d. Model number and size.
    - e. Manufacturer's serial number.
    - f. Arrangement and class.
  2. Motor Data:
    - a. Motor make, and frame type and size.
    - b. Horsepower and rpm.
    - c. Volts, phase, and hertz.
    - d. Full-load amperage and service factor.
  3. Test Data (Indicated and Actual Values):
    - a. Total airflow rate in cfm.
    - b. Total system static pressure in inches wg.
    - c. Fan rpm.
    - d. Discharge static pressure in inches wg.
    - e. Suction static pressure in inches wg.
- F. Round, Flat-Oval, and Rectangular Duct Traverse Reports: Include a diagram with a grid representing the duct cross-section and record the following:
  1. Report Data:
    - a. System and air-handling-unit number.
    - b. Location and zone.
    - c. Traverse air temperature in deg F.
    - d. Duct static pressure in inches wg.
    - e. Duct size in inches.
    - f. Duct area in sq. ft..
    - g. Indicated airflow rate in cfm.
    - h. Indicated velocity in fpm.
    - i. Actual airflow rate in cfm.
    - j. Actual average velocity in fpm.
    - k. Barometric pressure in psig.
- G. Air-Terminal-Device Reports:
  1. Unit Data:
    - a. System and air-handling unit identification.
    - b. Location and zone.
    - c. Apparatus used for test.
    - d. Area served.
    - e. Make.
    - f. Number from system diagram.
    - g. Type and model number.
    - h. Size.
    - i. Effective area in sq. ft..
  2. Test Data (Indicated and Actual Values):
    - a. Airflow rate in cfm.

- b. Air velocity in fpm.
  - c. Preliminary airflow rate as needed in cfm.
  - d. Preliminary velocity as needed in fpm.
  - e. Final airflow rate in cfm.
  - f. Final velocity in fpm.
  - g. Space temperature in deg F.
3. Test Data (Indicated and Actual Values):
- a. Static head in feet of head or psig.
  - b. Pump shutoff pressure in feet of head or psig.
  - c. Actual impeller size in inches.
  - d. Full-open flow rate in gpm.
  - e. Full-open pressure in feet of head or psig.
  - f. Final discharge pressure in feet of head or psig.
  - g. Final suction pressure in feet of head or psig.
  - h. Final total pressure in feet of head or psig.
  - i. Final water flow rate in gpm.
  - j. Voltage at each connection.
  - k. Amperage for each phase.

H. Instrument Calibration Reports:

1. Report Data:
- a. Instrument type and make.
  - b. Serial number.
  - c. Application.
  - d. Dates of use.
  - e. Dates of calibration.

3.10 ADDITIONAL TESTS

- A. Within 90 days of completing TAB, perform additional TAB to verify that balanced conditions are being maintained throughout and to correct unusual conditions.
- B. Seasonal Periods: If initial TAB procedures were not performed during near-peak summer and winter conditions, perform additional TAB during near-peak summer and winter conditions.

END OF SECTION 230593

## SECTION 230713 - DUCT INSULATION

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes insulating the following duct services:
  - 1. Indoor, concealed supply air.
  - 2. Indoor, concealed return located in unconditioned space.
- B. Related Sections:
  - 1. Section 233113 "Metal Ducts" for duct liners.

#### 1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

#### 1.3 QUALITY ASSURANCE

- A. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84, by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
  - 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
  - 2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

### PART 2 - PRODUCTS

#### 2.1 INSULATION MATERIALS

- A. Comply with requirements in "Duct Insulation Schedule, General," "Indoor Duct and Plenum Insulation Schedule," and "Aboveground, Outdoor Duct and Plenum Insulation Schedule" articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.

- E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.

## 2.2 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.
- B. ASJ Adhesive, and FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.

## 2.3 MASTICS

- A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.
- B. Vapor-Barrier Mastic: Water based; suitable for indoor use on below ambient services.
  - 1. Water-Vapor Permeance: ASTM E 96/E 96M, Procedure B, 0.013 perm at 43-mil dry film thickness.
  - 2. Service Temperature Range: Minus 20 to plus 180 deg F.
  - 3. Solids Content: ASTM D 1644, 58 percent by volume and 70 percent by weight.
  - 4. Color: White.
- C. Breather Mastic: Water based; suitable for indoor and outdoor use on above ambient services.
  - 1. Water-Vapor Permeance: ASTM F 1249, 1.8 perms at 0.0625-inch dry film thickness.
  - 2. Service Temperature Range: Minus 20 to plus 180 deg F.
  - 3. Solids Content: 60 percent by volume and 66 percent by weight.
  - 4. Color: White.

## 2.4 SEALANTS

- A. FSK and Metal Jacket Flashing Sealants:
  - 1. Materials shall be compatible with insulation materials, jackets, and substrates.
  - 2. Fire- and water-resistant, flexible, elastomeric sealant.
  - 3. Service Temperature Range: Minus 40 to plus 250 deg F.
  - 4. Color: Aluminum.
- B. ASJ Flashing Sealants, and Vinyl and PVC Jacket Flashing Sealants:
  - 1. Materials shall be compatible with insulation materials, jackets, and substrates.
  - 2. Fire- and water-resistant, flexible, elastomeric sealant.
  - 3. Service Temperature Range: Minus 40 to plus 250 deg F.
  - 4. Color: White.

## 2.5 FIELD-APPLIED FABRIC-REINFORCING MESH

- A. Woven Polyester Fabric: Approximately 1 oz./sq. yd. with a thread count of 10 strands by 10 strands/sq. in., in a Leno weave, for ducts.

## 2.6 TAPES

- A. Aluminum-Foil Tape: Vapor-retarder tape with acrylic adhesive.
  - 1. Width: 2 inches.
  - 2. Thickness: 3.7 mils.
  - 3. Adhesion: 100 ounces force/inch in width.
  - 4. Elongation: 5 percent.
  - 5. Tensile Strength: 34 lbf/inch in width.

## 2.7 SECUREMENTS

- A. Aluminum Bands: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 1/2 inch wide with wing seal or closed seal.
- B. Insulation Pins and Hangers:
  - 1. Metal, Adhesively Attached, Perforated-Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
    - a. Baseplate: Perforated, galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
    - b. Spindle: Aluminum, fully annealed, 0.106-inch-diameter shank, length to suit depth of insulation indicated.
    - c. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.
  - 2. Nonmetal, Adhesively Attached, Perforated-Base Insulation Hangers: Baseplate fastened to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
    - a. Baseplate: Perforated, nylon sheet, 0.030 inch thick by 1-1/2 inches in diameter.
    - b. Spindle: Nylon, 0.106-inch-diameter shank, length to suit depth of insulation indicated, up to 2-1/2 inches.
    - c. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.
  - 3. Self-Sticking-Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
    - a. Baseplate: Galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
    - b. Spindle: Aluminum, fully annealed, 0.106-inch-diameter shank, length to suit depth of insulation indicated.
    - c. Adhesive-backed base with a peel-off protective cover.
  - 4. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick, aluminum sheet, with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
    - a. Protect ends with capped self-locking washers incorporating a spring steel insert to ensure permanent retention of cap in exposed locations.



5. Nonmetal Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick nylon sheet, with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
- C. Staples: Outward-clinching insulation staples, nominal 3/4-inch-wide, stainless steel or Monel.
- D. Wire: 0.080-inch nickel-copper alloy.

### PART 3 - EXECUTION

#### 3.1 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

#### 3.2 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of ducts and fittings.
- B. Install insulation materials, vapor barriers or retarders, jackets, and thicknesses required for each item of duct system as specified in insulation system schedules.
- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Keep insulation materials dry during application and finishing.
- G. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- H. Install insulation with least number of joints practical.
- I. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
  1. Install insulation continuously through hangers and around anchor attachments.
  2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
  3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.

- J. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- K. Install insulation with factory-applied jackets as follows:
  - 1. Draw jacket tight and smooth.
  - 2. Cover circumferential joints with 3-inch-wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
  - 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 2 inches o.c.
    - a. For below ambient services, apply vapor-barrier mastic over staples.
  - 4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
  - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to duct flanges and fittings.
- L. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- M. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- N. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.

### 3.3 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  - 3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
  - 4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.

3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
  4. Seal jacket to wall flashing with flashing sealant.
- C. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- D. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Terminate insulation at fire damper sleeves for fire-rated wall and partition penetrations. Externally insulate damper sleeves to match adjacent insulation and overlap duct insulation at least 2 inches.
1. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping and fire-resistive joint sealers.
- E. Insulation Installation at Floor Penetrations:
1. Duct: For penetrations through fire-rated assemblies, terminate insulation at fire damper sleeves and externally insulate damper sleeve beyond floor to match adjacent duct insulation. Overlap damper sleeve and duct insulation at least 2 inches.
  2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

### 3.4 INSTALLATION OF MINERAL-FIBER INSULATION

- A. Blanket Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.
1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
  2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
  3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
    - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
    - b. On duct sides with dimensions larger than 18 inches, place pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
    - c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
    - d. Do not overcompress insulation during installation.
    - e. Impale insulation over pins and attach speed washers.
    - f. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.
  4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch

- o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
- a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
  - b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.
5. Overlap unfaced blankets a minimum of 2 inches on longitudinal seams and end joints. At end joints, secure with steel bands spaced a maximum of 18 inches o.c.
6. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
7. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch-wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.
- B. Board Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.
1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
  2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
  3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
    - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
    - b. On duct sides with dimensions larger than 18 inches, space pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
    - c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
    - d. Do not overcompress insulation during installation.
    - e. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.
  4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
    - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
    - b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped

pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.

5. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Groove and score insulation to fit as closely as possible to outside and inside radius of elbows. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
6. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch-wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

### 3.5 FINISHES

- A. Insulation with ASJ or Other Paintable Jacket Material: Paint jacket with paint system identified below.
  1. Flat Acrylic Finish: Two finish coats over a primer that is compatible with jacket material and finish coat paint. Add fungicidal agent to render fabric mildew proof.
    - a. Finish Coat Material: Interior, flat, latex-emulsion size.
- B. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.
- C. Do not field paint aluminum or stainless-steel jackets.

### 3.6 DUCT INSULATION SCHEDULE

- A. Refer to plans.

END OF SECTION 230713

## SECTION 233113 - METAL DUCTS

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Section Includes:

1. Rectangular ducts and fittings.
2. Round ducts and fittings.
3. Sheet metal materials.
4. Sealant and gaskets.
5. Hangers and supports.

B. Related Sections:

1. Section 230593 "Testing, Adjusting, and Balancing for HVAC" for testing, adjusting, and balancing requirements for metal ducts.
2. Section 233300 "Air Duct Accessories" for dampers, sound-control devices, duct-mounting access doors and panels, turning vanes, and flexible ducts.

#### 1.2 PERFORMANCE REQUIREMENTS

- A. Delegated Duct Design: Duct construction, including sheet metal thicknesses, seam and joint construction, reinforcements, and hangers and supports, shall comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" and performance requirements and design criteria indicated in "Duct Schedule" Article.
- B. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

### PART 2 - PRODUCTS

#### 2.1 RECTANGULAR DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" based on indicated static-pressure class unless otherwise indicated.
- B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-1, "Rectangular Duct/Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support

intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

- C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Duct/Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- D. Elbows, Transitions, Offsets, Branch Connections, and Other Duct Construction: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 4, "Fittings and Other Construction," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

## 2.2 ROUND DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on indicated static-pressure class unless otherwise indicated.
- B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-1, "Round Duct Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
  - 1. Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged.
- C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-2, "Round Duct Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
  - 1. Fabricate round ducts larger Than 90 inches in diameter with butt-welded longitudinal seams.
- D. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

## 2.3 SHEET METAL MATERIALS

- A. General Material Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

- B. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
  - 1. Galvanized Coating Designation: G60.
  - 2. Finishes for Surfaces Exposed to View: Mill phosphatized.
- C. Carbon-Steel Sheets: Comply with ASTM A 1008/A 1008M, with oiled, matte finish for exposed ducts.
- D. Stainless-Steel Sheets: Comply with ASTM A 480/A 480M, Type 304 or 316, as indicated in the "Duct Schedule" Article; cold rolled, annealed, sheet. Exposed surface finish shall be No. 2B, No. 2D, No. 3, or No. 4 as indicated in the "Duct Schedule" Article.
- E. Aluminum Sheets: Comply with ASTM B 209 Alloy 3003, H14 temper; with mill finish for concealed ducts, and standard, one-side bright finish for duct surfaces exposed to view.
- F. Reinforcement Shapes and Plates: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
  - 1. Where black- and galvanized-steel shapes and plates are used to reinforce aluminum ducts, isolate the different metals with butyl rubber, neoprene, or EPDM gasket materials.
- G. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

#### 2.4 SEALANT AND GASKETS

- A. General Sealant and Gasket Requirements: Surface-burning characteristics for sealants and gaskets shall be a maximum flame-spread index of 25 and a maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.
- B. Two-Part Tape Sealing System:
  - 1. Tape: Woven cotton fiber impregnated with mineral gypsum and modified acrylic/silicone activator to react exothermically with tape to form hard, durable, airtight seal.
  - 2. Tape Width: 3 inches.
  - 3. Sealant: Modified styrene acrylic.
  - 4. Water resistant.
  - 5. Mold and mildew resistant.
  - 6. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
  - 7. Service: Indoor and outdoor.
  - 8. Service Temperature: Minus 40 to plus 200 deg F.
  - 9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum.
  - 10. For indoor applications, sealant shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 11. Sealant shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- C. Water-Based Joint and Seam Sealant:
  - 1. Application Method: Brush on.



2. Solids Content: Minimum 65 percent.
3. Shore A Hardness: Minimum 20.
4. Water resistant.
5. Mold and mildew resistant.
6. VOC: Maximum 75 g/L (less water).
7. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
8. Service: Indoor or outdoor.
9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.

D. Flanged Joint Sealant: Comply with ASTM C 920.

1. General: Single-component, acid-curing, silicone, elastomeric.
2. Type: S.
3. Grade: NS.
4. Class: 25.
5. Use: O.
6. For indoor applications, sealant shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
7. Sealant shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

E. Flange Gaskets: Butyl rubber, neoprene, or EPDM polymer with polyisobutylene plasticizer.

F. Round Duct Joint O-Ring Seals:

1. Seal shall provide maximum leakage class of 3 cfm/100 sq. ft. at 1-inch wg and shall be rated for 10-inch wg static-pressure class, positive or negative.
2. EPDM O-ring to seal in concave bead in coupling or fitting spigot.
3. Double-lipped, EPDM O-ring seal, mechanically fastened to factory-fabricated couplings and fitting spigots.

## 2.5 HANGERS AND SUPPORTS

A. Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts.

B. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct."

C. Steel Cables for Galvanized-Steel Ducts: Galvanized steel complying with ASTM A 603.

D. Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.

E. Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.

F. Trapeze and Riser Supports:

1. Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.

2. Supports for Stainless-Steel Ducts: Stainless-steel shapes and plates.
3. Supports for Aluminum Ducts: Aluminum or galvanized steel coated with zinc chromate.

### PART 3 - EXECUTION

#### 3.1 DUCT INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of duct system. Indicated duct locations, configurations, and arrangements were used to size ducts and calculate friction loss for air-handling equipment sizing and for other design considerations. Install duct systems as indicated unless deviations to layout are approved on Shop Drawings and Coordination Drawings.
- B. Install ducts according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" unless otherwise indicated.
- C. Install round ducts in maximum practical lengths.
- D. Install ducts with fewest possible joints.
- E. Install factory- or shop-fabricated fittings for changes in direction, size, and shape and for branch connections.
- F. Unless otherwise indicated, install ducts vertically and horizontally, and parallel and perpendicular to building lines.
- G. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building.
- H. Install ducts with a clearance of 1 inch, plus allowance for insulation thickness.
- I. Route ducts to avoid passing through transformer vaults and electrical equipment rooms and enclosures.
- J. Where ducts pass through non-fire-rated interior partitions and exterior walls and are exposed to view, cover the opening between the partition and duct or duct insulation with sheet metal flanges of same metal thickness as the duct. Overlap openings on four sides by at least 1-1/2 inches.
- K. Where ducts pass through fire-rated interior partitions and exterior walls, install fire dampers. Comply with requirements in Section 233300 "Air Duct Accessories" for fire and smoke dampers.
- L. Protect duct interiors from moisture, construction debris and dust, and other foreign materials. Comply with SMACNA's "IAQ Guidelines for Occupied Buildings Under Construction," Appendix G, "Duct Cleanliness for New Construction Guidelines."

### 3.2 DUCT SEALING

- A. Seal ducts for duct static-pressure, seal classes, and leakage classes specified in "Duct Schedule" Article according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- B. Seal ducts to the following seal classes according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible":
  - 1. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
  - 2. Unconditioned Space, Supply-Air Ducts in Pressure Classes 2-Inch wg and Lower: Seal Class B.
  - 3. Unconditioned Space, Supply-Air Ducts in Pressure Classes Higher Than 2-Inch wg: Seal Class A.
  - 4. Unconditioned Space, Return-Air Ducts: Seal Class B.

### 3.3 HANGER AND SUPPORT INSTALLATION

- A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 5, "Hangers and Supports."
- B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
  - 1. Where practical, install concrete inserts before placing concrete.
  - 2. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
  - 3. Use powder-actuated concrete fasteners for standard-weight aggregate concretes or for slabs more than 4 inches thick.
  - 4. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes or for slabs less than 4 inches thick.
  - 5. Do not use powder-actuated concrete fasteners for seismic restraints.
- C. Hanger Spacing: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct," for maximum hanger spacing; install hangers and supports within 24 inches of each elbow and within 48 inches of each branch intersection.
- D. Hangers Exposed to View: Threaded rod and angle or channel supports.
- E. Support vertical ducts with steel angles or channel secured to the sides of the duct with welds, bolts, sheet metal screws, or blind rivets; support at each floor and at a maximum intervals of 16 feet .
- F. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

### 3.4 CONNECTIONS

- A. Make connections to equipment with flexible connectors complying with Section 233300 "Air Duct Accessories."

- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for branch, outlet and inlet, and terminal unit connections.

### 3.5 DUCT CLEANING

- A. Clean new and existing duct system(s) within area of work before testing, adjusting, and balancing.
  - 1.

- B. Clean the following components by removing surface contaminants and deposits:

- 1. Air outlets and inlets (registers, grilles, and diffusers).
- 2. Supply, return, and exhaust fans including fan housings, plenums (except ceiling supply and return plenums), scrolls, blades or vanes, shafts, baffles, dampers, and drive assemblies.
- 3. Air-handling unit internal surfaces and components including mixing box, coil section, air wash systems, spray eliminators, condensate drain pans, humidifiers and dehumidifiers, filters and filter sections, and condensate collectors and drains.
- 4. Coils and related components.
- 5. Return-air ducts, dampers, actuators, and turning vanes except in ceiling plenums and mechanical equipment rooms.
- 6. Supply-air ducts, dampers, actuators, and turning vanes.
- 7. Dedicated exhaust and ventilation components and makeup air systems.

- C. Mechanical Cleaning Methodology:

- 1. Clean metal duct systems using mechanical cleaning methods that extract contaminants from within duct systems and remove contaminants from building.
- 2. Use vacuum-collection devices that are operated continuously during cleaning. Connect vacuum device to downstream end of duct sections so areas being cleaned are under negative pressure.
- 3. Use mechanical agitation to dislodge debris adhered to interior duct surfaces without damaging integrity of metal ducts, duct liner, or duct accessories.
- 4. Clean fibrous-glass duct liner with HEPA vacuuming equipment; do not permit duct liner to get wet. Replace fibrous-glass duct liner that is damaged, deteriorated, or delaminated or that has friable material, mold, or fungus growth.
- 5. Clean coils and coil drain pans according to NADCA 1992. Keep drain pan operational. Rinse coils with clean water to remove latent residues and cleaning materials; comb and straighten fins.
- 6. Provide drainage and cleanup for wash-down procedures.
- 7. Antimicrobial Agents and Coatings: Apply EPA-registered antimicrobial agents if fungus is present. Apply antimicrobial agents according to manufacturer's written instructions after removal of surface deposits and debris.

### 3.6 START UP

- A. Air Balance: Comply with requirements in Section 230593 "Testing, Adjusting, and Balancing for HVAC."

ORANGE COUNTY SHERIFF'S OFFICE  
CENTRAL OPERATIONS CENTER -  
SHERIFF'S OFFICE COMMAND AND MONITOR CENTER  
ORANGE COUNTY, FLORIDA

METAL DUCTS  
SECTION 233113

3.7 DUCT SCHEDULE

- A. Refer to schedule on plans.

END OF SECTION 233113

## SECTION 233300 - AIR DUCT ACCESSORIES

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Section Includes:

1. Backdraft dampers.
2. Manual volume dampers.
3. Fire dampers.
4. Flange connectors.
5. Turning vanes.
6. Duct-mounted access doors.
7. Flexible connectors.
8. Duct accessory hardware.

B. Related Requirements:

1. Section 283111 "Digital, Addressable Fire-Alarm System" for duct-mounted fire and smoke detectors.

#### 1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.

### PART 2 - PRODUCTS

#### 2.1 ASSEMBLY DESCRIPTION

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

#### 2.2 MATERIALS

- A. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.

1. Galvanized Coating Designation: G60.
2. Exposed-Surface Finish: Mill phosphatized.

- B. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.

- C. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

### 2.3 BACKDRAFT DAMPERS

- A. Description: Gravity balanced.
- B. Maximum Air Velocity: 2000 fpm.
- C. Maximum System Pressure: 2-inch wg.
- D. Frame: Hat-shaped, 0.05-inch-thick, galvanized sheet steel, with welded corners or mechanically attached and mounting flange.
- E. Blades: Multiple single-piece blades, maximum 6-inch width, 0.025-inch-thick, roll-formed aluminum with sealed edges.
- F. Blade Action: Parallel.
- G. Blade Seals: Extruded vinyl, mechanically locked.
- H. Blade Axles:
  - 1. Material: Galvanized steel.
  - 2. Diameter: 0.20 inch.
- I. Tie Bars and Brackets: Aluminum.
- J. Return Spring: Adjustable tension.
- K. Bearings: Steel ball or synthetic pivot bushings.
- L. Accessories:
  - 1. Adjustment device to permit setting for varying differential static pressure.
  - 2. Counterweights and spring-assist kits for vertical airflow installations.
  - 3. Electric actuators.
  - 4. Chain pulls.
  - 5. Screen Mounting: Front mounted in sleeve.
    - a. Sleeve Thickness: 20 gage minimum.
    - b. Sleeve Length: 6 inches minimum.
  - 6. Screen Mounting: Rear mounted.
  - 7. 90-degree stops.

### 2.4 MANUAL VOLUME DAMPERS

- A. Standard, Steel, Manual Volume Dampers:
  - 1. Standard leakage rating.
  - 2. Suitable for horizontal or vertical applications.

3. Frames:
    - a. Frame: Hat-shaped, 0.094-inch-thick, galvanized sheet steel.
    - b. Mitered and welded corners.
    - c. Flanges for attaching to walls and flangeless frames for installing in ducts.
  4. Blades:
    - a. Multiple or single blade.
    - b. Parallel- or opposed-blade design.
    - c. Stiffen damper blades for stability.
    - d. Galvanized-steel, 0.064 inch thick.
  5. Blade Axles: Galvanized steel.
  6. Bearings:
    - a. Oil-impregnated bronze.
    - b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
  7. Tie Bars and Brackets: Galvanized steel.
- B. Standard, Aluminum, Manual Volume Dampers:
1. Standard leakage rating.
  2. Suitable for horizontal or vertical applications.
  3. Frames: Hat-shaped, 0.10-inch-thick, aluminum sheet channels; frames with flanges for attaching to walls and flangeless frames for installing in ducts.
  4. Blades:
    - a. Multiple or single blade.
    - b. Parallel- or opposed-blade design.
    - c. Stiffen damper blades for stability.
    - d. Roll-Formed Aluminum Blades: 0.10-inch-thick aluminum sheet.
    - e. Extruded-Aluminum Blades: 0.050-inch-thick extruded aluminum.
  5. Blade Axles: Galvanized steel.
  6. Bearings:
    - a. Oil-impregnated bronze.
    - b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
  7. Tie Bars and Brackets: Aluminum.
- C. Jackshaft:
1. Size: 0.5-inch diameter.
  2. Material: Galvanized-steel pipe rotating within pipe-bearing assembly mounted on supports at each mullion and at each end of multiple-damper assemblies.
  3. Length and Number of Mountings: As required to connect linkage of each damper in multiple-damper assembly.
- D. Damper Hardware:



1. Zinc-plated, die-cast core with dial and handle made of 3/32-inch-thick zinc-plated steel, and a 3/4-inch hexagon locking nut.
2. Include center hole to suit damper operating-rod size.
3. Include elevated platform for insulated duct mounting.

## 2.5 FIRE DAMPERS

- A. Contractor shall verify operation of existing fire dampers at area of work. Notify owner if any are non-functional.

## 2.6 FLANGE CONNECTORS

- A. Description: Add-on or roll-formed, factory-fabricated, slide-on transverse flange connectors, gaskets, and components.
- B. Material: Galvanized steel.
- C. Gage and Shape: Match connecting ductwork.

## 2.7 TURNING VANES

- A. Manufactured Turning Vanes for Metal Ducts: Curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
  1. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.
- B. Manufactured Turning Vanes for Nonmetal Ducts: Fabricate curved blades of resin-bonded fiberglass with acrylic polymer coating; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
- C. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 4-3, "Vaness and Vane Runners," and 4-4, "Vane Support in Elbows."
- D. Vane Construction: Double wall.

## 2.8 DUCT-MOUNTED ACCESS DOORS

- A. Duct-Mounted Access Doors: Fabricate access panels according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 7-2, "Duct Access Doors and Panels," and 7-3, "Access Doors - Round Duct."
  1. Door:
    - a. Double wall, rectangular.
    - b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
    - c. Vision panel.
    - d. Hinges and Latches: 1-by-1-inchbutt or piano hinge and cam latches.

- e. Fabricate doors airtight and suitable for duct pressure class.
- 2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
- 3. Number of Hinges and Locks:
  - a. Access Doors Less Than 12 Inches Square: No hinges and two sash locks.
  - b. Access Doors up to 18 Inches Square: Continuous and two sash locks.

## 2.9 FLEXIBLE CONNECTORS

- A. Materials: Flame-retardant or noncombustible fabrics.
- B. Coatings and Adhesives: Comply with UL 181, Class 1.
- C. Metal-Edged Connectors: Factory fabricated with a fabric strip 3-1/2 inches wide attached to two strips of 2-3/4-inch-wide, 0.028-inch-thick, galvanized sheet steel or 0.032-inch-thick aluminum sheets. Provide metal compatible with connected ducts.
- D. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.
  - 1. Minimum Weight: 26 oz./sq. yd..
  - 2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
  - 3. Service Temperature: Minus 40 to plus 200 deg F.

## 2.10 DUCT ACCESSORY HARDWARE

- A. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct-insulation thickness.
- B. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.
- B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, stainless-steel accessories in stainless-steel ducts, and aluminum accessories in aluminum ducts.
- C. Install backdraft dampers at inlet of exhaust fans or exhaust ducts as close as possible to exhaust fan unless otherwise indicated.

- D. Install volume dampers at points on supply, return, and exhaust systems where branches extend from larger ducts. Where dampers are installed in ducts having duct liner, install dampers with hat channels of same depth as liner, and terminate liner with nosing at hat channel.
  - 1. Install steel volume dampers in steel ducts.
  - 2. Install aluminum volume dampers in aluminum ducts.
- E. Set dampers to fully open position before testing, adjusting, and balancing.
- F. Install test holes at fan inlets and outlets and elsewhere as indicated.
- G. Install duct access doors on sides of ducts to allow for inspecting, adjusting, and maintaining accessories and equipment at the following locations:
  - 1. Downstream from backdraft dampers.
  - 2. Adjacent to and close enough to fire or smoke dampers, to reset or reinstall fusible links. Access doors for access to fire or smoke dampers having fusible links shall be pressure relief access doors and shall be outward operation for access doors installed upstream from dampers and inward operation for access doors installed downstream from dampers.
  - 3. Elsewhere as indicated.
- H. Install access doors with swing against duct static pressure.
- I. Access Door Sizes:
  - 1. One-Hand or Inspection Access: 8 by 5 inches.
  - 2. Two-Hand Access: 12 by 6 inches.
  - 3. Head and Hand Access: 18 by 10 inches.
  - 4. Head and Shoulders Access: 21 by 14 inches.
  - 5. Body Access: 25 by 14 inches.
  - 6. Body plus Ladder Access: 25 by 17 inches.
- J. Label access doors to indicate the purpose of access door.
- K. Install flexible connectors to connect ducts to equipment.
- L. Connect diffusers or light troffer boots to ducts with maximum 60-inch lengths of flexible duct clamped or strapped in place.
- M. Connect flexible ducts to metal ducts with adhesive plus sheet metal screws.
- N. Install duct test holes where required for testing and balancing purposes.

END OF SECTION 233300

SECTION 233346 - FLEXIBLE DUCTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
  - 1. Insulated flexible ducts.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 ASSEMBLY DESCRIPTION

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- C. Comply with the Air Diffusion Council's "ADC Flexible Air Duct Test Code FD 72-R1."
- D. Comply with ASTM E 96/E 96M, "Test Methods for Water Vapor Transmission of Materials."

2.2 INSULATED FLEXIBLE DUCTS

- A. Insulated, Flexible Duct: UL 181, Class 1, two-ply vinyl film supported by helically wound, spring-steel wire; fibrous-glass insulation; aluminized vapor-barrier film.
  - 1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
  - 2. Maximum Air Velocity: 4000 fpm.
  - 3. Temperature Range: Minus 10 to plus 160 deg F.
  - 4. Insulation R-Value: R6.
- B. Insulated, Flexible Duct: UL 181, Class 1, multiple layers of aluminum laminate supported by helically wound, spring-steel wire; fibrous-glass insulation; aluminized vapor-barrier film.
  - 1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
  - 2. Maximum Air Velocity: 4000 fpm.
  - 3. Temperature Range: Minus 20 to plus 210 deg F.
  - 4. Insulation R-Value: R6.

### 2.3 FLEXIBLE DUCT CONNECTORS

- A. Clamps: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action in sizes 3 through 18 inches, to suit duct size.
- B. Non-Clamp Connectors: Adhesive plus sheet metal screws.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install flexible ducts according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.

Install in indoor applications only. Flexible ductwork should not be exposed to UV lighting.

- C. Connect diffusers or light troffer boots to ducts with maximum 60-inch lengths of flexible duct clamped or strapped in place.
- D. Connect flexible ducts to metal ducts with adhesive plus sheet metal screws.
- E. Install duct test holes where required for testing and balancing purposes.
- F. Installation:
  - 1. Install ducts fully extended.
  - 2. Do not bend ducts across sharp corners.
  - 3. Bends of flexible ducting shall not exceed a minimum of one duct diameter.
  - 4. Avoid contact with metal fixtures, water lines, pipes, or conduits.
  - 5. Install flexible ducts in a direct line, without sags, twists, or turns.
- G. Supporting Flexible Ducts:
  - 1. Suspend flexible ducts with bands 1-1/2 inches wide or wider and spaced a maximum of 48 inches apart. Maximum centerline sag between supports shall not exceed 1/2 inch per 12 inches.
  - 2. Install extra supports at bends placed approximately one duct diameter from center line of the bend.
  - 3. Ducts may rest on ceiling joists or truss supports. Spacing between supports shall not exceed the maximum spacing per manufacturer's written installation instructions.
  - 4. Vertically installed ducts shall be stabilized by support straps at a maximum of 72 inches o.c.

END OF SECTION 233346

SECTION 233600 - AIR TERMINAL UNITS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
  - 1. Shutoff, single-duct air terminal units.
  - 2. Parallel, fan-powered air terminal units.
  - 3. Casing liner.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of air terminal unit.

1.3 CLOSEOUT SUBMITTALS

- A. Operation and maintenance data.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and System Start-up."
- C. ASHRAE Compliance: Applicable requirements in ASHRAE/IES 90.1, "Section 6 - Heating, Ventilating, and Air Conditioning."

2.2 SHUTOFF, SINGLE-DUCT AIR TERMINAL UNITS

- A. Configuration: Volume-damper assembly inside unit casing with control components inside a protective metal shroud.
- B. Casing: 0.040-inch-thick galvanized steel, single wall.
  - 1. Casing Liner: Comply with requirements in "Casing Liner" Article for flexible elastomeric duct liner.
  - 2. Air Inlet: Round stub connection or S-slip and drive connections for duct attachment.
  - 3. Air Outlet: S-slip and drive connections.
  - 4. Access: Removable panels for access to parts requiring service, adjustment, or maintenance; with airtight gasket.

5. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.
- C. Regulator Assembly: System-air-powered bellows section incorporating polypropylene bellows for volume regulation and thermostatic control. Bellows shall operate at temperatures from zero to 140 deg F, shall be impervious to moisture and fungus, shall be suitable for 10-inch wg static pressure, and shall be factory tested for leaks.
- D. Volume Damper: Galvanized steel with peripheral gasket and self-lubricating bearings.
  1. Maximum Damper Leakage: AHRI 880 rated, 2 percent of nominal airflow at 3-inch wg inlet static pressure.
  2. Damper Position: Normally open.
- E. Electric-Resistance Heating Coils: Nickel-chromium heating wire, free of expansion noise and hum, mounted in ceramic inserts in a galvanized-steel housing; with primary automatic, and secondary manual, reset thermal cutouts. Terminate elements in stainless-steel, machine-staked terminals secured with stainless-steel hardware.
  1. SCR controlled.
  2. Access door interlocked disconnect switch.
  3. Downstream air temperature sensor with local connection to override discharge-air temperature to not exceed a maximum temperature set point (adjustable).
  4. Nickel chrome 80/20 heating elements.
  5. Airflow switch for proof of airflow.
  6. Fan interlock contacts.
  7. Fuses in terminal box for overcurrent protection (for coils more than 48 A).
  8. Mercury contactors.
- F. Control devices shall be compatible with temperature controls system.
  1. Electronic Damper Actuator: 24 V, powered open, capacitous return.
  2. Electric Thermostat: Wall-mounted electronic type with clock display, temperature display in Fahrenheit and Celsius, and space temperature set point.
  3. Electronic Thermostat: Wall-mounted electronic type with temperature set-point display in Fahrenheit and Celsius.
  4. Terminal Unit Controller: Pressure-independent, variable-air-volume (VAV) controller with electronic airflow transducer with multipoint velocity sensor at air inlet, factory calibrated to minimum and maximum air volumes, and having the following features:
    - a. Occupied and unoccupied operating mode.
    - b. Remote reset of airflow or temperature set points.
    - c. Adjusting and monitoring with portable terminal.
    - d. Communication with temperature-control system.
  5. Room Sensor: Wall mounted with temperature set-point adjustment and access for connection of portable operator terminal.
- G. Controls:
  1. Suitable for operation with duct pressures between 0.25- and 3.0-inch wg inlet static pressure.
  2. System-powered, wall-mounted thermostat.

H. Control Sequences:

1. Occupied:

- a. In a call for cooling, airflow will increase as the damper opens towards maximum setting to satisfy set point.
- b. In a call for less cooling, airflow will decrease as the damper closes towards minimum setting to satisfy set point.

2. Unoccupied:

- a. Damper closes to minimum maximum setting.

2.3 PARALLEL FAN-POWERED AIR TERMINAL UNITS

A. Configuration: Volume-damper assembly and fan in parallel arrangement inside unit casing with control components inside a protective metal shroud. Designed for quiet operation.

B. Casing: 0.040-inch-thick galvanized steel, single wall.

1. Casing Liner: Comply with requirements in "Casing Liner" Article for flexible elastomeric duct liner.
2. Air Inlets: Round stub connections or S-slip and drive connections for duct attachment.
3. Air Outlet: S-slip and drive connections.
4. Access: Removable panels for access to parts requiring service, adjustment, or maintenance; with airtight gasket and quarter-turn latches.
5. Fan: Forward-curved centrifugal, located at plenum air inlet.
6. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

C. Volume Damper: Galvanized steel with flow-sensing ring and peripheral gasket and self-lubricating bearings.

1. Maximum Damper Leakage: AHRI 880 rated, 2 percent of nominal airflow at 3-inch wg inlet static pressure.
2. Damper Position: Normally open.

D. Velocity Sensors: Multipoint array with velocity sensors.

E. Motor:

1. Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors.
2. Type: Electronically commutated motor.
3. Fan-Motor Assembly Isolation: Rubber isolators.
4. Enclosure: Totally enclosed, fan cooled.
5. Efficiency: Premium efficient.

F. Electric-Resistance Heating Coils: Nickel-chromium heating wire, free of expansion noise and hum, mounted in ceramic inserts in a galvanized-steel housing; with primary automatic, and



secondary manual, reset thermal cutouts. Terminate elements in stainless-steel, machine-staked terminals secured with stainless-steel hardware.

1. Location: Plenum air inlet.
  2. SCR controlled.
  3. Access door interlocked disconnect switch.
  4. Downstream air temperature sensor with local connection to override discharge-air temperature to not exceed a maximum temperature set point (adjustable).
  5. Nickel chrome 80/20 heating elements.
  6. Airflow switch for proof of airflow.
  7. Fan interlock contacts.
  8. Fuses in terminal box for overcurrent protection (for coils more than 48 A).
  9. Mercury contactors.
- G. Factory-Mounted and -Wired Controls: Electrical components mounted in control box with removable cover. Incorporate single-point electrical connection to power source.
1. Control Transformer: Factory mounted for control voltage on electric and electronic control units with terminal strip in control box for field wiring of thermostat and power source.
  2. Wiring Terminations: Fan and controls to terminal strip. Terminal lugs to match quantities, sizes, and materials of branch-circuit conductors. Enclose terminal lugs in terminal box that is sized according to NFPA 70.
  3. Disconnect Switch: Factory-mounted, fuse type.
- H. Control Panel Enclosure: NEMA 250, Type 1, with access panel sealed from airflow and mounted on side of unit.
- I. Control devices shall be compatible with temperature controls system.
1. Electronic Damper Actuator: 24 V, powered open, capacitive return.
  2. Electric Thermostat: Wall-mounted electronic type with clock display, temperature display in Fahrenheit and Celsius, and space temperature set point.
  3. Electronic Thermostat: Wall-mounted electronic type with temperature set-point display in Fahrenheit and Celsius.
  4. Terminal Unit Controller: Pressure-independent, VAV controller with electronic airflow transducer with multipoint velocity sensor at air inlet, factory calibrated to minimum and maximum air volumes, and having the following features:
- J. Control Sequence:
1. Occupied (Primary Airflow On):
    - a. Operate as throttling control for cooling.
    - b. As cooling requirement decreases, control valve throttles toward minimum airflow.
    - c. As heating requirement increases, fan energizes to draw in warm plenum air and electric heat modulates under SCR control.
  2. Unoccupied (Primary Airflow Off):
    - a. When pressure at primary inlet is zero or less, fan is de-energized.
    - b. As heating requirement increases, fan energizes to draw in warm plenum air and electric heat modulates under SCR control.

## 2.4 CASING LINER

- A. Casing Liner: Flexible elastomeric duct liner fabricated of preformed, cellular, closed-cell, sheet materials complying with ASTM C 534, Type II, Grade 1; and with NFPA 90A or NFPA 90B.
  - 1. Minimum Thickness: 3/4 inch.
  - 2. Surface-Burning Characteristics: Maximum flame-spread index of 25 and maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.
  - 3. Liner Adhesive: As recommended by insulation manufacturer and complying with NFPA 90A or NFPA 90B.

## 2.5 SOURCE QUALITY CONTROL

- A. Factory Tests: Test assembled air terminal units according to AHRI 880.
  - 1. Label each air terminal unit with plan number, nominal airflow, maximum and minimum factory-set airflows, coil type, and AHRI certification seal.

## PART 3 - EXECUTION

### 3.1 HANGER AND SUPPORT INSTALLATION

- A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Ch. 5, "Hangers and Supports" and with Section 230529 "Hangers and Supports for HVAC Piping and Equipment."
- B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
  - 1. Where practical, install concrete inserts before placing concrete.
  - 2. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
  - 3. Use powder-actuated concrete fasteners for standard-weight aggregate concretes and for slabs more than 4 inches thick.
  - 4. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes and for slabs less than 4 inches thick.
  - 5. Do not use powder-actuated concrete fasteners for seismic restraints.
- C. Hangers Exposed to View: Threaded rod and angle or channel supports.
- D. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

### 3.2 TERMINAL UNIT INSTALLATION

- A. Install air terminal units according to NFPA 90A, "Standard for the Installation of Air Conditioning and Ventilating Systems."

- B. Install air terminal units level and plumb. Maintain sufficient clearance for normal service and maintenance.
- C. Install wall-mounted thermostats.
- D. Where installing piping adjacent to air terminal unit, allow space for service and maintenance.
- E. Make connections to air terminal units with flexible connectors complying with requirements in Section 233300 "Air Duct Accessories."
- F. Label each air terminal unit with plan number, nominal airflow, and maximum and minimum factory-set airflows. Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for equipment labels and warning signs and labels.

END OF SECTION 233600

SECTION 233713 - AIR DIFFUSERS AND GRILLES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Rectangular and square ceiling diffusers.
2. Adjustable blade face grilles.
3. Fixed face grilles

B. Related Requirements:

1. Section 233300 "Air Duct Accessories" for fire and smoke dampers and volume-control dampers not integral to diffusers.
2. Section 233713.23 "Air Registers and Grilles" for adjustable-bar register and grilles, fixed-face registers and grilles, and linear bar grilles.
3. Section 233713.43 "Security Registers and Grilles" for security registers and security grilles.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 RECTANGULAR AND SQUARE CEILING DIFFUSERS

- A. Devices shall be specifically designed for variable-air-volume flows.
- B. Material: Steel.
- C. Finish: Baked enamel, white.
- D. Face Size: 24 by 24 inches.
- E. Face Style: Three cone.
- F. Mounting: Surface or T-bar.
- G. Pattern: Two position.
- H. Accessories:
1. Plaster ring.
  2. Safety chain.
  3. Wire guard.

## 2.2 GRILLES

- A. Adjustable Blade Face Grille:
  - 1. Material: Steel.
  - 2. Finish: Baked enamel, white.
  - 3. Face Blade Arrangement: Vertical spaced 1/2 inch apart.
  - 4. Core Construction: Integral.
  - 5. Frame: 1 inch wide.
  - 6. Mounting: Countersunk screw.
  
- B. Fixed Face Grille:
  - 1. Material: Steel.
  - 2. Finish: Baked enamel, white.
  - 3. Face Blade Arrangement: Horizontal; spaced 1/2 inch apart.
  - 4. Face Arrangement: Perforated core.
  - 5. Core Construction: Integral.
  - 6. Frame: 1 inch wide.
  - 7. Mounting: Concealed or Lay in.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install diffusers and grilles level and plumb.
  
- B. Ceiling-Mounted Outlets and Inlets: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practical. For units installed in lay-in ceiling panels, locate units in the center of panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.
  
- C. Install diffusers and grilles with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

### 3.2 ADJUSTING

- A. After installation, adjust diffusers to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION 233713

SECTION 238146 - WATER-SOURCE UNITARY HEAT PUMPS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes unitary heat pumps with refrigerant-to-water heat exchangers, refrigeration circuits, and refrigerant compressor(s).

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1.3 INFORMATIONAL SUBMITTALS

- A. Seismic Qualification Certificates: For water-source unitary heat pumps, accessories, and components, from manufacturer.
- B. Field quality-control reports.
- C. Sample Warranty: For manufacturer's warranty.

1.4 CLOSEOUT SUBMITTALS

- A. Operation and maintenance data.

1.5 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of water-source unitary heat pumps that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, refrigeration components.
  - 2. Warranty Period: Four years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. ASHRAE Compliance:
  - 1. ASHRAE 15.
- B. Comply with NFPA 70.

- C. Comply with safety requirements in UL 484 for assembly of free-delivery, water-source heat pumps.

## 2.2 WATER-SOURCE UNITARY HEAT PUMPS

- A. Description: Packaged water-source unitary heat pump with temperature controls; factory assembled, piped, wired, tested, and rated according to ASHRAE/ARI/ISO-13256-1.

- 1. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

- B. Cabinet and Chassis: Galvanized-steel casing with the following features:

- 1. Access panel for access and maintenance of internal components.
- 2. Knockouts for electrical and piping connections.
- 3. Cabinet Insulation: Glass-fiber liner, minimum, 3/4 inch thick, complying with UL 181, ASTM C 1071, and ASTM G 21.

- C. Water Circuits:

- 1. Refrigerant-to-Water Heat Exchangers:

- a. Source-side coaxial heat exchangers with copper water tube, with enhanced heat-transfer surfaces inside a steel shell; both shell and tube are leak tested to 450 psig on refrigerant side and 400 psig on water side.
- b. Load-side coaxial heat exchangers with copper water tube, with enhanced heat-transfer surfaces inside a steel shell; both shell and tube are leak tested to 450 psig on refrigerant side and 400 psig on water side.
- c. Stainless-steel, brazed-plate heat exchanger is leak tested to 450 psig on refrigerant side and 400 psig on water side. Factory mount heat exchanger in unit on resilient rubber vibration isolators.
- d. Hot-water generator, copper water tube with enhanced heat-transfer surfaces inside a steel shell; both shell and tube are leak tested to 450 psig on refrigerant side and 400 psig on water side, pump, circuit breaker, high water temperature and low water refrigerant cutoffs, and tank connection.

- D. Refrigerant Circuit Components:

- 1. Sealed Refrigerant Circuit: Charge with R-410A refrigerant.
- 2. Filter-Dryer: Factory installed to clean and dehydrate the refrigerant circuit.
- 3. Charging Connections: Service fittings on suction and liquid for charging and testing on each circuit.
- 4. Reversing Valve: Four-way, solenoid-activated valve designed to be fail-safe in heating position with replaceable magnetic coil.
- 5. Compressor:
  - a. Scroll.
  - b. Two stage.
  - c. Installed on vibration isolators and mounted on a structural steel base plate and full-length channel stiffeners.

- d. Exterior of compressor shall be wrapped with a high-density sound-attenuating blanket and housed in an acoustically treated enclosure.
  - e. Factory-Installed Safeties:
    - 1) Antirecycle timer.
    - 2) High-pressure cutout.
    - 3) Low-pressure cutout or loss of charge switch.
    - 4) Internal thermal-overload protection.
    - 5) Freezestat to stop compressor if water-loop temperature in refrigerant-to-water heat exchanger falls below 35 deg F.
    - 6) Water-coil, low-temperature switch.
  - 6. Refrigerant Piping Materials: ASTM B 743 copper tube with wrought-copper fittings and brazed joints.
  - 7. Pipe Insulation: Refrigerant minimum 3/8-inch-thick, flexible elastomeric insulation on piping exposed to airflow through the unit. Maximum 25/50 flame-spread/smoke-developed indexes according to ASTM E 84.
  - 8. Refrigerant Metering Device: Thermal-expansion valve.
  - 9. Refrigerant Metering Device: Dual-port, thermal-expansion valve to allow specified operation with entering-water temperatures from 25 to 125 deg F.
- E. Controls:
- 1. Basic Unit Control Modes and Devices:
    - a. Unit shutdown on high or low refrigerant pressures.
    - b. Unit shutdown on low water temperature.
    - c. Low- and high-voltage protection.
    - d. Overcurrent protection for compressor.
    - e. Random time delay, three to 10 seconds, start on power-up.
    - f. Time delay override for servicing.
    - g. Control voltage transformer.
    - h. Water-coil freeze protection (selectable for water or antifreeze).
    - i. Automatic intelligent reset. Unit shall automatically reset five minutes after trip if the fault has cleared. Should a fault reoccur three times sequentially, lockout requiring manual reset occurs.
    - j. Ability to defeat time delays for servicing.
    - k. Digital display to indicate high pressure, low pressure, low voltage, and high voltage.
    - l. The low-pressure switch shall not be monitored for the first 90 seconds after a compressor start command to prevent nuisance safety trips.
    - m. Remote fault-type indication at thermostat.
    - n. Selectable 24-V dc or pilot duty dry contact alarm output.
    - o. 24-V dc output to cycle a motorized water valve with compressor contactor.
    - p. Service test mode for troubleshooting and service.
    - q. Unit-performance sentinel warns when heat pump is running inefficiently.
    - r. Compressor soft start.
  - 2. Tie unit into existing building control system. Contractor to provide necessary components to accomplish tie-in.
  - 3. Thermostat:
    - a. Wall-mounted temperature sensor.



- F. Electrical Connection: Single electrical connection.

### 2.3 ACCESSORIES

- A. Hose Kits: Tag hose kits to equipment designations.

1. Minimum Working Pressure: 400 psig.
2. Operating Temperatures: From 33 to 211 deg F.
3. Hose Length: 24 inches.
4. Minimum Hose Diameter: Equal to water-source unitary heat-pump piping connection.
5. Hose Material: Braided stainless steel with adapters for pipe connections.
6. Isolation Valves: Two-piece, bronze-body ball valves with stainless-steel ball and stem, standard-port threaded connections, and galvanized-steel lever handle. Valves shall be factory installed on supply and return connections of both load-side and source-side heat exchangers. If balancing valve is combination shutoff type with memory stop, the isolation valve may be omitted on the return.
7. Strainer: Y-pattern with blowdown valve in supply connections of both load and source side of heat exchangers.
8. Balancing Valves: Mount in return connection. Include meter ports to allow flow measurement with differential pressure gage.
  - a. Automatic balancing valve, factory set to operate within 10 percent of design flow rate over a pressure range of 2 to 80 psig.
  - b. Manual, calibrated-orifice balancing valve with memory stop.
  - c. Manual, venturi-type balancing valve with memory stop.
9. Water-Regulating Valve Assemblies: A direct acting valve regulates discharge pressure during the cooling cycle, and a reverse acting valve regulates the suction pressure during the heating cycle. Valves shall close when heat-pump compressor is not running.
10. Motorized Water Valve: Stop water flow through the unit when compressor is off. Slow-acting, 24-V dc valve with threaded connections is installed between isolation valves and heat exchanger.

- B. Hose Kit Assemblies:

1. Minimum Working Pressure: 400-psig.
2. Operating Temperatures: From 33 to 211 deg F.
3. Hose Length: 24 inches.
4. Minimum Hose Diameter: Equal to water-source unitary heat-pump piping connection.
5. Hose Material: Braided stainless steel with adapters for pipe connections.
6. Supply and return hoses having ball valve with pressure-temperature port.
7. Supply hose having ball valve with pressure-temperature port; return hose having automatic flow regulator valve with pressure-temperature ports and ball valve.
8. Supply hose having Y-pattern strainer with blowdown valve and ball valve with pressure-temperature port; return hose having automatic flow regulator with pressure-temperature ports and ball valve.
9. Supply hose having Y-pattern strainer with blowdown valve and ball valve with pressure-temperature port; return hose having ball valve with pressure-temperature port.

- C. Loop Controller: Six stages; two stages for heating and four stages for cooling.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Suspend water-source, unitary heat pumps from structure with all-thread hanger rods and spring hangers.
- B. Install wall-mounting thermostats and switch controls in electrical outlet boxes at heights to match lighting controls.
- C. Drawings indicate general arrangement of piping, fittings, and specialties. Specific connection requirements are as follows:
  - 1. Connect supply and return hydronic piping to heat pump with unions and shutoff valves or hose kits.
- D. Install electrical devices furnished by manufacturer but not specified to be factory mounted.
- E. Install piping adjacent to machine to allow space for service and maintenance.

END OF SECTION 238146

SECTION 260519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Building wires and cables rated 600 V and less.
2. Connectors, splices, and terminations rated 600 V and less.

B. Related Requirements:

1. Section 271500 "Communications Horizontal Cabling" for cabling used for voice and data circuits.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1.3 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

PART 2 - PRODUCTS

2.1 CONDUCTORS AND CABLES

- A. Copper Conductors: Comply with NEMA WC 70/ICEA S-95-658.
- B. Conductor Insulation: Comply with NEMA WC 70/ICEA S-95-658 for Type THHN/THWN-2.
- C. Multiconductor Cable: Comply with NEMA WC 70/ICEA S-95-658 for armored cable, Type AC, metal-clad cable, Type MC, nonmetallic-sheathed cable, Type NM, with ground wire.

2.2 CONNECTORS AND SPLICES

- A. Description: Factory-fabricated connectors and splices of size, ampacity rating, material, type, and class for application and service indicated.

2.3 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

- B. Comply with NFPA 70.

### PART 3 - EXECUTION

#### 3.1 CONDUCTOR MATERIAL APPLICATIONS

- A. Feeders: Copper for feeders smaller than No. 4 AWG; and aluminum for feeders No. 4 AWG and larger. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
- B. Branch Circuits: Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger, except VFC cable, which shall be extra flexible stranded.

#### 3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

- A. Exposed Feeders: Type THW, single conductors in raceway.
- B. Feeders Concealed in Ceilings, Walls, Partitions, and Crawlspace: Type THHN/THWN-2, single conductors in raceway.
- C. Feeders Concealed in Concrete, below Slabs-on-Grade, and Underground: Type THHN/THWN-2, single conductors in raceway.
- D. Feeders Installed below Raised Flooring: Type THHN/THWN-2, single conductors in raceway.
- E. Exposed Branch Circuits, Including in Crawlspace: Type THHN/THWN-2, single conductors in raceway.
- F. Branch Circuits Concealed in Ceilings, Walls, and Partitions: Type THHN/THWN-2, single conductors in raceway.
- G. Branch Circuits Concealed in Concrete, below Slabs-on-Grade, and Underground: Type THHN/THWN-2, single conductors in raceway.
- H. Branch Circuits Installed below Raised Flooring: Type THHN/THWN-2, single conductors in raceway.
- I. Cord Drops and Portable Appliance Connections: Type SO, hard service cord with stainless-steel, wire-mesh, strain relief device at terminations to suit application.
- J. VFC Output Circuits: Type XHHW-2 in metal conduit with braided shield.

#### 3.3 INSTALLATION OF CONDUCTORS AND CABLES

- A. Conceal cables in finished walls, ceilings, and floors unless otherwise indicated.
- B. Complete raceway installation between conductor and cable termination points according to Section 260533 "Raceways and Boxes for Electrical Systems" prior to pulling conductors and cables.

- C. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- D. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.
- E. Install exposed cables parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- F. Support cables according to Section 260529 "Hangers and Supports for Electrical Systems."

### 3.4 CONNECTIONS

- A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.
- B. Make splices, terminations, and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.
  - 1. Use oxide inhibitor in each splice, termination, and tap for aluminum conductors.
- C. Wiring at Outlets: Install conductor at each outlet, with at least 6 inches of slack.

### 3.5 IDENTIFICATION

- A. Identify and color-code conductors and cables according to Section 260553 "Identification for Electrical Systems."
- B. Identify each spare conductor at each end with identity number and location of other end of conductor, and identify as spare conductor.

### 3.6 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

### 3.7 FIRESTOPPING

- A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Section 078413 "Penetration Firestopping."

3.8 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
1. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
  2. Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each splice in conductors No. 3 AWG and larger. Remove box and equipment covers so splices are accessible to portable scanner. Correct deficiencies determined during the scan.
    - a. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each splice 11 months after date of Substantial Completion.
    - b. Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
    - c. Record of Infrared Scanning: Prepare a certified report that identifies splices checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.
- B. Test and Inspection Reports: Prepare a written report to record the following:
1. Procedures used.
  2. Results that comply with requirements.
  3. Results that do not comply with requirements and corrective action taken to achieve compliance with requirements.
- C. Cables will be considered defective if they do not pass tests and inspections.

END OF SECTION 260519

SECTION 260526 - GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes grounding and bonding systems and equipment.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

2.2 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with UL 467 for grounding and bonding materials and equipment.

2.3 CONDUCTORS

- A. Insulated Conductors: Copper wire or cable insulated for 600 V unless otherwise required by applicable Code or authorities having jurisdiction.
- B. Bare Copper Conductors:
  - 1. Solid Conductors: ASTM B 3.
  - 2. Stranded Conductors: ASTM B 8.
  - 3. Tinned Conductors: ASTM B 33.
  - 4. Bonding Cable: 28 kcmil, 14 strands of No. 17 AWG conductor, 1/4 inch in diameter.
  - 5. Bonding Conductor: No. 4 or No. 6 AWG, stranded conductor.
  - 6. Bonding Jumper: Copper tape, braided conductors terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.
  - 7. Tinned Bonding Jumper: Tinned-copper tape, braided conductors terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.

## 2.4 CONNECTORS

- A. Listed and labeled by an NRTL acceptable to authorities having jurisdiction for applications in which used and for specific types, sizes, and combinations of conductors and other items connected.
- B. Bolted Connectors for Conductors and Pipes: Copper or copper alloy.
- C. Welded Connectors: Exothermic-welding kits of types recommended by kit manufacturer for materials being joined and installation conditions.
- D. Bus-Bar Connectors: Mechanical type, cast silicon bronze, solderless exothermic-type wire terminals, and long-barrel, two-bolt connection to ground bus bar.

## 2.5 GROUNDING ELECTRODES

- A. Ground Rods: Copper-clad steel, sectional type; minimum dimensions of 5/8 inch in diameter by 8 feet in length.

## PART 3 - EXECUTION

### 3.1 APPLICATIONS

- A. Conductors: Install solid conductor for No. 8 AWG and smaller, and stranded conductors for No. 6 AWG and larger unless otherwise indicated.
- B. Underground Grounding Conductors: Install bare copper conductor, No. 2/0 AWG minimum.
  - 1. Bury at least 24 inches below grade.
- C. Conductor Terminations and Connections:
  - 1. Pipe and Equipment Grounding Conductor Terminations: Bolted connectors.
  - 2. Underground Connections: Welded connectors except at test wells and as otherwise indicated.
  - 3. Connections to Ground Rods at Test Wells: Bolted connectors.
  - 4. Connections to Structural Steel: Welded connectors.

### 3.2 GROUNDING AT THE SERVICE

- A. Equipment grounding conductors and grounding electrode conductors shall be connected to the ground bus. Install a main bonding jumper between the neutral and ground buses.

### 3.3 GROUNDING UNDERGROUND DISTRIBUTION SYSTEM COMPONENTS

- A. Comply with IEEE C2 grounding requirements.



### 3.4 EQUIPMENT GROUNDING

- A. Install insulated equipment grounding conductors with all feeders and branch circuits.
- B. Install insulated equipment grounding conductors with the following items, in addition to those required by NFPA 70:
  - 1. Feeders and branch circuits.
  - 2. Lighting circuits.
  - 3. Receptacle circuits.
  - 4. Single-phase motor and appliance branch circuits.
  - 5. Three-phase motor and appliance branch circuits.
  - 6. Flexible raceway runs.
  - 7. Armored and metal-clad cable runs.
  - 8. Busway Supply Circuits: Install insulated equipment grounding conductor from grounding bus in the switchgear, switchboard, or distribution panel to equipment grounding bar terminal on busway.
- C. Air-Duct Equipment Circuits: Install insulated equipment grounding conductor to duct-mounted electrical devices operating at 120 V and more, including air cleaners, heaters, dampers, humidifiers, and other duct electrical equipment. Bond conductor to each unit and to air duct and connected metallic piping.
- D. Water Heater, Heat-Tracing, and Antifrost Heating Cables: Install a separate insulated equipment grounding conductor to each electric water heater and heat-tracing cable. Bond conductor to heater units, piping, connected equipment, and components.

### 3.5 INSTALLATION

- A. Grounding Conductors: Route along shortest and straightest paths possible unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.
- B. Ground Bonding Common with Lightning Protection System: Comply with NFPA 780 and UL 96 when interconnecting with lightning protection system. Bond electrical power system ground directly to lightning protection system grounding conductor at closest point to electrical service grounding electrode. Use bonding conductor sized same as system grounding electrode conductor, and install in conduit.
- C. Ground Rods: Drive rods until tops are 2 inches below finished floor or final grade unless otherwise indicated.
  - 1. Interconnect ground rods with grounding electrode conductor below grade and as otherwise indicated. Make connections without exposing steel or damaging coating if any.
  - 2. For grounding electrode system, install at least three rods spaced at least one-rod length from each other and located at least the same distance from other grounding electrodes, and connect to the service grounding electrode conductor.
- D. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance except where routed through short lengths of conduit.

1. Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate any adjacent parts.
2. Bonding to Equipment Mounted on Vibration Isolation Hangers and Supports: Install bonding so vibration is not transmitted to rigidly mounted equipment.
3. Use exothermic-welded connectors for outdoor locations; if a disconnect-type connection is required, use a bolted clamp.

E. Grounding and Bonding for Piping:

1. Metal Water Service Pipe: Install insulated copper grounding conductors, in conduit, from building's main service equipment, or grounding bus, to main metal water service entrances to building. Connect grounding conductors to main metal water service pipes; use a bolted clamp connector or bolt a lug-type connector to a pipe flange by using one of the lug bolts of the flange. Where a dielectric main water fitting is installed, connect grounding conductor on street side of fitting. Bond metal grounding conductor conduit or sleeve to conductor at each end.
2. Water Meter Piping: Use braided-type bonding jumpers to electrically bypass water meters. Connect to pipe with a bolted connector.
3. Bond each aboveground portion of gas piping system downstream from equipment shutoff valve.

3.6 FIELD QUALITY CONTROL

- A. Perform tests and inspections. Inspect physical and mechanical condition. Verify tightness of accessible, bolted, electrical connections with a calibrated torque wrench according to manufacturer's written instructions.

END OF SECTION 260526

SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
1. Hangers and supports for electrical equipment and systems.
  2. Construction requirements for concrete bases.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Signed and sealed by a qualified professional engineer. For fabrication and installation details for electrical hangers and support systems.
- C. Delegated-Design Submittal: For hangers and supports for electrical systems.
1. Include design calculations and details of trapeze hangers.

1.3 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plan(s) and other details, drawn to scale, and coordinated with each other, using input from installers of the items involved:
- B. Welding certificates.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design hanger and support system.

2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Steel Slotted Support Systems: Comply with MFMA-4 factory-fabricated components for field assembly.
1. Material: Pre-galvanized steel.
  2. Channel Width: 1-5/8 inches.
  3. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
  4. Nonmetallic Coatings: Manufacturer's standard PVC, polyurethane, or polyester coating applied according to MFMA-4.

5. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
  6. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
  7. Channel Dimensions: Selected for applicable load criteria.
- B. Conduit and Cable Support Devices: Steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- C. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for nonarmored electrical conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body shall be made of malleable iron.
- D. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M steel plates, shapes, and bars; black and galvanized.
- E. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
1. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened Portland Cement Concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
  2. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened Portland Cement Concrete, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
  3. Concrete Inserts: Steel or malleable-iron, slotted support system units are similar to MSS Type 18 units and comply with MFMA-4 or MSS SP-58.
  4. Clamps for Attachment to Steel Structural Elements: MSS SP-58 units are suitable for attached structural element.
  5. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.
  6. Toggle Bolts: All-steel springhead type.
  7. Hanger Rods: Threaded steel.

### 2.3 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

- A. Description: Welded or bolted structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.

## PART 3 - EXECUTION

### 3.1 APPLICATION

- A. Comply with NECA 1 and NECA 101 for application of hangers and supports for electrical equipment and systems unless requirements in this Section are stricter.

- B. Comply with requirements for raceways and boxes specified in Section 260533 "Raceways and Boxes for Electrical Systems."
- C. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for EMTs, IMCs, and RMCs as scheduled in NECA 1, where its Table 1 lists maximum spacings that are less than those stated in NFPA 70. Minimum rod size shall be 1/4 inch in diameter.
- D. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted or other support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
  - 1. Secure raceways and cables to these supports with single-bolt conduit clamps using spring friction action for retention in support channel].
- E. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1-1/2-inch and smaller raceways serving branch circuits and communication systems above suspended ceilings and for fastening raceways to trapeze supports.

### 3.2 SUPPORT INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this article.
- B. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.
- C. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements.
- D. Drill holes for expansion anchors in concrete at locations and to depths that avoid the need for reinforcing bars.

### 3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
- B. Field Welding: Comply with AWS D1.1/D1.1M.

### 3.4 PAINTING

- A. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 260529

## SECTION 260533 - RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

### PART 1 - GENERAL

#### 1.1 SUMMARY

##### A. Section Includes:

1. Metal conduits, tubing, and fittings.
2. Nonmetal conduits, tubing, and fittings.
3. Metal wireways and auxiliary gutters.
4. Nonmetal wireways and auxiliary gutters.
5. Surface raceways.
6. Boxes, enclosures, and cabinets.
7. Handholes and boxes for exterior underground cabling.

#### 1.2 ACTION SUBMITTALS

- A. Product Data: For surface raceways, wireways and fittings, floor boxes, hinged-cover enclosures, and cabinets.
- B. Shop Drawings: For custom enclosures and cabinets. Include plans, elevations, sections, and attachment details.

#### 1.3 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Conduit routing plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of items involved:
  1. Structural members in paths of conduit groups with common supports.
  2. HVAC and plumbing items and architectural features in paths of conduit groups with common supports.
- B. Seismic Qualification Certificates: For enclosures, cabinets, and conduit racks and their mounting provisions, including those for internal components, from manufacturer.

PART 2 - PRODUCTS – Match Drawing Notes

2.1 METAL CONDUITS, TUBING, AND FITTINGS

- A. Listing and Labeling: Metal conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. GRC: Comply with ANSI C80.1 and UL 6.
- C. ARC: Comply with ANSI C80.5 and UL 6A.
- D. IMC: Comply with ANSI C80.6 and UL 1242.
- E. PVC-Coated Steel Conduit: PVC-coated rigid steel conduit.
  - 1. Comply with NEMA RN 1.
  - 2. Coating Thickness: 0.040 inch, minimum.
- F. EMT: Comply with ANSI C80.3 and UL 797.
- G. FMC: Comply with UL 1; zinc-coated steel.
- H. LFMC: Flexible steel conduit with PVC jacket and complying with UL 360.
- I. Fittings for Metal Conduit: Comply with NEMA FB 1 and UL 514B.
  - 1. Conduit Fittings for Hazardous (Classified) Locations: Comply with UL 886 and NFPA 70.
  - 2. Fittings for EMT:
    - a. Material: Aluminum
    - b. Type: compression.
  - 3. Expansion Fittings: PVC or steel to match conduit type, complying with UL 651, rated for environmental conditions where installed, and including flexible external bonding jumper.
  - 4. Coating for Fittings for PVC-Coated Conduit: Minimum thickness of 0.040 inch, with overlapping sleeves protecting threaded joints.
- J. Joint Compound for IMC, GRC, or ARC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

## 2.2 NONMETALLIC CONDUITS, TUBING, AND FITTINGS

- A. Listing and Labeling: Nonmetallic conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. ENT: Comply with NEMA TC 13 and UL 1653.
- C. RNC: Type EPC-40-PVC, complying with NEMA TC 2 and UL 651 unless otherwise indicated.
- D. LFNC: Comply with UL 1660.
- E. Continuous HDPE: Comply with UL 651B.
- F. Coilable HDPE: Preassembled with conductors or cables, and complying with ASTM D 3485.
- G. Fittings for ENT and RNC: Comply with NEMA TC 3; match to conduit or tubing type and material.
- H. Fittings for LFNC: Comply with UL 514B.
- I. Solvent cements and adhesive primers shall have a VOC content of 510 and 550 g/L or less, respectively, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- J. Solvent cements and adhesive primers shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

## 2.3 METAL WIREWAYS AND AUXILIARY GUTTERS

- A. Description: Sheet metal, complying with UL 870 and NEMA 250, Type 1 unless otherwise indicated, and sized according to NFPA 70.
  - 1. Metal wireways installed outdoors shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Fittings and Accessories: Include covers, couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.



## 2.4 NONMETALLIC WIREWAYS AND AUXILIARY GUTTERS

- A. Listing and Labeling: Nonmetallic wireways and auxiliary gutters shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Description: Fiberglass polyester, extruded and fabricated to required size and shape, without holes or knockouts. Cover shall be gasketed with oil-resistant gasket material and fastened with captive screws treated for corrosion resistance. Connections shall be flanged and have stainless-steel screws and oil-resistant gaskets.
- C. Description: PVC, extruded and fabricated to required size and shape, and having snap-on cover, mechanically coupled connections, and plastic fasteners.
- D. Fittings and Accessories: Couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings shall match and mate with wireways as required for complete system.
- E. Solvent cements and adhesive primers shall have a VOC content of 510 and 550 g/L or less, respectively, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- F. Solvent cements and adhesive primers shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

## 2.5 SURFACE RACEWAYS

- A. Listing and Labeling: Surface raceways and tele-power poles shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Surface Metal Raceways: Galvanized steel with snap-on covers complying with UL 5.
- C. Surface Nonmetallic Raceways: Two- or three-piece construction, complying with UL 5A, and manufactured of rigid PVC. Product shall comply with UL 94 V-0 requirements for self-extinguishing characteristics.

## 2.6 BOXES, ENCLOSURES, AND CABINETS

- A. General Requirements for Boxes, Enclosures, and Cabinets: Boxes, enclosures, and cabinets installed in wet locations shall be listed for use in wet locations.
- B. Sheet Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- C. Cast-Metal Outlet and Device Boxes: Comply with NEMA FB 1, aluminum, Type FD, with gasketed cover.

- D. Nonmetallic Outlet and Device Boxes: Comply with NEMA OS 2 and UL 514C.
- E. Metal Floor Boxes:
  - 1. Material: Cast metal.
  - 2. Type: Fully adjustable.
  - 3. Shape: Rectangular.
  - 4. Listing and Labeling: Metal floor boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- F. Nonmetallic Floor Boxes: Nonadjustable, round.
  - 1. Listing and Labeling: Nonmetallic floor boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- G. Luminaire Outlet Boxes: Nonadjustable, designed for attachment of luminaire weighing 50 lb. Outlet boxes designed for attachment of luminaires weighing more than 50 lb shall be listed and marked for the maximum allowable weight.
- H. Paddle Fan Outlet Boxes: Nonadjustable, designed for attachment of paddle fan weighing 70 lb.
  - 1. Listing and labeling: Paddle fan outlet boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- I. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- J. Cast-Metal Access, Pull, and Junction Boxes: Comply with NEMA FB 1 and UL 1773, cast aluminum with gasketed cover.
- K. Box extensions used to accommodate new building finishes shall be of same material as recessed box.
- L. Device Box Dimensions: 4 inches square by 2-1/8 inches deep.
- M. Gangable boxes are allowed.
- N. Hinged-Cover Enclosures: Comply with UL 50 and NEMA 250, Type 1 with continuous-hinge cover with flush latch unless otherwise indicated.
  - 1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
  - 2. Nonmetallic Enclosures: Plastic.
  - 3. Interior Panels: Steel; all sides finished with manufacturer's standard enamel.
- O. Cabinets:

1. NEMA 250, Type 1 galvanized-steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel.
2. Hinged door in front cover with flush latch and concealed hinge.
3. Key latch to match panelboards.
4. Metal barriers to separate wiring of different systems and voltage.
5. Accessory feet where required for freestanding equipment.
6. Nonmetallic cabinets shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
7. Conduit Entrance Provisions: Conduit-terminating fittings shall mate with entering ducts for secure, fixed installation in enclosure wall.

### PART 3 - EXECUTION

#### 3.1 RACEWAY APPLICATION

A. Outdoors: Apply raceway products as specified below unless otherwise indicated:

1. Exposed Conduit: GRC.
2. Concealed Conduit, Aboveground: EMT.
3. Underground Conduit: RNC, Type EPC-40-PVC.
4. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC or LFNC.
5. Boxes and Enclosures, Aboveground: NEMA 250, Type 3R.

B. Indoors: Apply raceway products as specified below unless otherwise indicated.

1. Exposed, Not Subject to Physical Damage: EMT.
2. Exposed, Not Subject to Severe Physical Damage: EMT.
3. Exposed and Subject to Severe Physical Damage: GRC. Raceway locations include the following:
  - a. Loading dock.
  - b. Corridors used for traffic of mechanized carts, forklifts, and pallet-handling units.
  - c. Mechanical rooms.
  - d. Gymnasiums.
4. Concealed in Ceilings and Interior Walls and Partitions: EMT.
5. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): FMC, except use LFMC in damp or wet locations.
6. Damp or Wet Locations: GRC.
7. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4 stainless steel in institutional and commercial kitchens and damp or wet locations.

C. Minimum Raceway Size: 3/4-inch trade size.

- D. Raceway Fittings: Compatible with raceways and suitable for use and location.
  - 1. Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings unless otherwise indicated. Comply with NEMA FB 2.10.
  - 2. PVC Externally Coated, Rigid Steel Conduits: Use only fittings listed for use with this type of conduit. Patch and seal all joints, nicks, and scrapes in PVC coating after installing conduits and fittings. Use sealant recommended by fitting manufacturer and apply in thickness and number of coats recommended by manufacturer.
  - 3. EMT: Use compression, steel fittings. Comply with NEMA FB 2.10.
  - 4. Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.
- E. Do not install aluminum conduits, boxes, or fittings in contact with concrete or earth.
- F. Install surface raceways only where indicated on Drawings.
- G. Do not install nonmetallic conduit where ambient temperature exceeds 120 deg F.

### 3.2 INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except where requirements on Drawings or in this article are stricter. Comply with NECA 102 for aluminum conduits. Comply with NFPA 70 limitations for types of raceways allowed in specific occupancies and number of floors.
- B. Keep raceways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.
- C. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for hangers and supports.
- D. Arrange stub-ups so curved portions of bends are not visible above finished slab.
- E. Install no more than the equivalent of three 90-degree bends in any conduit run except for control wiring conduits, for which fewer bends are allowed. Support within 12 inches of changes in direction.
- F. Conceal conduit and EMT within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
- G. Support conduit within 12 inches of enclosures to which attached.
- H. Raceways Embedded in Slabs:
  - 1. Run conduit larger than 1-inch trade size, parallel or at right angles to main reinforcement. Where at right angles to reinforcement, place conduit close to slab support. Secure raceways to reinforcement at maximum 10-foot intervals.

2. Arrange raceways to cross building expansion joints at right angles with expansion fittings.
  3. Arrange raceways to keep a minimum of 1 inch of concrete cover in all directions.
  4. Do not embed threadless fittings in concrete unless specifically approved by Architect for each specific location.
  5. Change from ENT to RNC, Type EPC-40-PVC, before rising above floor.
- I. Stub-ups to Above Recessed Ceilings:
1. Use EMT, IMC, or RMC for raceways.
  2. Use a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.
- J. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.
- K. Coat field-cut threads on PVC-coated raceway with a corrosion-preventing conductive compound prior to assembly.
- L. Raceway Terminations at Locations Subject to Moisture or Vibration: Use insulating bushings to protect conductors including conductors smaller than No. 4 AWG.
- M. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install bushings on conduits up to 1-1/4-inch trade size and insulated throat metal bushings on 1-1/2-inch trade size and larger conduits terminated with locknuts. Install insulated throat metal grounding bushings on service conduits.
- N. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb tensile strength. Leave at least 12 inches of slack at each end of pull wire. Cap underground raceways designated as spare above grade alongside raceways in use.
- O. Surface Raceways:
1. Install surface raceway with a minimum 2-inch radius control at bend points.
  2. Secure surface raceway with screws or other anchor-type devices at intervals not exceeding 48 inches and with no less than two supports per straight raceway section. Support surface raceway according to manufacturer's written instructions. Tape and glue are not acceptable support methods.
- P. Install raceway sealing fittings at accessible locations according to NFPA 70 and fill them with listed sealing compound. For concealed raceways, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces.
- Q. Install devices to seal raceway interiors at accessible locations. Locate seals so no fittings or boxes are between the seal and the following changes of environments. Seal the interior of all raceways at the following points:

1. Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
2. Where an underground service raceway enters a building or structure.
3. Where otherwise required by NFPA 70.

R. Expansion-Joint Fittings:

1. Install in each run of aboveground RNC that is located where environmental temperature change may exceed 30 deg F and that has straight-run length that exceeds 25 feet.
2. Install type and quantity of fittings that accommodate temperature change listed for each of the following locations:
  - a. Outdoor Locations Not Exposed to Direct Sunlight: 125 deg F temperature change.
  - b. Outdoor Locations Exposed to Direct Sunlight: 155 deg F] temperature change.
  - c. Indoor Spaces Connected with Outdoors without Physical Separation: 125 deg F temperature change.
  - d. Attics: 135 deg F temperature change.
3. Install fitting(s) that provide expansion and contraction for at least 0.00041 inch per foot of length of straight run per degree F of temperature change for PVC conduits.
4. Install expansion fittings at all locations where conduits cross building or structure expansion joints.
5. Install each expansion-joint fitting with position, mounting, and piston setting selected according to manufacturer's written instructions for conditions at specific location at time of installation. Install conduit supports to allow for expansion movement.

S. Flexible Conduit Connections: Comply with NEMA RV 3. Use a maximum of 72 inches of flexible conduit for recessed and semirecessed luminaires, equipment subject to vibration, noise transmission, or movement; and for transformers and motors.

1. Use LFMC in damp or wet locations subject to severe physical damage.
2. Use LFMC or LFNC in damp or wet locations not subject to severe physical damage.

T. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to bottom of box unless otherwise indicated.

U. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surfaces to provide a flat surface for a raintight connection between the box and cover plate or the supported equipment and box.

- V. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.
- W. Locate boxes so that cover or plate will not span different building finishes.
- X. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for the purpose.
- Y. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.
- Z. Set metal floor boxes level and flush with finished floor surface.
- AA. Set nonmetallic floor boxes level. Trim after installation to fit flush with finished floor surface.

### 3.3 INSTALLATION OF UNDERGROUND CONDUIT

#### A. Direct-Buried Conduit:

1. Install manufactured duct elbows for stub-up at poles and equipment and at building entrances through floor unless otherwise indicated. Encase elbows for stub-up ducts throughout length of elbow.
2. Install manufactured rigid steel conduit elbows for stub-ups at poles and equipment and at building entrances through floor.
  - a. Couple steel conduits to ducts with adapters designed for this purpose, and encase coupling with 3 inches of concrete for a minimum of 12 inches on each side of the coupling.
  - b. For stub-ups at equipment mounted on outdoor concrete bases and where conduits penetrate building foundations, extend steel conduit horizontally a minimum of 60 inches from edge of foundation or equipment base. Install insulated grounding bushings on terminations at equipment.
3. Underground Warning Tape: Comply with requirements in Section 260553 "Identification for Electrical Systems."

### 3.4 INSTALLATION OF UNDERGROUND HANDHOLES AND BOXES

- A. Install handholes and boxes level and plumb and with orientation and depth coordinated with connecting conduits to minimize bends and deflections required for proper entrances.
- B. Unless otherwise indicated, support units on a level bed of crushed stone or gravel, graded from 1/2-inch sieve to No. 4 sieve and compacted to same density as adjacent undisturbed earth.

- C. Elevation: In paved areas, set so cover surface will be flush with finished grade. Set covers of other enclosures 1 inch above finished grade.
- D. Install handholes with bottom below frost line.
- E. Field-cut openings for conduits according to enclosure manufacturer's written instructions. Cut wall of enclosure with a tool designed for material to be cut. Size holes for terminating fittings to be used, and seal around penetrations after fittings are installed.

### 3.5 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

### 3.6 FIRESTOPPING

- A. Install firestopping at penetrations of fire-rated floor and wall assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

### 3.7 PROTECTION

- A. Protect coatings, finishes, and cabinets from damage and deterioration.
  - 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
  - 2. Repair damage to PVC coatings or paint finishes with matching touchup coating recommended by manufacturer.

END OF SECTION 260533



SECTION 260544 - SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Sleeves for raceway and cable penetration of non-fire-rated construction walls and floors.
2. Sleeve-seal systems.
3. Sleeve-seal fittings.
4. Grout.
5. Silicone sealants.

B. Related Requirements:

1. Section 078413 "Penetration Firestopping" for penetration firestopping installed in fire-resistance-rated walls, horizontal assemblies, and smoke barriers, with and without penetrating items.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 SLEEVES

A. Wall Sleeves:

1. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc coated, plain ends.
2. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.

- B. Sleeves for Conduits Penetrating Non-Fire-Rated Gypsum Board Assemblies: Galvanized-steel sheet; 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint, with tabs for screw-fastening the sleeve to the board.

C. Sleeves for Rectangular Openings:

1. Material: Galvanized sheet steel.
2. Minimum Metal Thickness:
  - a. For sleeve cross-section rectangle perimeter less than 50 inches and with no side larger than 16 inches, thickness shall be 0.052 inch.

- b. For sleeve cross-section rectangle perimeter 50 inches or more and one or more sides larger than 16 inches, thickness shall be 0.138 inch.

## 2.2 SLEEVE-SEAL SYSTEMS

- A. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and raceway or cable.
  1. Manufacturers:
    - a. CALPICO, Inc
    - b. Metraflex Company
    - c. Proco Products, Inc.
  2. Sealing Elements: EPDM rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
  3. Pressure Plates: [Carbon steel] [Plastic] [Stainless steel].
  4. Connecting Bolts and Nuts: [Carbon steel, with corrosion-resistant coating,] [Stainless steel] of length required to secure pressure plates to sealing elements.

## 2.3 SLEEVE-SEAL FITTINGS

- A. Description: Manufactured plastic, sleeve-type, waterstop assembly made for embedding in concrete slab or wall. Unit shall have plastic or rubber waterstop collar with center opening to match piping OD.
  1. Manufacturer: HOLDRITE, or equal.

## 2.4 GROUT

- A. Description: Nonshrink; recommended for interior and exterior sealing openings in non-fire-rated walls or floors.
- B. Standard: ASTM C 1107/C 1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
- C. Design Mix: 5000-psi, 28-day compressive strength.
- D. Packaging: Premixed and factory packaged.

## 2.5 SILICONE SEALANTS

- A. Silicone Sealants: Single-component, silicone-based, neutral-curing elastomeric sealants of grade indicated below.
  1. Grade: Pourable (self-leveling) formulation for openings in floors and other horizontal surfaces that are not fire rated.
- B. Silicone Foams: Multicomponent, silicone-based liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.

### PART 3 - EXECUTION

#### 3.1 SLEEVE INSTALLATION FOR NON-FIRE-RATED ELECTRICAL PENETRATIONS

- A. Comply with NECA 1.
- B. Comply with NEMA VE 2 for cable tray and cable penetrations.
- C. Sleeves for Conduits Penetrating Above-Grade Non-Fire-Rated Concrete and Masonry-Unit Floors and Walls:
  - 1. Interior Penetrations of Non-Fire-Rated Walls and Floors:
    - a. Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Section 079200 "Joint Sealants."
    - b. Seal space outside of sleeves with mortar or grout. Pack sealing material solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect material while curing.
  - 2. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
  - 3. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and raceway or cable unless sleeve seal is to be installed or unless seismic criteria require different clearance.
  - 4. Install sleeves for wall penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of walls. Cut sleeves to length for mounting flush with both surfaces of walls. Deburr after cutting.
  - 5. Install sleeves for floor penetrations. Extend sleeves installed in floors 2 inches above finished floor level. Install sleeves during erection of floors.
- D. Sleeves for Conduits Penetrating Non-Fire-Rated Gypsum Board Assemblies:
  - 1. Use circular metal sleeves unless penetration arrangement requires rectangular sleeved opening.
  - 2. Seal space outside of sleeves with approved joint compound for gypsum board assemblies.
- E. Roof-Penetration Sleeves: Seal penetration of individual raceways and cables with flexible boot-type flashing units applied in coordination with roofing work.
- F. Aboveground, Exterior-Wall Penetrations: Seal penetrations using steel pipe sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
- G. Underground, Exterior-Wall and Floor Penetrations: Install cast-iron pipe sleeves. Size sleeves to allow for 1-inch annular clear space between raceway or cable and sleeve for installing sleeve-seal system.

### 3.2 SLEEVE-SEAL-SYSTEM INSTALLATION

- A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at raceway entries into building.
- B. Install type and number of sealing elements recommended by manufacturer for raceway or cable material and size. Position raceway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between raceway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

### 3.3 SLEEVE-SEAL-FITTING INSTALLATION

- A. Install sleeve-seal fittings in new walls and slabs as they are constructed.
- B. Assemble fitting components of length to be flush with both surfaces of concrete slabs and walls. Position waterstop flange to be centered in concrete slab or wall.
- C. Secure nailing flanges to concrete forms.
- D. Using grout, seal the space around outside of sleeve-seal fittings.

END OF SECTION 260544

## SECTION 260553 - IDENTIFICATION FOR ELECTRICAL SYSTEMS

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Section Includes:

1. Identification for raceways.
2. Identification of power and control cables.
3. Identification for conductors.
4. Underground-line warning tape.
5. Warning labels and signs.
6. Instruction signs.
7. Equipment identification labels, including arc-flash warning labels.
8. Miscellaneous identification products.

#### 1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Delegated-Design Submittal: For arc-flash hazard study.

### PART 2 - PRODUCTS

#### 2.1 PERFORMANCE REQUIREMENTS

- A. Comply with ASME A13.1 and IEEE C2.
- B. Comply with NFPA 70.
- C. Comply with 29 CFR 1910.144 and 29 CFR 1910.145.
- D. Comply with ANSI Z535.4 for safety signs and labels.
- E. Adhesive-attached labeling materials, including label stocks, laminating adhesives, and inks used by label printers, shall comply with UL 969.

#### 2.2 COLOR AND LEGEND REQUIREMENTS

- A. Raceways and Cables Carrying Circuits at 600 V or Less:
1. Black letters on an orange field.
  2. Legend: Indicate voltage and system or service type.
- B. Warning labels and signs shall include, but are not limited to, the following legends:

1. Multiple Power Source Warning: "DANGER - ELECTRICAL SHOCK HAZARD - EQUIPMENT HAS MULTIPLE POWER SOURCES."
2. Workspace Clearance Warning: "WARNING - OSHA REGULATION - AREA IN FRONT OF ELECTRICAL EQUIPMENT MUST BE KEPT CLEAR FOR 36 INCHES."

## 2.3 LABELS

- A. Vinyl Labels for Raceways Carrying Circuits at 600 V or Less: Preprinted, flexible labels laminated with a clear, weather- and chemical-resistant coating and matching wraparound clear adhesive tape for securing label ends.
- B. Self-Adhesive Labels:
  1. Preprinted, 3-mil-thick, vinyl flexible label with acrylic pressure-sensitive adhesive.
  2. Vinyl, thermal, transfer-printed, 3-mil-thick, multicolor, weather- and UV-resistant, pressure-sensitive adhesive labels, configured for display on front cover, door, or other access to equipment unless otherwise indicated.
    - a. Nominal Size: 3.5-by-5-inch.

## 2.4 TAPES AND STENCILS:

- A. Marker Tapes: Vinyl or vinyl-cloth, self-adhesive wraparound type, with circuit identification legend machine printed by thermal transfer or equivalent process.
- B. Self-Adhesive Vinyl Tape: Colored, heavy duty, waterproof, fade resistant; not less than 3 mils thick by 1 to 2 inches wide; compounded for outdoor use.
- C. Floor Marking Tape: 2-inch-wide, 5-mil pressure-sensitive vinyl tape, with yellow and black stripes and clear vinyl overlay.
- D. Underground-Line Warning Tape
  1. Tape:
    - a. Recommended by manufacturer for the method of installation and suitable to identify and locate underground electrical and communications utility lines.
    - b. Printing on tape shall be permanent and shall not be damaged by burial operations.
    - c. Tape material and ink shall be chemically inert and not subject to degradation when exposed to acids, alkalis, and other destructive substances commonly found in soils.
  2. Color and Printing:
    - a. Comply with ANSI Z535.1, ANSI Z535.2, ANSI Z535.3, ANSI Z535.4, and ANSI Z535.5.
    - b. Inscriptions for Red-Colored Tapes: "ELECTRIC LINE, HIGH VOLTAGE".
    - c. Inscriptions for Orange-Colored Tapes: "TELEPHONE CABLE, CATV CABLE, COMMUNICATIONS CABLE, OPTICAL FIBER CABLE".
  3. Tag: Type I:

- a. Pigmented polyolefin, bright colored, continuous-printed on one side with the inscription of the utility, compounded for direct-burial service.
  - b. Width: 3 inches.
  - c. Thickness: 4 mils. Weight: 18.5 lb/1000 sq. ft..
  - d. Tensile according to ASTM D 882: 30 lbf and 2500 psi.
4. Tag: Type ID:
- a. Detectable three-layer laminate, consisting of a printed pigmented polyolefin film, a solid aluminum-foil core, and a clear protective film that allows inspection of the continuity of the conductive core; bright colored, continuous-printed on one side with the inscription of the utility, compounded for direct-burial service.
  - b. Width: 3 inches.
  - c. Overall Thickness: 5 mils.
  - d. Foil Core Thickness: 0.35 mil.
  - e. Weight: 28 lb/1000 sq. ft..
  - f. Tensile according to ASTM D 882: 70 lbf and 4600 psi.
5. Tag: Type IID:
- a. Reinforced, detectable three-layer laminate, consisting of a printed pigmented woven scrim, a solid aluminum-foil core, and a clear protective film that allows inspection of the continuity of the conductive core; bright-colored, continuous-printed on one side with the inscription of the utility, compounded for direct-burial service.
  - b. Width: 3 inches
  - c. Overall Thickness: 8 mils.
  - d. Foil Core Thickness: 0.35 mil.
  - e. Weight: 34 lb/1000 sq. ft..
  - f. Tensile according to ASTM D 882: 300 lbf and 12,500 psi.

## 2.5 Tags

- A. Metal Tags: Brass or aluminum, 2 by 2 by 0.05 inch, with stamped legend, punched for use with self-locking cable tie fastener.
- B. Nonmetallic Preprinted Tags: Polyethylene tags, 0.023 inch thick, color-coded for phase and voltage level, with factory printed permanent designations; punched for use with self-locking cable tie fastener.
- C. Write-On Tags:
  1. Polyester Tags: 0.010 inch thick, with corrosion-resistant grommet and cable tie for attachment to raceway, conductor, or cable.
  2. Marker for Tags: Permanent, waterproof, black ink marker recommended by tag manufacturer.
  3. Marker for Tags: Machine-printed, permanent, waterproof, black ink marker recommended by printer manufacturer.

## 2.6 Signs

- A. Baked-Enamel Signs:

1. Preprinted aluminum signs, punched or drilled for fasteners, with colors, legend, and size required for application.
2. 1/4-inch grommets in corners for mounting.
3. Nominal Size: 7 by 10 inches.

B. Metal-Backed Butyrate Signs:

1. Weather-resistant, nonfading, preprinted, cellulose-acetate butyrate signs, with 0.0396-inch galvanized-steel backing and with colors, legend, and size required for application.
2. 1/4-inch grommets in corners for mounting.
3. Nominal Size: 10 by 14 inches.

C. Laminated Acrylic or Melamine Plastic Signs:

1. Engraved legend.
2. Thickness:
  - a. For signs up to 20 sq. inches, minimum 1/16-inch.
  - b. For signs larger than 20 sq. inches, 1/8 inch thick.
  - c. Engraved legend with black letters on white face.
  - d. Punched or drilled for mechanical fasteners.
  - e. Framed with mitered acrylic molding and arranged for attachment at applicable equipment.

## 2.7 CABLE TIES

A. General-Purpose Cable Ties: Fungus inert, self-extinguishing, one piece, self-locking, Type 6/6 nylon.

1. Minimum Width: 3/16 inch.
2. Tensile Strength at 73 deg F according to ASTM D 638: 12,000 psi.
3. Temperature Range: Minus 40 to plus 185 deg F.
4. Color: Black, except where used for color-coding.

B. UV-Stabilized Cable Ties: Fungus inert, designed for continuous exposure to exterior sunlight, self-extinguishing, one piece, self-locking, Type 6/6 nylon.

1. Minimum Width: 3/16 inch.
2. Tensile Strength at 73 deg F according to ASTM D 638: 12,000 psi.
3. Temperature Range: Minus 40 to plus 185 deg F.
4. Color: Black.

C. Plenum-Rated Cable Ties: Self-extinguishing, UV stabilized, one piece, self-locking.

1. Minimum Width: 3/16 inch.
2. Tensile Strength at 73 deg F according to ASTM D 638: 7000 psi.
3. UL 94 Flame Rating: 94V-0.
4. Temperature Range: Minus 50 to plus 284 deg F.
5. Color: Black.



## 2.8 MISCELLANEOUS IDENTIFICATION PRODUCTS

- A. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment.
- B. Apply identification devices to surfaces that require finish after completing finish work.
- C. Attach signs and plastic labels that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.
- D. Attach plastic raceway and cable labels that are not self-adhesive type with clear vinyl tape, with adhesive appropriate to the location and substrate.
- E. Cable Ties: For attaching tags. Use general-purpose type, except as listed below:
  - 1. Outdoors: UV-stabilized nylon.
  - 2. In Spaces Handling Environmental Air: Plenum rated.
- F. During backfilling of trenches, install continuous underground-line warning tape directly above cable or raceway at 6 to 8 inches below finished grade. Use multiple tapes where width of multiple lines installed in a common trench or concrete envelope exceeds 16 inches overall.

### 3.2 IDENTIFICATION SCHEDULE

- A. Accessible Raceways and Metal-Clad Cables, 600 V or Less, for Service, Feeder, and Branch Circuits, More Than 30 A and 120 V to Ground: Identify with self-adhesive vinyl label. Install labels at 10-foot maximum intervals.
- B. Accessible Raceways and Cables within Buildings: Identify the covers of each junction and pull box of the following systems with self-adhesive vinyl labels containing the wiring system legend and system voltage. System legends shall be as follows:
  - 1. "EMERGENCY POWER."
  - 2. "POWER."
  - 3. "UPS."
- C. Power-Circuit Conductor Identification, 600 V or Less: For conductors in vaults, pull and junction boxes, manholes, and handholes, use color-coding conductor tape to identify the phase.
  - 1. Color-Coding for Phase- and Voltage-Level Identification, 600 V or Less: Use industry standard colors for ungrounded service, feeder, and branch-circuit conductors.

- a. Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns for a minimum distance of 6 inches from terminal points and in boxes where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding. Locate bands to avoid obscuring factory cable markings.
- D. Control-Circuit Conductor Identification: For conductors and cables in pull and junction boxes, manholes, and handholes, use self-adhesive vinyl labels with the conductor or cable designation, origin, and destination.
- E. Control-Circuit Conductor Termination Identification: For identification at terminations, provide self-adhesive vinyl labels with the conductor designation.
- F. Conductors to Be Extended in the Future: Attach marker tape to conductors and list source.
- G. Auxiliary Electrical Systems Conductor Identification: Identify field-installed alarm, control, and signal connections.
  1. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, and pull points. Identify by system and circuit designation.
  2. Use system of marker-tape designations that is uniform and consistent with system used by manufacturer for factory-installed connections.
  3. Coordinate identification with Project Drawings, manufacturer's wiring diagrams, and operation and maintenance manual.
- H. Locations of Underground Lines: Identify with underground-line warning tape for power, lighting, communication, and control wiring and optical-fiber cable.
  1. Limit use of underground-line warning tape to direct-buried cables.
  2. Install underground-line warning tape for direct-buried cables and cables in raceways.
- I. Workspace Indication: Install floor marking tape to show working clearances in the direction of access to live parts. Workspace shall comply with NFPA 70 and 29 CFR 1926.403 unless otherwise indicated. Do not install at flush-mounted panelboards and similar equipment in finished spaces.
- J. Warning Labels for Indoor Cabinets, Boxes, and Enclosures for Power and Lighting: Baked-enamel warning signs.
  1. Comply with 29 CFR 1910.145.
  2. Identify system voltage with black letters on an orange background.
  3. Apply to exterior of door, cover, or other access.
  4. For equipment with multiple power or control sources, apply to door or cover of equipment, including, but not limited to, the following:
    - a. Power-transfer switches.
    - b. Controls with external control power connections.
- K. Arc Flash Warning Labeling: Self-adhesive thermal transfer vinyl labels.
  1. Comply with NFPA 70E and ANSI Z535.4.
  2. Comply with Section 260574 "Overcurrent Protective Device Arc-Flash Study" requirements for arc-flash warning labels.

- L. Operating Instruction Signs: Install instruction signs to facilitate proper operation and maintenance of electrical systems and items to which they connect. Install instruction signs with approved legend where instructions are needed for system or equipment operation.
- M. Emergency Operating Instruction Signs: Install instruction signs with white legend on a red background with minimum 3/8-inch-high letters for emergency instructions at equipment used for power transfer or load shedding.
- N. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and operation and maintenance manual.
  - 1. Labeling Instructions:
    - a. Indoor Equipment: Engraved, laminated acrylic or melamine plastic label, punched or drilled for mechanical fasteners. Unless otherwise indicated, provide a single line of text with 1/2-inch-high letters on 1-1/2-inch-high label; where two lines of text are required, use labels 2 inches high.
    - b. Outdoor Equipment: Engraved, laminated acrylic or melamine label.
    - c. Elevated Components: Increase sizes of labels and letters to those appropriate for viewing from the floor.
    - d. Unless labels are provided with self-adhesive means of attachment, fasten them with appropriate mechanical fasteners that do not change the NEMA or NRTL rating of the enclosure.

END OF SECTION 260553

SECTION 260923 - LIGHTING CONTROL DEVICES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Photoelectric switches.
2. Indoor occupancy, switchbox-mounted occupancy, and outdoor motion sensors.

B. Related Requirements:

1. Section 262726 "Wiring Devices" for wall-box dimmers, wall-switch occupancy sensors, and manual light switches.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.3 INFORMATIONAL SUBMITTALS

A. Field quality-control reports.

1.4 CLOSEOUT SUBMITTALS

A. Operation and maintenance data

PART 2 - PRODUCTS

2.1 INDOOR OCCUPANCY SENSORS

A. General Requirements for Sensors: Wall- or ceiling-mounted, solid-state indoor occupancy sensors with a separate power pack.

1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
2. Operation: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
3. Sensor Output: Contacts rated to operate the connected relay, complying with UL 773A. Sensor is powered from the power pack.

4. Power Pack: Dry contacts rated for 20-A ballast load at 120- and 277-V ac, for 13-A tungsten at 120-V ac, and for 1 hp at 120-V ac. Sensor has 24-V dc, 150-mA, Class 2 power source, as defined by NFPA 70.
  5. Mounting:
    - a. Sensor: Suitable for mounting in any position on a standard outlet box.
    - b. Relay: Externally mounted through a 1/2-inch knockout in a standard electrical enclosure.
    - c. Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged door.
  6. Indicator: Digital display, to show when motion is detected during testing and normal operation of sensor.
  7. Bypass Switch: Override the "on" function in case of sensor failure.
  8. Automatic Light-Level Sensor: Adjustable from 2 to 200 fc; turn lights off when selected lighting level is present.
- B. Dual-Technology Type: Ceiling mounted; detect occupants in coverage area using PIR and ultrasonic detection methods. The particular technology or combination of technologies that control on-off functions is selectable in the field by operating controls on unit.
1. Sensitivity Adjustment: Separate for each sensing technology.
  2. Detector Sensitivity: Detect occurrences of 6-inch-minimum movement of any portion of a human body that presents a target of not less than 36 sq. in., and detect a person of average size and weight moving not less than 12 inches in either a horizontal or a vertical manner at an approximate speed of 12 inches/s.
  3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. when mounted on a 96-inch-high ceiling.

## 2.2 SWITCHBOX-MOUNTED OCCUPANCY SENSORS

- A. General Requirements for Sensors: Automatic-wall-switch occupancy sensor, suitable for mounting in a single gang switchbox.
1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
  2. Operating Ambient Conditions: Dry interior conditions, 32 to 120 deg F.
  3. Switch Rating: Not less than 800-VA fluorescent at 120 V, 1200-VA fluorescent at 277 V, and 800-W incandescent.
- B. Wall-Switch Sensor:
1. Standard Range: 180-degree field of view, field adjustable from 180 to 40 degrees; with a minimum coverage area of 2100 sq. ft.
  2. Sensing Technology: Dual technology - PIR and ultrasonic.
  3. Switch Type: SP, field selectable automatic "on," or manual "on" automatic "off."
  4. Voltage: Match the circuit voltage; dual-technology type.
  5. Ambient-Light Override: Concealed, field-adjustable, light-level sensor from 10 to 150 fc. The switch prevents the lights from turning on when the light level is higher than the set point of the sensor.
  6. Concealed, field-adjustable, "off" time-delay selector at up to 30 minutes.
  7. Concealed "off" time-delay selector at 30 seconds, and 5, 10, and 20 minutes.

8. Adaptive Technology: Self-adjusting circuitry detects and memorizes usage patterns of the space and helps eliminate false "off" switching.

### 2.3 CONDUCTORS AND CABLES

- A. Power Wiring to Supply Side of Remote-Control Power Sources: Not smaller than No. 12 AWG. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
- B. Classes 2 and 3 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 18 AWG. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."
- C. Class 1 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 14 AWG. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install and aim sensors in locations to achieve not less than 90 percent coverage of areas indicated. Do not exceed coverage limits specified in manufacturer's written instructions.
- B. Occupancy Adjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in adjusting sensors to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.
  1. For occupancy and motion sensors, verify operation at outer limits of detector range. Set time delay to suit Owner's operations.
- C. Mount electrically held lighting contactors with elastomeric isolator pads to eliminate structure-borne vibration, unless contactors are installed in an enclosure with factory-installed vibration isolators.
- D. Wiring Method: Comply with Section 260519 "Low-Voltage Electrical Power Conductors and Cables." Minimum conduit size is 1/2 inch.
- E. Identify components and power and control wiring according to Section 260553 "Identification for Electrical Systems."

### 3.2 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to evaluate lighting control devices and perform tests and inspections.
- B. Perform the following tests and inspections with the assistance of a factory-authorized service representative:

1. Operational Test: After installing time switches and sensors, and after electrical circuitry has been energized, start units to confirm proper unit operation.
  2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- C. Lighting control devices will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

END OF SECTION 260923

SECTION 262416 - PANELBOARDS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Distribution panelboards.
2. Lighting and appliance branch-circuit panelboards.

1.2 DEFINITIONS

- A. MCCB: Molded-case circuit breaker.
- B. SPD: Surge protective device.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of panelboard.
- B. Shop Drawings: For each panelboard and related equipment.
1. Include dimensioned plans, elevations, sections, and details.
  2. Detail enclosure types including mounting and anchorage, environmental protection, knockouts, corner treatments, covers and doors, gaskets, hinges, and locks.
  3. Detail bus configuration, current, and voltage ratings.
  4. Short-circuit current rating of panelboards and overcurrent protective devices.
  5. Include evidence of NRTL listing for series rating of installed devices.
  6. Include evidence of NRTL listing for SPD as installed in panelboard.
  7. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices and auxiliary components.
  8. Include wiring diagrams for power, signal, and control wiring.
  9. Key interlock scheme drawing and sequence of operations.
  10. Include time-current coordination curves for each type and rating of overcurrent protective device included in panelboards.

1.4 INFORMATIONAL SUBMITTALS

- A. Panelboard schedules for installation in panelboards.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and maintenance data.



1.6 FIELD CONDITIONS

- A. Service Conditions: NEMA PB 1, usual service conditions, as follows:
1. Ambient temperatures within limits specified.
  2. Altitude not exceeding 6600 feet.

1.7 WARRANTY

- A. Manufacturer's Warranty: Manufacturer agrees to repair or replace panelboards that fail in materials or workmanship within specified warranty period.
1. Panelboard Warranty Period: 18 months from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PANELBOARDS COMMON REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NEMA PB 1.
- C. Comply with NFPA 70.
- D. Enclosures: Flush and Surface-mounted, dead-front cabinets.
1. Rated for environmental conditions at installed location.
    - a. Indoor Dry and Clean Locations: NEMA 250, Type 1.
    - b. Outdoor Locations: NEMA 250, Type 4.
    - c. Wash-Down Areas: NEMA 250, Type 4X stainless steel.
    - d. Other Wet or Damp Indoor Locations: NEMA 250, Type 4.
    - e. Indoor Locations Subject to Dust, Falling Dirt, and Dripping Noncorrosive Liquids: NEMA 250, Type 5.
  2. Height: 84 inches maximum.
  3. Front: Secured to box with concealed trim clamps. For surface-mounted fronts, match box dimensions; for flush-mounted fronts, overlap box. Trims shall cover all live parts and shall have no exposed hardware.
  4. Hinged Front Cover: Entire front trim hinged to box and with standard door within hinged trim cover. Trims shall cover all live parts and shall have no exposed hardware.
- E. Incoming Mains Location: Convertible between top and bottom.
- F. Phase, Neutral, and Ground Buses: Hard-drawn copper, 98 percent conductivity.
- G. Conductor Connectors: Suitable for use with conductor material and sizes.
1. Material: Hard-drawn copper, 98 percent conductivity.

2. Main and Neutral Lugs: Compression type, with a lug on the neutral bar for each pole in the panelboard.
  3. Ground Lugs and Bus-Configured Terminators: Compression type, with a lug on the bar for each pole in the panelboard.
  4. Feed-Through Lugs: Compression type, suitable for use with conductor material. Locate at opposite end of bus from incoming lugs or main device.
  5. Subfeed (Double) Lugs: Compression type suitable for use with conductor material. Locate at same end of bus as incoming lugs or main device.
- H. NRTL Label: Panelboards shall be labeled by an NRTL acceptable to authority having jurisdiction for use as service equipment with one or more main service disconnecting and overcurrent protective devices. Panelboards shall have meter enclosures, wiring, connections, and other provisions for utility metering. Coordinate with utility company for exact requirements.
- I. Future Devices: Panelboards shall have mounting brackets, bus connections, filler plates, and necessary appurtenances required for future installation of devices.
- J. Panelboard Short-Circuit Current Rating: Rated for series-connected system with integral or remote upstream overcurrent protective devices and labeled by an NRTL. Include label or manual with size and type of allowable upstream and branch devices listed and labeled by an NRTL for series-connected short-circuit rating.
- K. Panelboard Short-Circuit Current Rating: Fully rated to interrupt symmetrical short-circuit current available at terminals. Assembly listed by an NRTL for 100 percent interrupting capacity.

## 2.2 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Panelboards shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified."
- B. Surge Suppression: Factory installed as an integral part of indicated panelboards, complying with UL 1449 SPD Type 1.

## 2.3 POWER PANELBOARDS

- A. Panelboards: NEMA PB 1, distribution type.
- B. Doors: Secured with vault-type latch with tumbler lock; keyed alike.
1. For doors more than 36 inches high, provide two latches, keyed alike.
- C. Mains: Circuit breaker.
- D. Branch Overcurrent Protective Devices for Circuit-Breaker Frame Sizes 125 A and Smaller: Bolt-on circuit breakers.
- E. Branch Overcurrent Protective Devices for Circuit-Breaker Frame Sizes Larger Than 125 A: Bolt-on circuit breakers.

- F. Branch Overcurrent Protective Devices: Fused switches.
- G. Contactors in Main Bus: NEMA ICS 2, Class A, electrically held, general-purpose controller, with same short-circuit interrupting rating as panelboard.
  - 1. External Control-Power Source: 120-V branch circuit.

#### 2.4 LIGHTING AND APPLIANCE BRANCH-CIRCUIT PANELBOARDS

- A. Panelboards: NEMA PB 1, lighting and appliance branch-circuit type.
- B. Mains: Circuit breaker.
- C. Branch Overcurrent Protective Devices: Bolt-on circuit breakers, replaceable without disturbing adjacent units.
- D. Contactors in Main Bus: NEMA ICS 2, Class A, electrically held, general-purpose controller, with same short-circuit interrupting rating as panelboard.
  - 1. External Control-Power Source: 120-V branch circuit.
- E. Doors: Concealed hinges; secured with flush latch with tumbler lock; keyed alike.
- F. Column-Type Panelboards: Single row of overcurrent devices with narrow gutter extension and overhead junction box equipped with ground and neutral terminal buses.

#### 2.5 DISCONNECTING AND OVERCURRENT PROTECTIVE DEVICES

- A. MCCB: Comply with UL 489, with interrupting capacity to meet available fault currents.
  - 1. Thermal-Magnetic Circuit Breakers:
    - a. Inverse time-current element for low-level overloads.
    - b. Instantaneous magnetic trip element for short circuits.
    - c. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
  - 2. Adjustable Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
  - 3. Electronic Trip Circuit Breakers:
    - a. RMS sensing.
    - b. Field-replaceable rating plug or electronic trip.
    - c. Digital display of settings, trip targets, and indicated metering displays.
    - d. Multi-button keypad to access programmable functions and monitored data.
    - e. Ten-event, trip-history log. Each trip event shall be recorded with type, phase, and magnitude of fault that caused the trip.
    - f. Integral test jack for connection to portable test set or laptop computer.
    - g. Field-Adjustable Settings:
      - 1) Instantaneous trip.
      - 2) Long- and short-time pickup levels.

- 3) Long and short time adjustments.
  - 4) Ground-fault pickup level, time delay, and I squared T response.
4. Current-Limiting Circuit Breakers: Frame sizes 400 A and smaller; let-through ratings less than NEMA FU 1, RK-5.
  5. GFCI Circuit Breakers: Single- and double-pole configurations with Class A ground-fault protection (6-mA trip).
  6. GFEP Circuit Breakers: Class B ground-fault protection (30-mA trip).
  7. Arc-Fault Circuit Interrupter Circuit Breakers: Comply with UL 1699; 120/240-V, single-pole configuration.
  8. Subfeed Circuit Breakers: Vertically mounted.
  9. MCCB Features and Accessories:
    - a. Standard frame sizes, trip ratings, and number of poles.
    - b. Breaker handle indicates tripped status.
    - c. UL listed for reverse connection without restrictive line or load ratings.
    - d. Lugs: Mechanical style, suitable for number, size, trip ratings, and conductor materials.
    - e. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HID for feeding fluorescent and HID lighting circuits.
    - f. Ground-Fault Protection: Integrally mounted relay and trip unit with adjustable pickup and time-delay settings, push-to-test feature, and ground-fault indicator.
    - g. Communication Capability: Universal-mounted communication module with functions and features compatible with power monitoring and control system specified in Section 260913 "Electrical Power Monitoring and Control."
    - h. Shunt Trip: 120-V trip coil energized from separate circuit, set to trip at 55 percent of rated voltage.
    - i. Handle Padlocking Device: Fixed attachment, for locking circuit-breaker handle in on or off position.
    - j. Handle Clamp: Loose attachment, for holding circuit-breaker handle in on position.
- B. Fused Switch: NEMA KS 1, Type HD; clips to accommodate specified fuses; lockable handle.
1. Fuses and Spare-Fuse Cabinet: Comply with requirements specified in Section 262813 "Fuses."

## 2.6 IDENTIFICATION

- A. Panelboard Label: Manufacturer's name and trademark, voltage, amperage, number of phases, and number of poles shall be located on the interior of the panelboard door.
- B. Breaker Labels: Faceplate shall list current rating, UL and IEC certification standards, and AIC rating.
- C. Circuit Directory: Directory card inside panelboard door, mounted in metal frame with transparent protective cover.

## 2.7 ACCESSORY COMPONENTS AND FEATURES

- A. Portable Test Set: For testing functions of solid-state trip devices without removing from panelboard. Include relay and meter test plugs suitable for testing panelboard meters and switchboard class relays.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Comply with NECA 1.
- B. Install panelboards and accessories according to NECA 407 and NEMA PB 1.1.
- C. Comply with mounting and anchoring requirements specified in Section 260548.16 "Seismic Controls for Electrical Systems."
- D. Mount top of trim 90 inches above finished floor unless otherwise indicated.
- E. Mount panelboard cabinet plumb and rigid without distortion of box.
- F. Mount recessed panelboards with fronts uniformly flush with wall finish and mating with back box.
- G. Install overcurrent protective devices and controllers not already factory installed.
  - 1. Set field-adjustable, circuit-breaker trip ranges.
- H. Make grounding connections and bond neutral for services and separately derived systems to ground. Make connections to grounding electrodes, separate grounds for isolated ground bars, and connections to separate ground bars.
- I. Install filler plates in unused spaces.
- J. Stub four 1-inch empty conduits from panelboard into accessible ceiling space or space designated to be ceiling space in the future. Stub four 1-inch empty conduits into raised floor space or below slab not on grade.
- K. Arrange conductors in gutters into groups and bundle and wrap with wire ties.

### 3.2 IDENTIFICATION

- A. Identify field-installed conductors, interconnecting wiring, and components; install warning signs complying with requirements in Section 260553 "Identification for Electrical Systems."
- B. Create a directory to indicate installed circuit loads; incorporate Owner's final room designations. Obtain approval before installing. Handwritten directories are not acceptable. Install directory inside panelboard door.

- C. Panelboard Nameplates: Label each panelboard with a nameplate complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems."
- D. Device Nameplates: Label each branch circuit device in power panelboards with a nameplate complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems."
- E. Install warning signs complying with requirements in Section 260553 "Identification for Electrical Systems" identifying source of remote circuit.

### 3.3 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Acceptance Testing Preparation:
  - 1. Test insulation resistance for each panelboard bus, component, connecting supply, feeder, and control circuit.
  - 2. Test continuity of each circuit.
- C. Tests and Inspections:
  - 1. Perform each visual and mechanical inspection and electrical test for low-voltage air circuit breakers stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
  - 2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
- D. Panelboards will be considered defective if they do not pass tests and inspections.
- E. Prepare test and inspection reports, including a certified report that identifies panelboards included and that describes scanning results, with comparisons of the two scans. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

END OF SECTION 262416

SECTION 262726 - WIRING DEVICES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Receptacles, receptacles with integral GFCI, and associated device plates.
2. Weather-resistant receptacles.
3. Snap switches and wall-box dimmers.
4. Solid-state fan speed controls.
5. Wall-switches.

1.2 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Receptacles for Owner-Furnished Equipment: Match plug configurations.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: List of legends and description of materials and process used for premarking wall plates.

1.4 INFORMATIONAL SUBMITTALS

A. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

A. Operation and maintenance data.

PART 2 - PRODUCTS

A. Source Limitations: Obtain each type of wiring device and associated wall plate from single source from single manufacturer.

B. Coordinate with manufacturer for equipment that will need to be rated for use with aluminum conductors.

## 2.2 GENERAL WIRING-DEVICE REQUIREMENTS

- A. Wiring Devices, Components, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.
- C. Devices that are manufactured for use with modular plug-in connectors may be substituted under the following conditions:
  - 1. Connectors shall comply with UL 2459 and shall be made with stranding building wire.
  - 2. Devices shall comply with the requirements in this Section.

## 2.3 STRAIGHT-BLADE RECEPTACLES

- A. Convenience Receptacles, 125 V, 20 A: Comply with NEMA WD 1, NEMA WD 6 Configuration 5-20R, UL 498, and FS W-C-596.

## 2.4 GFCI RECEPTACLES

- A. General Description:
  - 1. Straight blade, feed-through type.
  - 2. Comply with NEMA WD 1, NEMA WD 6, UL 498, UL 943 Class A, and FS W-C-596.
  - 3. Include indicator light that shows when the GFCI has malfunctioned and no longer provides proper GFCI protection.
- B. Duplex GFCI Convenience Receptacles, 125 V, 20 A:

## 2.5 TOGGLE SWITCHES

- A. Comply with NEMA WD 1, UL 20, and FS W-S-896.
- B. Switches, 120/277 V, 20 A.
- C. Pilot-Light Switches, 20 A:
  - 1. Description: Single pole, with neon-lighted handle, illuminated when switch is "off."

## 2.6 WALL-BOX DIMMERS

- A. Dimmer Switches: Modular, full-wave, solid-state units with integral, quiet on-off switches, with audible frequency and EMI/RFI suppression filters.
- B. Control: Continuously adjustable toggle switch; with single-pole or three-way switching. Comply with UL 1472.
- C. Incandescent Lamp Dimmers: 120 V; control shall follow square-law dimming curve. On-off switch positions shall bypass dimmer module.



1. 600 W; dimmers shall require no derating when ganged with other devices. Illuminated when "off."

- D. Fluorescent Lamp Dimmer Switches: Modular; compatible with dimmer ballasts; trim potentiometer to adjust low-end dimming; dimmer-ballast combination capable of consistent dimming with low end not greater than 20 percent of full brightness.

## 2.7 WALL PLATES

- A. Single and combination types shall match corresponding wiring devices.
  1. Plate-Securing Screws: Metal with head color to match plate finish.
  2. Material for Finished Spaces: Smooth, high-impact thermoplastic.
  3. Material for Unfinished Spaces: Smooth, high-impact thermoplastic.
  4. Material for Damp Locations: Thermoplastic with spring-loaded lift cover, and listed and labeled for use in wet and damp locations.
- B. Wet-Location, Weatherproof Cover Plates: NEMA 250, complying with Type 3R, weather-resistant, die-cast aluminum with lockable cover.

## 2.8 FINISHES

- A. Device Color:
  1. Wiring Devices Connected to Normal Power System: Black unless otherwise indicated or required by NFPA 70 or device listing.
  2. Wiring Devices Connected to Emergency Power System: Red.
  3. TVSS Devices: Blue.
- B. Wall Plate Color: For plastic covers, match device color.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Comply with NECA 1, including mounting heights listed in that standard, unless otherwise indicated.
- B. Coordination with Other Trades:
  1. Protect installed devices and their boxes. Do not place wall finish materials over device boxes and do not cut holes for boxes with routers that are guided by riding against outside of boxes.
  2. Keep outlet boxes free of plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other material that may contaminate the raceway system, conductors, and cables.
  3. Install device boxes in brick or block walls so that the cover plate does not cross a joint unless the joint is troweled flush with the face of the wall.
  4. Install wiring devices after all wall preparation, including painting, is complete.

C. Conductors:

1. Do not strip insulation from conductors until right before they are spliced or terminated on devices.
2. Strip insulation evenly around the conductor using tools designed for the purpose. Avoid scoring or nicking of solid wire or cutting strands from stranded wire.
3. The length of free conductors at outlets for devices shall meet provisions of NFPA 70, Article 300, without pigtails.
4. Existing Conductors:
  - a. Cut back and pigtail, or replace all damaged conductors.
  - b. Straighten conductors that remain and remove corrosion and foreign matter.
  - c. Pigtailing existing conductors is permitted, provided the outlet box is large enough.

D. Device Installation:

1. Replace devices that have been in temporary use during construction and that were installed before building finishing operations were complete.
2. Keep each wiring device in its package or otherwise protected until it is time to connect conductors.
3. Do not remove surface protection, such as plastic film and smudge covers, until the last possible moment.
4. Connect devices to branch circuits using pigtails that are not less than 6 inches in length.
5. When there is a choice, use side wiring with binding-head screw terminals. Wrap solid conductor tightly clockwise, two-thirds to three-fourths of the way around terminal screw.
6. Use a torque screwdriver when a torque is recommended or required by manufacturer.
7. When conductors larger than No. 12 AWG are installed on 15- or 20-A circuits, splice No. 12 AWG pigtails for device connections.
8. Tighten unused terminal screws on the device.
9. When mounting into metal boxes, remove the fiber or plastic washers used to hold device-mounting screws in yokes, allowing metal-to-metal contact.

E. Receptacle Orientation:

1. Install ground pin of vertically mounted receptacles up, and on horizontally mounted receptacles to the right.

F. Device Plates: Do not use oversized or extra-deep plates. Repair wall finishes and remount outlet boxes when standard device plates do not fit flush or do not cover rough wall opening.

G. Dimmers:

1. Install dimmers within terms of their listing.
2. Verify that dimmers used for fan speed control are listed for that application.
3. Install unshared neutral conductors on line and load side of dimmers according to manufacturers' device listing conditions in the written instructions.

H. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical and with grounding terminal of receptacles on top. Group adjacent switches under single, multigang wall plates.

- I. Adjust locations of service poles to suit arrangement of partitions and furnishings.

### 3.2 GFCI RECEPTACLES

- A. Install non-feed-through-type GFCI receptacles where protection of downstream receptacles is not required.

### 3.3 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
  - 1. Test Instruments: Use instruments that comply with UL 1436.
  - 2. Test Instrument for Convenience Receptacles: Digital wiring analyzer with digital readout or illuminated digital-display indicators of measurement.
- B. Tests for Convenience Receptacles:
  - 1. Line Voltage: Acceptable range is 105 to 132 V.
  - 2. Percent Voltage Drop under 15-A Load: A value of 6 percent or higher is unacceptable.
  - 3. Ground Impedance: Values of up to 2 ohms are acceptable.
  - 4. GFCI Trip: Test for tripping values specified in UL 1436 and UL 943.
  - 5. Using the test plug, verify that the device and its outlet box are securely mounted.
  - 6. Tests shall be diagnostic, indicating damaged conductors, high resistance at the circuit breaker, poor connections, inadequate fault current path, defective devices, or similar problems. Correct circuit conditions, remove malfunctioning units and replace with new ones, and retest as specified above.
- C. Wiring device will be considered defective if it does not pass tests and inspections.
- D. Prepare test and inspection reports.

END OF SECTION 262726

SECTION 262816 - ENCLOSED SWITCHES AND CIRCUIT BREAKERS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
  - 1. Fusible switches.
  - 2. Nonfusible switches.

1.2 DEFINITIONS

- A. NC: Normally closed.
- B. NO: Normally open.
- C. SPDT: Single pole, double throw.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of enclosed switch, circuit breaker, accessory, and component indicated.
- B. Shop Drawings: For enclosed switches and circuit breakers. Include plans, elevations, sections, details, and attachments to other work.
  - 1. Wiring Diagrams: For power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and maintenance data.

1.6 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.

## PART 2 - PRODUCTS

### 2.1 FUSIBLE SWITCHES

- A. Type HD, Heavy Duty, Single Throw, 600-V ac, 1200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, with clips or bolt pads to accommodate indicated fuses, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position. Service entrance rated for 400A.
- B. Accessories:
  - 1. Equipment Ground Kit: Internally mounted and labeled for copper and aluminum ground conductors.
  - 2. Neutral Kit: Internally mounted; insulated, capable of being grounded and bonded; labeled for copper and aluminum neutral conductors.
  - 3. Class R Fuse Kit: Provides rejection of other fuse types when Class R fuses are specified.
  - 4. Lugs: Suitable for number, size, and conductor material.
  - 5. Service-Rated Switches: Labeled for use as service equipment.

### 2.2 NONFUSIBLE SWITCHES

- A. Type HD, Heavy Duty, Single Throw, 600-V ac, 1200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position.
- B. Accessories:
  - 1. Equipment Ground Kit: Internally mounted and labeled for copper and aluminum ground conductors.
  - 2. Neutral Kit: Internally mounted; insulated, capable of being grounded and bonded; labeled for copper and aluminum neutral conductors.
  - 3. Lugs: Suitable for number, size, and conductor material.

### 2.3 ENCLOSURES

- A. Enclosed Switches and Circuit Breakers: NEMA AB 1, NEMA KS 1, NEMA 250, and UL 50, to comply with environmental conditions at installed location.
  - 1. Indoor, Dry and Clean Locations: NEMA 250, Type 1.
  - 2. Outdoor Locations: NEMA 250, Type 3R.
  - 3. Wash-Down Areas: NEMA 250, Type 4X stainless steel.
  - 4. Other Wet or Damp, Indoor Locations: NEMA 250, Type 4.
  - 5. Indoor Locations Subject to Dust, Falling Dirt, and Dripping Noncorrosive Liquids: NEMA 250, Type 12.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install individual wall-mounted switches and circuit breakers with tops at uniform height unless otherwise indicated.
- B. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from enclosures and components.
- C. Install fuses in fusible devices.
- D. Comply with NECA 1.

#### 3.2 IDENTIFICATION

- A. Comply with requirements in Section 260553 "Identification for Electrical Systems."
  - 1. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs.
  - 2. Label each enclosure with engraved metal or laminated-plastic nameplate.

#### 3.3 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Acceptance Testing Preparation:
  - 1. Test insulation resistance for each enclosed switch and circuit breaker, component, connecting supply, feeder, and control circuit.
  - 2. Test continuity of each circuit.
- C. Tests and Inspections:
  - 1. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
  - 2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
- D. Enclosed switches and circuit breakers will be considered defective if they do not pass tests and inspections.
- E. Prepare test and inspection reports, including a certified report that identifies enclosed switches and circuit breakers and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

END OF SECTION 262816

## SECTION 265100 - INTERIOR LIGHTING

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Section Includes:

1. Interior lighting fixtures, lamps, and ballasts.
2. Emergency lighting units.
3. Exit signs.
4. Lighting fixture supports.
5. Retrofit kits for fluorescent lighting fixtures.

B. Related Sections:

1. Section 260923 "Lighting Control Devices" for automatic control of lighting, including time switches, photoelectric relays, occupancy sensors, and multipole lighting relays and contactors.
2. Section 262726 "Wiring Devices" for manual wall-box dimmers for incandescent lamps.

#### 1.2 ACTION SUBMITTALS

- A. Product Data: For each type of lighting fixture, arranged in order of fixture designation. Include data on features, accessories, and finishes.
- B. Shop Drawings: Show details of nonstandard or custom lighting fixtures. Indicate dimensions, weights, methods of field assembly, components, features, and accessories. Product Certificates: For each type of ballast for bi-level and dimmer-controlled fixtures, from manufacturer.

#### 1.3 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

#### 1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, product(s) indicated on Drawings.

### 2.2 GENERAL REQUIREMENTS FOR LIGHTING FIXTURES AND COMPONENTS

- A. Recessed Fixtures: Comply with NEMA LE 4 for ceiling compatibility for recessed fixtures.
- B. Fluorescent Fixtures: Comply with UL 1598. Where LER is specified, test according to NEMA LE 5 and NEMA LE 5A as applicable.
- C. Metal Parts: Free of burrs and sharp corners and edges.
- D. Sheet Metal Components: Steel unless otherwise indicated. Form and support to prevent warping and sagging.
- E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.
- F. Diffusers and Globes:
  - 1. Acrylic Lighting Diffusers: 100 percent virgin acrylic plastic. High resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
    - a. Lens Thickness: At least 0.125 inch minimum unless otherwise indicated.
    - b. UV stabilized.
  - 2. Glass: Annealed crystal glass unless otherwise indicated.

### 2.3 BALLASTS FOR LINEAR FLUORESCENT LAMPS

- A. General Requirements for Electronic Ballasts:
  - 1. Comply with UL 935 and with ANSI C82.11.
  - 2. Designed for type and quantity of lamps served.
  - 3. Ballasts shall be designed for full light output unless another BF, dimmer, or bi-level control is indicated.
  - 4. Sound Rating: Class A.
  - 5. Total Harmonic Distortion Rating: Less than 10 percent.
  - 6. Transient Voltage Protection: IEEE C62.41.1 and IEEE C62.41.2, Category A or better.
  - 7. Operating Frequency: 42 kHz or higher.
  - 8. Lamp Current Crest Factor: 1.7 or less.
  - 9. BF: 0.88 or higher.
  - 10. Power Factor: 0.95 or higher.



- B. Luminaires controlled by occupancy sensors shall have programmed-start ballasts.
- C. Electromagnetic Ballasts: Comply with ANSI C82.1; energy saving, high-power factor, Class P, and having automatic-reset thermal protection.
  - 1. Ballast Manufacturer Certification: Indicated by label.
- D. Single Ballasts for Multiple Lighting Fixtures: Factory wired with ballast arrangements and bundled extension wiring to suit final installation conditions without modification or rewiring in the field.
- E. Ballasts for Low-Temperature Environments: Electronic type rated for 0 deg F starting and operating temperature with indicated lamp types.
- F. Ballasts for Residential Applications: Fixtures designated as "Residential" may use low-power-factor electronic ballasts having a Class B sound rating and total harmonic distortion of approximately 30 percent.
- G. Ballasts for Dimmer-Controlled Lighting Fixtures: Electronic type.
  - 1. Dimming Range: 100 to 5 percent of rated lamp lumens.
  - 2. Ballast Input Watts: Can be reduced to 20 percent of normal.
  - 3. Compatibility: Certified by manufacturer for use with specific dimming control system and lamp type indicated.
  - 4. Control: Coordinate wiring from ballast to control device to ensure that the ballast, controller, and connecting wiring are compatible.
- H. Ballasts for Bi-Level Controlled Lighting Fixtures: Electronic type.
  - 1. Operating Modes: Ballast circuit and leads provide for remote control of the light output of the associated lamp between high- and low-level and off.
    - a. High-Level Operation: 100 percent of rated lamp lumens.
    - b. Low-Level Operation: 30 percent of rated lamp lumens.
  - 2. Ballast shall provide equal current to each lamp in each operating mode.
  - 3. Compatibility: Certified by manufacturer for use with specific bi-level control system and lamp type indicated.
- I. Ballasts for Tri-Level Controlled Lighting Fixtures: Electronic type.
  - 1. Operating Modes: Ballast circuit and leads provide for remote control of the light output of the associated lamp between high- and low-level and off.
    - a. High-Level Operation: 100 percent of rated lamp lumens.
    - b. Low-Level Operation: 30 and 50 percent of rated lamp lumens.
  - 2. Ballast shall provide equal current to each lamp in each operating mode.
  - 3. Compatibility: Certified by manufacturer for use with specific tri-level control system and lamp type indicated.

## 2.4 BALLASTS FOR COMPACT FLUORESCENT LAMPS

- A. Description: Electronic-programmed rapid-start type, complying with UL 935 and with ANSI C 82.11, designed for type and quantity of lamps indicated. Ballast shall be designed for full light output unless dimmer or bi-level control is indicated:
1. Lamp end-of-life detection and shutdown circuit.
  2. Automatic lamp starting after lamp replacement.
  3. Sound Rating: Class A.
  4. Total Harmonic Distortion Rating: Less than 20 percent.
  5. Transient Voltage Protection: IEEE C62.41.1 and IEEE C62.41.2, Category A or better.
  6. Operating Frequency: 20 kHz or higher.
  7. Lamp Current Crest Factor: 1.7 or less.
  8. BF: 0.95 or higher unless otherwise indicated.
  9. Power Factor: 0.95 or higher.
  10. Interference: Comply with 47 CFR 18, Ch. 1, Subpart C, for limitations on electromagnetic and radio-frequency interference for nonconsumer equipment.

## 2.5 EMERGENCY FLUORESCENT POWER UNIT

- A. Internal Type: Self-contained, modular, battery-inverter unit, factory mounted within lighting fixture body and compatible with ballast. Comply with UL 924.
1. Emergency Connection: Operate one fluorescent lamp(s) continuously at an output of 1100lumens each. Connect unswitched circuit to battery-inverter unit and switched circuit to fixture ballast.
  2. Nightlight Connection: Operate one fluorescent lamp continuously.
  3. Test Push Button and Indicator Light: Visible and accessible without opening fixture or entering ceiling space.
    - a. Push Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
    - b. Indicator Light: LED indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.
  4. Battery: Sealed, maintenance-free, nickel-cadmium type.
  5. Charger: Fully automatic, solid-state, constant-current type with sealed power transfer relay.
  6. Integral Self-Test: Factory-installed electronic device automatically initiates code-required test of unit emergency operation at required intervals. Test failure is annunciated by an integral audible alarm and a flashing red LED.

## 2.6 EXIT SIGNS

- A. General Requirements for Exit Signs: Comply with UL 924; for sign colors, visibility, luminance, and lettering size, comply with authorities having jurisdiction.
- B. Internally Lighted Signs:
1. Lamps for AC Operation: Fluorescent, two for each fixture, 20,000 hours of rated lamp life.

2. Lamps for AC Operation: LEDs, 50,000 hours minimum rated lamp life.
3. Self-Powered Exit Signs (Battery Type): Integral automatic charger in a self-contained power pack.
  - a. Battery: Sealed, maintenance-free, nickel-cadmium type.
  - b. Charger: Fully automatic, solid-state type with sealed transfer relay.
  - c. Operation: Relay automatically energizes lamp from battery when circuit voltage drops to 80 percent of nominal voltage or below. When normal voltage is restored, relay disconnects lamps from battery, and battery is automatically recharged and floated on charger.
  - d. Test Push Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
  - e. LED Indicator Light: Indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.

## 2.7 EMERGENCY LIGHTING UNITS

- A. General Requirements for Emergency Lighting Units: Self-contained units complying with UL 924.
  1. Battery: Sealed, maintenance-free, lead-acid type.
  2. Charger: Fully automatic, solid-state type with sealed transfer relay.
  3. Operation: Relay automatically turns lamp on when power-supply circuit voltage drops to 80 percent of nominal voltage or below. Lamp automatically disconnects from battery when voltage approaches deep-discharge level. When normal voltage is restored, relay disconnects lamps from battery, and battery is automatically recharged and floated on charger.
  4. Test Push Button: Push-to-test type, in unit housing, simulates loss of normal power and demonstrates unit operability.
  5. LED Indicator Light: Indicates normal power on. Normal glow indicates trickle charge; bright glow indicates charging at end of discharge cycle.
  6. Wire Guard: Heavy-chrome-plated wire guard protects lamp heads or fixtures.
  7. Integral Time-Delay Relay: Holds unit on for fixed interval of [15] <Insert period> minutes when power is restored after an outage.

## 2.8 FLUORESCENT LAMPS

- A. T8 rapid-start lamps, rated 32 W maximum, nominal length of 48 inches, 2800 initial lumens (minimum), CRI 75 (minimum), color temperature 3500K, and average rated life 20,000 hours unless otherwise indicated.
- B. T8 rapid-start lamps, rated 17 W maximum, nominal length of 24 inches, 1300 initial lumens (minimum), CRI 75 (minimum), color temperature 3500K, and average rated life of 20,000 hours unless otherwise indicated.
- C. Compact Fluorescent Lamps: 4-Pin, CRI 80 (minimum), color temperature 3500K, average rated life of 10,000 hours at three hours operation per start, and suitable for use with dimming ballasts unless otherwise indicated.
  1. 13 W: T4, double or triple tube, rated 900 initial lumens (minimum).
  2. 18 W: T4, double or triple tube, rated 1200 initial lumens (minimum).

3. 26 W: T4, double or triple tube, rated 1800 initial lumens (minimum).
4. 32 W: T4, triple tube, rated 2400 initial lumens (minimum).
5. 42 W: T4, triple tube, rated 3200 initial lumens (minimum).
6. 57 W: T4, triple tube, rated 4300 initial lumens (minimum).
7. 70 W: T4, triple tube, rated 5200 initial lumens (minimum).

## 2.9 LIGHTING FIXTURE SUPPORT COMPONENTS

- A. Comply with Section 260529 "Hangers and Supports for Electrical Systems" for channel- and angle-iron supports and nonmetallic channel and angle supports.
- B. Single-Stem Hangers: 1/2-inch steel tubing with swivel ball fittings and ceiling canopy. Finish same as fixture.
- C. Twin-Stem Hangers: Two, 1/2-inch steel tubes with single canopy designed to mount a single fixture. Finish same as fixture.
- D. Wires: ASTM A 641/A 641M, Class 3, soft temper, zinc-coated steel, 12 gage.
- E. Wires for Humid Spaces: ASTM A 580/A 580M, Composition 302 or 304, annealed stainless steel, 12 gage.
- F. Rod Hangers: 3/16-inch minimum diameter, cadmium-plated, threaded steel rod.
- G. Hook Hangers: Integrated assembly matched to fixture and line voltage and equipped with threaded attachment, cord, and locking-type plug.

## 2.10 RETROFIT KITS FOR FLUORESCENT LIGHTING FIXTURES

- A. Reflector Kit: UL 1598, Type I. Suitable for two- to four-lamp, surface-mounted or recessed lighting fixtures by improving reflectivity of fixture surfaces.
- B. Ballast and Lamp Change Kit: UL 1598, Type II. Suitable for changing existing ballast, lamps, and sockets.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Lighting fixtures: Set level, plumb, and square with ceilings and walls. Install lamps in each fixture.
- B. Comply with NFPA 70 for minimum fixture supports.
- C. Suspended Lighting Fixture Support:
  1. Pendants and Rods: Where longer than 48 inches, brace to limit swinging.
  2. Stem-Mounted, Single-Unit Fixtures: Suspend with twin-stem hangers.

3. Continuous Rows: Use tubing or stem for wiring at one point and tubing or rod for suspension for each unit length of fixture chassis, including one at each end.
- D. Adjust aimable lighting fixtures to provide required light intensities.
- E. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables."

### 3.2 FIELD QUALITY CONTROL

- A. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery and retransfer to normal.
- B. Prepare a written report of tests, inspections, observations, and verifications indicating and interpreting results. If adjustments are made to lighting system, retest to demonstrate compliance with standards.

END OF SECTION 265100

SECTION 265119 - LED INTERIOR LIGHTING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior solid-state luminaires that use LED technology.
2. Lighting fixture supports.

B. Related Requirements:

1. Section 260923 "Lighting Control Devices" for automatic control of lighting, including time switches, photoelectric relays, occupancy sensors, and multipole lighting relays and contactors.

1.2 DEFINITIONS

A. CCT: Correlated color temperature.

B. CRI: Color Rendering Index.

C. Fixture: See "Luminaire."

D. IP: International Protection or Ingress Protection Rating.

E. LED: Light-emitting diode.

F. Lumen: Measured output of lamp and luminaire, or both.

G. Luminaire: Complete lighting unit, including lamp, reflector, and housing.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product, arranged by designation.

B. Shop Drawings: For nonstandard or custom luminaires.

1. Include plans, elevations, sections, and mounting and attachment details.
2. Include details of luminaire assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.

C. LEED Submittals:

1. Product Data for Credit IEQ 4.2: For paints and coatings, documentation including printed statement of VOC content.
  2. Laboratory Test Reports for Credit IEQ 4.2: For paints and coatings, documentation indicating that products comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- D. Product Schedule: For luminaires and lamps. Use same designations indicated on Drawings.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plan(s) and other details, drawn to scale and coordinated with each other, using input from installers of the items involved:
- B. Seismic Qualification Certificates: For luminaires, accessories, and components, from manufacturer.
- C. Product Certificates: For each type of luminaire.
- D. Sample warranty.

#### 1.5 CLOSEOUT SUBMITTALS

- A. Operation and maintenance data.

#### 1.6 WARRANTY

- A. Warranty: Manufacturer and Installer agree to repair or replace components of luminaires that fail in materials or workmanship within specified warranty period.
- B. Warranty Period: Five year(s) from date of Substantial Completion.

### PART 2 - PRODUCTS

#### 2.1 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Luminaires shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
- B. Seismic Performance: Luminaires and lamps shall be labeled vibration and shock resistant.
  1. The term "withstand" means "the luminaire will remain in place without separation of any parts when subjected to the seismic forces specified and the luminaire will be fully operational during and after the seismic event."

## 2.2 LUMINAIRE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. NRTL Compliance: Luminaires for hazardous locations shall be listed and labeled for indicated class and division of hazard by an NRTL.
- C. FM Global Compliance: Luminaires for hazardous locations shall be listed and labeled for indicated class and division of hazard by FM Global.
- D. Recessed Fixtures: Comply with NEMA LE 4.
- E. CRI of 80. CCT of 3000 K.
- F. Rated lamp life of 35,000 hours.
- G. Lamps dimmable from 100 percent to 0 percent of maximum light output.
- H. Internal driver.
- I. Nominal Operating Voltage: 120 V ac.
  - 1. Lens Thickness: At least 0.125 inch minimum unless otherwise indicated.
- J. Housings:
  - 1. Extruded-aluminum housing and heat sink.
  - 2. powder-coat finish.

## 2.3 DOWNLIGHT

- A. Minimum 1,000 lumens. Minimum allowable efficacy of 80 lumens per watt.
- B. Universal mounting bracket.
- C. Integral junction box with conduit fittings.

## 2.4 RECESSED LINEAR

- A. Minimum 2,000 lumens. Minimum allowable efficacy of 85 lumens per watt.
- B. Integral junction box with conduit fittings.

## 2.5 STRIP LIGHT

- A. Minimum 750 lumens. Minimum allowable efficacy of 80 lumens per watt.
- B. Integral junction box with conduit fittings.



2.6 SURFACE MOUNT, LINEAR

- A. Minimum 750 lumens. Minimum allowable efficacy of 80 lumens per watt.
- B. Integral junction box with conduit fittings.

2.7 SURFACE MOUNT, NONLINEAR

- A. Minimum 750 lumens. Minimum allowable efficacy of 80 lumens per watt.
- B. Integral junction box with conduit fittings.

2.8 SUSPENDED, LINEAR

- A. Minimum 2,000 lumens. Minimum allowable efficacy of 85 lumens per watt.

2.9 SUSPENDED, NONLINEAR

- A. Minimum 2,000 lumens. Minimum allowable efficacy of 85 lumens per watt.
- B. Integral junction box with conduit fittings.

2.10 MATERIALS

A. Metal Parts:

- 1. Free of burrs and sharp corners and edges.
- 2. Sheet metal components shall be steel unless otherwise indicated.
- 3. Form and support to prevent warping and sagging

- B. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

C. Diffusers, and Globes:

- 1. diffuse glass
- 2. Acrylic: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
- 3. Glass: Annealed crystal glass unless otherwise indicated.
- 4. Lens Thickness: At least 0.125 inch minimum unless otherwise indicated.

D. Housings:

- 1. Extruded-aluminum housing and heat sink.
- 2. powder-coat finish.

2.11 METAL FINISHES

- A. Variations in finishes are unacceptable in the same piece. Variations in finishes of adjoining components are acceptable if they are within the range of approved Samples and if they can be and are assembled or installed to minimize contrast.

2.12 LUMINAIRE SUPPORT COMPONENTS

- A. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for channel and angle iron supports and nonmetallic channel and angle supports.
- B. Single-Stem Hangers: 1/2-inch steel tubing with swivel ball fittings and ceiling canopy. Finish same as luminaire.
- C. Wires: ASTM A 641/A 641 M, Class 3, soft temper, zinc-coated steel, 12 gage.
- D. Rod Hangers: 3/16-inch minimum diameter, cadmium-plated, threaded steel rod.
- E. Hook Hangers: Integrated assembly matched to luminaire, line voltage, and equipment with threaded attachment, cord, and locking-type plug.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with NECA 1.
- B. Install luminaires level, plumb, and square with ceilings and walls unless otherwise indicated.
- C. Install lamps in each luminaire.
- D. Supports: Sized and rated for luminaire weight.
- E. Flush-Mounted Luminaire Support: Secured to outlet box.
- F. Wall-Mounted Luminaire Support:
  - 1. Attached to structural members in walls.
  - 2. Do not attach luminaires directly to gypsum board.
- G. Ceiling-Mounted Luminaire Support:
  - 1. Ceiling mount with two 5/32-inch-diameter aircraft cable supports adjustable to 120 inches in length
  - 2. Ceiling mount with pendant mount with 5/32-inch-diameter aircraft cable supports adjustable to 120 inches in length.
  - 3. Ceiling mount with hook mount.
- H. Suspended Luminaire Support:

1. Pendants and Rods: Where longer than 48 inches, brace to limit swinging.
  2. Stem-Mounted, Single-Unit Luminaires: Suspend with twin-stem hangers. Support with approved outlet box and accessories that hold stem and provide damping of luminaire oscillations. Support outlet box vertically to building structure using approved devices.
  3. Continuous Rows of Luminaires: Use tubing or stem for wiring at one point and tubing or rod for suspension for each unit length of luminaire chassis, including one at each end.
  4. Do not use ceiling grid as support for pendant luminaires. Connect support wires or rods to building structure.
- I. Ceiling-Grid-Mounted Luminaires:
1. Secure to any required outlet box.
  2. Secure luminaire using approved fasteners in a minimum of four locations, spaced near corners of luminaire.
- J. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for wiring connections.
- K. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

### 3.2 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
1. Operational Test: After installing luminaires, switches, and accessories, and after electrical circuitry has been energized, test units to confirm proper operation.
  2. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery power and retransfer to normal.
- B. Luminaire will be considered defective if it does not pass operation tests and inspections.
- C. Prepare test and inspection reports.

END OF SECTION 265119

SECTION 27 05 00 – COMMON WORK RESULTS FOR COMMUNICATIONS

PART 1 - GENERAL

1.1 GENERAL

- A. The work described herein and on the drawings consists of labor, materials, equipment, programming, testing, and other services necessary to provide and install the systems called for within Division 27 or 28. Any labor, material, programming, testing, etc. not specifically mentioned within these specifications or not shown on the drawings but required for proper performance of the system and completion of the work of this project shall be provided and installed by the Contractor.
- B. It is understood that the Contractor may employ Installers to accomplish the actual installation of the systems outlined herein. Use of the term "Installer" shall not relieve the Contractor from responsibility to complete the work in accordance with the intent of the contract documents.
- C. Where conflicts exist the most stringent requirement shall apply.

1.2 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.3 RELATED SECTIONS

- A. Comply with applicable requirements of the following divisions and sections, including additional information outlined within this section and other Division 27 or 28 sections:
  - 1. Division 01 Section "Project Management and Coordination"
  - 2. Division 01 Section "Submittal Procedures"
  - 3. Division 01 Section "Product Requirements"
  - 4. Division 01 Section "Closeout Procedures"
  - 5. Division 01 Section "Warranties"
  - 6. Division 07 Section "Firestopping"
  - 7. Division 08 Section "Access Doors and Frames."
  - 8. Division 09 Section "Interior Painting"
  - 9. Division 26
  - 10. Division 27
  - 11. Division 28
- B. The requirements outlined within this section shall apply to all other Division 27 or 28 sections. Refer to individual Division 27 or 28 sections for requirements in addition to those outlined herein.

1.4 DEFINITIONS

- A. NEC: National Electric Code, NFPA 70

1.5 SUMMARY

- A. Section Includes:

1. General

- a. Standards, Codes, References and Regulatory Requirements
- b. Quality Assurance
- c. Submittals
- d. Requests for Substitution
- e. Requests for Information
- f. Project Conditions
- g. Delivery, Storage and Handling
- h. Coordination
- i. Closeout Documents
- j. Warranty
- k. Maintenance Service
- l. Spare Capacity
- m. Extra Materials
- n. Testing
- o. Owner's Training

2. Products

- a. General
- b. General Pathway Requirements
- c. Service Entrance Pathways
- d. Terminal Cabinets
- e. Sleeves for Pathways and Cables
- f. Grout
- g. Conduit Bushings
- h. Pull Strings
- i. Surge Suppression Equipment
- j. Labels
- k. Magnetic Tape

3. Execution

- a. General
- b. Sleeve Installation For Communications Penetrations
- c. Pathways
- d. Grounding
- e. Terminal Boxes, Junction Boxes, and Cabinets
- f. Cables/Wires
- g. Surge Suppression
- h. Outlets
- i. Raceway Identification

- j. Labels
- k. Protection And Cleaning
- l. Testing
- m. Demonstration

## 1.6 STANDARDS, CODES, REFERENCES AND REGULATORY REQUIREMENTS

- A. The requirements for the Division 27 or 28 systems outlined in the drawings and these specifications comply, to the best of the Designer's knowledge, with applicable codes at the time of design. However, it is the Contractor's responsibility to coordinate and verify the requirements of the Authority Having Jurisdiction over this project. The Contractor shall submit in writing any discrepancies to the Designer immediately upon discovery.
- B. The Contractor shall comply with applicable Standards, Codes, References, and Regulatory Requirements outlined below as well as those additional requirements outlined in individual Division 27 or 28 sections.
- C. The equipment and installation shall comply with the current and applicable provisions of the following standards, codes, references, and regulatory requirements including all ratified addenda:
  - 1. American Society for Testing and Materials (ASTM)
  - 2. FCC: Federal Communication Commission Part 68 as modified by Wiring Docket 88-57.
  - 3. NFPA 70 - National Electrical Code (NEC), 2008 Edition
  - 4. NFPA 262 - Standard Method of Test for Flame Travel and Smoke of Wires and Cables for Use in Air-Handling Spaces, 2011 Edition
  - 5. UL 444 – Communications Cables
  - 6. UL 497 – Protectors for Paired Conductor Communications Circuits
  - 7. UL 497A – Secondary Protectors for Communications Circuits
  - 8. UL 497B – Protectors for Data Communication and Fire Alarm Cables
  - 9. UL 1449– Standard for Safety, Transient Voltage Surge Suppressors.
- D. The equipment and installation shall comply with the latest adopted provisions of the following codes and laws:
  - 1. Americans with Disabilities Act (ADA): Where applicable, the system shall comply with ADA, Public Law 101-336, 1990 and with the ADA Accessibility Guidelines (ADAAG).
  - 2. Local and State Building Codes.
    - a. Florida Building Code: 2014 edition including references and revisions.
    - b. Florida Fire Prevention Code: 2014 edition including references and revisions.
    - c. Authority Having Jurisdiction: The systems shall comply with applicable Codes, Ordinances and Standards as interpreted and enforced by the local authority having jurisdiction.

- E. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by Underwriters Laboratory, and marked for intended location and application.

#### 1.7 QUALITY ASSURANCE

- A. All quality assurance requirements shall be as of the date the project bid. Failure of the Manufacturer or Installer to meet the quality assurance requirements on or before the date of the project bid shall render the Manufacturer or Installer unacceptable for this project.
- B. Manufacturer: Company specializing in manufacturing the products specified with a minimum 5 years documented experience.
- C. Installer - General:
  - 1. Company or person installing system must specialize in and have been actively engaged in the business of selling, installing, and servicing the system with minimum five (5) years documented experience going back from the date the project bid.
  - 2. The Installer shall maintain an office within fifty (50) miles of the project with capability to provide emergency service 7-days-a-week, 24 hours a day.
  - 3. The Installer shall be a direct sales division of, or the authorized and designated distributor for, the equipment manufacturer whose product he intends to install.
  - 4. The Installer shall own and maintain tools and equipment necessary for successful installation and testing of the system and have personnel who are adequately trained in the use of such tools and equipment.
  - 5. The Installer shall be currently licensed by the Electrical Contractors' Licensing Board as a Statewide Low Voltage System Specialty Contractor (ES-069) unless specifically noted otherwise within an individual Division 27 or 28 section.
  - 6. The Installer's technical staff shall be certified by the equipment manufacturer as qualified to install, program, test, adjust, and service the equipment to be installed.
- D. Cabling
  - 1. Surface-Burning Characteristics: As determined by testing identical products according to ASTM E 84 by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
    - a. Flame-Spread Index: 25 or less for all cables
    - b. Smoke-Developed Index: 50 or less for Category 6 cables; 450 or less for other cables.
- E. Contractor Responsibilities: In addition to other requirements outlined within the contract documents, the Contractor shall be responsible for the following:

1. Where the Contractor has questions or there are inconsistencies between Divisions or Sections or where information appears to be incomplete or incorrect, it shall be the Contractor's responsibility to confirm the requirements in writing prior to submission of a bid.
  2. Unspecified Equipment and Materials: Any item of equipment or material not specifically addressed within the contract documents and required to provide a complete and functional system shall be provided and installed by the Contractor at a level of quality consistent with other specified items.
  3. The Contractor shall be responsible for any damage to any surfaces or work disrupted as a result of his work. Repair of surfaces, including patching and painting, shall be included as necessary.
- F. Where devices, cable terminations, or boxes are installed above inaccessible ceilings or behind walls, the Contractor shall, whether or not shown on the drawings, provide and install an appropriately sized access panel matching the fire rating of the ceiling or wall where installed.

## 1.8 SUBMITTALS

### A. General

1. Submit in accordance with Division 01 Section "Submittals" and specific requirements outlined in individual Division 27 and 28 sections. The Contractor shall provide submittals as outlined herein to the Designer for review. Failure of the Contractor to provide submittals for review in timely manner shall result in the Contractor being solely responsible for any remedial work necessary to meet the intent or requirements of the contract documents.
2. The Contractor shall assemble submittal requirements for each individual section as a single package. This package shall include all Qualifications data, Product data, and Shop Drawings as outlined below. Partial submittals shall not be reviewed and shall be returned to the Contractor for completion. Individual section submittal packages shall not be combined with submittals for other specification sections. Individual section submittal packages shall be tailored to the specific requirements of the individual section.
3. The Contractor shall provide submittals in electronic format for review. Submittals shall be in PDF format. The use of other electronic formats shall not be acceptable.
  - a. Where the Authority Having Jurisdiction requires approved Shop Drawings to be provided with the permit application in a format other than PDF (e.g. DWF), the Contractor, upon receipt of approved Shop Drawings (i.e. those that are stamped as "Reviewed" by the Designer with no outstanding comments), shall provide the Designer with a copy in the AHJ's preferred format for the Designer to stamp.
4. Electronic submittals shall comply with the following:



- a. Two files shall be provided. One file shall contain Qualifications data and Product data (e.g. all cutsheets and documentation that are typically 8-1/2 x 11" in size). One file shall include Shop Drawings of the same size as the contract drawings.
  - b. The Qualifications and Product data file shall be in full color and shall include fully legible literature as provided by the equipment manufacturers.
  - c. The Shop Drawings file shall be in black and white. The use of colors (e.g. layer colors resulting from AutoCAD) shall not be acceptable. Including multiple systems in a single Shop Drawing file shall not be acceptable.
5. The Contractor shall provide submittals based on the requirements of the contract documents. Requests for Information (RFI), suggestions for design changes, or other issues pertaining to equipment or installation of the system shall not delay the Contractor's timely submission of submittal data. Issues identified by the Contractor, Installer, or Designer shall be addressed separate from the submittals and the submittal process.
  6. The Contractor shall submit Shop Drawings prepared by the Installer to demonstrate the Installer understands the scope of work and project requirements. Submission of the contract drawings in an attempt to meet the requirement for submittal shop drawings shall not be acceptable.
  7. Basic electrical materials shall be as specified in Section 26 . Submittals for Division 27 and 28 systems are not required to include information on materials specified in Division 26. However, any basic electrical materials required for Division 27 and 28 systems and not specifically called out in Division 26 or where specifically called out in Division 27 and 28 sections shall be included with the submittals for the individual Division 27 or 28 system.
  8. The Contractor shall refer to the individual Division 27 and 28 sections for additional submittal requirements.
- B. Electronic Submittals Formatting
1. Electronic submittals shall comply with the following:
    - a. Two files shall be provided. One file shall contain Qualifications data and Product data (e.g. all cutsheets and documentation that are typically 8-1/2 x 11" in size). One file shall include Shop Drawings of the same size as the contract drawings.
    - b. The Qualifications and Product data file shall be in full color and shall include fully legible literature as provided by the equipment manufacturers.
    - c. The Shop Drawings file shall be created in AutoCAD (hand-drawn Shop Drawings shall not be acceptable) and shall be in black and white. The use of colors (e.g. layer colors resulting

from AutoCAD) shall not be acceptable. Including multiple systems in a single Shop Drawing file shall not be acceptable.

2. Revisions

- a. Where the initial submission of Submittals by the Contractor does not result in a "Reviewed" stamp from the Designer, the Contractor shall resolve all outstanding items and comments from the Designer and resubmit the Submittals for further review. Revisions to the Submittals shall be clouded to identify changes made by the Contractor (or Installer). Revision clouds shall be such that they are easily and clearly identifiable and include all changes to the documents. Revisions to the Submittals that are not clearly identified shall not be considered valid revisions and corrections at a later date necessary to resolve the unidentified issues shall be the sole responsibility of the Contractor.
- b. The Contractor shall resubmit as necessary to address and clear all comments from the Designer.

C. Qualifications

1. Submit a notarized letter signed by an officer of the installing company that includes the following statements (do not change wording except to insert information noted in brackets):
  - a. As of the time of bid and currently:
    - 1) [Company Name] did and does specialize in and has been actively engaged in the business of selling, installing, and servicing [System Name] systems with a minimum of five (5) years documented experience going back from the date the project bid.
    - 2) [Company Name] did and does maintain an office within fifty (50) miles of the project with capability to provide emergency service 7-days-a-week, 24 hour days. [Company Name]'s office is located at [Company Office Address].
    - 3) [Company Name] was and is the authorized distributor for the equipment submitted.
    - 4) [Company Name] did and does own all necessary test equipment required to test the system at the completion of the installation.
2. Submit a letter from the major equipment manufacturers confirming the Installer is currently an authorized distributor in good standing with the ability to provide sales and service.

3. Submit a list of all test equipment owned including the manufacturer, model number, serial number, and last calibration date that will be used to test the system.
4. Submit a copy of the Installer's current Florida Statewide Low Voltage System Specialty Contractor (ES-069) license or other license specifically called for within individual Division 27 or 28 sections.
5. Submit a technical resume of experience for the Installer's Field Supervisor who will be assigned to this project. Resume shall be clearly marked as "Field Supervisor"
6. Submit a list of at least three (3) system projects completed within the last two (2) years of similar type and size with contact names and telephone numbers of the Owner's Project Manager for each.
7. Submit one (1) copy of each manufacturer's certification of successful completion of factory training for each member of the Installer's staff who will install, program, test, or adjust the system to be installed.
8. The use of Sub-Installers (i.e. Installers two levels removed from the Electrical Sub-Contractor) shall not be allowed.

D. Product Data

1. Submit a narrative for each system outlining the sequence of operation.
2. Submit original cutsheets, as provided by the manufacturer, for each piece of equipment, material, cable, etc. to be provided and installed as part of the system.
  - a. Cutsheets shall provide full technical specifications for each piece of equipment being submitted on.
  - b. Scanned documents that are faded, skewed or illegible shall not be acceptable.
  - c. Copies of non-technical information, cutsheets from distributor's catalogs, or screen prints from web site pages, etc. shall not be acceptable.
  - d. The first page of each product cutsheet shall identify the specification section and paragraph in the upper right hand corner of the page for which the Contractor is submitting (e.g. Place "Section 27 10 00, Paragraph 2.1" or similar)
  - e. Each cutsheet shall clearly identify, either through highlighting or a stamped arrow, the exact model number of each piece of equipment or material to be provided and installed.
  - f. Each cutsheet shall clearly identify the specification section number and associated paragraph number that the individual piece of equipment is being submitted for.
3. In addition to the above, the Contractor shall, prior to submitting, verify the following are included:
  - a. Flush grade pull boxes.
  - b. Specialty terminal cabinets.

- c. Each type of wire and cable to be installed as part of the system. Cable cutsheets shall be labeled with the same identifier used in the Matrix to be included in the Shop Drawings to ensure clarity in regard to which cable(s) is required for each device.
- d. Connectors and required tooling.
- e. Terminations system components for each cable type.
- f. Cable suspension J-hooks, cable fasteners, etc.
- g. Grounding and surge suppression system components for the system portion of the project.
- h. Installation manuals for each active (i.e. powered) piece of equipment or software application to be installed as part of the system.
- i. Operations manuals for each active piece of equipment or software application to be installed as part of the system.

E. Shop Drawings

- 1. Submit complete shop drawings showing how the Contractor intends to install the system. Shop drawings shall, as a minimum, include the following:
  - a. Symbol Legend showing:
    - 1) Unique symbols for all system racks, cabinets, panels, equipment, and devices to be installed.
  - b. Cable matrix showing:
    - 1) All system cables to be installed as part of the system.
    - 2) A unique identifier for each cabletype
    - 3) Each cable's type, manufacturer, and model number.
  - c. Site Plans showing:
    - 1) Backbone conduits with quantity and sizes shown for each run.
    - 2) Pull boxes (i.e. Flush Grade, Rack Mounted, Wall Mounted, etc.) with dimensions
    - 3) Backbone cables (either in conduit or direct buried) with cable type and quantities.
  - d. Phasing Plan showing:
    - 1) The order in which work will be accomplished. Identify phases as planned for construction. Where the Contractor determines phasing is not required for a system the requirement for the Phasing Plan may be omitted but the submitted Site Plan (or Floor Plans

- where the project includes no site work) shall include the statement "No phasing of work sequences required".
- 2) Temporary infrastructure (conduit and cabling sizes and quantities) for each system affected. Clearly note how the Contractor plans on maintaining existing systems in a functional condition in areas that the Owner will continue to occupy during construction.
- e. Floor Plans showing:
- 1) System equipment racks, cabinets, panels, terminal cabinets, and major pull boxes.
  - 2) System devices
  - 3) Conduit or J-Hook runs connecting devices to termination equipment. Contractor shall accomplish preliminary coordination with other trades and shall show conduit and J-hook runs as he intends on installing them, including cables by identifier and quantity.
  - 4) Conduit sleeves including quantities and sizes.
  - 5) Required interconnections to other systems.
- f. Enlarged Plans:
- 1) Show all major equipment (i.e. equipment racks, equipment cabinets, equipment panels, terminal cabinets, etc. as shown on the floor plans).
  - 2) Whether in Communications Rooms or other building spaces the Contractor's Shop Drawings shall show each piece of equipment as he intends to install it. Any conflicts with other building systems shall be identified and resolved prior to the starting the submittal process.
- g. Elevations showing:
- 1) All four walls of each Communication Room showing the coordination of all wall and floor mounted equipment for all systems in the space. Submittals for each system shall show all equipment regardless of system with the equipment for the system being submitted on printing in black and all other systems equipment printing 50% screened.
- h. Details showing:
- 1) System Point-to-Point Wiring Diagram: The Contractor shall include in his Shop Drawings a Point-to-Point Wiring Diagram that includes all equipment, devices,

cabling, signal types, and interconnections to other systems or equipment as necessary to show a logical diagram of how the system's parts and pieces are interconnected. The Block Diagram shall identify all system cables identified by quantity and type outlined in the Cable Matrix noted above.

- 2) Terminal Cabinet Layouts
- 3) Front Elevations: of system equipment racks and cabinets showing all equipment, shelves, wire management, etc. as the Installer intends on assembling the cabinets.
- 4) Rear Elevations: of system equipment rack and cabinets showing any system equipment not shown on the front elevations.
- 5) Details of any special or field fabricated assemblies to be installed as part of the system.
- 6) Submit calculations in table format for sizing of UPS's including:
  - a) A matrix showing a line item for each piece of equipment to be powered by the UPS. This shall include manufacturer, model number, quantity and description in separate columns.
  - b) The primary side voltage for each piece of equipment
  - c) The current requirements for each piece of equipment
  - d) The extended total current requirements for each line item
  - e) The total current requirements for all equipment.
  - f) The total power capacity of each UPS showing a minimum of twenty (20) minutes of full load run time for the total calculated wattage plus fifty percent spare capacity.

2. Prior to submitting Shop Drawings, the Contractor shall coordinate the termination equipment for each system such that there are no conflicts between building systems.

#### 1.9 REQUESTS FOR SUBSTITUTION

- A. Submit requests for substitution in accordance with Division 01 Section "Product Requirements".
- B. Requests for Substitution shall be submitted in writing explaining why the substitution is being requested and how the proposed item(s) will meet or exceed the specifications. Submitted information shall be adequate information to support the Request for Substitution or it shall be rejected. The Designer reserves the right to be the sole judge of whether or not a requested substitution is acceptable.

- C. Requests for Substitution after the project bid-opening date will only be accepted for review where 1) the equipment manufacturer either no longer manufacturer's a specified piece of equipment or has replaced a specified piece of equipment with another piece of equipment and 2) there is no other acceptable manufacturer listed in the specifications. In this case, the Contractor shall submit a Request for Substitution with documentation necessary to support the substitution request and confirm that the proposed substitution meets or exceeds the specified equipment in all respects. Requests for Substitution shall not result in additional cost to the Owner.
- D. Where the Contractor proposes to substitute the specified cable (either copper or fiber optic) he shall provide to the Designer a complete copy of the U.L. Test report for that product. Proposed cable substitutions that are not accompanied by the appropriate U.L. test report shall be rejected.
- E. The Contractor, if requested to do so by the Designer, shall be prepared to show by "proof-of-performance" test that the equipment being furnished on the job is equal to or better than the equipment specifications listed herein. This proof shall be shown by actual tests and not by printed sales literature. To this end, the Contractor shall provide qualified technicians and such test equipment as required to perform this function.

#### 1.10 REQUESTS FOR INFORMATION

- A. Due to the complexity of the system it is understood that the Contractor may need to submit Requests for Information (RFI) to the Designer in order to obtain clarifications of project requirements, advise the Designer of potential problems, or suggest methods to improve the installed system. In any instance where the Contractor feels it is necessary to submit an RFI he shall do so in a manner that allows the Designer to review and comment on the issue identified within the RFI in a timely manner. The Contractor shall include in his RFI the following information:
  - 1. A reference to the specific drawing number and note number or specification section and paragraph number, and
  - 2. A narrative that clearly identifies the potential issue, and
  - 3. The Contractor's proposed solution, and
  - 4. Costs, if any, associated with implementing the Contractor's proposed solution. If an indication of cost is not included it will be assumed no cost is associated with the Contractor's proposed solution.
- B. It shall be incumbent upon the Contractor when submitting an RFI to provide any additional information (equipment cutsheets, sketches, etc.) as necessary to ensure that the Designer fully understands the issue and the proposed solution.
- C. Submitted RFI's that do not include the information outlined above shall not be reviewed and shall be returned to the Contractor for correction.
- D. The Contractor shall submit RFI's in a timely manner, after discovery of the issue, which allows the Designer adequate time to review and comment on the issue identified.

#### 1.11 OBSOLESCENCE OF EQUIPMENT

- A. Where a manufacturer makes a specified piece of equipment obsolete or supersedes it with a newer model, the Contractor shall provide replacement equipment that meets or exceeds the technical specifications of the original piece of equipment -- by the original equipment manufacturer or one of the listed Acceptable Substitution manufacturers or another manufacturer if no equipment is available from the Basis of Design manufacturer or no Acceptable Substitution manufacturers are listed – at no additional cost to the Owner. Replacement of the specified equipment under these conditions shall not delay the Contractor's timely submission of submittals as outlined elsewhere in this section.

#### 1.12 PROJECT CONDITIONS

- A. Environmental Limitations:
  - 1. Do not deliver or install cables and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.
  - 2. Do not deliver or install equipment, frames, cabinets, etc. until spaces are enclosed and weathertight, wet work in spaces is complete and dry, and work above ceilings is complete.

#### 1.13 DELIVERY, STORAGE, AND HANDLING

- A. Test cables upon receipt at Project site.
- B. Test optical fiber cable to determine the continuity of the strand end to end. Use optical fiber flashlight.
- C. Test optical fiber cable while on reels. Use an optical time domain reflectometer to verify the cable length and locate cable defects, splices, and connector, including the loss value of each. Retain test data and include the record in maintenance data.
- D. Test each pair of UTP, STP, or multi-conductor cable for open and short circuits.
- E. Document in spreadsheet format the date, time, name of Installer personnel accomplishing test, tests accomplished, and initials of Installer's Supervisor confirming testing was completed. Maintain electronic and hard copy of documentation on site.

#### 1.14 COORDINATION

- A. Comply with the requirements of Division 01 Section "Project Management and Coordination".
- B. Coordinate arrangement, mounting, and support of communications materials and equipment:
  - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.



2. To provide code required clearances and working room in front of and around equipment, cabinets, and racks. Exceed code requirements where noted within contract documents.
  3. To provide for ease of disconnecting the equipment with minimum interference to other installations.
  4. To allow right of way for piping and conduit installed at required slope.
  5. So connecting pathways, cables, wireways, cable trays, and busways will be clear of obstructions and of the working and access space of other equipment.
- C. Coordinate layout and installation of equipment, pathways, and cabling. Coordinate service entrance arrangement with local utilities.
1. Adjust arrangements and locations of equipment with equipment and materials of other communications, electronic safety and security, and related systems that share space.
  2. Modify as-built drawings to reflect adjustments.
  3. Coordinate location of power raceways, circuits and receptacles with locations of equipment requiring electrical power to operate.
- D. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.
- E. Coordinate location of access panels and doors for equipment that are behind finished surfaces or otherwise concealed. Access doors and panels are specified in Division 08 Section "Access Doors and Frames."
- F. Coordinate work with other trades as necessary.
- G. Coordinate work associated with Owner provided equipment as necessary.

#### 1.15 CLOSE-OUT DOCUMENTS

- A. Submit close-out documents in accordance with Division 01 Section "Closeout Procedures" and specific requirements outlined in individual Division 27 or 28 sections.
- B. In addition to requirements outlined in Division 01 Section "Closeout Procedures" comply with the following:
1. Submit cable routings for backbone, tie, and riser cable terminations.
  2. Submit an original copy, on CD, as provided by the original manufacturer, of each software program provided as part of the system.
  3. Submit a hard copy and an electronic copy of the final system programming as accomplished by the Installer. The hard copy shall be a printout of the software programming code accomplished by the Installer.
  4. Submit a documented list of all system passwords. The Contractor shall provide the Owner with all system passwords. The use of master

or backdoor passwords known only to the Contractor or Installer shall not be acceptable.

5. Submit a "Sequence of Operation" for each active system.
6. For those systems with active controls or equipment with functions and features that can be adjusted as part of the normal operation, submit detailed, written documentation of all system settings and adjustments at the time of project completion including but not limited to:
  - a. Level settings for all potentiometers, switches, and other settings on all system equipment.
  - b. Photographs of all equipment knob, button, rheostat, slider control, switch, and other settings necessary to document the original system configuration and settings at the completion of construction. Photographs shall clearly indicate the equipment and settings. The Contractor may utilize digital photography for documentation purposes. In the event that digital photography is used, the Contractor shall provide one (1) electronic copy and one (1) color hard copy of all photographs.
  - c. Other applicable equipment settings as may be required by the Owner.
  - d. The documentation shall be formatted and presented in a manner that will allow the Owner to return the system to its original settings without assistance.
7. The Contractor shall submit a draft copy of Close-Out documentation to the Designer seven (7) days prior to requesting Substantial Completion and a final copy of Close-Out documentation to the Designer no less than seven (7) days prior to requesting Final Completion of the project. Both draft and final copies shall be submitted on a properly labeled DVD.

#### 1.16 WARRANTY

- A. Submit warranties in accordance with Division 01 Section "Warranties" and specific requirements outlined in individual Division 27 or 28 sections.
- B. Where a manufacturer's stated warranty exceeds that called for in these specifications, the Contractor shall honor the manufacturer's warranty as if it had been specified herein.

#### 1.17 MAINTENANCE SERVICE

- A. Comply with the requirements of individual Division 27 or 28 sections

#### 1.18 SPARE CAPACITY

- A. Comply with requirements of individual Division 27 or 28 sections

#### 1.19 EXTRA MATERIALS

- A. Comply with requirements of individual Division 27 or 28 sections.
- B. Keys: Provide a minimum of three (3) sets of keys, identified by system and lock, for each different type of lock installed for each system. Keys sets shall be on individual key rings with permanent plastic or metal tag identifying the system, lock location, and key number.

1.20 TESTING

- A. Accomplishing system testing as called for herein. Comply with additional requirements where called for in an individual Division 27 or 28 section.

1.21 OWNER'S TRAINING

- A. The Contractor shall, after Substantial Completion but prior to Final Completion, provide the Owner with training on the systems within in Division 27 or 28. Individual training sessions shall be provided for each system. Combining training systems into a single training session shall not be acceptable.
- B. Training shall be comprised of:
  - 1. A walk-through of the facility to identify all system equipment and equipment locations.
  - 2. A review of:
    - a. The system's Close-Out documents
    - b. The system's final documented test results
    - c. The system's Manufacturer's warranties
    - d. The system's software, programming, and passwords
    - e. The system's equipment settings and adjustments

PART 2 - PRODUCTS

2.1 GENERAL

- A. The Contractor shall provide and install all equipment and materials necessary for complete, operational systems whether or not specifically shown on the drawings or specified herein.
- B. The Contractor shall provide all labor, programming, and testing necessary to complete the work related to the Division 27 or 28 systems and provide the Owner, at the completion of the project, with fully functional and properly operating systems in accordance with the manufacturer's recommendations, the requirements of the contract documents, and applicable industry standards.
- C. The Contractor shall install, program, and test Owner furnished equipment where required by the contract documents.

- D. Equipment and components shall be new, and the manufacturer's current model. All equipment and materials shall be suitable for use intended, and meet all stated performance requirements for the system configurations specified herein.
- E. Equipment and components shall be installed in strict compliance with manufacturers' recommendations. Consult the manufacturer's installation manuals for all wiring diagrams, schematics, physical equipment sizes, etc., before beginning system installation.
- F. Unless specifically noted otherwise, equipment shall be attached to walls and ceiling/floor assemblies and shall be held firmly in place. Fasteners and supports shall be adequate to support the required load.

## 2.2 GENERAL PATHWAY REQUIREMENTS

- A. General:
  - 1. Pathways (conduit, raceways, wireways, pullboxes, outlet boxes, etc.) shall comply with applicable requirements of Division 26.
- B. Conduit:
  - 1. EMT fittings shall be steel, compression type connectors, with insulated bushings and separate lock nuts on conduits entering panel cabinets.
  - 2. Bushings: Provide insulated bushings on ends of all raceway. All metallic conduits shall have bonding bushings and be bonded to the Systems Ground Bus Bar with an insulated #6 AWG wire.
  - 3. Pull cords: Install pull cords in all raceway runs that are installed without cable.
  - 4. Size:
    - a. Minimum size shall be as shown on the drawings.
    - b. The Contractor shall size raceways in accordance with the NEC for the quantity of cables to be installed unless noted otherwise.
- C. Boxes:
  - 1. Boxes shall be sized as required by NEC for cables, conduit and device installed unless noted otherwise.

## 2.3 TERMINAL CABINETS

- A. Comply with applicable requirements of Division 26 unless noted otherwise.
- B. Provide and install terminal cabinets where shown on the drawings. Size either as shown on the drawings or as required by the National Electric Code (NEC).
- C. Provide terminal cabinets for all surge suppression equipment and associated terminations including 120VAC power surge suppressor as required in Division 26.

- D. Terminal cabinets in exterior applications or in non-conditioned spaces shall be weatherproof.
- E. Manufacturers
  - 1. Interior
    - a. Basis of Design
      - 1) Square "D".
    - b. Acceptable Substitutions
      - 1) Hoffman
      - 2) Bud

#### 2.4 SLEEVES FOR PATHWAYS AND CABLES

- A. Provide and install sleeves for penetrations through exterior walls above and below grade.
- B. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- C. Sleeves for Rectangular Openings: Galvanized sheet steel.
  - 1. Minimum Metal Thickness:
    - a. For sleeve cross-section rectangle perimeter less than 50 inches (1270 mm) and no side more than 16 inches (400 mm), thickness shall be 0.052 inch (1.3 mm).
    - b. For sleeve cross-section rectangle perimeter equal to, or more than, 50 inches (1270 mm) and 1 or more sides equal to, or more than, 16 inches (400 mm), thickness shall be 0.138 inch (3.5 mm).

#### 2.5 GROUT

- A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

#### 2.6 CONDUIT BUSHINGS

- A. Grounding Bushings: All metallic conduits shall have bonding bushings and be bonded to the Systems Ground Bus Bar with an insulated #6 AWG wire.
- B. Insulation Bushings: Provide insulated bushings on ends of all raceway.
- C. Manufacturers

1. Basis of Design

- a. Arlington EMT Series Insulating Bushings or acceptable substitution

2.7 CABLE SUPPORT SYSTEM

- A. UL listed and labeled for support of Category 6 cabling, designed to prevent degradation of cable performance and pinch points that could damage cable.
- B. Horizontal cables shall be suspended by pre-manufactured CAT 6 rated cable hangers in closets where J-hooks, ladder tray or rack management is not available. All supports shall be permanently attached to the structure using all-thread suspension, beam clamps, or wall mount to the structural metal or wooden members. The J-hooks shall feature a wide base loop with smooth curves to eliminate snag potential and cable deformation.
- C. J-hooks are to be in accordance with the NEC, EIA/TIA requirements for structured cabling systems.

- D. The use of non-metallic cable supports shall not be acceptable.

E. Manufacturers

1. Basis of Design

- a. Erico Caddy CAT12, CAT21, CAT32

2. Acceptable Substitution

- a. B-Line Series BCH 12, BCH 21, BCH 32  
b. Panduit J-Pro Series JP75, JP131, JP2

2.8 PULL STRINGS

- A. Install pull cords in all raceway runs that are installed without cable.

B. Manufacturers

1. Basis of Design

- a. Jet Line #232 or acceptable substitution

2.9 SURGE SUPPRESSION EQUIPMENT

- A. For Power Circuits (120 volt):

1. UL 1449 listed.  
2. 15 amp, 120V rated.  
3. Suppressors shall be tested per IEEE, C62.41-1991 for Categories A and B.

4. Normal mode (L-N), and common mode (L+N-G) protection.
5. Internal fusing.
6. Hybrid design.
7. Indicators for normal operation and failure indication.
8. Enclosure:
  - a. Fire retardant high impact, phenolic or plastic housing or metal enclosure.
9. Clamping voltage UL 1449, Line to Neutral, Category B Impulse At (3KA, 8 x 20  $\mu$ s): 385V @ 120V.
10. Maximum Surge Capacity: 20,000 amps.
11. Maximum Continuous Operating Voltage: 115% of line voltage.
12. Provide hardwire connection or add 15 amp receptacle device to hardwired devices to match equipment being protected and maintain UL listing.
13. Provide additional 15 amp in-line fusing as required to comply with UL and the NEC when connected to a 20 amp, 120V circuit.
14. Manufacturers
  - a. Basis of Design
    - 1) Leviton #51020-WM (hardwired).
  - b. Acceptable Substitution
    - 1) EDCO #HSP-121BL2
    - 2) Eaton Bussmann

## 2.10 LABELS

- A. Comply with TIA/EIA-606-A and UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.
- B. Comply with requirements in Division 26 Section "Identification for Electrical Systems."
- C. Manufacturers
  1. Basis of Design
    - a. Brady Corporation
  2. Acceptable Substitution
    - a. HellermannTyton.
    - b. Kroy LLC.

## PART 3 - EXECUTION

3.1 GENERAL

- A. Comply with NECA 1.
- B. The Contractor is advised that circuit routing for this system is not necessarily shown on the project drawings. The Contractor shall provide and install raceways, wiring and cabling required for complete and fully functional systems as intended by these specifications.
- C. The Contractor shall provide and install a properly sized, flush mounted outlet box for every floor, wall, and ceiling mounted device.
- D. In locations where pathways are not accessible after completion of the project, raceway shall be extended from device to device or fire rated access panels shall be installed to provide access to pull boxes. Routing of raceway from device to device shall only be acceptable where the wiring scheme of the system, as recommended by the manufacturer, requires cable to pass from device to device.
- E. Contractor shall properly terminate each device according to the manufacturer's recommendations. Unless specifically noted otherwise, the Contractor shall provide and install cabling to connect all circuitry associated with a device.
- F. Equipment shall be installed in accordance with manufacturer's instructions.
- G. Install electrical basic materials per applicable sections of these specifications.
- H. Equipment, other than portable equipment, shall be held firmly in place. The exception shall be when the Contractor is required to use resilient shock mounting to decouple equipment from the structure it is being mounted to.
- I. Support raceways, backboards, and cabinets per applicable sections of these specifications, as shown on the drawings, and as recommended by the manufacturer. Fastenings and supports shall be adequate to support their loads with a safety factor of five (5).
- J. Switches, connectors, outlets, etc., shall be clearly, logically, and permanently marked during installation. Where the equipment manufacturer does not provide markings or for fabricated and installed equipment the Contractor shall provide and install permanent, engraved labels for proper identification.
- K. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- L. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- M. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both communications equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.



- N. Right of Way: Give to piping systems installed at a required slope.

### 3.2 FIRESTOPPING

- A. Contractor shall provide and install firestopping on all penetrations through rated walls and floors to match the rating of the wall or floor assembly. Refer to Division 7 for additional information.

### 3.3 SLEEVE INSTALLATION FOR COMMUNICATIONS PENETRATIONS

- A. Penetrations occur when pathways, cables, wireways, or cable trays penetrate concrete slabs, concrete or masonry walls, or fire-rated floor and wall assemblies.
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- D. Cut sleeves to length for mounting flush with both surfaces of walls.
- E. Extend sleeves installed in floors a minimum of 2 inches above finished floor level.
- F. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and pathway or cable, unless indicated otherwise.
- G. Seal space outside of sleeves with grout for penetrations of concrete and masonry
  - 1. Promptly pack grout solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect grout while curing.
- H. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and pathway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants."
- I. Roof-Penetration Sleeves: Seal penetration of individual pathways and cables with flexible boot-type flashing units applied in coordination with roofing work. The use of pitch pockets is not acceptable.
- J. Aboveground, Exterior-Wall Penetrations: Seal penetrations using steel pipe sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch (25-mm) annular clear space between pipe and sleeve for installing mechanical sleeve seals.
- K. Underground, Exterior-Wall Penetrations: Install cast-iron pipe sleeves. Size sleeves to allow for 1-inch annular clear space between pathway or cable and sleeve for installing mechanical sleeve seals.

### 3.4 CONDUIT

- A. Conduit systems for individual systems shall not be shared by power or any other electrical wiring that is not part of the system.

- B. Backbone cables shall be in a complete conduit system. Refer to the drawings for additional information.
- C. Conduits run underground shall be installed a minimum of 24" below grade. Provide and install magnetic tape above underground runs to allow the Owner to easily locate in the future.
- D. Conduit fill shall not exceed 40 percent of interior cross sectional area where three or more cables are contained within a single conduit.
- E. Bend conduits with minimum inside radius of 6 times the internal diameter. Increase bend radius to 10 times for conduit larger than 2 inch size. Provide proper bend for all changes of direction. Pull and splice boxes shall not be used in lieu of a bend.
- F. Install conduits so no more than two 90o bends are in any conduit section without a pullbox. Install additional pullboxes as required to maintain maximum of two 90o bends between pullboxes and/or termination points.
- G. Install interior conduits so no more than one hundred (100) feet of conduit are in any conduit section without a pullbox. Install additional pullboxes as required to maintain a maximum of one hundred (100) feet between pullboxes and termination points.
- H. Install Outside Plant (OSP) conduits and ductbanks so that no more than three hundred (300) feet of conduit are in any conduit section without a pullbox. Install additional pullboxes as required to maintain a maximum of three hundred (300) feet between pullboxes and termination points.
- I. In installations where the electrical contractor does not provide a counterpoise system in conjunction with the underground conduit system, the Contractor shall provide a coupling conductor within the underground conduit system to run alongside copper conductors. Coupling conductors shall be sized according to applicable codes and standards.
- J. Label conduits at both ends to indicate destination and source. Also indicate length of conduit. This labeling/identification shall be fully documented in as-built (record) drawings.
- K. Install pull string in each empty conduit over 10 feet in length or containing a bend.
- L. Properly support cables/wire not installed in conduits.
- M. Special Conduit Systems: Special conduit systems may be specified for some portions of the system. Refer to the drawings and other sections of these specifications to determine where or if such systems are used.
- N. Use of ceiling tiles, grid or hanger wires for the support cables shall be prohibited.
- O. Comply with requirements in Division 26 Section "Conduit and Boxes for Electrical Systems" for installation of conduits and wireways.

### 3.5 RACEWAY IDENTIFICATION

- A. All conduit system junction boxes (except those subject to view in public areas) for Division 27 and 28 systems shall be color coded as listed below utilizing the Krylon colors noted:
  - 1. Fire Alarm - Safety Orange 2410
  - 2. Fiber Optics - Safety Purple 1929
  - 3. Sound System - Safety Yellow 1813
  - 4. Intercom - True Blue K1910
  - 5. Computer/Data - Bright Gold K1701
  - 6. TV - Glossy White K1501
  - 7. Security/CCTV - John Deer Green K1817
  - 8. Telephone - Safety Green 2012
- B. Refer to Section 26 05 53 for additional information

### 3.6 GROUNDING

- A. Provide and install complete grounding system as required to comply with the drawings, other Division 27 or 28 sections, Division 26, and applicable codes.
- B. Communications bonding and grounding shall be in accordance with the National Electrical Code (NEC), NFPA and EIA/TIA grounding and bonding standards.
- C. A 2/0 AWG stranded copper wire cable in PVC conduit shall be extended between new ground bars located at each communications room (or other location shown on drawings) and the building main electrical service ground point or secondary transformer ground point. Building steel, equipment racks and cabinets, cable tray, and surge suppressor devices shall be bonded to the ground bar via a #6 AWG stranded copper cable and UL approved connecting hardware.
- D. Install grounding according to BICSI TDMM, "Grounding, Bonding, and Electrical Protection" Chapter.
- E. Comply with ANSI-J-STD-607-A.
- F. Locate ground bus bar to minimize the length of bonding conductors. Fasten to wall allowing at least 2-inch (50-mm) clearance behind the grounding bus bar.
- G. Connect cable shields to ground bus bar in an industry approved manner. Connections shall be soldered or crimped.
- H. The Contractor shall take such precautions as are necessary to guard against electromagnetic and electrostatic hum, and to install all equipment so as to provide maximum safety to the person who operates it.

### 3.7 SURGE SUPPRESSION

- A. Provide and install surge suppression devices on:

1. Each copper cable (unshielded twisted pair, shielded twisted pair, coaxial, etc.) entering or leaving a building. Install surge suppression devices at system terminal board or in a cabinet.
  2. In other locations where required by the manufacturer or required to properly protect the equipment and the system.
- B. Install surge suppression device on all 120 volt power sources to equipment. Surge suppression on 120 VAC circuits shall be provided and installed by the electrical subcontractor. Coordinate with Division 26 to ensure that surge suppression for 120 VAC power circuit and surge suppression required by this section for each system are installed in same terminal cabinet and bonded together.
- C. Bond surge and suppression device to building ground system as called for in Division 26.
- D. Contractor shall take extreme care to ensure a properly surge protected system.
- E. Surge protection equipment must be selected by contractor to match the equipment being protected including wire sizes, operating volts, amps, and circuit impedance.
- F. Installation of surge protection equipment and its grounding shall be per manufacturer's recommendations to assure short and proper ground paths.
- G. Terminal Cabinets
1. Surge suppression devices shall be installed in terminal cabinets whether or not shown on the drawings. Where required, install surge suppression terminal cabinet in termination area of individual system being protected.
  2. Size terminal cabinets as required to facilitate installation of terminations and surge suppression in a neat and workmanlike manner.
  3. Coordinate location of terminal cabinets with adjacent equipment and materials.
- H. Equipment Installation
1. Install surge suppression equipment per manufacturer's recommendation
  2. Install surge suppression equipment terminal cabinets, etc. as required to facilitate installation of surge protection equipment and terminal points. Size terminal cabinets as required to facilitate installation of surge suppression equipment and terminal blocks.
- I. Ground Installation
1. Ground Bus Connections
    - a. Provide "local" ground bus in each terminal cabinet housing surge protection equipment (with lugs, etc. as required).

- b. Bond "local" ground bus to terminal cabinet with minimum #6 copper wire.
    - c. Connect terminal cabinet "local" ground bus to "systems" ground bus installed per with minimum #6 copper insulated wire (unless otherwise noted) in conduit.
    - d. Note that "systems" ground bar is also to be used for power transformation ground (480V to 208V) where applicable.
  2. Surge suppression equipment grounding
    - a. Connect each surge suppressor to local ground bus in terminal cabined with wire sized as recommended by manufacturer.
    - b. Coordinate with Division 26 to ensure that 120 VAC power source/supply surge suppressor is also grounded to same local ground bus as surge suppressors provided in these criteria.
  3. Conductors
    - a. Bends in excess of 90 degrees in any grounding conductor shall not be permitted.
    - b. Do not bundle unprotected conductors with protected conductors.
    - c. Conductors shall be kept as short as possible.
    - d. Conductors shall be secured at 12" intervals with an accepted copper clamp
    - e. Grounding conductors shall be properly connected to the building service ground by accepted clamps.
  4. Grounding Connectors
    - a. Connectors, splicers, and other fittings used to interconnect grounding conductors, bond to equipment or grounding bars, shall be UL Listed for the purpose.
    - b. All connectors and fittings are to be of the Nicopress crimp or compression set screw type.
    - c. Special treatment to fittings lugs, or other connectors of dissimilar materials are to be applied to prevent electro-galvanic action.
- J. Isolation of cable shields
  1. Cable shields shall be suitably protected at each termination point to avoid incidental contact with grounded elements of the building structure. Shield continuity shall be maintained throughout the entire cabling system. Ground reference of the building ground system shall be matched at the Communications Rooms Ground Bus Bar.
  2. Isolation of the shields shall be individually verified by resistance measurements as connections are made.

3.8 TERMINAL BOXES, JUNCTION BOXES AND CABINETS

- A. Boxes and cabinets shall be UL listed for their use and purpose.
- B. Install boxes and cabinets plumb and square with wall. Where flush mounted boxes and cabinets shall be flush with wall surface.

3.9 CABLES/WIRES

- A. The Contractor shall provide and install all copper and fiber optic cable required to complete the scope of work of this project. Refer to individual Division 27 or 28 sections for specific cabling requirements.
- B. Terminate all conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, cross-connects, and patch panels.
- C. Cables shall not be spliced. Secure and support cables at intervals not exceeding 30 inches (760 mm) and not more than 6 inches (150 mm) from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
- D. Do not install bruised, kinked, scored, deformed, or abraded cable. Remove and discard cable if damaged during installation and replace it with new cable.
- E. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps shall not be used for heating.
- F. In the communications equipment room, install a 10-foot- (3-m-) long service loop on each end of cable.
- G. Pulling Cable: Comply with BICSI ITSIM, Ch. 4, "Pulling Cable." Monitor cable pull tensions.
- H. All cable and wire shall be new.
- I. Install cables/wires in accordance with manufacturer's instructions.
- J. Cables shall be installed as illustrated on the drawings except where necessary to avoid EMI sources or other obstacles. Major deviations from the illustrated path must be accepted in advance by the Designer. Where illustrated path is not show on the drawings, Contractor shall include intended, general routing path within his submittals.
- K. The Contractor shall install cabling to avoiding EMI. Provide clearances of at least 48" from any motor or transformer; 12" from conduit and cables used for electrical power distribution; and 12" from fluorescent lighting. Pathways are to cross fluorescent lighting and electrical power cables and conduits in a perpendicular fashion only.
- L. Conceal conductors and cables in accessible ceilings, walls, and floors where possible.
- M. Install cables in raceways (refer to drawings) and cable trays except within consoles, cabinets, desks, and counters. Conceal raceway and cables except in unfinished spaces.

1. Install plenum cable in environmental air spaces, including plenum ceilings.
  2. Comply with requirements for raceways and boxes specified in Division 26 Section "Raceway and Boxes for Electrical Systems."
- N. Comply with BICSI ITSIM, Ch. 6, "Cable Termination Practices."
- O. Do not untwist UTP cables more than 1/2 inch (12 mm) from the point of termination to maintain cable geometry.
- P. All cable terminations and testing of cable installed under this project shall be accomplished by the Contractor unless specifically noted otherwise.
- Q. Cable runs shall include a service slack prior to the termination point. Provide for a 12-inch service slack in the ceiling above each outlet. Service slack in Communications Rooms shall consist of a 10-foot slack section for all station cables located and placed neatly in the cable tray above the equipment rack or cabinet.
- R. Cables placed under ground, below slab on grade, in slab on grade, or in other wet locations, whether in conduit or direct buried, shall be gel-filled or water blocking type.
- S. Interior backbone cables shall be Riser rated unless otherwise stated or required by code.
- T. Bundle, lace, and train conductors and cables to terminal points without exceeding manufacturer's limitations on bending radii. Install lacing bars and distribution spools.
- U. Install system wiring and/or raceways away from any surface that may become hot, including and not limited to, hot water piping and heating ducts.
- V. Maintain proper separation between system cables and all power and/or unshielded cables, as required to prevent noise, crosstalk, etc.
1. Wiring crossing power circuits shall be at right angles. For metal enclosed electric light or power or Class 1 circuits, separation may be reduced as described in the National Electric Code (NEC). Increase separation if so required to comply with referenced standards.
  2. Cable must be separated from any open conductors of power, or Class 1 circuits, and shall not be placed in any conduit, junction box or raceway containing these conductors.
  3. Separation between open communications cables or cables in non-metallic raceways and unshielded power conductors and electrical equipment shall be as follows:
    - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 5 inches (127 mm).
    - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 12 inches (300 mm).
    - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 24 inches (610 mm).

4. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment shall be as follows:
    - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches (64 mm).
    - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches (150 mm).
    - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches (300 mm).
  5. Separation between communications cables in grounded metallic raceways and power lines and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:
    - a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
    - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches (76 mm).
    - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches (150 mm).
  6. Separation between Communications Cables and Electrical Motors and Transformers, 5 kVA or HP and Larger: A minimum of 48 inches (1200 mm).
  7. Separation between Communications Cables and Fluorescent Fixtures: A minimum of 5 inches (127 mm).
- W. The majority of the system wiring will be installed above ceilings. Cabling used throughout this project shall comply with the requirements outlined in the National Electric Code (NEC). Cabling shall bear CMP and/or appropriate markings for the environment in which they are installed.
- X. Provide a minimum of two cable support hangers at corners and 90 degree turns. Attachment shall be to the building structure and framework at a maximum of five (5) foot intervals. Where cable is routed above the ceiling in areas where there are no walls, all-thread shall be used (minimum 1/4"; sized to support the intended weight) with the appropriate hanger for cross-room support. Support rods shall be level and plumb after cable installation. Requirements for bending radius and pulling tension of cables shall be adhered to.
- Y. Above suspended ceilings and below raised floor areas where duct, cable trays, or conduits are not available, cables shall be bundled in groups of 40 or less. Secure loosely with cable ties. Cables shall be loose enough to be rotated easily by hand. Cable ties used in plenum areas shall be plenum rated.
- Z. Provide protection for exposed cables.

### 3.10 OUTLETS



- A. The Contractor shall provide and install an outlet plate with appropriate connectors for each device whether or not shown on the drawings.
- B. Install devices/inserts in outlets so that same orientation is used throughout project.
- C. Install wall plates with all inserts required to properly connect all equipment circuits and complete the installation in a professional manner.

### 3.11 LABELS

- A. The Contractor shall provide and install permanent, engraved labels on all equipment where the original manufacturer has not already provided labels.
- B. Custom, fabricated, or field assembled assemblies and equipment shall be provided with permanent engraved or non-removable silk-screened labels. The Contractor shall provide samples of labels to Designer for review and approval prior to fabrication or final installation. The Contractor shall modify labeling as required by the Designer.
- C. The Contractor shall provide and install a permanent, machine printed, protected label on both ends of each system cable. The label at each end of the cable shall provide the following information:
  - 1. System identifier
  - 2. Room number where other end of cable is terminated
    - a. Where system cables are routed between buildings the Contractor shall preface the Room Number with a Building Number
    - b. Room numbers shall coincide with numbering scheme included in contract documents.
  - 3. Device identifier where other end of cable is terminated
    - a. Device identifier shall provide a clear indication of device connected to.
  - 4. Label each cable within 4 inches (100 mm) of each termination and tap, where it is accessible in a cabinet or junction or outlet box, and elsewhere as indicated.
  - 5. Each wire connected to building-mounted devices is not required to be numbered at device if color of wire is consistent with associated wire connected and numbered within panel or cabinet.
  - 6. Exposed Cables and Cables in Cable Trays and Wire Troughs: Label each cable at intervals not exceeding 15 feet (4.5 m).
  - 7. Label each terminal strip and screw terminal in each cabinet, rack, or panel.
    - a. Individually number wiring conductors connected to terminal strips, and identify each cable or wiring group being extended

- from a panel or cabinet to a building-mounted device shall be identified with name and number of particular device as shown.
- b. Label each unit and field within distribution racks and frames.
8. Identification within Connector Fields in Equipment Rooms and Wiring Closets: Label each connector and each discrete unit of cable-terminating and connecting hardware. Where similar jacks and plugs are used for both voice and data communication cabling, use a different color for jacks and plugs of each service.
- D. Equipment, control, and system cabling shall be provided with permanent descriptive labels.
  - E. Labels shall be preprinted or computer-printed type with printing area and font color that contrasts with cable jacket color but still complies with requirements in TIA/EIA-606-A.
    1. Cables shall use flexible vinyl or polyester that flexes as cables are bent.

### 3.12 PROTECTION AND CLEANING

- A. The Contractor shall ensure that all system equipment is fully protected from damage, work of other trades, construction material, dirt, and dust to the point that upon occupancy by the Owner the equipment shall appear new and as if it had just been removed from the manufacturer's original packing.
- B. The Contractor shall be responsible for ensuring that all system enclosures and equipment is clean and in like new condition prior to requesting Substantial Completion. As a minimum, this shall include:
  1. The interior of equipment cabinets, terminal cabinets, and all other system enclosures shall be free of installation remnants, construction materials, dust, dirt, and other evidence of construction.
  2. The exterior of equipment cabinets, terminal cabinets, and all other system enclosures shall be free of scrapes, nicks, dents, discoloration, abrasions, excess construction materials, or other evidence of damage.
  3. System equipment backboxes, outlet boxes shall be free of damage and excess construction materials that hinder the installation of equipment or reduce the interior volume of the box.
  4. Equipment exteriors shall be clean and free of fingerprints, dust, stains, scratches, abrasions, marks, excess construction materials, or other contaminants.
  5. All system devices shall be clean and free of damage or visible markings.
- C. Field touch-up painting of racks, cabinets, and system enclosures to hide the evidence of damage shall not be acceptable. The Contractor shall replace racks, cabinets, or system enclosures that have visible exterior damage.

- D. In the event that the Designer determines that the equipment has not been protected properly, evidence of damage is visible, or the degree of installation remnants, construction material intrusion, dust, dirt, or other evidence of construction appears excessive, the Contractor shall clean the equipment and enclosures to the satisfaction of the Designer or shall, at the direction of the Designer, replace the equipment with new.

### 3.13 TESTING

- A. Perform testing as necessary or specified to verify fully functional systems with no visual, audible, or operational degradation. Replace and/or repair and retest components that fail performance standards. Test cables, outlets, devices, and equipment in accordance with industry acceptable practices for each individual system.
- B. Provide factory trained personnel to perform the tests and adjust the system.
- C. Test Equipment
  - 1. Provide all required test equipment and associated apparatus necessary to successfully complete the system testing.
  - 2. Kits, home-built, and other nonprofessional test equipment shall not be acceptable.
  - 3. Test instruments shall meet or exceed applicable requirements in TIA/EIA-568-B.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
- D. Cable
  - 1. General
    - a. Visually inspect jacket materials for NRTL certification markings. Inspect cabling terminations for compliance with color-coding for pin assignments, and inspect cabling connections for compliance with TIA/EIA-568-B.1.
    - b. Visually inspect cable placement, cable termination, equipment and patch cords, and labeling of all components.
    - c. Visually confirm cables and outlets have been properly labeled.
    - d. Visually inspect grounding and bonding for completeness and termination tightness.
    - e. Test operation of shorting bars in connection blocks.
  - 2. UTP and Multi-Conductor Cable
    - a. Test each cable. Perform the following tests:
    - b. DC loop resistance

- c. Shorts
- d. Opens
- e. Intermittent faults
- f. Polarity between conductors.

E. Corrective Action

- 1. The Contractor shall submit to the Designer, within five (5) business days of accomplishing the initial testing, a list identifying cables that do not meet the testing requirements. The Designer shall review the documentation and determine corrective action to be taken. This may include replacement of defective materials at no additional expense to the Owner.
- 2. The Contractor shall be responsible for repairing or replacement of defective equipment, materials, and cable as necessary to provide 100% satisfactory testing.
- 3. Remove and replace cabling where test results indicate that they do not comply with specified requirements. End-to-end cabling will be considered defective if it does not pass tests and inspections.

F. Documentation of Tests, Measurements, and Adjustments Performed:

- 1. Provide system verification and acceptance documentation signed and dated by the Contractor at the completion of testing. Document the following:
  - a. List of personnel in attendance during testing including the name of the Technician who performed each individual test.
  - b. List of certified test equipment used with serial numbers
  - c. List date of last calibration for each piece of test equipment
  - d. Date of each test
  - e. List reference settings of test equipment used for tests
  - f. Submit testing results in hard copy and native electronic format.
- 2. System verification and acceptance documentation shall be provided with the Contractor's request for Substantial Completion.

3.14 DEMONSTRATION

- A. Demonstrate system to designated Owner personnel as required by applicable sections of these specifications. Accomplish Owner's training as described in Part 1.
- B. Complete operation of the system shall be demonstrated. Hands-on demonstrations of the operation of all system components and the entire system including program changes and functions shall be provided.
- C. The Contractor shall provide a typewritten "Sequence of Operation" for each system.

END OF SECTION 27 05 01

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 27 10 00 – VOICE-DATA CABLE INFRASTRUCTURE (EMPTY RACEWAY)

PART 1 - GENERAL

1.1 RELATED SECTIONS

- A. Comply with the requirements of Section 27 05 00 "Common Work Results for Communications"
- B. In addition to the requirements of Section 27 05 00 comply with the following requirements:
  - 1. Definitions
    - a. BICSI: Building Industry Consulting Service International.
    - b. RCDD: Registered Communications Distribution Designer.
    - c. PoE: Power over Ethernet
    - d. VoIP: Voice over Internet Protocol
  - 2. Standards, Codes, References And Regulatory Requirements
    - a. The equipment and installation shall comply with the current and applicable provisions of the following standards, codes, references, and regulatory requirements including all ratified addenda:
      - 1) American Society for Testing and Materials (ASTM)
        - a) ANSI/TIA-568-C.0, Generic Telecommunications Cabling for Customer Premises
        - b) ANSI/TIA/EIA-568-C.1, Commercial Building Telecommunications Cabling Standard
        - c) ANSI/TIA/EIA-568-C.2, Balanced Twisted Pair Telecommunications Cabling and Components Standard
        - d) ANSI/TIA/EIA-568-C.3, Optical Fiber Cabling Components Standard
        - e) ANSI/EIA/TIA-569-B, Commercial Building Standard for Telecommunication Pathways and Spaces
        - f) ANSI/TIA/EIA-606-A, Administration Standard for The Telecommunications Infrastructure of Commercial Buildings
        - g) ANSI/TIA/EIA-607-B, Commercial Building Grounding and Bonding Requirements for Telecommunications
        - h) ANSI/TIA/EIA-758-A, Customer-Owned Outside Plant Telecommunications Cabling Standard
        - i) ASTM D 4566-94, Standard Test Methods for Electrical Performance Properties of Insulations and Jackets of Telecommunications Wire and Cable

- 2) IEC 60603-7, Connectors for frequencies below 3 MHz for use with printed boards – Part 7: Detail specification for connectors, 8-way, including fixed and free connectors with common mating features, with assessed quality
- 3) IEC 61935-1, Generic Specification for the Testing of Balanced Communications Cabling in Accordance with ISO/IEC 11801
- 4) Building Industry Consulting Service International (BICSI), Telecommunications Distribution Methods Manual, (Latest Revision)
- 5) Building Industry Consulting Service International (BICSI), Customer-Owned Outside Plant Design Manual, (Latest Revision)
- 6) Building Industry Consulting Service International (BICSI), Telecommunications Cabling Installation Manual, (Latest Revision)
- 7) Building Industry Consulting Service International (BICSI), LAN and Internetworking Design Manual, (Latest Revision)

## 1.2 DESCRIPTION OF SYSTEM:

- A. Provide and install a complete empty raceway system ready for the Owner's Vendor to install a complete Voice/Data Cable Infrastructure System.
- B. Section Includes:
  1. Systems Ground Bus Bars
  2. Termination Backboards
  3. Labels

## 1.3 SPECIAL REQUIREMENTS

- A. The Owner will have their Vendor provide and install all equipment, material, labor and testing of the Voice/Data Cable Infrastructure. The Contractor shall prepare all power, grounding, raceway, and outlet boxes as necessary. The Contractor shall coordinate with the Owner's Vendor as necessary for a complete properly installed and fully functional system.

## 1.4 FUNCTIONS AND OBJECTIVES

- A. Installation of a complete empty raceway system as described herein and shown on the drawings.

## PART 2 - PRODUCTS

### 2.1 GENERAL

- A. The Contractor shall provide and install all required equipment and materials necessary whether or not specifically shown on the drawings or specified herein.

- B. Equipment and components shall be new, and the manufacturer's current model. All equipment and materials shall be suitable for use intended, and meet all stated performance requirements for the system configurations specified herein.
- C. Equipment and components shall be installed in strict compliance with manufacturers' recommendations. Consult the manufacturer's installation manuals for all wiring diagrams, schematics, physical equipment sizes, etc., before beginning system installation.
- D. Unless specifically noted otherwise, equipment shall be attached to walls and ceiling/floor assemblies and shall be held firmly in place. Fasteners and supports shall be adequate to support the required load.

## 2.2 GENERAL PATHWAY REQUIREMENTS

- A. General:
  - 1. Comply with Section 27 05 00.
  - 2. Pathways (conduit, raceways, wireways, pullboxes, outlet boxes, etc.) shall comply with applicable requirements of Division 26

## 2.3 RACK AND FRAME EQUIPMENT

- A. Network Electronics:
  - 1. Provided and installed by Owner.
- B. Uninterruptible Power Supply (UPS):
  - 1. Provided and installed by Owner.

## 2.4 CABLE SUPPORT SYSTEM

- A. Provided and installed by the Owner's Vendor.

## 2.5 "SYSTEMS" AND "LOCAL" GROUND BUS BARS

- A. Provided and installed by Contractor.
- B. Communications systems ground bus bar shall be installed where shown on the drawings.
- C. Connectors: Mechanical type, cast silicon bronze, solderless compression-type wire terminals, and long-barrel, two-bolt connection to ground bus bar.
- D. Ground Bus Bar: Copper, minimum 1/4 inch thick by 4 inches wide by 12" long.
  - 1. #6 two-hole lugs with 1/4" hardware
  - 2. #2 and 2/0 two-hole lugs with 3/8" hardware
- E. Stand-Off Insulators: Comply with UL 891 for use in switchboards, 600 V. Lexan or PVC, impulse tested at 5000 V.



- F. Comply with ANSI-J-STD-607-A.
- G. Manufacturers
  - 1. Basis of Design
    - a. Chatsworth #40156-012 or acceptable substitution

## 2.6 TERMINATION BACKBOARDS

- A. Provided and installed by Contractor.
- B. Backboards shall start at 4" A.F.F. and be installed to a height of 8'-4" AFF all around room as shown in the drawings. Plywood shall be installed with the best side out. Imperfections and voids shall be filled, sealed and sanded prior to being primed and painted with 2 coats of UL Classified, gray fire retardant intumescent paint on the front, back and all four sides of the plywood. Fire retardant coating is to be tested to UL723, "Test for Surface Burning Characteristics of Building Materials". Backboards are to be clearly labeled with the name of the backboard manufacturer, UL Classification of the Fire Retardant Coating, NFPA 255 Coating Flame Spread Index Class and the APA Grade of the plywood.
- C. Contractor may field fabricate to all the specifications listed above. The Contractor shall provide proof that AC Grade Plywood and UL Classified paint was used in making the backboards. The Contractor shall also verify that backboards were primed, and painted on all sides (front, back and all sides) with two coats of the required paint with all voids filled and sanded prior to being primed and painted.
- D. Material: 3/4" A/C grade, Class A Flame Spread plywood.
- E. Manufacturers
  - 1. Basis of Design
    - a. Pathways& Spaces, Inc. ReadySpec #RB-AD4896Gor acceptable substitution

## 2.7 HORIZONTAL COPPER CABLE

- A. Provided and installed by the Owner's Vendor.

## 2.8 COPPER PATCH PANELS

- A. Provided and installed by the Owner's Vendor.

## 2.9 WORKSTATION OUTLETS

- A. Provided and installed by the Owner's Vendor.

## 2.10 COPPER PATCH CORDS

- A. Provided and installed by the Owner.

PART 3 - EXECUTION

3.1 GENERAL

- A. Comply with the requirements of Section 27 05 00.

3.2 PATHWAYS

- A. Pathway Installation in Communications Equipment Rooms:
  - 1. Position conduit ends adjacent to a corner on backboard where a single piece of plywood is installed, or in the corner of room where multiple sheets of plywood are installed around perimeter walls of room.
  - 2. Secure conduits to backboard when entering room from overhead.
  - 3. Extend conduits 3 inches (76 mm) above finished floor.

3.3 TERMINAL BOXES, JUNCTION BOXES AND CABINETS

- A. Boxes and cabinets shall be UL listed for their use and purpose.

3.4 TERMINATION BACKBOARDS

- A. Comply with requirements in Division 09 Section "Interior Painting" for painting backboards. For fire-resistant plywood, do not paint over manufacturer's label.
- B. Install backboards with 96-inch (2440-mm) dimension vertical.
- C. Butt adjacent sheets tightly, and form smooth gap-free corners and joints.

END OF SECTION 27 10 00

ORANGE COUNTY SHERIFF'S OFFICE  
CENTRAL OPERATIONS CENTER -  
SHERIFF'S OFFICE COMMAND AND MONITOR CENTER  
ORANGE COUNTY, FLORIDA

VOICE-DATA CABLE  
SECTION 27 10 00

PAGE LEFT INTENTIONALLY BLANK

SECTION 27 41 13 - AUDIO AND VIDEO SYSTEMS

PART 1 - GENERAL

1.1 RELATED SECTIONS

- A. Comply with the requirements of Section 27 05 00 "Common Work Results for Communications".
- B. In addition to the requirements of Section 27 05 00 comply with the following requirements:
  - 1. Standards, Codes, References, And Regulatory Requirements
    - a. The equipment and installation shall comply with the current or applicable provisions of the following standards, codes, references, and regulatory requirements:
    - b. Sound System Engineering by Don & Carolyn Davis (2nd Edition, Published by Howard W. Sams & Co., Inc.)
      - 1) UL 813 - Commercial Audio Equipment
      - 2) UL 1410 - Television Receivers and High-Voltage Video Products
      - 3) UL 1419 - Professional Video and Audio Equipment
      - 4) UL 1492 - Audio-Video Products and Accessories
      - 5) UL 1971 - Signaling Devices for the Hearing Impaired
  - 2. Submittals
    - a. Shop Drawings: The Contractor shall provide complete shop drawings showing how he intends to install the A/V system. Shop drawings shall, as a minimum, include the following:
      - 1) A point-to-point wiring diagram showing:
        - a) All system equipment, cabling, interconnections to other systems, etc.
        - b) Identifiers for the various types of cable to be used. This shall include a matrix that identifies the manufacturer, model number and descriptive identifier for each cable
        - c) Quantity of cables in each conduit
        - d) Signal type: Provide signal type designation on all cables. Signal type shall be identified in a fashion similar to that on the contract drawings (e.g. HDMI, RGBHV, S-Video, Composite, etc. for video; mic, line, 70V, etc. for audio; and data, RS-232, etc. for control).
  - 3. Spare Capacity

- a. The Contractor shall provide and install A/V system equipment and materials in quantities that will provide the Owner with twenty percent (20%) spare capacity (e.g. termination points, jacks, ports, etc.) after connection of all circuits as required by the contract documents.

4. Extra Materials

- a. Provide two (2) extra of each type of system patch cord.

1.2 DESCRIPTION OF SYSTEM:

- A. Provide and install a complete Audio and Video System, as described herein and shown on the drawings, providing the following:

1. The pickup, amplification, distribution, and reproduction of voice and/or other audio program material from various audio and video sources.
2. The pickup, processing, distribution, and reproduction of video program material from various video sources.

- B. System to include but not be limited to:

1. General Equipment and Materials

- a. Equipment Racks
- b. UPS

2. Video

- a. RF Tuners
- b. Video Scalers
- c. Matrix Switcher
- d. Control System Equipment
- e. Quad Splitters
- f. HDMI Extenders
- g. Video Patch Panels
- h. Video Monitors
- i. Video Projection Screens

3. Audio

- a. Line Level Mixer
- b. Audio Mixers
- c. Digital Signal Processors (DSP)
- d. 2-Channel Audio Power Amplifiers
- e. Audio 2-Channel Relays
- f. Speakers

4. Cable Systems

- a. Fiber Optic Patch Cords
- b. Fiber Optic Patch Panel

- c. Cable
  - 1) Video Cables
    - a) Shielded Category 6
    - b) Fiber Optic
  - 2) Audio cables
    - a) Line Level
    - b) Speaker

### 1.3 SPECIAL REQUIREMENTS

#### A. Owner Furnished Equipment

- 1. The following equipment will be Owner furnished, Contractor installed:
  - a. Vizio E420-A0 Video Monitors for Main Office (100) and Command Area (102).
  - b. Samsung 400UX-3 Video Monitors with Wall Mounts for Traffic Monitoring Area (104)
  - c. Mitsubishi FD730U Projectors with Ceiling Mounts
  - d. Workstation Computers with Desktop Video Monitors.
- 2. All equipment required for a complete and fully functional system beyond what is listed above shall be provided and installed by the Contractor.

#### B. Programming

- 1. The Contractor shall be responsible for programming services associated with touch screens associated with the AV Control System. In general the Control System shall provide full capability associated with all equipment to which it is interconnected as shown on the drawings. The Contractor shall, as part of his submittals, provide a detailed list recommending the functions and features for the Control System organized by touch screen page in a logical manner that clearly outlines his recommendations as to the organization of the touch screens as a group and each screen's individual layout showing all functions and features (i.e. buttons, controls, and other interactive items). The Designer will review the submittal information and provide comments in regard to revisions to the Contractor's recommendations. The Contractor shall take the resulting information and prepare draft layouts for each touch screen page and provide a single PDF file with all touch screen pages generally in the order in which they would appear on the touch screen for review by the Designer and the Owner. After the Designer and Owner have reviewed the drawings touch screen pages a meeting will be scheduled to review and discuss required changes with the Contractor and system Installer. Based on the results of the meeting, the Contractor shall prepare the preliminary Control System programming and, once the AV and Control System are functional, shall install the programming and put the system into a functional state. Once the touch screen programming is functional the Contractor shall request a 2<sup>nd</sup> meeting with the Owner and Designer to review the actual operation of the Control

System. The Contractor shall make final adjustments to the Control System and touch screen programming based on that meeting and complete all work prior to requesting the Substantial Completion inspection for the project. During the Substantial Completion inspection the Contractor shall be prepared to demonstrate to the Owner and the Designer that all items regarding the system operation and programming and been properly completed.

#### 1.4 FUNCTIONS AND OBJECTIVES

- A. The design and configuration of the A/V system as installed shall allow all source signals to be routed to all target devices. The contractor shall program the A/V system in a manner that allows all control points in the system to view any A/V source in the system.
1. Video
    - a. Provide video capture from source devices
    - b. Provide video distribution to target devices
    - c. Provide routing and switching as necessary to send video signals through system to and from various points to meet the design intent.
    - d. Provide video distribution to remote locations as indicated in the drawings and outlined within these specifications.
    - e. Provide routing and switching of audio signals as required for interfacing the Video System with the Audio System.
  2. Audio
    - a. Provide audio distribution to various locations.
    - b. Provide audio reinforcement on the room floor.
      - 1) Provide even distribution of the reinforced audio throughout the seating area, typically plus or minus 3 dB front to back and side to side for the one octave band centered at 4000 Hz. Total variation from the worst to best seats shall not exceed plus or minus 4 dB.
      - 2) Provide uniform frequency response throughout the audience area. Typically, plus or minus 3 dB as measured with 1/3-octave bands of pink noise at positions across the main seating area.
      - 3) Provide adequate dynamic range at an acoustic distortion level sufficiently low to ensure minimum listening fatigue. The system shall be capable of delivering 75 dB average program level with additional 10 dB peaking margin to any seat in the audience area at an acoustic distortion level below 5% THD.
- B. The Contractor shall adjust the equipment of the audio system such that there shall be no discernable difference in audio levels when switching from one audio source to another.
- C. The Audio and Video Systems as shown on the drawings and described herein interconnects to a variety of systems either outlined in other specification sections or provided and installed by the owner. The Installer shall be responsible for providing all

equipment, cabling, patch cords and other materials necessary to transfer signals from those other systems to the A/V system at the other system's primary equipment location unless specifically noted otherwise. The A/V installer shall coordinate the work of this section for the location where required signals of other systems are to be obtained and provide all equipment and materials necessary to do so. The documents describe as fully as possible the signal types and locations for these other systems. However, the A/V installer is ultimately responsible for providing the interconnection and processing of signals as necessary for the proper operation of the A/V system.

## PART 2 - PRODUCTS

### 2.1 GENERAL EQUIPMENT AND MATERIALS

#### A. Floor Mount Equipment Racks (Four Post)

1. Shall be a seven foot (7'0") tall equipment rack.
2. Technical
  - a. Freestanding equipment rack
    - 1) Includes:
    - 2) Welded steel and bolted aluminum four-post frame
    - 3) Equipment mounting rails, two pairs
    - 4) Leveler feet
    - 5) Factory installed grounding/bonding system
    - 6) Equipment mounting hardware
  - b. Equipment support:
    - 1) Two pairs of equipment mounting rails in the cabinet body 1-3/4" U, marked and numbered on all rails
    - 2) 19" wide, EIA-310-D Standard Universal 5/8" -5/8" -1/2" vertical hole spacing
    - 3) Threaded holes
    - 4) Includes 50 each #12-24 screws with threaded rails
  - c. Load Capacity: 2500 lb. Static on leveler feet.
  - d. Material: Steel sheet and aluminum castings, aluminum extrusion on front door, plastic cable managers.
  - e. Construction: Welded frame, mounting rails bolt to frame.
  - f. Finish: Epoxy-polyester hybrid powder coat paint in Black
3. One double-sided vented shelf (21" deep) in bottom for UPS equipment for each rack section.
4. Minimum of one (1) additional single-sided ventilated shelves for each rack section. Contractor shall coordinate with Owner prior to installation of system equipment to confirm equipment arrangement in equipment racks. If all shelves will not fit in equipment racks Contractor shall turn over shelves to Owner for future use.



5. Provide cable management devices (clamps, guides, supports, etc. as required to neatly dress/organize cables in and out of rack (or enclosure). With the exception of wire management devices specified below, devices shall be installed per requirements to be determined in the field. As a minimum, Contractor shall provide horizontal and vertical (full rack height) cable management as shown on the drawings. Wire management fill rate shall not exceed 50% condition when all provided jacks are in use. Contractor shall provide wire management sized as necessary for the number of cables installed and for the type of installation (i.e. rack or cabinet).
6. Each equipment rack shall have one vertical wire manager installed on each side of the equipment rack. Multiple contiguously installed equipment racks shall have a vertical wire manager installed between the adjoining equipment racks.
7. When mounting in another enclosure or millwork, provide width, height, hardware, etc. as required for complete and coordinated installation.
8. Provide all panels as required to mount equipment, including panel for power strip.
9. Provide ground bus full height minus six (6) inches. Mount to back of equipment rack. Connect to Systems ground bus bar.
10. Provide all brackets to mount non-rack mountable equipment such as termination blocker (where called for.)
11. Provide all hardware, supports, etc. as required to mount/house all equipment called for and/or shown at each location.
12. Provide additional shelves as required for each piece of equipment mounted in rack that requires a shelf.
13. Equipment rack shall be provided with isolation pad utilizing non-conductive washers.
14. Rack area to include two (2) 20 amp, 120V duplex receptacles, each connected to separate 20 amp, 120V dedicated circuit. Mount in bottom area of rack. Refer to power drawings.
15. Rack to include two (2) power strips. Power strip to plug into UPS power back-up system which will be plugged into power outlet provided within equipment rack.
16. Power Strips: Comply with UL 1363.
  - a. Rack mounting.
  - b. Six, 20-A, 120-V ac, NEMA WD 6, Configuration 5-20R receptacles.
  - c. LED indicator lights for power and protection status.
  - d. LED indicator lights for reverse polarity and open outlet ground.
  - e. Circuit Breaker and Thermal Fusing: When protection is lost, circuit opens and cannot be reset.
  - f. Cord connected with 15-foot (4.5-m) line cord.
  - g. Rocker-type on-off switch, illuminated when in on position.
  - h. Peak Single-Impulse Surge Current Rating: 33 kA per phase.
  - i. Protection modes shall be line to neutral, line to ground, and neutral to ground. UL 1449 clamping voltage for all 3 modes shall be not more than 330 V.
17. Project Performance Requirements
  - a. Rack Units Required: Forty-four (44)

18. Manufacturers
  - a. Basis of Design
    - 1) Chatsworth Quadra Rack
19. Acceptable Substitution
  - a. Hubble
  - b. Great Lakes
- B. Uninterruptible Power Source (UPS)
  1. Shall be an interactive UPS with enhanced LCD interface offering network-grade power protection for critical server, network, and telecommunications equipment.
  2. Shall have built-in Auto-Voltage Regulation (AVR) to actively correct for brownouts and over-voltages back to usable levels while maintaining a full battery charge in case of power failure.
  3. Features
    - a. 2RU rack mount UPS with 500 VA
    - b. Corrects for brownouts and over-voltages from 83 to 145V
    - c. NEMA L5-30P input plug; 8 NEBA 5-15/20R and 1 L5-30R output receptacles. Two independently switchable output load banks.
    - d. 98% efficiency rating in line-power mode
    - e. Internal batteries offering 10 minutes at 50% load and 3.5 minutes at 100% load
    - f. Hot-swappable, user-replaceable internal batteries.
    - g. Front panel LCD monitoring screen with MODE and ENTER buttons reporting operating mode with 5-bar battery charge graphic plus seven selectable screens of detailed UPS and site power information.
  4. Shall include:
    - a. PowerAlert software with USB, Serial, and IPO cabling
    - b. 4-post rack mount kit
    - c. Instruction manual
  5. Project Performance Requirements
    - a. Shall be provided with SNMPWEBCARD.
    - b. Shall provide emergency power for the Audio/Video System rack mounted equipment being installed in the right hand equipment rack under this project (not including any equipment the Owner may install in the left hand equipment racks). Refer to the rack elevation detail in the drawings.
  6. Manufacturers
    - a. Basis of Design

- 1) TrippLiteSmartPro 500 UPS(SMART500RT1U) or acceptable substitution

## 2.2 VIDEO SYSTEM

### A. RF Tuner

1. Shall be a compact, high performance analog cable TV tuner designed to provide maximum performance and control in professional AV environments.
2. Functions and Features
  - a. Front panel, RS-232, and modulated IR control
  - b. Save and recall configuration files via RS-232
  - c. Preset channel memories
  - d. Remote Control
  - e. Rack mountable
3. Technical
  - a. RF Video Input
    - 1) Number: 1 radio frequency (RF)
    - 2) Off Air TV and Cable Channels: 48 MHz to 855 Mhz
    - 3) Impedance: 75 ohms
    - 4) Vertical Frequency: 60 Hz
  - b. Video Input: One (1) composite video
  - c. Sync: NTSC 3.58
  - d. Audio: THD + Noise – 0.4% @ 1 kHz
  - e. Audio Output: One (1) balanced/unbalanced
  - f. Control/Remote Tuner
    - 1) Serial Control Port: RS-232
    - 2) IR Controller Module: Remote
4. Manufacturers
  - a. Basis of Design
    - 1) Extron AVT 100 Analog Closed Circuit TV Tuner or acceptable substitution

### B. HDMI SCALER

1. Shall be a compact video scaler that accepts a wide variety of video formats including HDMI, HDTV, RGB, and standard definition video.
2. Features
  - a. HDMI, RGB, HDTV, and video scaling to HDMI
  - b. Auto-switching between inputs
  - c. HDMI audio embedding

- d. Advanced scaling engine with 30-bit processing and 1080i deinterlacing
  - e. HDCP compliant
  - f. Supports DMI specification features including data rates up to 6.75 Gbps, Deep Color, and HD lossless audio formats
  - g. EDID minder
  - h. Aspect ratio control
  - i. HDCP visual confirmation providing a green signal when encrypted content is sent to a non-compliant display
  - j. Seamless switching
  - k. Frame lock
  - l. Image freeze control
  - m. Auto-Image setup
  - n. Output standby mode
  - o. Power save mode
  - p. Automatic 3:2 and 2:2 pulldown detection.
  - q. Quad standard, 3D composite video decoding
  - r. Internal test patterns for calibration and setup
  - s. Audio switching transitions
  - t. Front panel security lockout
  - u. RS-232 control port
  - v. Front panel USB configuration port.
3. Technical
- a. Video Input Number/Signal Type: One (1) Composite; One (1) RGBHV/YUV; One (1) HDMI/DVI
  - b. Video Resolution Range: 640x480 to 1600x1200 NTSC, PAL, SECAM, 480p, 576p, 720p, 1080i, 1080p, and 2K
  - c. Video Processing Analog Sampling: 12 bits per color; 13.5 MHz standard (video); 170 MHz standard (RGB)
  - d. Video Processing Digital Pixel Data Bit Depth: 8, 10, 12 bits per channel; 165 MHz pixel clock (HDMI)
  - e. Video Output: One (1) HDMI
  - f. Audio
    - 1) Frequency Response: 20 Hz to 20 kHz
    - 2) THD + Noise: <0.1% @ 1 KHz
    - 3) S/N: > 90 dB at maximum output
  - g. Control: One (1) bidirectional RS-232; One (1) USB
4. Project Performance Requirements
- a. Provide one (1) HDMI Scaler to the Owner as portable equipment.
5. Manufacturers
- a. Basis of Design

- 1) Extron DSC 301 HD Three Input Compact HDCP-Compliant Video Scaler or acceptable substitution

C. HDMI Matrix Switcher

1. The Video Matrix Switcher shall be a flexible, reliable digital and analog video switching and distribution device connecting local and remote endpoints. The Switcher shall be configurable to 32x32 using a wide variety of available input and output boards. It shall send high-resolution video, audio, RS-232, Ethernet, and power up to 330 feet over a single Category 6 shielded cable to remote CRP transmitters and receivers. The Switcher shall also support direct HDMI, DVI, VGA, video, and audio connections to local sources and displays. The Switcher shall deliver robust signal routing and reliability with ultra-fast digital video switching and advanced system monitoring.
2. Functions and Features
  - a. 15.2 Gbps data-rate digital backplane
  - b. Fully digital signal routing
  - c. Wide selection of input and output boards
  - d. RS-232 insertion from the Ethernet control port
  - e. Remote power to transmitters and receivers
  - f. Supports HDMI specification features including data rates up to 6.75 Gbps, Deep Color up to 12-bit, 3D, and HD lossless audio formats.
  - g. HDCP compliant
  - h. Speedswitch technology for exceptional switching speed for HDPC-encrypted content
  - i. SD Pro processing to provide deinterlacing of standard definition video.
  - j. EDID Minder to automatically manage EDID communication between connected devices.
  - k. Key Minder to continuously verify HDCP compliance for quick, reliable switching
  - l. Modular, field-upgradable and hot-swappable design
  - m. Audio breakaway
  - n. Ethernet extension
  - o. HDCP authentication and signal presence confirmation via RS-232 or Ethernet.
  - p. HDCP visual confirmation to provide a green signal when encrypted content is sent to a non-compliant display
  - q. Ethernet monitors and control
  - r. Optional redundant power supply
  - s. Global presets
3. Technical - Switcher
  - a. Architecture requirements
    - 1) The matrix switcher shall support a modular, hot swappable input and output board design
    - 2) The matrix switcher shall support a mix of digital and analog source signal types through interchangeable modular input boards.

- a)
    - a) Eight (8) configurable input slots
    - b) Eight (8) configurable output slots
  - 3) The matrix switcher shall support field configuration of input and output boards
    - a) Boards shall be hot-swappable
  - 4) Audio and video signals may be routed independently (break-away routing)
  - 5) The matrix shall support the extension of Ethernet data from a third party network switch and pass-through the Ethernet data to remote transmitters and / or receivers
  - 6) The matrix shall not have an integrated managed or unmanaged Ethernet switch
  - 7) The matrix switcher shall support the option for a redundant power supply
  - 8) The matrix switcher shall support multiple means of control for I/O selection and general operation
    - a) Front panel
    - b) USB
    - c) Ethernet control
    - d) RS-232 control
  - 9) The matrix switcher front panel shall provide status feedback
  - 10) The matrix switcher shall have a digital backplane with support for data rates up to 15.2 Gbps
- b. Inputs requirements
- 1) Shall provide support for local direct device connections
  - 2) Shall provide support for deinterlacing of standard definition video signals
  - 3) Shall provide cable equalization for each digital input
  - 4) Shall provide support for remote device connections via twisted pair transmitters
  - 5) Shall provide support for video, audio, control, and Ethernet extension over a shielded CATx cable
  - 6) Shall provide support for remote power of remote transmitters via shielded twisted pair cable
- c. Outputs requirements
- 1) Shall provide support for local direct device connections
  - 2) Shall reshape and restore timing of digital video signals at each output
  - 3) Shall provide support for remote device connections via twisted pair receivers
  - 4) Shall provide support for video, audio, control, and Ethernet extension over a shielded CATx cable

- 5) Shall provide support for remote power of remote receivers via shielded twisted pair cable
  - 6) Shall provide support for automatically adjusting color bit depth output based on the attached display EDID information
- d. HDCP and EDID Management requirements
- 1) The unit shall be HDCP compliant
    - a) Provide authentication and maintain continuous verification of HDCP key exchange between connected devices
    - b) Provide the option to disable HDCP processing at applicable inputs when passing unencrypted content
    - c) Provide visual confirmation of HDCP compliance when encrypted content is routed to a non-HDCP compliant display
      - (1) The video output is a solid green color
    - d) HDCP authentication and signal presence confirmation via RS-232 or Ethernet
  - 2) Provide EDID management between connected devices
    - a) Provide a set of pre-stored EDID files
    - b) Support capture of EDID from any connected display
    - c) Support user uploading of EDID files
    - d) Support assignment of any pre-stored, captured, or uploaded EDID file to any input
- e. Audio requirements
- 1) The matrix shall support independent routing of audio and video signals (break-away routing)
  - 2) The matrix shall support downmixing of embedded multi-channel audio
  - 3) The matrix shall support embedding of analog audio
  - 4) The matrix shall support de-embedding of digital audio
  - 5) The matrix shall support audio input gain and attenuation for analog signals
  - 6) The matrix shall support audio output volume adjustment and muting for analog signals
- f. Transmission requirements
- 1) The matrix shall support a maximum signal transmission distance of 330' (100 m) at 1920x1200 or 1080p @ 60 Hz with deep color using a shielded twisted pair cable
  - 2) Support HDMI specifications up to 1080p /60 Deep Color (12-bit) and 1920x1200 at data rates up to 6.75 Gbps

- 3) Support embedded HD lossless audio formats
  - 4) Actively buffer DDC channels
- g. Control requirements
- 1) The matrix switcher shall support multiple means of control for I/O selection and general operation
    - a) Front panel
    - b) USB
    - c) Ethernet control
    - d) RS-232 control
  - 2) Shall provide RS-232 insertion from the Ethernet port to remote transmitters and/or receivers
  - 3) Shall provide Ethernet monitoring and control using standard TCP/IP protocols
    - a) Support proactive monitoring and system management over a LAN, WAN, or the Internet
    - b) Support remote selection of input and output ties, adjustment and control of audio input and output levels, and advanced system diagnostics
  - 4) Front panel shall provide physical buttons for
    - a) Creating ties within the matrix
    - b) Audio output volume adjustment and muting
    - c) Recalling presets
- h. General requirements
- 1) Shall be rack mountable
  - 2) Shall offer remote powering for XTP transmitters and/or receivers
  - 3) Shall provide redundant power supply as an optional feature
  - 4) Shall meet regulatory compliance
    - a) CE, c-UL, UL
    - b) CE, C-tick, FCC Class A, ICES, VCCI
  - 5) Shall provide a 3 years parts and labor warranty
4. Technical – Input/Output Cards
- a. Four Input or Output HDMI Boards
- 1) Four HDMI inputs or four HDMI outputs with stereo audio
  - 2) Shall support computer and video resolutions up to 1920 x 1200 including 1080p/60 Deep Color and 2K



- 3) Supported HDMI specification features shall include data rates up to 6.75 Gbps, Deep Color up to 12-bit, 3D, and HD lossless audio formats.
- 4) HDCP compliant
- 5) Speed switch technology for HDCP-encrypted content.
- 6) EDID minder
- 7) Key minder
- 8) Automatic color bit depth management
- 9) HDMI to DVI interface format correction.
- 10) Local analog stereo audio inputs and outputs.
- 11) Output volume control
- 12) Automatic cable equalization
- 13) Automatic output reclocking
- 14) Internal color bars test pattern with or without audio for setup and calibration
- 15) +5 VDC, 250 mA power and HDMI outputs for external peripheral devices.
- 16) Supports data rates to 6.75 Gbps – 2.25 Gbps per color
- 17) Hot-swappable

5. Project Performance Requirements

- a. The Switcher shall be configured for inputs/outputs as shown on the drawings.
- b. The Contractor shall provide and required input/output cards as necessary to meet all functional and operational requirements of the project.

6. Manufacturers:

- a. Basis of Design
  - 1) Extron XTP CrossPoint 3200 Series Modular Digital Matrix Switcher with XTP CP 4i HDMI Input Boards, and XTP CP 4o HDMI Output Boards or acceptable substitution

D. Control System

1. IP Control Processor

- a. Shall be an Ethernet enabled control processor for the purpose of remotely controlling, monitoring and troubleshooting connected AV equipment and AV systems.
- b. Configuration-based, Ethernet enabled control processor
- c. Provide one bidirectional configurable RS-232 ports on captive screw connectors located on the back of the processor that can be configured for control of AV system components
- d. Device shall have a female RJ-45 jack located on the back of the enclosure that supports 10/100/1000Base-T, half/full duplex with auto-detect for connection to a LAN or WAN and includes link and activity LED indicators located on the left and right of the jack for

- troubleshooting network issues as well as supports PoE- Power over Ethernet, 802.3af
- e. Device shall have an optional 12 volt captive screw connection located on the back of the panel should PoE not be available
  - f. Device shall support the following protocols: ICMP (ping), IPv4, TCP, UDP, DHCP, DNS, HTTP, HTTPS, NTP, SFTP, SMTP, SNMP, SSH
  - g. Device shall include a multi-function button that allows for the reset of the device or its communication properties at minimum
  - h. Supports a web-based AV resource management application that provides a means to manage, monitor, and control AV equipment
  - i. Provide an internal real-time clock with a 30 years backup battery that is used to keep track of the date and time
  - j. Device shall have at least 512 MB nonvolatile user memory
  - k. Provide front panel led activity indicators for power status, RS-232 status, and network status
  - l. Device shall include an energy-efficient external 12 VDC, 1 A power supply
  - m. Mounting requirements
    - 1) Device shall be housed in a 1" high, quarter EIA rack width metal enclosure
    - 2) Device shall be able to be rack mounted using an optional rack shelf
    - 3) Device shall be able to be installed under a table, desk, or other flat surface using an optional mounting kit
    - 4) Device shall be able to be mounted on a projector mounting pole using an optional mounting kit
  - n. Software requirements
    - 1) Device shall be configured using Global Configurator Plus or Professional with support for the following:
      - a) Provide support for up to eight configurable TouchLink Pro touchpanels
      - b) Provide remote monitoring and control via Ethernet
      - c) Provide the ability to create E-mail notifications
      - d) Provide multiple levels of password protection
      - e) Provide the ability to create schedules and monitors
      - f) Supports up to 32 Ethernet-controllable AV devices
      - g) Supports local variables and conditional logic
    - 2) Shall meet regulatory compliances
      - a) CE
      - b) UL
      - c) c-UL
      - d) C-tick
      - e) FCC Class A
      - f) ICES
      - g) VCCI

- 3) Product Warranty
  - a) Shall provide at least 3 years parts and labor
2. Touch Screen Panel (12")
  - a. Shall be a 12" touch panel with active matrix TFT color display.
  - b. Functions and Features
    - 1) Resolution: 1280x800
    - 2) Dot/Pixel Pitch: 125 dpi
    - 3) Aspect Ratio: Wide screen
    - 4) Color Depth: 16 million colors
    - 5) Transparency: 8-bit alpha channel
    - 6) Brightness: 400 nits (cd/m2)
    - 7) Contrast: 1000:1
    - 8) Backlight: LED
    - 9) Viewing Angle: 88 degrees
    - 10) Touchscreen: Capacitive.
  - c. Technical
    - 1) Memory
      - a) SDRAM: 512 MB
      - b) Flash: 512 MB
    - 2) Twisted Pair
      - a) Termination Standard: TIA/EIA T568A or T568B
      - b) Signal Transmission Distance: 330 feet using Category 6
    - 3) Video Input
      - a) Signal: One (1) HDMI; One (1) Twisted Pair
      - b) Horizontal Frequency: 18.75 kHz to 75 kHz
      - c) Vertical Frequency: 24 Hz to 75 Hz.
      - d) Standards: DVI 1.0, HDMI, HDCP
    - 4) Video Processing: 8, 10, 12 bits per channel; 165 MHz pixel clock
    - 5) Colors: 1 billion.
    - 6) Control
      - a) Motion Sensor: on/off
      - b) Light Sensor: on/off.
      - c) Ethernet: Yes
3. Data Switch

- a. Shall be a Gigabit Ethernet PoE Data Switch.
  - b. Functions and Features
    - 1) 10/100/1000 Mbps switched ports.
    - 2) Shall be capable of powering up to four PoE devices
    - 3) IEEE 802.1p QoS for automatic traffic prioritization
    - 4) Jumbo Frame support
    - 5) Auto MDI/MDI-X Crossover
    - 6) IEEE 802.3x Flow Control
    - 7) Supports MAC Address learning
    - 8) Limited Lifetime Warranty
  - c. Technical
    - 1) Switching Capability: 16 Gbps
    - 2) Standards: IEEE 802.3, 802.3u, 802.3ab, 802.3x, 802.1p
    - 3) POE: Total budget 52 watts.
4. Project Performance Requirements
- a. Touch screen in Command Area (102) shall be a 12" desktop device.
  - b. Touch screen in Executive Policy Conference Room (105) shall be a 12" wall mount device. Provide and install wall mount bracket.
  - c. Touch screen in IDF (116) shall be a 12" rack mount device. Provide and install rack mount.
5. Manufacturers
- a. Basis of Design
    - 1) Extron IPCP Pro 550 IP Link Pro Control Processor, Extron TLP Pro 12200TG or 1220MG Touch Link Pro Touchpanel, and D-Link DGS-1024P 8-Port Gigabit Ethernet PoE Switch or acceptable substitution
- E. Quad Splitter
- 1. Shall be a Multi-Image Processor and Presentation Scaler/Switcher designed for displaying up to four sources simultaneously on a single screen in a variety of layouts.
  - 2. Functions and Features
    - a. I/O resolutions up to 4K UHD
    - b. Multiple inputs including 4X HDMI, 2X Display Port, and 1X RGB
    - c. HDMI 1.4b output
    - d. 16 preset layouts
    - e. Auto scaler for each input
    - f. HDCP compliance and EDID management
    - g. Analog and optical audio outputs
    - h. Audio follow and audio breakaway modes
    - i. Control via web GUI, IR remote, and RE-232

3. Technical

a. Inputs

- 1) Video: 7 total
- 2) Resolution (max): 3840 x 2160 @ 30 Hz
- 3) HDCP: v1.4 compliant
- 4) Audio: 7x 3.5 mm mini-pin, stereo

b. Outputs

- 1) Video: 1x HDMI
- 2) Resolutions: Auto, 3840x2160 # 30 Hz, 1920x1080 @ 60 Hz, 1280x720 @ 620 Hz, 1900x1200 @ 60 Hz, 1600x1200 @ 60 Hz, 1280x800 @ 60 Hz, 1024x768 @ 60 Hz
- 3) HDCP: v1.4 compliant
- 4) Audio: 1x HDMI, 1x optical, 4x analog (8 channels)

c. Control

- 1) Built-in Setup/Configuration GUI
- 2) IR Remote, Ethernet 10/100/1000 BASET, Telnet, RS-232

4. Manufacturers

a. Basis of Design

- 1) RGB Spectrum QuadView UHD or acceptable substitution

F. HDMI Extender

1. Shall be an HDMI equalizer for extending HDMI signals beyond suggested maximum distance limit of 45 feet for HDMI cables.
2. Shall be used in conjunction with cables up to 200 feet in length to provide signals at 1080p/60 with 8-bit color minimum. It shall automatically provide the necessary active equalization to ensure optimal image quality with HDTV signals 1080p/60 and high resolution computer-video signals up to 1920 x 1200.
3. Shall be HDCP compliant ensuring display of content-protected media and interoperability with other HDP-compliant devices.
4. Functions and Features
  - a. HDMI 1.3 compatible
  - b. Powered by device at distances up to 125 feet.
  - c. LED indicator for source signal presence and power
  - d. Cable lacing brackets
5. Project Performance Requirements
  - a. Contractor shall provide and install an HDMI Cable Equalizer on each HDMI cable that exceeds 75 feet in length.

6. Manufacturers
  - a. Basis of Design
    - 1) Extron HDMI 101 Plus or acceptable substitution
- G. Video Patch Panels
  1. The Video Patch Panels shall be custom manufactured, rack mountable Patch Panels configured to allow HDMI video to be input to rack mounted equipment. Connectors shall be as necessary to allow input and output of the specified signals.
  2. The Video Patch Panels shall be custom engraved to indentify the information regarding the signals being transmitted. The Contractor shall use the information in the drawings as a starting point and shall provide with his submittals proofs from the manufacturer for review.
  3. Manufacturers
    - a. Basis of Design
      - 1) RCI Custom Products or acceptable substitution
- H. Video Monitors (55")
  1. Shall be an LED-backlit, commercial-grade LCD display.
  2. Technical
    - a. Panel Technology: MVA
    - b. Viewable image size: 55"
    - c. Native Resolution: 1920 x 1080
    - d. Brightness (Typ/Max): 450 cd/m2
    - e. Contrast Ratio: 5000: 1
    - f. Aspect Ratio: 16:9
    - g. Orientation: Landscape
    - h. Displayable Colors: more than 1.07 billion
    - i. PC/Max Signal Compatibility: Yes
    - j. Input Terminals: VGA, HDMI x 2, Display Port, DVI
  3. Project Performance Requirements
    - a. Shall be provided with integral speakers.
    - b. Shall be provided with compatible wall mount
    - c. Shall be provided and install in Break-Out (106) and Break-Out (107) only.
  4. Manufacturers
    - a. Basis of Design
      - 1) Monitor: NEC E551 Video Monitor or acceptable substitution
      - 2) Monitor Wall Mount: Peerless, Chief Manufacturing, or VMP

- I. Video Monitors (70")
  - 1. Shall be an LED-backlit, commercial-grade LCD display.
  - 2. Technical
    - a. Panel Technology: UV2A
    - b. Viewable image size: 70"
    - c. Native Resolution: 1920 x 108
    - d. Brightness (Typ/Max): 360/450 cd/m2
    - e. Contrast Ratio: 4000: 1
    - f. Viewing Angle: 176 degrees
    - g. Aspect Ratio: 16:9
    - h. Orientation: Landscape
    - i. Displayable Colors: more than 1.07 billion
    - j. PC/Max Signal Compatibility: Yes
    - k. Input Terminals: VGA, HDMI x 2, Display Port, DVI
  - 3. Project Performance Requirements
    - a. Shall be provided with compatible wall mount
    - b. Shall be provided and install in Executive Policy Conference Room (105) only.
  - 4. Manufacturers
    - a. Basis of Design
      - 1) Monitor: NEC E705 Video Monitor or acceptable substitution
      - 2) Monitor Wall Mount: Peerless, Chief Manufacturing, or VMP
- J. Projection Screens
  - 1. Shall be an HDTV 16:9 format video projection screen designed for commercial applications.
  - 2. Shall be a wall mount type projection screen with a powder coated white 22-gauge octagonal steel case with flat back design and fitted end caps concealing roller ends. Shall include integral bearing surface to support roller and integral brackets for wall mounting by means of slotted screw holes. Bottom of fabric shall be mounted securely into a powder coated tubular steel slat. Shall have masking borders on flame retardant and mildew resistant fiberglass fabric. Fabric shall be mounted into a metal strip in a metal Camlok roller system without tape, glue, staples or cords so that fabric may be easily replaced yet cannot be pulled from roller.
  - 3. Size: 42" x 92"; Nominal Diagonal of 106"
  - 4. Screen Material: Half Angle of 35 degrees; Gain of 1.5
  - 5. Manufacturers
    - a. Basis of Design
      - 1) Da-Lite Model B with Video Spectra 1.5 Screen Material

b. Acceptable Substitutions

- 1) Draper
- 2) Stewart Filmscreen

2.3 AUDIO SYSTEM

A. Line Level Mixer

1. The Line Level Mixer shall be a two input, two output device design for mixing two audio sources. It shall allow two mic or line level source to be combined and output as either a mic or line level signal.
2. Technical
  - a. Inputs: Two (2) selectable mic or line
  - b. Input Level for +4 dBu Output:
    - 1) Mic: -45 dBu to +65 dBu; Max input -28 dBu
    - 2) Line: -18 dBv to +1- dBu; Max input +22 dBu
  - c. Input Impedance: Mic 200 Ohm; Line 20 k Ohm bridging
  - d. Input or Output Configuration: Balanced or unbalanced
  - e. Outputs: Two (2); mic or line
  - f. Output impedance: 150 Ohms (mic or line)
  - g. Frequency Response:
    - 1) Mic: 25 Hz to 50 kHz ( $\pm 1$  dB)
    - 2) Line: 10 Hz to 30 kHz ( $\pm 0.25$  dB)
  - h. THD+N:
    - 1) Mic: < 0.05% 25 to 20 kHz
    - 2) Line: < 0.005%
    - 3) IMD: < 0.004%
  - i. Output Level: Mic: -45 dBu; Line +4 dBu
  - j. Headroom:
    - 1) Mic Input: >22 dB
    - 2) Line Input: >32 dB
    - 3) Output: > 20 dB
  - k. Noise: Mic: <-70 dB; Line <-90 dB
  - l. CMRR: Mic: > 65 dB; Line >45 dB
3. The Mixer shall be provided with a power supply
4. Contractor shall provide and install Line Level Mixers where necessary to convert a stereo audio signal to a mono audio signal or where multiple audio sources are combined into a single audio mixer input.
5. Manufacturers



- a. Basis of Design
  - 1) Radio Design Labs St-MS2 Line Level Mixer or acceptable substitution
- B. Audio DSP
  1. Shall be a compact 4x4 audio matrix mixer featuring a digital signal processing platform for audio signal routing and control.
  2. Functions and Features
    - a. 4x4 line level audio matrix mixer
    - b. DSP audio signal processing
    - c. 24-bit/48 kHz analog-to-digital and digital-to-analog converters
    - d. Fixed, low latency DSP processing
    - e. DSP Configurator software
    - f. Intuitive graphical user environment
    - g. Building blocks processor templates
    - h. Console view with gain settings, metering, and routing in a single window
    - i. Three digital input ports for remote triggering
  3. Technical
    - a. Audio
      - 1) Frequency Response: 20 Hz to 20 kHz, +/- 0.3 dB
      - 2) THD + Noise: < 0.02% @ 1 kHz
      - 3) S/N: >100 dB
    - b. Audio Input: Four (4) mono, line, balanced/unbalanced
    - c. Audio Processing: 24 bit, 48 kHz sampling
    - d. Audio Output: Four (4) mono, line, balanced/unbalanced
    - e. Serial Control: One (1) bi-directional RS-232
    - f. USB Control: One (1) front panel female mini USB B
    - g. Control – Digital Inputs: Three (3) configurable
    - h. Rack Mount: Yes
  4. Manufacturers
    - a. Basis of Design
      - 1) Extron DMP 44 LC Digital Matrix Processor or acceptable substitution
- C. Audio 2-Channel Power Amplifier
  1. Shall be a compact power amplifier designed for installation in racks, lecterns, or above ceilings.
  2. Functions and Features

- a. Energy Star qualified
    - b. Professional grade single-to-noise and THD+N performance
    - c. Class D ripple suppression
    - d. Convection cooled, fanless operation
    - e. Ultra low inrush current.
    - f. Power factor correction
    - g. Rack-mountable
    - h. UL 2043 plenum rated.
  3. Technical
    - a. Audio Input: Two (2) mono, balanced/unbalanced
    - b. Audio Output: Two (2) mono, 70V
    - c. Output Power: 100 watts rms, 70V per channel
    - d. Frequency Response: 20 Hz to 20 kHz
    - e. THD+Noise: 0.05W% @ 20 Hz – 20 kHz
    - f. S/N: 105 dB, 20 Hz – 20kHz
  4. Manufacturers
    - a. Basis of Design
      - 1) Extron XPA 1002-70V 2-Channel Amplifier or acceptable substitution
- D. 2-Channel Audio Relays
  1. The 2-Channel Audio Relay shall include a 12VDC external power supply. Unit shall be wired and ready for mounting and deployment. The Relay shall utilize user selectable triggers to energize the switching functions. Included relay functions to switch shall be normally open and normally closed modes for the externally switched dual (two) channel amplifier (not included). Power handling is 350 watts per channel. Individual sensitivity controls- line level (20mV - 3V), speaker Level (3V - 45V), external voltage trigger (5 - 24VDC) or contact closure will allow the Relay to be controlled by a variety of input triggers. Unit shall also have a variable recovery adjust circuit that can be adjusted from 1 - 30 seconds (user selectable). Two color LED shall indicate operational status Red – Standby Mode, Green – Active Mode. The unit's inputs and outputs shall be terminated at plug in phoenix style screw terminals for easy access. The chassis shall be constructed of 18-gauge CRS. Models shall include a silk-screened termination diagram.
  2. Manufacturers
    - a. Basis of Design
      - 1) Atlas Sound AA-PPRC Audio Relay or acceptable substitution
- E. Speakers

1. The Speaker shall consist of an 8" full range, point source, constant directivity dual concentric transducer and passive frequency dividing network mounted in a vented, injection molded, paintable front baffle in UL94V-0 ABS material.
2. The back can shall be constructed of zinc plated steel. A recessed termination box shall be integrated with the back can, a removable locking connector with screw terminals for secure wire termination with loop through facility shall be provided. Strain relief shall be provided by a clamping mechanism for use with plenum rated cable or conduit.
3. Performance of the Speaker shall meet or exceed the following criteria:
  - a. The Speaker shall have a conical coverage pattern of 100 degrees (1kHz to 6 kHz).
  - b. Frequency response measure on axis shall be 40 Hz – 34 kHz (-10 dB from rated sensitivity, measured in an IEC baffle in an anechoic chamber) with no equalization.
  - c. Sensitivity shall be 92 dB (1W @ 1m).
  - d. Long term power handling capacity as defined in EIA-426B test shall be 90W, recommended amplifier power 180W. Dynamic high frequency protection shall be provided for occasional overpowering.
  - e. The nominal system impedance shall be 8 Ohms (in low impedance setting).
4. The Speaker shall be equipped with a 60W high performance line transformer for use in 70.7 and 100 V distributed audio systems with 60, 30, 15, and 7.5 Watt taps available. An easily accessible rotary switch located on the front baffle shall be available for selecting transformer and low impedance settings. A weather resistant perforated steel grille shall cover the transducer and switch.
5. Two support rails and one C-ring shall be included with the Speaker.
6. Manufacturers
  - a. Basis of Design
    - 1) Tannoy CMS 801DC Ceiling Speaker Assembly
  - b. Acceptable Substitution
    - 1) JBL
    - 2) Extron

## 2.4 CABLE SYSTEMS

### A. Fiber Optic Patch Panels

1. Modular panels housing multiple-numbered, duplex cable connectors.
2. Number of Connectors per Field: As shown on the drawings. Include quantity necessary for each fiber of cable or cables assigned to field, plus spares and blank positions adequate to suit specified expansion criteria.
3. Shall be fully loaded with a minimum of forty-eight (48) LC connectors.
4. Durable metal construction with mounting for standard EIA 19" equipment racks/cabinets.
5. Shall include cable entry holes on top, bottom and sides
6. Shall include removable hinged front and rear doors.

7. Provide rack mounted or wall mounted as shown on the drawings.
8. Manufacturers

- a. Basis of Design

- 1) Siemon

- b. Acceptable Substitutions

- 1) Ortronics
- 2) Hubbell

B. Fiber Optic Patch Cords

1. Shall be by the same Manufacturer as the Fiber Optic Patch Panels.
2. Shall be provided with the same connector type as the Fiber Optic Patch Panel.
3. Shall meet the same specifications as the backbone Fiber Optic cable being installed as part of this project.
4. Shall be of lengths necessary to meet the requirements of the project.
5. Manufacturers

- a. Basis of Design

- 1) Siemon

- b. Acceptable Substitutions

- 1) Ortronics
- 2) Hubbell

C. Cable

1. Video

- a. Shielded Category 6

- 1) General

- a) Provide and install Category 6 Shielded cable engineered for superior performance with twisted pair video equipment.
- b) Certified to 475 MHz bandwidth at distances up to 330 feet.
- c) SF/UTP design with four unshielded twisted pairs inside an overall braid and foil shield.
- d) 24 AWG solid copper construction
- e) Available in plenum and non-plenum versions.

- 2) Project Performance Requirements

- a) The use of non-shielded Category 6 cable shall not be acceptable.
  - 3) Manufacturers
    - a) Basis of Design
      - (1) Extron XTP DTP 24 or acceptable substitution
  - b. Fiber Optic (Backbone)
    - 1) General
      - a) Shall be an OM2, Grade 4, 50/125  $\mu\text{m}$  indoor/outdoor, multimode fiber optic cable rated both for plenum spaces and cable tray installations.
      - b) Interior building cables shall be tight buffered, non gel-filled design.
      - c) Multimode Cable Construction (50  $\mu\text{m}$ ):
        - (1) Number of fibers: As shown on the drawings
        - (2) Core/Cladding: 50  $\mu\text{m}$ /125  $\mu\text{m}$
        - (3) Fiber: 10G/300 fiber
        - (4) Buffering: 900  $\mu\text{m}$
        - (5) Attenuation:  $\leq 3.5$  dB/kilometer at 850 nanometers,  $\leq 1.25$  dB/kilometer at 1300 nanometers
        - (6) Minimum laser bandwidth: 2000 MHz/kilometer at 850 nanometers, 500 MHz/kilometer at 1300 nanometers.
        - (7) Sheath Construction: Non-metallic.
    - 2) Manufacturers
      - a) Basis of Design
        - (1) Mohawk Wire and Cable #M9X204
      - b) Acceptable Substitutions
        - (1) CommScope
        - (2) B
        - (3) Belden
  - c. All other video cables and connectors shall be as recommended by the equipment manufacturer.
2. Audio
- a. Line Level Cable:
    - 1) General

- a) The speaker cable shall be a power-limited type suitable for sound and audio applications.
  - b) Two (2) conductor, 22 AWG Solid, tinned copper, 17.5 ohm per 1000 feet, overall 75 degree PVC jacket with a nominal O.D. of .118 inch, 22 AWG solid drain wire. UL Listed NEC Type CM; constructed in accordance with UL Standard 444; complies with UL 1581 Vertical Tray Flame Test; meets 300 volt requirements as specified in Section 800-51 of the NEC.
- 2) Manufacturers
- a) Basis of Design
    - (1) West Penn #450
  - b) Acceptable Substitutions
    - (1) Belden
    - (2) CommScope
- b. Speaker Cable:
- 1) General
    - a) The speaker cable shall be a power-limited type suitable for sound and audio applications.
    - b) Two (2) conductor minimum 16 AWG, UL Listed NEC type CL2, complying with UL 1581 Vertical Tray Flame Test, bare copper, nominal DCR of 4.2 Ohms per 1000 feet, with PVC insulation with nylon, and short overall twist lengths.
  - 2) Project Performance Requirements
    - a) The Contractor shall increase the size of speaker cables as necessary for the connected speaker load.
  - 3) Manufacturers
    - a) Basis of Design
      - (1) West Penn #C205
    - b) Acceptable Substitutions
      - (1) Belden
      - (2) CommScope

PART 3 - EXECUTION

3.1 Comply with the requirements of Section 27 05 00.

3.2 Labels

A. General

1. All equipment, control and system cabling shall be provided with permanent descriptive labels.
2. The Contractor shall provide samples of labeling with his submittals for review by the Designer.
3. Equipment and cable labels shall be noted on the Contractor's as-built drawings exactly as they are installed on the equipment or cables.

B. Equipment

1. The Contractor shall provide and install permanent, engraved labels on all equipment where the original manufacturer has not already provided labels.
2. All custom, fabricated, or field assembled assemblies and equipment shall be provided with permanent engraved or non-removable silk-screened labels. The Contractor shall provide samples of labels to Designer for review and approval prior to fabrication or final installation. The Contractor shall modify labeling as required by the Designer.

C. Outlet Plates

1. Shall be installed level and flush with the mounting surface.

D. Cables

1. The Contractor shall provide and install a permanent, machine printed, protected label on both ends of each system cable. The label at each end of the cable shall provide the following information:
  - a. Signal type shall be either plain English or represented by the following designators
    - 1) M = microphone level audio
    - 2) L = line level audio
    - 3) S = speaker level audio
    - 4) R = RGBHV video
    - 5) V = S-Video
    - 6) C = Composite video
    - 7) +C = Control
  - b. Room number where other end of cable is terminated
  - c. Where system cables are routed between buildings the Contractor shall preface the Room Number with a Building Number
  - d. Room numbers shall coincide with numbering scheme included in contract documents.
  - e. Device identifier where other end of cable is terminated

- f. Device identifier shall provide a clear indication of device connected to (i.e. VCR 1, slide-to-video, projector 1, speaker zone A, microphone outlet 5, etc.)

### 3.3 TESTING

A. Comply with Section 27 05 00 "Common Work Results for Communications"

B. Audio

1. Equalization

- a. The purpose of the equalization is to adjust the acoustic amplitude response of the Audio system to a specified uniformity measured throughout the entire audience area. This adjustment is made to realize maximum acoustic gain and optimum tonal balance from the Audio system throughout the audience area and stage monitoring area.
- b. Instrumentation: Provide the following minimal standard laboratory test equipment. Any substitutions or additions to the following list must be accepted by the Designer.

- 1) Impedance Bridge.
- 2) Audio Oscillator.
- 3) Random-noise generator.
- 4) Precision sound level meter.
- 5) Octave real-time audio frequency analyzer.
- 6) Oscilloscope.
- 7) Sound level calibrator.
- 8) Master equalizer set with broad band (i.e. full octave) and narrow band (i.e. 1/3 octave), high-pass, and low-pass filters, plus comparator switch and attenuator.
- 9) Digital camera.

c. Inspection of Audio System Prior to Equalization:

- 1) Prior to undertaking equalization of the Audio System, perform the following inspections on the Audio System, and submit to the Designer the written results of each inspection for inclusion on the permanent records of the Audio System.
- 2) Measure and record the impedance of each loudspeaker line before connecting it to the output of its respective amplifier. The load impedance shall be equal to or greater than the rated impedance. Record the total impedance.
- 3) Measure and record the output impedance of each active device operating as a source to any passive device or series of passive devices. Record the dc resistance of any buildout resistor used.
- 4) Measure and record the input impedance of any active device used to terminate passive devices, and record the total impedance of all such devices. Record the dc resistance of any terminating resistor used.



- 5) Measure and record the acoustic distribution of the loudspeakers in the Audio System throughout the entire seating area. Record the location of all positions in the seating area where any 1/3 octave band, from 250 to 5000 Hz. deviates more than #3 dB from the desired house curve.
  - 6) Measure and record the polarity of all microphones to be used in the system.
  - 7) Measure and record, with an oscilloscope, the output of each power amplifier. The input source to each amplifier being measured shall be a sinewave oscillator with less than 0.5% THD adjusted to 10 dB less than full power output of the amplifier. Inspect the output sinewave appearing on the oscilloscope of complete freedom from hum, noise, parasitic oscillation and RF interference.
  - 8) Measure and record the frequency response of each mixer preamplifier and power amplifier in the system.
- d. House-Curve Equalization: Temporarily install the master equalizer set in the appropriate link circuit in the Audio System. Use pink noise as a source signal, and place a calibrated measuring microphone in the seating area at twice the critical distance (2dc). (Critical distance is defined as that distance from the sound source at which the direct sound from the source and the reverberation sound are in a ratio of one to one.) The acoustic amplitude response that appears on the screen to the real-time spectrum analyzer shall be recorded. Point-to-point measurements, averaging estimates, and other non-real-time dynamic measurements shall be unacceptable under this specification. After the unequalized acoustic amplitude response is recorded, the master equalizer set shall be used to bring the observed acoustic amplitude with +3 dB uniformity (or better, if possible) and to conform to the predetermined high frequency roll-off detected by the combination effect of humidity, air absorption, and the random incidence of the measuring microphone. The equalized house curve shall be recorded.
- 1) Control of Microphone Characteristics and Preferred Feedback Frequencies: Install the required filters in the link circuit ahead of the power amplifier input; then reconnect the master equalizer set in the link circuit following the microphone mixer amplifier. The Audio System gain shall be adjusted until it reaches regeneration (feedback). Determine the frequency of regeneration by observing the response of the real-time audio spectrum analyzer, and adjust the appropriate filter until the observed regeneration ceases.
  - 2) Microphone Proximity Instability: Suppress the tendency of the Audio system microphone to become unstable when approached by a talker. Identify the 1/3 octave band affected by the approach of a person, and provide enough attenuation to ensure stability. Records shall be made of additional attenuation provided.
- e. Documentation of Tests, Measurements, and Adjustments Performed:
- 1) List of personnel and certified test equipment used.

- 2) Impedance of all loudspeaker lines.
  - 3) Output impedance of all active sources connected to passive devices and the value of any buildout resistor used.
  - 4) The input impedance of all active devices used to terminate passive devices and the value of any termination resistor used.
  - 5) The variation of acoustic distribution throughout the seating area above and below a reference level at each 1/3 octave center frequency from 20 to 5000 Hz.
  - 6) The recorded polarity of the loudspeakers.
  - 7) The documented information for all settings in the audio mixer / processor.
  - 8) The list of microphones tested.
  - 9) The recorded inspection results observed for hum, noise, parasitic oscillation, and RF interference from the output of each power amplifier.
  - 10) The unequalized house curve made with the measuring microphone.
  - 11) The electrical response of the house-curve filters without the microphone filters.
  - 12) The electrical response of the house-curve filters with the microphone filters.
  - 13) The unequalized house curve made with the Audio System microphone.
  - 14) The proximity frequencies and attenuations
  - 15) All filter settings.
  - 16) The factors  $D_c$ , %ALcons,  $D_1$ ,  $D_s$ ,  $D_2$ ,  $D_0$ , NAG, PAG, EAD and EPR for the Audio System and the room:
    - 17)  $D_c$  = Critical distance
    - 18) %ALcons =  $656D_2^2RT602/VQ$
    - 19)  $D_0$  = Distance from the talker to the farthest listener
    - 20)  $D_1$  = Distance from the microphone to the nearest loudspeaker
    - 21)  $D_s$  = Distance from the microphone to the talker
    - 22)  $D_2$  = Distance from the loudspeaker to the farthest listener
    - 23) NAG = Needed acoustic gain
    - 24) PAG = Potential acoustic gain
    - 25) EAD = Equivalent acoustic distance
    - 26) EPR = Electrical power required
    - 27) Q = Directivity of the loudspeaker
    - 28) RT60 = Reverberation time
    - 29) V = Volume of room in cubic feet
- f. Equalization Filters:
- 1) No filters shall be accepted that are not constant-K, 600 ohm filters. Any filter whose impedance changes at its resonant frequency will not be accepted.
  - 2) Active circuit equalizers of the minimum phase band rejection type may be substituted for the constant K passive type.
- g. Upon completion of all equalization adjustments the Contractor shall permanently, in a highly professional manner, mark the equalizer with

the final settings. This marking shall be permanent, highly visible and shall not damage the surface of the equalizer.

C. Video

1. Test all cables for shorts, opens, and grounds. Record results.
2. Accomplish an operational test of the video signals utilizing color bars, still pictures, and motion video to demonstrate proper video signal to all video targets.
3. Visible evidence of banding, bending, blooming, chroma delay, improper convergence, hum bars, ground loops, jaggies, jitter, luma delay, retrace, signal loss, smearing, horizontal double images, vertical double images, or wrap around shall not be acceptable. The Contractor shall make system adjustments as necessary to eliminate any of these abnormalities.

D. Control

1. Accomplish full operational test of the system to verify all system programming is correct and functions as intended.

END OF SECTION 27 41 13

SECTION 28 21 10 – INTRUSION DETECTION SYSTEM (EXTENSION OF EXISTING)

PART 1 - GENERAL

1.1 RELATED SECTIONS

- A. Comply with the requirements of Section 27 05 00 "Common Work Results for Communications".

1.2 DEFINITIONS

- A. Not used.

1.3 DESCRIPTION OF SYSTEM:

- A. Provide and install a complete and fully functional extension of the existing Intrusion Detection System as shown on the drawings and specified herein.
- B. System shall include:
  - 1. Audio Sensors
  - 2. System Wire and Cable
  - 3. Raceway, fittings, outlet boxes, etc.
  - 4. Wire and cable labeling
  - 5. J-Hook type support assemblies

1.4 SPECIAL REQUIREMENTS

- A. Not used.

1.5 FUNCTIONS AND OBJECTIVES

- A. Provide and install a complete and satisfactorily functioning extension of the existing system.

PART 2 - PRODUCTS

2.1 AUDIO SENSORS

- A. The existing Audio Sensors are to be removed and reinstalled as noted on the drawings.

2.2 CABLE:

- A. General

1. Provide multi-conductor insulated copper conductors with overall jacket as required by the intrusion detection system manufacturer to provide a complete, fully operational, UL Listed Intrusion Detection System.
2. Cables shall be plenum rated where installed in plenum spaces.
3. Cables shall not be installed below slab or in wet locations.
4. The Contractor shall field verify routing of cables prior to submitting Product Data or Shop Drawings under the submittal process.

B. Device Requirements

1. Audio Sensors

- a. Homerun from each device to serving IDF room as shown on the drawings.
- b. Shall be a 22 AWG, 4 conductor, unshielded, twisted, jacketed cable.
- c. Manufacturers

1) Basis of Design

- a) Belden 5502UE (non-plenum) or acceptable substitution
- b) Belden 6502UE (plenum) or acceptable substitution

PART 3 - EXECUTION

3.1 GENERAL

- A. Comply with the requirements of Sections 27 05 00 and 27 10 00.
- B. Circuit routing for the system is not necessarily shown on the project drawings. The Contractor shall be responsible for the installation of the raceways, wiring and cabling necessary for a complete and fully functional system.
- C. The contractor shall provide and install the intrusion detection system (including raceways, pull and back boxes, and cable/wire) in accordance with the intrusion detection system manufacturer's requirements.
- D. Installation of device back boxes shall be in accordance with the system manufacturer's requirements.
- E. Termination of devices shall be in accordance with manufacturer's requirements.

3.2 TESTING

- A. Comply with the requirements of Section 27 05 00.

END OF SECTION 28 21 10

SECTION 28 22 10 – ACCESS CONTROL SYSTEM (EMPTY RACEWAY)

PART 1 - GENERAL

1.1 RELATED SECTIONS

- A. Comply with the requirements of Section 27 05 00 "Common Work Results for Communications".

1.2 DEFINITIONS

- A. OFOI: Owner Furnished, Owner Installed.

1.3 DESCRIPTION OF SYSTEM:

- A. Provide and install a complete empty raceway system for the Owner furnished and installed Access Control System as shown on the drawings and specified herein.
- B. System shall include:
  - 1. Raceway, fittings, outlet boxes, etc.
  - 2. Power (refer to Division 26)
  - 3. Grounding
  - 4. Surge Suppression

1.4 SPECIAL REQUIREMENTS

- A. The Owner's staff will provide and install all equipment, materials, cabling, programming, testing, and labor necessary for the Access Control system.
- B. Door Hardware will be powered by the OFOI Access Control system.

1.5 FUNCTIONS AND OBJECTIVES

- A. Provide and install a complete empty raceway system in accordance with the drawings.

PART 2 - PRODUCTS

- A. Not used.

PART 3 - EXECUTION

3.1 GENERAL

- A. Comply with the requirements of Section 27 05 00.
- B. Installation of device back boxes shall be in accordance with the system manufacturer's requirements.

### 3.2 SURGE SUPPRESSION

- A. Install surge suppression device on all 120 volt power sources to equipment. Surge suppression on 120 VAC circuits shall be provided and installed by the electrical sub-contractor. Coordinate with Division 26 to ensure that surge suppression for 120 VAC power circuit and surge suppression required by this section for each system are installed in same terminal cabinet and bonded together.

### 3.3 TESTING

- A. Comply with the requirements of Section 27 05 00.

END OF SECTION 28 22 10

SECTION 28 31 00 – FIRE ALARM SYSTEM (EXTENSION OF EXISTING)

PART 1 - GENERAL

1.1 RELATED SECTIONS

- A. Comply with the requirements of Section 27 05 00 "Common Work Results for Communications".
- B. Comply with applicable requirements of Division 23.
- C. In addition to the requirements of 27 05 00 comply with the following requirements:
  - 1. Related Sections
    - a. Applicable sections of these specifications with regard to, but not limited to:
      - 1) Doors
      - 2) Sound Systems
    - b. Standards, Codes, References, And Regulatory Requirements
      - 1) The system shall have proper listing and/or approval from the following nationally recognized agencies:
        - a) UL Underwriters Laboratories Inc
        - b) ULC Underwriters Laboratories Canada
        - c) MEA Material Equipment Acceptance (NYC)
        - d) FM Factory Mutual
        - e) CSFM California State Fire Marshal
  - 2. Submittals
    - a. Where the Authority Having Jurisdiction requires the Contractor to submit signed and sealed drawings with his permit application it shall be the responsibility of the Fire Alarm Installer to have his drawings signed and sealed by his own Professional Engineer. The Engineer of Record for the project will not sign and seal the Contractor's drawings.
- D. The equipment and installation shall comply with the current or applicable provisions of the following standards, codes, references, and regulatory requirements:
  - 1. NFPA
    - a. NFPA 13 – Standard for the installation of Sprinkler Systems
    - b. NFPA 72 – National Fire Alarm Code
    - c. NFPA 90A – Standard for the Installation of Air-Conditioning and Ventilating Systems



- d. NFPA 101 – Safety to Life from Fire in Buildings and Structures
2. Underwriters Laboratories
- a. UL 13 – Power-Limited Circuit Cables
  - b. UL 38 – Manual Signaling Boxes for Fire Alarm Systems
  - c. UL 217 – Single and Multiple Station Smoke Alarms
  - d. UL 228 – Door Closers-Holders, With or Without Integral Smoke Detectors
  - e. UL 268 – Smoke Detectors for Fire Protective Signaling Systems
  - f. UL 268A – Smoke Detectors for Duct Application
  - g. UL 521 – Heat Detectors for Fire Protective Signaling Systems
  - h. UL 539 – Single and Multiple Station Heat Detectors
  - i. UL 864 – Control Units for Fire Protective Signaling Systems
  - j. UL 1424 – Cables for Power-Limited Fire Alarm Circuits
  - k. UL 1425 – Cables for Non-Power-Limited Fire-Alarm Circuits
  - l. UL 1480 – Speakers for Fire Protective Signaling Systems
  - m. UL 1481 – Power Supplies for Fire Protective Signaling Systems
  - n. UL 1635 – Digital Alarm Communicator System Units
  - o. UL 1711 – Amplifiers for Fire Protective Signaling Systems
  - p. UL 1971 - Signaling Devices for the Hearing Impaired
3. Local and State Building Codes
- a. Florida Building Code: 2014 edition including references and revisions.
  - b. Florida Fire Prevention Code: 2014 edition including references and revisions.
  - c. Florida Administrative Code. All applicable chapters.
  - d. Florida Department of Insurance:
    - 1) Insurance Code: The fire alarm system and installation thereof shall comply with the State of Florida Department of Insurance rules. The requirements of the Florida State Department of Insurance shall be as promulgated by the Division of State Fire Marshal.
    - 2) Fire Alarm Rules: The fire alarm system and installation thereof shall comply with the Fire Safety Rules promulgated by the Florida State Fire Marshal.
  - e. Authority Having Jurisdiction: The systems shall comply with applicable Codes, Ordinances and Standards as interpreted and enforced by the local authority having jurisdiction.
4. Surge Suppression
- a. Equipment Certification: When available by any one manufacturer, all surge suppression equipment shall be listed by Underwriters' Laboratories, shall bear the UL seal and be marked in accordance with referenced standard. Such surge suppression equipment shall be UL listed and labeled for intended use.

- b. Comply with all standards and guides as listed under "References" above.
5. Quality Assurance
- a. Installer:
    - 1) The Installer shall be currently licensed by the Electrical Contractors' Licensing Board as a Statewide Alarm Contractor I (EF).
    - 2) The Installer's Field Supervisor shall be currently certified by the National Institute for Certification in Engineering Technologies as a NICET Level III or Level IV. NICET Level I or Level II shall not be acceptable.
  - b. Manufacturer: Company specializing in manufacturing the products specified in this section with minimum ten (10) years experience and with service facilities within 50 miles of Project.
  - c. Installer:
    - 1) Company specializing in installing the products specified in this section with minimum ten (10) years experience.
    - 2) The Installer shall be currently licensed by the Electrical Contractors' Licensing Board as a Certified Alarm System Contractor I (EF).
    - 3) The installing Contractor shall be a direct sales division of, or the authorized and designated distributor for, a fire alarm system manufacturer.
    - 4) Installing Contractor shall maintain a local staff of specialists, including a Fire Alarm Planning Superintendent, for planning, installation, and service.
    - 5) The installing Contractor shall maintain an office within fifty (50) miles of the project with capability to provide emergency service 7-days-a-week, 24 hour days. The installing Contractor shall have been actively engaged in the business of selling, installing and servicing fire alarm systems for at least ten (10) consecutive years going back from date of bid.
6. Submittals
- a. Each system power supply including stand alone booster supplies
  - b. Each standby battery bank
  - c. Each notification appliance circuit
  - d. Each auxiliary control circuit that draws power from a system power supply.
  - e. Submit all load calculations and cable/wire sizing for each branch of the individual fire alarm field circuits. Wire sizing calculations to prove maximum three percent (3%) voltage drop at all AC voltages and maximum eight percent (8%) voltage drop at all DC voltages.
7. Additional Devices For Jurisdictional Compliance

- a. Prior to bid, the Contractor shall review plans and specifications carefully for compliance with all codes and in particular, the ADA Requirements and NFPA 72. Contractor shall include in bid price any devices required to provide a fully compliant system. Said additional devices shall be shown on shop drawings submitted by contractor.
8. Maintenance Service
- a. Furnish service and maintenance of fire alarm system for one (1) year from date of Substantial Completion.
  - b. No charge shall be made by the installer and/or contractor for any labor, equipment, or transportation during this period to maintain functions.
  - c. Respond to trouble call within twenty-four (24) hours after receipt of such call.
  - d. Provide annual testing and inspection of fire alarm system at end of first year in accordance with NFPA 72. Correct any deficiencies found at no cost to the Owner. Affix fire alarm tag to panel.
9. Extra Materials
- a. Provide six (6) keys of each type.
  - b. Provide three (3) of each type of surge suppression device.

## 1.2 DEFINITIONS

- A. Not Used.

## 1.3 SPECIAL REQUIREMENTS

- A. The work of this project is being accomplished in shell space of an existing building. The Contractor shall remove and reinstall and provide additional new devices as necessary to provide and install a fully functional, Code compliant extension of the existing system. The Contractor shall rework the existing system circuits in the area to incorporate reinstalled existing devices and new devices as necessary. The Contractor shall field verify the existing system power supplies for load and battery backup capacity and shall modify the system as necessary either through the addition of additional power supplies or increasing the size of the required batteries. Provide calculations as part of the submittal process to verify the specific requirements.

## 1.4 DESCRIPTION OF SYSTEM:

- A. Provide and install a complete extension of the existing system .
- B. The system equipment shall include but not be limited to:
  1. Smoke Detectors
  2. Duct Detectors
  3. Heat Detectors
  4. Analog and Addressable Fire Alarm Relays
  5. Combination Audible/Visual devices (indoor and outdoor weatherproof as indicated on the drawings)

6. Visual devices (indoor and outdoor weatherproof as indicated on the drawings)
  7. Remote power supplies (Remote power supplies shall be in a UL Listed assembly and be provided by the same manufacturer as the Fire Alarm Control Panel (FACP)).
  8. Surge Suppression
  9. Programming.
  10. Grounding
  11. Wire and cable labeling.
  12. Electrical power required to comply with all functions and operations called for in this section of the specifications. Contractor shall provide and install all 120 VAC circuits as required.
  13. Conduit, wire, wire fittings, terminal cabinets with plywood and terminal strips, and all accessories required to provide a complete operating system.
  14. A complete and accurate schematic/drawing of the fire alarm system to be placed adjacent to the fire alarm annunciator panel and the main fire alarm panel.
- C. Unless specifically noted otherwise, Fire Alarm System equipment shall be the product of a single manufacturer.
- D. Contractor shall furnish and install all equipment (raceways, wire/cable, circuit breakers, modules, relays, etc.) necessary, and as required by applicable code, to accomplish incidental functions of the fire alarm system including but not limited to the following:
1. HVAC system control and/or shutdown.
  2. Ventilation system (supply fans, exhaust fans, fan terminal boxes, etc.) control and/or shutdown.
- E. System shall operate as currently configured.
- F. System shall be wired as currently configured.
- G. System is to be a complete analog addressable system.
- H. Conduit and boxes to be installed by Electrical Contractor. System cabling, devices and equipment shall be by the Fire Alarm Installer.
- I. Fire alarm system shall not share a raceway, junction box, enclosure, manhole or device with any other system
- J. Provide and install wiring, equipment, etc. for connection to devices furnished under other divisions of the work.
- K. Provide and install wiring, equipment, etc. as required to deactivate power to computer power panels and air conditioning equipment by automatic or manual devices as shown on plans.
- L. Although they may not be indicated on the Fire Alarm system diagram and/or drawings, all required control and interlock wiring between the Fire Alarm system and building equipment shall be provided hereunder. Controls are required to/for/from:

1. Fire/smoke air and duct detectors
  2. Fire, smoke and/or combination fire/smoke dampers.
  3. Supply/Return fans, Exhaust fans, and/or Fan Terminal Boxes (FTB)
  4. Sprinkler and/or Fire Protection system components
- M. Provide and install all relays (electric-electric, electric-pneumatic, and/or pneumatic-electric) as required for a complete and operational fire alarm system, complying with all applicable codes and all requirements, and coordinated with all divisions of these specifications.
- N. Provide terminal cabinets sized to house terminal strips and surge suppression equipment.
- O. Surge Suppression
1. The contractor shall have equipment installed on the AC voltage supply and other lines taking care to arrest damaging electrical transient and spikes which can cause damage to the microprocessor components of the system. Central office telephone lines shall have equipment installed to arrest high voltages from electrical and/or lightning from entering the system and causing damage.
  2. Provide and install all materials, labor and auxiliaries required to furnish and install complete surge suppression for the protection of building fire alarm system from the effects of induced transient voltage surge and lightning discharge as indicated on drawings or specified in this section.
  3. Provide surge suppression equipment at the following locations:
    - a. On each conductor pair and cable sheath entering or leaving a building.
    - b. On each conductor associated with fire protection (sprinkler) system fire alarm connections.
    - c. On any and all telephone lines.
    - d. In other locations where equipment sensitivity to surges and transients requires additional protection beyond that inherent to the design of the equipment. Where equipment being protected has internal surge suppression equipment, the surge protection equipment herein specified is required to be installed in addition to internal equipment protection.

## 1.5 FUNCTIONS AND OBJECTIVES

- A. System Operation shall operate as currently programmed.
- B. Zoning shall match current installation.

## PART 2 - PRODUCTS

### 2.1 FIRE ALARM SYSTEM COMPONENTS:

- A. Audible Notification Devices:

1. General

- a. Shall be horn type devices.
- b. Audible notification devices located on the exterior of a building, or in a damp or wet location, shall be a weatherproof version and rated, by the manufacturer, for use in wet locations.
- c. Audible portion of the audible/visual notification devices shall be UL listed for fire protective service and shall provide 24 VDC inputs and sound output of not less than 75 dBA at 10 feet, or more than 120 dBA at the minimum hearing distance from the audible appliance.
- d. Audible portion of the audible/visual notification device shall comply with ANSI S3.41 for signal character conformance.
- e. Audible portion of audible/visual notification devices located on the exterior of a building, or in a damp or wet location, shall be a weatherproof version and rated, by the manufacturer, for use in wet locations.
- f. A suitable polycarbonate cover shall be provided to protect devices at locations where they may be subject to damage such as Gymnasiums.

B. Visual Notification Devices

1. Shall meet the requirements of the ADA, UL Standard 1971 and shall meet the following criteria:
  - a. The maximum pulse duration shall be 2/10 of one second.
  - b. Strobe intensity shall meet the requirements of UL 1971.
  - c. The flash rate shall meet the requirements of UL 1971.
2. Visual portion of the audible/visual notification devices shall comply with the Americans with Disabilities Act which includes the following:
  - a. Lamp shall be a xenon strobe type or equivalent.
  - b. Color shall be clear or nominal white (i.e. unfiltered or clear filtered white light).
  - c. Maximum pulse duration shall be two-tenths of one second (0.2 sec) with a maximum duty cycle of 40 percent. Pulse duration is defined as the time interval between initial and final points of 10 percent of maximum signal.
  - d. Intensity shall be a minimum of 75 candela. Use of visual devices rated at 15/75, 15 or 30 candela shall not be acceptable.
  - e. Flash rate shall be a minimum of 1 Hz and a maximum of 3 Hz.
  - f. More than two visible notification appliances in the same room or adjacent space within the field of view must flash in synchronization. This requirement shall not preclude synchronization of appliances that are not within the same field of view.
3. A suitable polycarbonate cover shall be provided to protect devices at locations where they may be subject to damage such as Gymnasiums.

C. Field Wiring Terminal Blocks

1. For ease of service all panel I/O wiring terminal blocks shall be removable, plug-in types and have sufficient capacity for #18 to #12 AWG wire. Terminal blocks which are permanently fixed are not acceptable.

D. Manufacturers

1. Basis of Design
  - a. Silent Knight or acceptable substitution

2.2 FIRE ALARM SYSTEM COMPONENTS – ADDRESSABLE DEVICES:

A. Addressable Devices – General

1. Addressable devices shall use simple to install and maintain decade, numbered 0 to 9, address switches. Detectors that have expanded addressing will have decade switch numbered from 0 to 15 for the most significant digit to allow detector addressing from 1 to 159.
2. Addressable devices which use a binary-coded address setting method, such as a DIP switch, are not an allowable substitute.
3. Detectors shall be intelligent (analog) and addressable, and shall connect with two wires to the fire alarm control panel signaling line circuits.
4. Addressable smoke and thermal detectors shall provide dual alarm and power/polling LEDs. Both LEDs shall flash under normal conditions, indicating that the detector is operational and in regular communication with the control panel, and both LEDs shall be placed into steady illumination by the control panel, indicating that an alarm condition has been detected. If required, the LED flash shall have the ability to be removed from the system program. An output connection shall also be provided in the base to connect an external remote alarm LED.
5. The fire alarm control panel shall permit detector sensitivity adjustment through field programming of the system. Sensitivity shall be automatically adjusted by the panel on a time-of-day basis.
6. Using software in the FACP, detectors shall automatically compensate for dust accumulation and other slow environmental changes that may affect their performance. The detectors shall be listed by UL as meeting the calibrated sensitivity test requirements of NFPA Standard 72, Chapter 7.
7. The detectors shall be ceiling-mount and shall include a separate twist-lock base with tamper proof feature. Base shall include a sounder base with a built-in (local) sounder rated at 85 DBA minimum, a relay base and an isolator base designed for Style 7 applications.
8. The detectors shall provide a test means whereby they will simulate an alarm condition and report that condition to the control panel. Such a test may be initiated at the detector itself (by activating a magnetic switch) or initiated remotely on command from the control panel.
9. Detectors shall also store an internal identifying type code that the control panel shall use to identify the type of device (ION, PHOTO, THERMAL).
10. Detectors will operate in an analog fashion, where the detector simply measures its designed environment variable and transmits an analog value to the FACP based on real-time measured values. The FACP software, not the detector, shall make the alarm/normal decision, thereby allowing the sensitivity of each detector to be set in the FACP program and allowing the system operator to view the current analog value of each detector.

11. Detectors shall provide address-setting means using decimal switches and shall also store an internal identifying code that the control panel shall use to identify the type of device. LEDs shall be provided that shall flash under normal conditions, indicating that the device is operational and is in regular communication with the control panel.
  12. Addressable devices shall provide address-setting means using decimal switches and shall also store an internal identifying code that the control panel shall use to identify the type of device. LED(s) shall be provided that shall flash under normal conditions, indicating that the device is operational and is in regular communication with the control panel.
  13. A magnetic test switch shall be provided to test detectors and modules. Detectors shall report an indication of an analog value reaching 100% of the alarm threshold.
- B. Intelligent Photoelectric Smoke Detector
1. The detectors shall use the photoelectric (light-scattering) principal to measure smoke density and shall, on command from the control panel, send data to the panel representing the analog level of smoke density.
- C. Intelligent Ionization Smoke Detector
1. The detectors shall use the dual-chamber ionization principal to measure products of combustion and shall, on command from the control panel, send data to the panel representing the analog level of products of combustion.
  2. Ionization Smoke Detectors shall be installed in locations such as Media Centers.
- D. Intelligent Thermal Detectors
1. Thermal detectors shall be intelligent addressable devices rated at 135 degrees Fahrenheit (58 degrees Celsius) and have a rate-of-rise element rated at 15 degrees F (9.4 degrees C) per minute. It shall connect via two wires to the fire alarm control panel signaling line circuit.
- E. Intelligent Duct Smoke Detector
1. The smoke detector housing shall accommodate either an intelligent ionization detector or an intelligent photoelectric detector, of that provides continuous analog monitoring and alarm verification from the panel.
  2. Detector shall be zoned so that when either the supply or the return detector senses smoke it will cause a supervisory/trouble indication at the Fire Alarm Control Panel and immediately shut down the air handler. The duct mounted detectors shall not cause a general alarm to sound.
- F. Addressable Control Module
1. Addressable control modules shall be provided to supervise and control the operation of one conventional NACs of compatible, 24 VDC powered, polarized audio/visual notification appliances. For fan shutdown and other auxiliary control functions, the control module may be set to operate as a dry contract relay.



2. The control module shall mount in a standard 4-inch square, 2-1/8 inch deep electrical box, or to a surface mounted backbox.
3. The control module NAC may be wired for Style Z or Style Y (Class A/B) with up to 1 amp of inductive A/V signal, or 2 amps of resistive A/V signal operation, or as a dry contact (Form-C) relay. The relay coil shall be magnetically latched to reduce wiring connection requirements, and to insure that 100% of all auxiliary relay or NACs may be energized at the same time on the same pair of wires.
4. Audio/visual power shall be provided by a separate supervised power circuit from the main fire alarm control panel or from a supervised, UL listed remote power supply.
5. The control module shall be suitable for pilot duty applications and rated for a minimum of 0.6 amps at 30 VDC.

G. Isolator Module

1. Isolator modules shall be provided to automatically isolate wire-to-wire short circuits on an SLC Class A or Class B branch. The isolator module shall limit the number of modules or detectors that may be rendered inoperative by a short circuit fault on the SLC loop segment or branch. At least one isolator module shall be provided for each floor or protected zone of the building.
2. If a wire-to-wire short occurs, the isolator module shall automatically open-circuit (disconnect) the SLC. When the short circuit condition is corrected, the isolator module shall automatically reconnect the isolated section.
3. The isolator module shall not require any address-setting, and its operations shall be totally automatic. It shall not be necessary to replace or reset an isolator module after its normal operation.
4. The isolator module shall mount in a standard 4-inch (101.6 mm) deep electrical box or in a surface mounted backbox. It shall provide a single LED that shall flash to indicate that the isolator is operational and shall illuminate steadily to indicate that a short circuit condition has been detected and isolated.

H. Manufacturers

1. Basis of Design
  - a. Silent Knight or acceptable substitution

2.3 FIRE ALARM SYSTEM BATTERIES:

- A. The battery shall have sufficient capacity to power the fire alarm system for not less than twenty-four hours plus 5 minutes of alarm upon a normal AC power failure.
- B. The batteries are to be completely maintenance free. No liquids are required. Fluid level checks for refilling, spills, and leakage shall not be required.
- C. If necessary to meet standby requirements, external battery and charger systems may be used.

2.4 RELAYS:

- A. Relays required for control (i.e. Air Handler shutdown, Supply Fan shutdown, Exhaust Fan shutdown, Fan Terminal Box shutdown, Door Lock release, Fire Shutter release, Smoke Damper closure, Fire Damper closure, Smoke/Fire Damper closure, or any other interface required by these specifications or applicable codes) shall be UL Listed relays suitable for use in Fire Alarm systems.
- B. Per NFPA, relays used for control of other systems shall be located within three feet (3') of the device to be controlled.
- C. Relays shall be analog addressable devices powered and controlled from the fire alarm system. Each relay shall contain address switches to assign a unique input point for programming or control by the system.
- D. Each relay shall provide at least one set of Form "C" dry relay contacts.
- E. Manufacturers
  - 1. Basis of Design
    - a. Silent Knight or acceptable substitution

2.5 PATHWAYS:

- A. Comply with the requirements of Section 27 05 00.

2.6 CABLE:

- A. Contractor shall provide and install cable as required by the manufacturer to provide a complete, fully operational, UL Listed Fire Alarm system.
- B. Fire alarm system cables installed in interior, exterior and/or underground raceways shall comply with the applicable sections of NEC Articles 760, 770 and 800.
- C. Cables shall be for power-limited fire alarm signal service Type FPL, and NRTL listed and labeled as complying with NFPA 70 Article 760, UL 1424 and UL 2196. Where installed in return air plenums cable shall be plenum rated. All vertical Fire Alarm cables and wiring traversing more than one level shall be routed in rated enclosures. In addition, all horizontal wiring serving devices located on floors other than where wiring originates shall be routed in 2-inch concrete encasement, suitable rated building construction, or 2-hour wrap application enclosure accepted by local authority having jurisdiction.
- D. Zip and zip type cables (e.g. West Penn 970, 971, 972, 974 or similarly constructed cables from other manufacturers) shall not be acceptable.
- E. Conductor: 98% conductivity, stranded copper with maximum of 19 strands. Stranded conductors shall have a compression lug installed at every end. Wrapping twisted strands at terminal block screw is not acceptable. As an acceptable equivalent, stranded conductors without crimp-on lugs may be terminated into terminal strips of box-lug connectors. SLC loops may use solid conductors.

- F. Insulation: A type accepted by NEC for the application. All cable shall be UL listed for fire-protective signaling application. Communication, Class 3 or Multi-Purpose cables shall not be substituted for FP cable types. All multiconductor cables shall have individually insulated conductors with an overall outer jacket.
- G. Size: All conductors shall be sized as prescribed by the system manufacturer, with following minimums:
1. Multiplex Signaling Line Circuit: AWG #16, solid.
  2. Notification Circuits, Devices: AWG #14, THHN/THWN stranded conductors.
  3. Initiating Circuits, Hard-Wired Devices: AWG #14, THHN/THWN stranded conductors.
  4. Initiating Circuits, Addressable Devices: AWG #14, shielded twisted pair.
  5. The above wire sizes shall be increased to size as required to comply with authority having jurisdiction or as required for voltage drop, load, etc. Provide larger conductors where required to maintain voltage drop or signal strength within acceptable limits.
  6. Multiplex signal line circuits and addressable circuits shall be either shielded or unshielded based on equipment manufacturer's recommendations for specific application.
- H. UL:
1. General: Fire-protective signaling cable shall be UL listed as non-power limited or power limited as needed to match the output of the fire alarm equipment.
  2. Non-Power Limited: Fire protective signaling circuits classified as non-power limited shall use cable listed under UL Electrical Construction Materials Directory. Category HNHT, "NON-POWER LIMITED FIRE-PROTECTIVE SIGNALING CABLE". All such cable shall have fire resistance, listing and markings as described in NEC 760. Minimum cable marking shall be NPLF.
  3. Power Limited: Fire protective signaling circuits classified as power limited shall use cable listed under UL Category HNIR, "POWER LIMITED FIRE-PROTECTIVE SIGNALING CABLE". All such circuits shall be durably marked where plainly visible at terminations to indicate that it is a power-limited fire protective signaling circuit. Refer to paragraph titled "Fire Resistance of Cables" for additional requirements.
  4. Fire Resistance of Cables: Power-limited fire-protective signaling circuit cables shall be UL listed as described in NEC 760. All such cable shall bear a cable marking that includes a Type designation as given in NEC 760. Provide Type FPL.
- I. Wiring color code shall be as follows:
1. Horns/Strobes: Black/Red
  2. Door Holders: White
  3. Air Handler Duct Detectors: Purple
  4. Gas Shut-Off Pull Stations: Orange
  5. Addressable: Twisted Pair Data Wire
  6. Hard-Wired: Brown/Blue
- J. Manufacturers

1. Basis of Design
  - a. Belden
2. Acceptable Substitutions
  - a. West Penn Wire
  - b. Draka

### PART 3 - EXECUTION

#### 3.1 GENERAL

- A. Comply with the requirements of Section 27 05 00.
- B. Pathways:
  1. Wiring for 24 volt DC control, alarm notification, emergency communication and similar power-limited auxiliary functions may be run in the same conduit as initiating and signaling line circuits. The system shall be designed to permit simultaneous operation of all circuits without interference or loss of signals.
  2. Conduit shall not enter the fire alarm control panel, or any other remotely mounted control panel equipment or backboxes, except where conduit entry is specified by the FACP manufacturer.
- C. Contractor is advised that circuit routing for this system is not necessarily shown on the project drawings. The contractor shall provide and install all raceways, wiring and cabling required for a complete and fully functional system as intended by these specifications. Contractor shall provide and install a properly sized, flush mounted outlet box for every device. Contractor shall size and route raceways to accommodate the proper installation of the system cabling. T-Tapped cabling shall not be acceptable. In locations where raceway and/or conduit is not accessible after completion of the project, conduit shall be routed from device to device or fire rated access panels shall be installed to provide access to junction and pull boxes. Routing of raceway from device to device shall only be acceptable where the wiring scheme of the system, as recommended by the manufacturer, requires cable to pass from device to device. Contractor shall properly terminate each device according to the manufacturer's recommendations.
- D. Locate, install, and test fire alarm and detection systems in accordance with the equipment manufacturer's written instructions, and the latest editions of the National Electric Code, the National Electrical Contractor's Association publication "Standard of Installation" and all applicable codes and standards referenced in this specification.
- E. Provide all work required for a complete system including complete system test and checkout. All components shall be properly mounted and wired. The installation of this system shall comply with the directions and recommendations of authorized factory representatives.
- F. Provide wiring, cabling, raceways, and electrical boxes in accordance with manufacturer's written instructions.

- G. Components shall be electrically "burned-in" by operating the component at full power for a period as recommended by the manufacturer.
- H. Installation shall be done in a neat workmanlike fashion by a firm regularly engaged in Fire Alarm Installation and Service.
- I. The installation and inspection of all fire detection and fire alarm devices and systems shall be performed by, or under the direct on-site supervision of, a licensed fire alarm technician or a fire alarm planning superintendent who shall certify the work upon completion of the activity. The certifying licensee shall be present for the final test prior to certification.
- J. As-built plans and wiring diagrams shall bear the signature and license number of the licensed fire alarm planning superintendent, the date of installation and the name, address, and certificate-of-registration number of the registered firm.
- K. All components shall be completely wired. System shall be fully operable when main power service has failed and the Emergency Standby Generator has assumed emergency system loads. This shall require that any devices which required 120 volt power shall receive supply from an emergency 120 volt source.
- L. Installation of detectors:
  - 1. All ceiling mounted detectors shall be installed in accordance with the requirements of NFPA 72.
  - 2. All concealed detectors shall be provided with a remote indicating lamp and test switch installed in an occupied space (corridor, etc.) on wall or on the ceiling grid indicating the type of detector and the zone to which it is connected. Label shall be red with white lettering.
  - 3. Duct detectors shall be installed in accordance with NFPA 90A. All brackets and hardware shall be provided as required to install detector housing in correct position. All detector housings shall be sealed as required to prevent air leakage between duct and housing. Sampling tubes of proper length shall be provided and installed to match duct width at the installed location.

### 3.2 RACEWAYS AND BOXES

- A. Comply with the requirements of Section 27 05 00.
- B. Provide dedicated raceway with applicable boxes for all fire alarm wiring in accordance with applicable sections of these specifications.
- C. All initiating, indicating and auxiliary control devices shall be mounted on UL listed outlet boxes.

### 3.3 WIRE/CABLE

- A. Comply with the requirements of Section 27 05 00.
- B. Comply with NECA 1 and NFPA 72.
- C. Connections of Installation Wiring:

1. Connections to Equipment: In accordance with NFPA for monitoring integrity and with the equipment manufacturer's instructions.
2. Connections of installation wiring to alarm initiating devices and alarm indicating appliances shall be monitored for integrity.
3. Interconnecting means shall be arranged so that a single break or single ground fault will not cause an alarm signal.
4. Apply a compression lug, similar to T&B Sta-Kon Terminal, to all stranded conductors at terminations or use box-lug terminal strips.
5. There shall be no wire splices. All wiring shall be continuous, uncut between devices and terminal blocks.
6. Install plenum cable in environmental air spaces, including plenum ceilings.
7. Fire alarm circuits and equipment control wiring associated with the fire alarm system shall be installed in a dedicated raceway system. This system shall not be used for any other wire or cable.
8. Cables and raceways used for fire alarm circuits, and equipment control wiring associated with the fire alarm system, may not contain any other wire or cable.
9. Fire-Rated Cables: Use of 2-hour, fire-rated fire alarm cables, NFPA 70, Types MI and CI, is not permitted.
10. Wiring shall be in accordance with local, state and national codes (e.g., NEC Article 760) and as recommended by the manufacturer of the fire alarm system. Number and size of conductors shall be as recommended by the fire alarm system manufacturer, but not less than 18 AWG (1.02 mm) for Initiating Device Circuits and Signaling Line Circuits, and 14 AWG (1.63 mm) for Notification Appliance Circuits.
11. All wire and cable shall be listed and/or approved by a recognized testing agency for use with a protective signaling system.
12. Wire and cable not installed in conduit shall have a fire resistance rating suitable for the installation as indicated in NFPA 70 (e.g., FPLR).
13. Wiring used for the multiplex communication circuit SLC shall be twisted and shielded and support a minimum wiring distance of 10,000 feet. The design of the system shall permit use of IDC and NAC wiring in the same conduit with the SLC communication circuit.
14. All field wiring shall be electrically supervised for open circuit and ground fault.

D. Rated Enclosures:

1. All vertical fire alarm wiring traversing more than one level shall be routed in rated enclosures. In addition, all horizontal wiring serving devices located on floors other than where wiring originates shall be routed in 2-inch concrete encasement, suitable rated building construction, or 2-hour wrap application enclosure accepted by local authority having jurisdiction.
2. Install wiring in a metal raceway system according to Division [26][16] Section "Raceway and Boxes for Electrical Systems."
  - a. Wire and cable shall be installed in a complete raceway system.
3. Wiring within Enclosures: Separate power-limited and non-power-limited conductors as recommended by manufacturer. Install conductors parallel with or at right angles to sides and back of the enclosure. Bundle, lace, and train conductors to terminal points with no excess. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with the fire alarm system to terminal blocks. Mark each terminal according to the

system's wiring diagrams. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors. Color-coding: Color-code fire alarm conductors differently from the normal building power wiring. Use one color-code for alarm circuit wiring and another for supervisory circuits. Color-code audible alarm-indicating circuits differently from alarm-initiating circuits. Use different colors for visible alarm-indicating devices. Paint fire alarm system junction boxes and cover red. Risers: Install at least two vertical cable risers to serve the fire alarm system. Separate risers in close proximity to each other with a minimum one-hour-rated wall, so the loss of one riser does not prevent the receipt or transmission of signals from other floors or zones.

### 3.4 MANUAL PULL STATIONS

- A. Install at 48 inches to top above finished floor.
- B. All manual stations shall be in unobstructed locations.
- C. Install to comply with NFPA, ADA, and all handicap/accessibility code requirements.
- D. Provide, install, and connect additional pull stations (from that shown on drawings) as required to comply with above requirements.
- E. Shall be installed within five (5) feet of each exit door.

### 3.5 AUDIBLE SIGNAL DEVICES, VISUAL SIGNAL DEVICES OR COMBINATION AUDIBLE/VISUAL SIGNAL DEVICES

- A. Shall comply with NFPA, the Americans with Disabilities Act and other applicable handicap/accessibility codes including but not limited to the following:
  - 1. Wall mounted devices shall have their bottom edge at heights above the finished floor of not less than 80 inches and no greater than 96 inches.
  - 2. In general, no place in any room or space required to have a visual signal appliance shall be more than 50 ft. (15 m) from the signal (in the horizontal plane). In large rooms and spaces exceeding 100 ft. (30 m) across, without obstructions 6 ft. (2 m) above the finished floor, such as auditoriums, devices may be placed around the perimeter, spaced a maximum 100 ft. (30 m) apart, in lieu of suspending appliances from the ceiling. Placement of visual devices shall not be less than the requirements as specified by NFPA 72.
  - 3. No place in common corridors or hallways in which visual alarm signaling appliances are required shall be more than 50 ft. (15 m) from the signal. Placement of visual devices shall not be less than the requirements as specified by NFPA 72.
  - 4. Audible device dB levels shall comply with NFPA 72 requirements and shall be a minimum of 15 dB above average ambient room noise or 5 dB above maximum room noise levels. The Contractor shall add devices as necessary to ensure dB levels per NFPA are met in all required spaces.

### 3.6 END-OF-LINE DEVICE

- A. Mount end-of-line device box with last device or separate box adjacent to last device in circuit.

### 3.7 DUCT DETECTORS

- A. Duct Detectors installed in concealed locations, locations more than ten feet (10'0") above finished floor, or installed so that the detector's supervisory indicator is not visible shall be provided with a remote test and indicator stations. Remote test and indicator stations shall be installed 48" A.F.F. in a readily accessible location.

### 3.8 AUXILIARY CONTROL RELAYS

- A. An auxiliary fire alarm relay used to control an emergency control device, e.g. motor controller for HVAC system fan or elevator controller shall be located within 3 ft. of the emergency control device.
- B. The installation wiring between the system panel and the auxiliary fire alarm relay shall be monitored for integrity.
- C. Auxiliary control relays shall be listed for use with fire alarm systems.

### 3.9 CABLE IDENTIFICATION

- A. Provide and install permanent cable markers on all cables/wire lines, telephone lines, etc. at terminal strips, terminal cabinets and at main equipment.

### 3.10 CONDUIT/BOX IDENTIFICATION

- A. Contractor shall identify fire alarm conduit and boxes with red paint in exposed locations. Identify conduit in concealed locations with 4" mark of red paint every 4'-0" O.C.

### 3.11 DEMONSTRATION

- A. When system is complete it shall be demonstrated to Owner's Representative who shall be given complete instructions, spare parts, manuals and maintenance information.

### 3.12 TESTING

- A. Comply with the requirements of Section 27 05 00.
- B. The service of a competent, factory-trained engineer or technician authorized by the manufacturer of the fire alarm equipment shall be provided to technically supervise and participate during all of the adjustments and tests for the system. All testing shall be in accordance with NFPA 72.
- C. Before energizing the cables and wires, check for correct connections and test for short circuits, ground faults, continuity, and insulation.
- D. Close each sprinkler system flow valve and verify proper supervisory alarm at the FACP.
- E. Verify activation of all waterflow switches.



- F. Open initiating device circuits and verify that the trouble signal actuates.
- G. Open and short signaling line circuits and verify that the trouble signal actuates.
- H. Open and short notification appliance circuits and verify that trouble signal actuates.
- I. Ground all circuits and verify response of trouble signals.
- J. Check presence and audibility of tone at all alarm notification devices.
- K. Check installation, supervision, and operation of all intelligent smoke detectors using the walk test.
- L. Each of the alarm conditions that the system is required to detect should be introduced on the system. Verify the proper receipt and the proper processing of the signal at the FACP and the correct activation of the control points.
- M. When the system is equipped with optional features, the manufacturer's manual shall be consulted to determine the proper testing procedures. This is intended to address such items as verifying controls performed by individually addressed or grouped devices, sensitivity monitoring, verification functionality and similar.

### 3.13 SYSTEM DEMONSTRATION

- A. Prior to certification of the fire alarm system the contractor shall accomplish a complete test of the fire alarm system in accordance with NFPA 72, Test Methods.
- B. Perform a complete, functional, component by component test of the entire fire alarm and detection system. Provide a detailed step by step testing procedure which is unique to this project, reflecting the type of system and the number and location of all components.
- C. Perform a sensitivity test of all smoke detectors and duct detectors. Perform a calibration/test of heat sensors.
- D. Demonstrate the proper operation of each component as follows:
  - 1. Photoelectric, and duct smoke detectors: activate the detector with a "false smoke" product which has been specifically formulated for testing smoke detection systems.
  - 2. Heat detectors: activate the detector by utilizing the detector check button.
  - 3. Pull Stations: activate the station by operating the station in its normal mode.
  - 4. Audible and Visual Alarms: verify proper operation when the system is put into the alarm mode.
  - 5. Sprinkler Flow Switches: open the sprinkler system's inspection test valve. Verify that the flow switch sends an alarm signal within the allowed time corresponding to the switch's time delay setting.
  - 6. Fire Alarm Panels: functionally check-out and test the panel per the manufacturer's written instructions. Demonstrate the proper operation of each modular component. Demonstrate automatic power change to batteries and back to building power upon a drop in voltage below the voltage threshold as specified by the panel manufacturer.

7. Demonstrate the supervisory function at each device loop circuit, and at all single component wiring runs such as for the sprinkler valve supervisory switches.

### 3.14 CERTIFICATION

- A. After completion of the installation of the system, the licensee shall complete a NFPA Inspection and Testing form. The Inspection and Testing form format shall be as indicated in NFPA 72, Inspection and Testing Form. When an Inspection and Testing form has been completed, legible copies shall be distributed as directed by the Authority Having Jurisdiction.
- B. After an installation has been complete, affix a Fire Alarm Tag to the control panel. The Fire Alarm Tag is in addition to the Inspection and Testing form. Protect the Fire Alarm Tag from vandalism by applying pressure sensitive label; do not use a "tie-on" tag. It shall be as required in the Fire Safety Rules.
- C. After completion of the installation and testing provide NFPA 72 Record of Completion form to the Owner.

### 3.15 FINAL DRAWINGS

- A. As-built drawings shall be given to the Owner's representative, at time of instruction, in addition to those to be supplied as general requirements of the job.

### 3.16 AUTHORITY HAVING JURISDICTION

- A. The drawings and specifications herein comply to the best of the Designer's knowledge with all applicable codes at time of design. However, it is this contractor's responsibility to coordinate/verify (prior to bid) the requirements of the Authority Having Jurisdiction over this project and bring any discrepancies to the engineer's attention at least 7 days prior to bid. No changes in contract cost will be acceptable after the bid for work/equipment required to comply with the authority having jurisdiction.

END OF SECTION 28 31 00

PAGE LEFT INTENTIONALLY BLANK