

March 28, 2017

**BOARD OF COUNTY COMMISSIONERS
ORANGE COUNTY, FLORIDA**

**ADDENDUM NO. 1 / IFB NO. Y17-745-RM
BITHLO PARK NEW PLAYGROUND & SHADOW BAY PARK PLAYGROUND
IMPROVEMENTS**

BID OPENING DATE IS APRIL 11, 2017

This Addendum is hereby incorporated into the bid documents of the project referenced above. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. Additions are indicated by underlining, deletions are indicated by ~~strikethrough~~.

A. The bid opening date remains April 11, 2017.

B. The following are questions/responses/clarifications:

1. **Question:** According to drawings, you will be only accepting Xccent, Gametime or Rep Services with no exceptions. Is that accurate?

Answer: Please refer to Section C #7 Substitute Material and Equipment of the solicitation.

2. Delete section 01005-1 of Volume II and replace with the attached revised section 01005-1
3. Delete section 01005-1 of Volume III and replace with the attached revised section 01005-1

C. All other terms, conditions and specifications remain the same.

The Bidder shall acknowledge receipt of this addendum by completing the applicable section in the solicitation or by completion of the acknowledgement information on the addendum. Either form of acknowledgement must be completed and returned not later than the date and time for receipt of the bid.

Receipt acknowledged by:

Authorized Signature

Date Signed

Title

Name of Firm

SECTION 01005-ADMINISTRATIVE PROVISIONS

PART I GENERAL

1.01 WORK COVERED BY CONTRACT DOCUMENTS

- A. Work of this Contract comprises site work, dewatering operations, road work, utilities, grading, paving, drainage, ditches, ponds, irrigation, demolition and related construction work to produce a complete and functional PLAYGROUND AT BITHLO PARK including but not limited to new PLAYGROUND, irrigation system, updated parking lot, site work, underground utilities, paving, concrete, excavation, compacting, and landscaping/irrigation for the construction of the NEW PLAYGROUND AT BITHLO PARK.

1.02 CONTRACT METHOD

- A. Construct the work under a single lump sum contract (or as otherwise defined in bid documents).

1.03 COORDINATION

- A. Coordinate work of the various Sections of Specifications to assure efficient and orderly sequence of installation of construction elements, with provisions for accommodating items installed later.
- B. Verify characteristics of elements of interrelated operating equipment are compatible; coordinate work of various Sections having interdependent responsibilities for installing, connecting to and placing in service such equipment. Differences shall be brought to the Owner's attention during bid process or remain the responsibility of the Contractor.
- C. Coordinate space requirements and installation of items, such as but not limited to, mechanical, plumbing, systems and electrical work which are indicated diagrammatically or otherwise on drawings. Follow routing shown for pipes, ducts and conduits, as closely as practicable; make runs parallel with lines of building. Utilize spaces efficiently to maximize accessibility for other installations, for facility maintenance and for future repairs.
- D. In finished areas (except as otherwise shown), conceal pipes, ducts, and wiring in the construction. Coordinate locations of fixtures and outlets with finish elements.
- E. Execute cutting and patching to integrate elements of work, uncover ill timed, defective and nonconforming work, provide openings for penetrations of existing surfaces and provide samples as specified in individual sections for

testing. Seal penetrations through floors, walls and ceilings, and fire safe where necessary as part of the lump sum price.

1.04 FIELD ENGINEERING SURVEYING

- A. Provide field engineering surveying services; establish grades, lines and levels, by use of engineering survey practices recognized as standard by the survey industry. Said work shall be required to be provided by a Professional Land Surveyor, registered as such in the State of Florida.

1.05 REFERENCE STANDARDS

- A. For products specified by association or trade standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.
- B. The date of the standard is that in effect when a specified date is specified and if no date is specified, use the latest edition.
- C. Obtain copies of referenced standards listed in individual specification sections. Maintain copy at job site during progress of the specific work.

END OF SECTION 01005

SECTION 01005-ADMINISTRATIVE PROVISIONS

PART I GENERAL

1.01 WORK COVERED BY CONTRACT DOCUMENTS

- A. Work of this Contract comprises site work, dewatering operations, road work, utilities, grading, paving, drainage, ditches, ponds, irrigation, demolition and related construction work to produce a complete and functional PLAYGROUND AND FITNESS AREA AT SHADOW BAY PARK including but not limited to, irrigation system, updated parking lot, site work, underground utilities, paving, concrete, excavation, compacting, and landscaping/irrigation for the construction of the NEW PLAYGROUND AND FITNESS AREA AT SHADOW BAY PARK.

1.02 CONTRACT METHOD

- A. Construct the work under a single lump sum contract (or as otherwise defined in bid documents).

1.03 COORDINATION

- A. Coordinate work of the various Sections of Specifications to assure efficient and orderly sequence of installation of construction elements, with provisions for accommodating items installed later.
- B. Verify characteristics of elements of interrelated operating equipment are compatible; coordinate work of various Sections having interdependent responsibilities for installing, connecting to and placing in service such equipment. Differences shall be brought to the Owner's attention during bid process or remain the responsibility of the Contractor.
- C. Coordinate space requirements and installation of items, such as but not limited to, mechanical, plumbing, systems and electrical work which are indicated diagrammatically or otherwise on drawings. Follow routing shown for pipes, ducts and conduits, as closely as practicable; make runs parallel with lines of building. Utilize spaces efficiently to maximize accessibility for other installations, for facility maintenance and for future repairs.
- D. In finished areas (except as otherwise shown), conceal pipes, ducts, and wiring in the construction. Coordinate locations of fixtures and outlets with finish elements.
- E. Execute cutting and patching to integrate elements of work, uncover ill timed, defective and nonconforming work, provide openings for penetrations of existing surfaces and provide samples as specified in individual sections for

testing. Seal penetrations through floors, walls and ceilings, and fire safe where necessary as part of the lump sum price.

1.04 FIELD ENGINEERING SURVEYING

- A. Provide field engineering surveying services; establish grades, lines and levels, by use of engineering survey practices recognized as standard by the survey industry. Said work shall be required to be provided by a Professional Land Surveyor, registered as such in the State of Florida.

1.05 REFERENCE STANDARDS

- A. For products specified by association or trade standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.
- B. The date of the standard is that in effect when a specified date is specified and if no date is specified, use the latest edition.
- C. Obtain copies of referenced standards listed in individual specification sections. Maintain copy at job site during progress of the specific work.

END OF SECTION 01005