

NOVEMBER 9, 2018
BOARD OF COUNTY COMMISSIONERS
ORANGE COUNTY, FLORIDA
IFB Y19-714-RC / ADDENDUM #1
ORANGE COUNTY SHERIFF'S OFFICE CENTRAL OPERATIONS SECURITY
ENHANCEMENTS

THE REVISED BID OPENING DATE IS NOVEMBER 20, 2018

This addendum is hereby incorporated into the bid documents of the project referenced above. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. Underlining indicates additions, deletions are indicated by ~~strikethrough~~.

A. The bid opening date remains unchanged.

B. Questions/Answers/Clarifications.

- 1. Question:** The door and hardware schedule calls for all glazing in doors to be level III ballistic resistant. The scope of work on A00.00 notes specifically that the door to human resources should be ballistic resistant and makes reference to ballistic components for other areas. However, the doors themselves are not noted as being ballistic resistant on the door schedule, and the frames are called out on the schedule as hollow metal frames. What are the ballistic resistance requirements for the doors?

Answer: Door and Frame should be level III ballistic resistant.

- 2. Question:** Door schedule shows one door in 1204A being replaced. The plan of 1204A on A01.01 shows two doors on the wall of 1204A that is being upgraded to ballistic resistant. Is the other door existing to remain? If so, is it a ballistic door/frame?

Answer: The other door is existing to remain and not ballistic resistant. The client only wanted to replace the one door as shown on the plans and elevations.

- 3. Question:** The scope of work on A00.00 notes that the wall of 1204A is to be upgraded to ballistic resistant; the plan on A01.01 only shows installing ballistic glazing and countertop. Please verify that no ballistic panels are being added to this wall.

Answer: No ballistic panels are being added to this wall. Only BR door, window and countertop.

- 4. Question:** Scope on A00.00 notes that the overhead doors are to be replaced and to 'meet current criteria'. What criteria are being referenced here?

Y19-714-RC
Addendum 1
November 9, 2018

Answer: Overhead door must comply with Florida Wind loads and have a Florida Product Approval

5. **Question:** Please provide door jamb and head details where needed to reflect the additional layer of ballistic paneling.

Answer: Similar to head detail 3/A00.32 verify with manufacturer installation recommendations.

6. **Question:** Please provide electrical details of doors having access control components showing required conduit runs.

Answer: Conduit runs will for door access control will consist of J-box in wall for device and conduit run from J-box to 6" above ceiling.

7. **Question:** Notes on A00.50 call for a maximum 5% run slope on sidewalks. 2/A00.50 shows 8% max for the sidewalk in the lower half of the plan. Is the 8% slope correct?

Answer: This should state 5% and not 8%. Sidewalk running slopes should not exceed 5% running slope as noted on sheet A00.50.

8. **Question:** Note 2 on sheet A00.50 refers to a landscaping plan that is not included in drawings. Can you please provide?

Answer: There are no landscape plans. General Contractor to replant bushes/hedges as necessary and return area to match existing conditions. Remove and salvage plantings and replant where possible.

- C. All other terms and conditions of the IFB remain the same. The Proposer shall acknowledge receipt of this addendum by completing the applicable section in the solicitation or by completion of the acknowledgement information on the addendum. Either form of acknowledgement must be completed and returned not later than the date and time for receipt of the bid.**

Receipt acknowledged by:

Authorized Signature

Date Signed

Title

Name of Firm