
SPT BORING RESULTS FOR CULVERT (EAST OF JOHN YOUNG PARKWAY) SCALE: AS SHOWN



LEGEND:

BT BORING TERMINATED

N STANDARD PENETRATION RESISTANCE, BLOWS PER FOOT

W/H WEIGHT OF HAMMER

W/R WEIGHT OF ROD

-200 PERCENT PASSING NO. 200 U.S. STANDARD SIEVE (FM 1-T 088)

OC ORGANIC CONTENT (%) (FM 1-T 267)

SOIL LEGEND

SAND	MUCK AND SAND
SILT AND SAND	MUCK

NOTES

SUBSURFACE CONDITIONS SHOWN ON THE BORING LOGS DO NOT NECESSARILY REPRESENT THE CONDITIONS BETWEEN THE BORINGS LOCATION. ACTUAL CONDITIONS IN THE VICINITY OF THE BORINGS MAY VARY FROM THOSE SHOWN. UNIFIED SOIL CLASSIFICATIONS SHOWN ON THE BORING LOGS ARE BASED ON VISUAL EXAMINATION AND THE LABORATORY TEST RESULTS SHOWN.

THE STANDARD PENETRATION TEST BORINGS WERE PERFORMED IN ACCORDANCE WITH ASTM D—1586. STANDARD PENETRATION RESISTANCES ARE SHOWN ON THE BORING LOGS AT THE TEST DEPTHS IN BLOWS PER FOOT UNLESS OTHERWISE NOTED.

THE BORING LOCATIONS WERE NOT SURVEYED BUT APPROXIMATED USING PROMINENT SITE FEATURES SHOWN ON PLANS PROVIDED BY LOCHRANE ENGINEERING INC.

BASED ON A REVIEW OF THE U.S. GEOLOGICAL SURVEY MAP ENTITLED "POTENTIOMETRIC SURFACE OF THE UPPER FLORIDAN AQUIFER IN THE SEPTEMBER 2005" FOR THE PROJECT AREA, THE MAXIMUM ELEVATION OF THE ARTESIAN HEAD IS ESTIMATED TO BE APPROXIMATELY +55 TO +60 ft. NGVD. THE CONTRACTOR SHALL BE PREPARED TO HANDLE ARTESIAN HEAD LEVELS UP TO +55 TO +60 ft. NGVD.

SPLIT SPOON SAMPLER:
INSIDE DIAMETER: 1.375 IN.
OUTSIDE DIAMETER: 2.0 IN.
AVG. HAMMER DROP: 30 IN.
HAMMER WEIGHT: 140 LBS.
HAMMER TYPE: SAFETY (MANUAL)

GRANULAR SOILS	N VALUE (blows/foot)	RELATIVE DENSITY
SANDS	0-4 4-10 10-30 30-50 OVER 50	VERY LOOSE LOOSE MED, DENSE DENSE VERY DENSE
NON-GRANULAR SOILS	N VALUE (blows/foot)	CONSISTENCY
SILTS, CLAYS, MUCK, PEAT	0-2 2-4 4-8 8-15 15-30 OVER 30	VERY SOFT SOFT FIRM STIFF VERY STIFF HARD

FIGURE 15

REVISIONS

DATE BY DESCRIPTION DATE BY DESCRIPTION

GECTECHNICAL AND ENVIRONMENTAL CONSULTANTS, INC.
1230 E. HILLGREST STREET ORLANDO, FLORIDA 32803
CERTIFICATE OF AUTHORIZATION NO. 00005882
M.CHAEL J. PREIM, P.E. 24041





HOLDEN A VENUE
BORING RESULTS

SHEET NO.

SPT BORING RESULTS FOR CULVERT SOUTH OF LAKE BUCHANNANLEGEND:







 $rac{
abla}{0.5}$ estimated seasonal high groundwater depth (ft.)

TE ENCOUNTERED GROUNDWATER DEPTH (FT.)

 ${\sf N}$ standard penetration resistance, blows per foot

(SP-SM) UNIFIED SOIL CLASSIFICATION SYMBOL

BT BORING TERMINATED

-200 percent passing no. 200 u.s. standard sieve (FM 1-T 088)

SOIL LEGEND



SILT AND SAND

NOTES

SUBSURFACE CONDITIONS SHOWN ON THE BORING LOGS DO NOT NECESSARILY REPRESENT THE CONDITIONS BETWEEN THE BORINGS LOCATION. ACTUAL CONDITIONS IN THE VICINITY OF THE BORINGS MAY VARY FROM THOSE SHOWN. UNIFIED SOIL CLASSIFICATIONS SHOWN ON THE BORING LOGS ARE BASED ON VISUAL EXAMINATION AND THE LABORATORY TEST RESULTS SHOWN.

THE STANDARD PENETRATION TEST BORINGS WERE PERFORMED IN ACCORDANCE WITH ASTM D—1586. STANDARD PENETRATION RESISTANCES ARE SHOWN ON THE BORING LOGS AT THE TEST DEPTHS IN BLOWS PER FOOT UNLESS OTHERWISE NOTED.

THE BORING LOCATIONS WERE STAKED AND SURVEYED BY LOCHRANE ENGINEERING, INC.

BASED ON A REVIEW OF THE U.S. GEOLOGICAL SURVEY MAP ENTITLED "POTENTIOMETRIC SURFACE OF THE UPPER FLORIDAN AQUIFER IN THE SEPTEMBER 2005" FOR THE PROJECT AREA, THE MAXIMUM ELEVATION OF THE ARTESIAN HEAD IS ESTIMATED TO BE APPROXIMATELY +55 TO +60 ft. NGVD. THE CONTRACTOR SHALL BE PREPARED TO HANDLE ARTESIAN HEAD LEVELS UP TO +55 TO +60 FT. NGVD.

SPLIT SPOON SAMPLER: INSIDE DIAMETER: 1.375 IN. OUTSIDE DIAMETER: 2.0 IN. AVG. HAMMER DROP: 30 IN. HAMMER WEIGHT: 140 LBS. HAMMER WEIGHT: 140 LBS.

GRANULAR SOILS	N VALUE (blows/foot)	RELATIVE DENSITY
SANDS	0-4 4-10 10-30 30-50 OVER 50	VERY LOOSE LOOSE MED. DENSE DENSE VERY DENSE

	N VALUE	
von-granular soils	(blows/foot)	CONSISTENCY
SILTS, CLAYS, MUCK, PEAT	0-2 2-4 4-8 8-15 15-30 0VER 30	VERY SOFT SOFT FIRM STIFF VERY STIFF HARD

FIGURE 16


REVISIONS DESCRIPTION DESCRIPTION DATE BY BY DATE





POND 3 BORING RESULTS

PB-5




BORING NO.

L 10 - 12


- 13

- 14 - 16 17

- 18 - 19



5.7



-200=5 K=6.8

6.0

7.5

BT @ 20'

HA-3

71+00



6.1 **V** 7.6

BT @ 20'

-200=7



BT @ 20'

5.9

7.4



5.9

7.4


















POND 1 BORING RESULTS












POND 3 PRELIMINARY HAND AUGER BORING RESULTS SCALE: AS SHOWN

BORING NO. HA-1





BT @ 20'






BT @ 20'

HA-2

70+40


450' RT

8-21-06



BORING LEGEND

BT @ 20'



-200= PERCENT PASSING NO. 200 U.S. STANDARD SIEVE (FM 1-T 088) K= PERMEABILITY (FEET PER DAY)

STRATUM NUMBER	AASHTO SOIL CLASSIFICATION SYMBOL	DESCRIPTION
1	A-3	BROWN TO GRAY FINE SAND AND FINE SAND WITH SILT, OCCASIONAL TRACE ORGANICS AND CEMENTED LENSES
2	A-2-4	BROWN TO GRAY FINE SAND WITH SILT AND SILTY FINE SAND, OCCASIONAL TRACE ORGANICS
3	A-8	DARK BROWN MUCKY FINE SAND TO SANDY MUCK

FIGURE 17

REVISIONS DATE BY DESCRIPTION BY DESCRIPTION DATE



HOLDEN A VENUE **BORING RESULTS**

SHEET NO.

STATION OFFSET		_12+50 50' RIGHT	_13+00 50' LEFT	_13+00 	_13+00_ 50' RIGHT	_13+50_ 50' LEFT		_13+50_ 50' RIGHT
	7.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 2.0 SAND (FT.)	2.0 STANDING WATER (FT.) 7.0 MUCK (FT.) 2.0 SAND (FT.)	0.5 STANDING WATER (FT.) 8.5 MUCK (FT.) 0.5 SAND (FT.)	5.0 STANDING WATER (FT.) 2.0 MUCK (FT.) 1.0 SAND (FT.)	0.5 STANDING WATER (FT.) 8.5 MUCK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) 8.0 MUCK (FT.) O.5 SAND (FT.)	5.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) 7.0 MUCK (FT.) 2.0 SAND (FT.)
STATION OFFSET	14+00 50' LEFT	14+00 	14+00 50' RIGHT	14+50 50' LEFT	14+50 C/L		15+00 50' LEFT	15+00
	O.5 STANDING WATER (FT.) 5.0 MUCK (FT.) 2.0 SAND (FT.)	4.5 STANDING WATER (FT.) O.O MUCK (FT.) 1.0 SAND (FT.)	1.0 STANDING WATER (FT.) 2.0 MUCK (FT.) 5.0 SAND (FT.)	0.5 STANDING WATER (FT.) 3.0 MUCK (FT.) 0.5 SAND (FT.)	4.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	O.5 STANDING WATER (FT.) 4.0 MUCK (FT.) O.5 SAND (FT.)	2.5 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)
STATION OFFSET	_15+00 50' RIGHT		15+50 	_15+50_ 50' RIGHT	16+00 	_16+00_ 50' RIGHT	16+50 	_16+50_ 50' RIGHT
	2.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) 4.O MUCK (FT.) O.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 1.0 MUGK (FT.) 0.5 SAND (FT.)	4.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 1.0 SAND (FT.)	5.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	2.0 STANDING WATER (FT.) 4.0 MUCK (FT.) 0.5 SAND (FT.)
STATION OFFSET	17+00 50' LEFT	17+00 	<u>17+00</u> 50' RIGHT	17+50 50' LEFT	17+50 		18+00 50' LEFT	18+00
	O.O STANDING WATER (FT.) 6.O MUCK (FT.) O.5 SAND (FT.)	5.0 STANDING WATER (FT.) O.0 MUCK (FT.) 2.0 SAND (FT.)	3.0 STANDING WATER (FT.) 5.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 4.0 MUCK (FT.) 0.5 SAND (FT.)	6.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	2.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 3.0 MUCK (FT.) 0.5 SAND (FT.)	5.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 3.0 SAND (FT.)
STATION OFFSET		18+50 50' LEFT	18+50 	<u>18+50</u> 50' RIGHT	19+00 C/L		19+50 50' LEFT	19+50 C/L
	2.0 STANDING WATER (FT.) 2.0 MUCK (FT.) 0.5 SAND (FT.)	O.5 STANDING WATER (FT.) 3.0 MUCK (FT.) C.5 SAND (FT.)	4.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 3.0 MUCK (FT.) 0.5 SAND (FT.)	4.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	1.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 1.5 MUCK (FT.) 0.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)
STATION OFFSET	_19+50_ 50' RIGHT	_20+00 C/L	<u>20+00</u> 50' RIGHT	_20+50 50' LEFT		_20+50_ 50' RIGHT	21+00 50' LEFT	21+00
	O.5 STANDING WATER (FT.) 3.0 MUCK (FT.) O.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 1.0 SAND (FT.)	0.5 STANDING WATER (FT.) 2.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 2.0 MUCK (FT.) 0.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 1.5 SAND (FT.)	O.5 STANDING WATER (FT.) 1.5 MUCK (FT.) O.5 SAND (FT.)	0.5 STANDING WATER (FT.) 2.0 MUCK (FT.) 0.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)
STATION OFFSET	_21+00 50' RIGHT	<u>21+50</u> 50' LEFT	21+50 					<u>22+50</u> 50' LEFT
	3.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 2.0 MUCK (FT.) 0.5 SAND (FT.)	2.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 1.5 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 2.0 MUCK (FT.) 0.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	1.5 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	O.5 STANDING WATER (FT.) 1.5 MUCK (FT.) O.5 SAND (FT.)
STATION OFFSET	22+50 C/L	<u>22+50</u> 50' RIGHT	<u>23+00</u> 50' LEFT	23+00 C/L	_ <u>23+00_</u> 50' RIGHT		23+50 C/L	<u>23+50</u> 50' RIGHT
	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	2.0 STANDING WATER (FT.) 1.5 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 1.5 MUCK (FT.) 0.5 SAND (FT.)	4.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 2.5 SAND (FT.)	0.5 STANDING WATER (FT.) 2.0 MUCK (FT.) SAND (FT.)	0.5 STANDING WATER (FT.) 1.0 MUCK (FT.) 1.0 SAND (FT.)	4.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)
STATION OFFSET	_24+00 50' LEFT		_24+00 50' RIGHT	_24+50_ 50' LEFT		_24+50_ 50' RIGHT	_25+00_ 50' LEFT	_25+00_ 50' RIGHT
	O.O STANDING WATER (FT.) 1.O MUCK (FT.) O.5 SAND (FT.)	O.5 STANDING WATER (FT.) AUCK (FT.) SAND (FT.)	1.5 STANDING WATER (FT.) O.5 MUCK (FT.) O.5 SAND (FT.)	0.5 STANDING WATER (FT.) 3.0 MUCK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) 3.0 MUCK (FT.) O.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 2.0 SAND (FT.)	0.5 STANDING WATER (FT.) 7.0 MUCK (FT.) 0.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)
					NOTES	DITIONS SHOWN ON THE PROPES SO NOT S	EDDESCRIT, THE SOUL CONDITIONS OF THE SOUL CONDITIONS	THE PROPER LOCATIONS

SUBSURFACE CONDITIONS SHOWN ON THE PROBES DO NOT REPRESENT THE SOIL CONDITIONS BETWEEN THE PROBE LOCATIONS. ACTUAL SOIL CONDITIONS BETWEEN THE PROBES MAY VARY FROM THOSE SHOWN ON THE PROBES. THE PROBE RESULTS ARE BASED ON VISUAL EXAMINATION.

THE PROBES WERE PERFORMED JULY 19-20. 2004.

FIGURE 18

ı	REVISIONS								
ľ	DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION			
ı									
ı									
L									

GECTECHNICAL AND ENVIRONMENTAL
CONSULTANTS, INC.
919 LAKE BALDWIN LANE
ORALNDO, FLORIDIA 32814
CERTIFICATE OF AUTHORIZATION NO. 00005882
MCHAEL J. PREM, P.E. 24041





SHEET NO.

STATION OFFSET		_25+50 50' RIGHT	_26+00 50' LEFT	_26+00 C/L	_26+00 50' RIGHT	26+50 50' LEFT		
	3.5 STANDING WATER (FT.) 7.0 MUGK (FT.) 0.5 SAND (FT.)	3.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 6.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	2.5 STANDING WATER (FT.) 0.0 MUGK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 3.5 MUGK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) O.O MUGK (FT.) O.5 SAND (FT.)	1.5 STANDING WATER (FT.) O.0 MUCK (FT.) SAND (FT.)
STATION OFFSET			_27+00_ 50' RIGHT	_27+50_ 50' LEFT	_27+50 	_27+50 50' RIGHT	_28+00 	
	O.O STANDING WATER (FT.) 2.5 MUCK (FT.) O.5 SAND (FT.)	O.O STANDING WATER (FT.) O.O MUCK (FT.) O.5 SAND (FT.)	2.5 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	2.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 1.0 SAND (FT.)	O.O STANDING WATER (FT.) O.O MUCK (FT.) O.5 SAND (FT.)
STATION OFFSET	_28+00_ 50' RIGHT	<u>28+50</u> 50' LEFT		<u>28+50</u> 50' RIGHT	<u>29+00</u> 50' LEFT		<u>29+00</u> 50' RIGHT	<u>29+50</u> 50' LEFT
	1.5 STANDING WATER (FT.) O.0 MUCK (FT.) 1.0 SAND (FT.)	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 1.0 SAND (FT.)	1.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 1.0 SAND (FT.)	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 0.5 SAND (FT.)	1.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) O.O MUCK (FT.) O.5 SAND (FT.)
STATION OFFSET	<u>29+50</u> C/L	<u>29+50</u> 50' RIGHT	<u>30+00</u> 50' LEFT	30+00 C/L	<u>30+00</u> 50' RIGHT	<u>30+50</u> 50' LEFT	30+50 C/L	<u>30+50</u> 50' RIGHT
	O.O STANDING WATER (FT.) O.5 MUCK (FT.) O.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	1.5 STANDING WATER (FT.) 0.0 MUCK (FT.) 1.0 SAND (FT.)	0.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	1.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)
STATION OFFSET	31+00 50' LEFT	31+00 C/L	<u>31+00</u> 50' RIGHT	31+50 50' LEFT	31+50 C/L	<u>31+50</u> 50' RIGHT	32+00 50' LEFT	32+00 C/L
	O.O STANDING WATER (FT.) 1.O MUCK (FT.) O.5 SAND (FT.)	O.O STANDING WATER (FT.) O.5 MUCK (FT.) O.5 SAND (FT.)	1.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 0.5 SAND (FT.)	1.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 1.0 SAND (FT.)	0.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) O.5 MUCK (FT.) O.5 SAND (FT.)
STATION OFFSET	_32+00_ 50' RIGHT	_32+50 50' LEFT	32+50 	_32+50_ 50' RIGHT	_41+00_ 34' RIGHT	<u>41+50</u> 50' RIGHT	_42+00_ 50' RIGHT	_42+50_ 50' RIGHT
	O.5 STANDING WATER (FT.) O.0 MUCK (FT.) O.5 SAND (FT.)	O.O STANDING WATER (FT.) O.O MUCK (FT.) O.5 SAND (FT.)	O.O STANDING WATER (FT.) O.O MUCK (FT.) O.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.0 SAND (FT.)	O.O STANDING WATER (FT.) O.O MUCK (FT.) O.5 SAND (FT.)	O.O STANDING WATER (FT.) O.O MUCK (FT.) O.5 SAND (FT.)	O.O STANDING WATER (FT.) O.5 MUCK (FT.) O.5 SAND (FT.)	O.O STANDING WATER (FT.) O.5 MUCK (FT.) SAND (FT.)
STATION OFFSET	43+00 50' LEFT	<u>43+00</u> 32' RIGHT	<u>43+50</u> 50' LEFT	<u>43+50</u> 50' RIGHT	44+00 50' LEFT	_44+00_ 50' RIGHT	44+50 50' LEFT	_ <u>44+50</u>
	O.O STANDING WATER (FT.) O.5 MUCK (FT.) O.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) 1.O MUCK (FT.) O.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 1.0 SAND (FT.)	0.5 STANDING WATER (FT.) 1.0 MUCK (FT.) 2.0 SAND (FT.)	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 1.5 MUCK (FT.) 0.5 SAND (FT.)	O.5 STANDING WATER (FT.) O.5 MUCK (FT.) O.5 SAND (FT.)
STATION OFFSET	45+00 30' LEFT	<u>45+00</u> 50' RIGHT	45+50 50' LEFT	_45+50_ 50' RIGHT	46+00 50' LEFT	_46+00_ 50' RIGHT	<u>46+50</u> 50' LEFT	<u>46+50</u> 50' RIGHT
	O.O STANDING WATER (FT.) O.O MUCK (FT.) SAND (FT.)	O.5 STANDING WATER (FT.) O.5 MUCK (FT.) O.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	2.0 STANDING WATER (FT.) 2.5 MUCK (FT.) 2.0 SAND (FT.)
STATION OFFSET	_47+00_ 50' LEFT	<u>47+00</u> 50' RIGHT	_47+50 50' LEFT	_47+50_ 50' RIGHT	<u>48+00</u> 50' LEFT	_48+00_ 50' RIGHT	_48+50_ 50' LEFT	_48+50_ 50' RIGHT
	4.0 STANDING WATER (FT.) 1.5 MUCK (FT.) 2.0 SAND (FT.)	O.O STANDING WATER (FT.) 3.O MUCK (FT.) 2.O SAND (FT.)	O.O STANDING WATER (FT.) 1.5 MUCK (FT.) O.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) 1.O MUCK (FT.) O.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.5 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) O.5 MUCK (FT.) O.5 SAND (FT.)
					NOTES subsurface cone	DITIONS SHOWN ON THE PROBES DO NOT R	EPRESENT THE SOIL CONDITIONS BETWEEN	THE PROBE LOCATIONS.

SUBSURFACE CONDITIONS SHOWN ON THE PROBES DO NOT REPRESENT THE SOIL CONDITIONS BETWEEN THE PROBE LOCATIONS. ACTUAL SOIL CONDITIONS BETWEEN THE PROBES MAY VARY FROM THOSE SHOWN ON THE PROBES. THE PROBE RESULTS ARE BASED ON VISUAL EXAMINATION.

THE PROBES WERE PERFORMED JULY 19-20. 2004.

FIGURE 19

	REVISIONS								
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION				







SHEET NO.

STATION OFFSET	49+00 25' LEFT	<u>49+00</u> 50' RIGHT	49+50 50' LEFT	<u>49+50</u> 50' RIGHT	50+00 50' LEFT	_50+00 50' RIGHT	50+50 50' LEFT	_50+50_ 5C' RIGHT
	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	O.5 STANDING WATER (FT.) 1.0 MUCK (FT.) O.5 SAND (FT.)	0.5 STANDING WATER (FT.) 3.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 0.5 SAND (FT.)	O.O STANDING WATER (FT.) O.O MUCK (FT.) O.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.0 MUCK (FT.) 0.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)
STATION	51+00 50' LEFT	_51+00_ 32' RIGHT						
	O.O STANDING WATER (FT.) O.O MUCK (FT.) O.5 SAND (FT.)	0.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)						
	BOX CULVERT MUCK Scale: as shown	<pre>< PROBE RESULTS *** </pre>	<u>(south of l</u> ake b	UCHANNAN)				
STATION	46+30	46+30	46+40	46+40	_46+50_	46+50_	46+60	46+60

OFFSET	40' RIGHT	50' RIGHT	40' RIGHT	50' RIGHT	40' RIGHT	50' RIGHT	40' RIGHT	5C' RIGHT
	0.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 1.5 SAND (FT.)	0.2 STANDING WATER (FT.) 0.5 MUCK (FT.) 3.0 SAND (FT.)	0.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 2.0 SAND (FT.)	3.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 2.0 SAND (FT.)	1.5 STANDING WATER (FT.) 1.0 MUCK (FT.) 1.0 SAND (FT.)	3.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 3.0 SAND (FT.)	1.5 STANDING WATER (FT.) 1.0 MUCK (FT.) 3.0 SAND (FT.)	2.0 STANDING WATER (FT.) 3.0 MUCK (FT.) 3.0 SAND (FT.)
STATION OFFSET	46+70 40' RIGHT	_46+70 50' RIGHT	46+80 40' RIGHT	46+80 50' RIGHT	47+00 40' LEFT	47+00 50' LEFT	47+10 40' LEFT	47+10 50' LEFT
	1.5 STANDING WATER (FT.) 0.5 MUCK (FT.) 3.0 SAND (FT.)	1.5 STANDING WATER (FT.) 1.0 MUCK (FT.) 2.0 SAND (FT.)	2.0 STANDING WATER (FT.) 2.0 MUCK (FT.) 3.0 SAND (FT.)	1.5 STANDING WATER (FT.) 3.0 MUCK (FT.) 2.0 SAND (FT.)	3.0 STANDING WATER (FT.) 1.5 MUCK (FT.) 0.5 SAND (FT.)	2.0 STANDING WATER (FT.) 0.5 MUCK (FT.) 0.5 SAND (FT.)	2.0 STANDING WATER (FT.) 2.0 MUCK (FT.) 0.5 SAND (FT.)	3.0 STANDING WATER (FT.) 2.0 MUCK (FT.) 2.0 SAND (FT.)
STATION OFFSET	47+20 40' LEFT	47+20 50' LEFT	47+30 40' LEFT	_47+30 50' LEFT	47+40 40' LEFT	47+40 50' LEFT	47+50 40' LEFT	47+50 50' LEFT
	2.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 1.0 SAND (FT.)	3.0 STANDING WATER (FT.) 2.0 MUCK (FT.) 2.0 SAND (FT.)	2.5 STANDING WATER (FT.) 1.0 MUCK (FT.) 1.0 SAND (FT.)	2.5 STANDING WATER (FT.) 1.5 MUCK (FT.) 1.0 SAND (FT.)	1.0 STANDING WATER (FT.) 1.5 MUCK (FT.) 1.0 SAND (FT.)	4.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 3.0 SAND (FT.)	0.5 STANDING WATER (FT.) 1.0 MUCK (FT.) 0.5 SAND (FT.)	4.0 STANDING WATER (FT.) 1.0 MUCK (FT.) 3.0 SAND (FT.)

FIGURE 20

		REVI	SIONS						
DATE	BY	DESCRIPTION DATE BY DESCRIPTION							
6-28-07	RT	ADD POND 1 MUCK PROBE RESULTS (TLM)							







FORMER RELOCATED POND 1 MUCK PROBE RESULTS (PERFORMED 3-1-07) SCALE: AS SHOWN

STATION OFFSET		18+35 400' LT	_19+45 	_20+40_ 400' LEFT	_20+45_ 510' LEFT	_20+50_ 605' LEFT	_20+55_ 700' LEFT	_20+55_ 815'_LEFT
	O STANDING WATER (FT.) 9.0 MUCK (FT.) 0.5 SAND (FT.)	0.3 STANDING WATER (FT.) 13.0 MUCK (FT.) 1.0 SAND (FT.)	O.5 STANDING WATER (FT.) 9.0 MUCK (FT.) 1.0 SAND (FT.)	0.0 STANDING WATER (FT.) 8.0 MUCK (FT.) 2.0 SAND (FT.)	0.5 STANDING WATER (FT.) 13.5 MUCK (FT.) 0.5 SAND (FT.)	0.2 STANDING WATER (FT.) 15.5 MUCK (FT.) 0.3 SAND (FT.)	0.2 STANDING WATER (FT.) 15.5 MUCK (FT.) 0.3 SAND (FT.)	0.0 STANDING WATER (FT.) 13.0 MUCK (FT.) 0.5 SAND (FT.)
STATION OFFSET	19+65 825' LEFT 0.0 STANDING WATER (FT.)		17+80 820' LEFT 0.0 STANDING WATER (FT.)					
	14.5 MUCK (FT.) 0.5 SAND (FT.)	14.5 MUCK (FT.) 0.5 SAND (FT.)	9.5 MUCK (FT.) O.5 SAND (FT.)					
	POND 1 MUCK PRO	BE RESULTS (PERF	ORMED 8-29-08)					

STATION OFFSET	12+20 120' LEFT 2.0 STANDING WATER (FT.) 2.5 MUCK (FT.) 1.5 SAND (FT.)	12+20 190' LEFT 3.0 STANDING WATER (FT.) 3.0 MUCK (FT.) 1.0 SAND (FT.)	2.0 STANDING WATER (FT.) 3.0 MUCK (FT.) 1.0 SAND (FT.)	13+00 120' LEFT 3.0 STANDING WATER (FT.) MUCK (FT.) 1.0 SAND (FT.)	13+00 160' LEFT 3.5 STANDING WATER (FT.) MUCK (FT.) 1.0 SAND (FT.)	2.0 STANDING WATER (FT.) 13.0 MUCK (FT.) SAND (FT.)	13+00 235' LEFT 3.5 STANDING WATER (FT.) 13.0 MUCK (FT.) 3.0 SAND (FT.)	3.5 STANDING WATER (FT.) 12.0 MUCK (FT.) 2.0 SAND (FT.)
STATION OFFSET	14+00 120' LEFT 3.0 STANDING WATER (FT.) 6.0 MUCK (FT.) 0.5 SAND (FT.)	14+00 160' LEFT 2.5 STANDING WATER (FT.) 6.0 MUCK (FT.) 0.5 SAND (FT.)	14+00 200' LEFT 3.0 STANDING WATER (FT.) 7.5 MUCK (FT.) 0 SAND (FT.)	14+00 235' LEFT 3.0 STANDING WATER (FT.) 8.0 MUCK (FT.) 0 SAND (FT.)		15+00 115' LEFT 3.0 STANDING WATER (FT.) 5.0 MUCK (FT.) 1.0 SAND (FT.)	15+00 160' LEFT 3.0 STANDING WATER (FT.) 5.0 MUCK (FT.) 0.5 SAND (FT.)	
STATION OFFSET	15+00 235' LEFT 3.0 STANDING WATER (FT.) 7.0 MUCK (FT.) 1.0 SAND (FT.)	15+00 270' LEFT 3.0 STANDING WATER (FT.) 8.0 MUCK (FT.) 0.5 SAND (FT.)	16+00 110' LEFT 2.0 STANDING WATER (FT.) 4.0 MUCK (FT.) 1.0 SAND (FT.)	16+00 150' LEFT 2.0 STANDING WATER (FT.) 4.0 MUCK (FT.) 1.0 SAND (FT.)	16+00 190' LEFT 3.0 STANDING WATER (FT.) 6.0 MUCK (FT.) 0.5 SAND (FT.)	15+00 235' LEFT 3.5 STANDING WATER (FT.) 5.0 MUCK (FT.) 1.0 SAND (FT.)	2.5 STANDING WATER (FT.) 4.5 MUCK (FT.) 5AND (FT.)	150' LEFT 2.0 STANDING WATER (FT.) 5.0 MUCK (FT.) 1.0 SAND (FT.)

STATION 16+50 OFFSET 235' LEFT

3.0 STANDING WATER (FT.)

REVISIONS

DESCRIPTION

6.0 MUCK (FT.)
0.5 SAND (FT.)

 DATE
 BY
 DESCRIPTION

 6-28-07
 RT
 ADD POND 1 MUCK PROBE RESULTS (TLM)


GEC
GECTECHNICAL AND ENVIRONMENTAL
CONSULTANTS, INC.
919 LAKE BALDWIN LANE
ORLANDO, FLORIDA 32814
CERTIFICATE OF AUTHORIZATION NO. 00005882
M CHAEL J. PREIM, P.E. 24041








SHEET NO.


FIGURE 21



































































































































































































































































8/8/2018 2:42:07 PM H:\projects\02076v8\dgn\Roadway\Rdxsrd02.plg





2:42:08 PM


8/8/2018


H:\projects\02076v8\dgn\Roadway\Rdxsrd03.plg








































2:42:10 PM H:\projects\02076v8\dgn\Roadway\Rdxsrd04.plg






















85' (140') LT (120') LT (100') LT (80') LT (60') LT (40') LT (20') LT STA. 3004+00 (20') RT (40') RT (60') RT (80') RT (120') RT (120') RT (140') RT (160') RT (180') RT (220') RT (240') RT STA. 3004+00' Scale - H: 1"=40', V: 1"=10'



85' (140') LT (120') LT (100') LT (80') LT (60') LT (40') LT (20') LT STA. 3005+00 (20') RT (40') RT (80') RT (100') RT (120') RT (140') RT (160') RT (180') RT (220') RT (240') RT STA. 3005+00' Scale - H: 1"=40', V: 1"=10'




(140') LT (120') LT (100') LT (80') LT (60') LT (40') (£0') LT STA. 3006+00 (20') RT (40') RT (60') RT (80') RT (100') RT (120') RT (140') RT (160') RT (180') RT (200') RT (240') RT STA. 3006+00' Scale - H: 1"=40', V: 1"=10'

2480 E, Michigan St, Orlando, Florida 32806 Tel: (407) 428-9200 • Fax: (407) 428-9222

	REVISIONS								
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION				





er Resources • Land Development • Civil Engineering 2480 E. Michigan St. Orlando, Florida 32806 "el: (407) 428-9200 • Fax: (407) 428-9222

Scale - H: 1"=40', V: 1"=10'

	REVISIONS							
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION			



HOLDEN AVENUE
POND 3 CROSS SECTIONS

The following narrative of the Stormwater Pollution Prevention Plan contains references to the Standard Specifications for Road and Bridge Construction, the Design Standards, and other sheets of these construction plans. The first sheet of the construction plans (called the Key Sheet) contains an index to the other sheets. The complete Stormwater Pollution Prevention Plan includes several items: this narrative description, the documents referenced in this narrative, the contractor's approved Erosion Control Plan required by Specification Section 104, and reports of inspections made during construction.

1.0 SITE DESCRIPTION

I.a Nature of Construction Activity:

Holden Avenue Phase I – Reconstruction of existing 2-lane rural roadway to 4-lane urban roadway including 2 stormwater ponds.

I.b Sequence of Major Soil Disturbing Activities:

In the Section 104 Erosion Control Plan, the contractor shall provide a detailed sequence of construction for all construction activities. The contractor shall follow the sequence of major activities described below, unless the contractor proposes a different sequence that is equal or better at controlling erosion and trapping sediment and is approved by the Engineer.

For each construction phase, install perimeter controls after clearing and grubbing necessary for installation of controls but before beginning other work for the construction phase. Remove perimeter controls only after all upstream areas are stabilized.

- I. Clearing and grubbing, earthwork, and storm sewer construction for the pond outfalls.
- 2. Clearing and grubbing, earthwork for the pond construction.
- 3. Storm sewer construction. Construct the storm drain pipe in the upstream direction.
- Earthwork associated with roadway, and construction of gravity and retaining walls, curb, subgrade, base, pavement, and sidewalk.

I.c Area Estimates:

Total site area: 30.98 acres Total area to be disturbed: 27.15 acres

I.d Runoff Data:

Runoff Coefficients: Before: 0.55 During: Varies from 0.55 to 0.74 After: 0.74

Outfall Information: There are two outfalls.

#I Description: Pond I. This pond discharges to existing wetlands which outfalls at the existing 38"x60" crossdrain under John Young Parkway (JYP-I) Location: Latitude 28°29'43" North, Longitude 81°24'57" West. Est. Drainage Area Size: 17.27 Ac. (Onsite area only; includes pond) Receiving Water Name: Lake Catherine floodplain/Shingle Creek

#2 Description: Pond 3. This pond discharges directly to Lake Tyler. Location: Latitude 28°29'38" N, Longitude 81°23'55"W
Estimated Drainage Area: 9.88 Ac. (Onsite area only; includes pond)
Receiving Water Name: Lake Tyler/Shingle Creek

Soils Data: The result of the soil borings along the roadway are shown in the Roadway Soil Survey Sheet(s). The results of soil borings done in the ponds are shown in the Pond Detail Sheets. The numbers for these are identified on the Key Sheet of these construction plans. In general the soils are clayey soils.

I.e Site Map:

The construction plans are being used as the site maps. The location of the required information is described below. The sheet numbers for the plan sheets referenced are identified on the Key Sheet of these construction plans.

- * Drainage Patterns: Drainage for the project area is collected by curb inlets and catch basins and conveyed via a storm sewer to the two stormwater ponds. The Cross Sections show overland flow direction at the right of way line.
- * Approximate Slopes: The slopes of the site can be seen in the Cross Section Sheets and the Plan and Profile Sheets.
- * Areas of Soil Disturbance: The areas to be disturbed are indicated on the Plan and Profile Sheets and the Cross Section Sheets. Any areas where permanent features are shown to be constructed above or below ground will be disturbed.

- * Areas Not To Be Disturbed: Essentially the whole project will be disturbed during construction.
- * Locations of Temporary Controls: Temporary Controls such as silt fence, turbidity barrier, hay bales, sod, seed and mulch, etc. shall be placed so the the runoff from the disturbed areas will be contained within the project area. Typical locations of these controls are shown on the erosion control sheets.
- * Locations of Permanent Controls: The stormwater ponds are the primary permanent stormwater management controls. These are shown on the Pond Detail Sheets.
- * Areas To Be Stabilized: Temporary stabilization practices are shown in the same location as the temporary controls mentioned above. Permanent stabilization is shown on the Typical Section Sheets, the Plan and Profile Sheets and the Pond Detail Sheets.
- * Surface Waters: The locations of the surface waters adjacent to the project are shown on the Drainage Maps.
- * Discharge Points To Surface Waters: There are two existing outfalls. These locations are shown on the Drainage Maps and the Plan and Profile Sheets.

I.f Receiving Waters:

See Section I.d for the outfall locations and receiving water names.

2.0 CONTROLS:

2.a Erosion And Sediment Controls:

In the Section IO4 Erosion Control Plan, the contractor shall describe the proposed stabilization and structural practices based on the contractor's proposed Traffic Control Plan. The following recommended guidelines are based on the Traffic Control Plan (TCP) outlined in the construction plans. Where following the Traffic Control Plan (TCP) outlined in these construction plans, the contractor may choose to accept the following guidelines or modify them in the Section IO4 Erosion Control Plan, subject to approval of the Engineer. As work progresses, the contractor shall modify the plan to adapt to seasonal variation, changes in construction activities, and the need for better practices.

For each construction phase, install perimeter controls after clearing and grubbing necessary for installation of controls but before beginning other work for the construction phase. Remove perimeter controls only after all upstream areas are stabilized.

Phase IA of Traffic Control Plans

Roadwa

Temporary pavement is to be constructed along the south side of Holden Avenue and the west side of Texas Avenue during this phase, at the locations shown in the Maintenance of Traffic Plans. Install staked silt fence along the right-of-way line prior to beginning construction operations along any segment of the roadway. Immediately after constructing this temporary pavement, stabilize the entire area between the edge of the temporary pavement and the right-of-way line using temporary sod.

Drainage

A temporary drainage swale is to be constructed along the south side of Holden Avenue between approximate stations 50+30 and 60+50 due to the temporary widening of the roadway for maintenance of traffic. Immediately after construction, stabilize the banks of this swale using temporary sod. Place other erosion control measures as necessary based on FDOT Index IO2 (hay bales, silt fence).

Several existing structures are to be moved and/or extended in this phase as shown in the Maintenance of Traffic Plans. During construction these inlets, manholes, and mitered end sections shall be protected from siltation and erosion using the measures shown in FDOT Index 102.

The existing box culvert at Lake Buchanan (station 46+80) is to be extended on its south side during this phase. During construction, utilize floating turbidity barrier in conjunction with staked silt fence on both the upstream and downstream sides of this structure.

Phase IB of Traffic Control Plans

Roadwav

Portions of Holden Avenue, Texas Avenue, Rio Grande Avenue, and John Young Parkway are to be constructed in this phase. Install silt fence along the right-of-way line prior to beginning construction operations along any segment of the roadway. During construction proposed inlets, manholes, and mitered end sections shall be protected from siltation and erosion using the measures shown in FDOT Index 102. Pipe shall be laid in the reverse direction of flow. Contractor shall have sand bags available at all times during construction of the proposed storm sewer system to substantially block runoff in the trench from entering the pipes. Immediately following construction of the proposed storm sewer system & sidewalk, stabilize the area from the back of the sidewalk to the right-of-way line using temporary sod.

Pond I

Clear and grub the pond site. Install staked silt fence (double row) around the right-of-way perimeter prior to beginning clearing and grubbing operations. Excavate the pond to its approximate dimensions, then seed and mulch the pond side slopes down to the water surface. Construct the proposed outfall weir. Construct the proposed storm sewer system in the upstream direction from the pond, to the limits shown in the maintenance of traffic plans. During construction proposed inlets, manholes, and mitered end sections shall be protected from siltation and erosion using the measures shown in FDOT Index 102.

Phase IIA of Traffic Control Plans

Temporary pavement is to be constructed along Holden Avenue, Texas Avenue, and Rio Grande Avenue during this phase, at the locations shown in the Maintenance of Traffic Plans. Construction is also continuing from previous phases. Install staked silt fence along the right-of-way line prior to beginning construction operations along any segment of the roadway not previously disturbed. Erosion control devices are to be maintained at all other active construction areas.

Phase IIB of Traffic Control Plans

Roadwa

Portions of Holden Avenue, Texas Avenue, Rio Grande Avenue, and John Young Parkway are to be constructed in this phase. Construction is also continuing from previous phases. Install silt fence along the right-of-way line prior to beginning construction operations along any segment of the roadway. During construction proposed inlets, manholes, and mitered end sections shall be protected from siltation and erosion using the measures shown in FDOT Index IO2. Pipe shall be laid in the reverse direction of flow. Contractor shall have sand bags available at all times during construction of the proposed storm sewer system to substantially block runoff in the trench from entering the pipes. Immediately following construction of the proposed storm sewer system & sidewalk, stabilize the area from the back of the sidewalk to the right-of-way using temporary sod.

Pond 3

Clear and grub the pond site. Install staked silt fence around the right-of-way perimeter prior to beginning clearing and grubbing operations. Excavate the pond to its approximate dimensions, then seed and mulch the pond side slopes down to the water surface. Construct the proposed outfall structure to Lake Tyler. Utilize floating turbidity barrier at the outfall point to the lake. Construct the proposed storm sewer system in the upstream direction from the pond, to the limits shown in the maintenance of traffic plans. During construction proposed inlets, manholes, and mitered end sections shall be protected from siltation and erosion using the measures shown in FDOT Index 102.

Phase IIIA of Traffic Control Plans

Temporary pavement is to be constructed along Rio Grande Avenue during this phase, at the locations shown in the Maintenance of Traffic Plans. Construction is also continuing from previous phases. Install staked silt fence along the right-of-way line prior to beginning construction operations along any segment of the roadway not previously disturbed. Erosion control devices are to be maintained at all other active construction areas.

Phase IIIB of Traffic Control Plans

Portions of Holden Avenue, Texas Avenue, Rio Grande Avenue, and John Young Parkway are to be constructed in this phase. Install staked silt fence along the right-of-way line prior to beginning construction operations along any segment of the roadway not previously disturbed. Erosion control devices are to be maintained at all other active construction areas. During construction proposed inlets, manholes, and mitered end sections shall be protected from siltation and erosion using the measures shown in FDOT Index IO2. Pipe shall be laid in the reverse direction of flow. Contractor shall have sand bags available at all times during construction of the proposed storm sewer system to substantially block runoff in the trench from entering the pipes. Immediately following construction of the proposed storm sewer system & sidewalk, stabilize the area from the back of the sidewalk to the right-of-way line using temporary sod.

R E V I S I O N S

DATE BY DESCRIPTION DATE BY DESCRIPTION

21
PH:(40

ENGINEERS • SURVEYORS
201 SOUTH BUMBY AVENUE ORLANDO, FLORIDA 32803
PH. (407) 886-3317 FAX. (407) 896-967 EMAIL: WWW.LOCHRANE.COM
CERTIFICATE OF AUTHORIZATION NO. 2856
FOREST W. ADKINS, P.E. P.E. NUMBER 56003



HOLDEN A VENUE STORMWATER POLLUTION PREVENTION PLAN SHEET NO:

261

Phase IVA of Traffic Control Plans

Portions of Holden Avenue, Texas Avenue, and Rio Grande Avenue are to be constructed in this phase (medians and traffic seperators). Install staked silt fence along the right-of-way line prior to beginning construction operations along any segment of the roadway not previously disturbed. Erosion control devices are to be maintained at all other active construction areas. During construction proposed inlets, manholes, and mitered end sections shall be protected from siltation and erosion using the measures shown in FDOT Index IO2. Pipe shall be laid in the reverse direction of flow. Contractor shall have sand bags available at all times during construction of the proposed storm sewer system to substantially block runoff in the trench from entering the pipes. Immediately following construction of the proposed storm sewer system & sidewalk, stabilize the area from the back of the sidewalk to the right-of-way line using temporary sod.

Phase IVB of Traffic Control Plans

After the entire basin is permanently stabilized, place permanent sod.

After the entire basin is permanently stabilized, fine grade the ponds to their final dimensions. Sod pond side slopes with permanent sod. Do not remove erosion control devices until final paving & placement of sod is complete.

2.a.I Stabilization Practices:

In the Section IO4 Erosion Control Plan, the contractor shall describe the stabilization practices proposed to control erosion. The contractor shall initiate all stabilization measures as soon as practical, but in no case more than 7 days, in portions of the site where construction activities have temporarily or permanently ceased. The stabilization practices shall include at least the following, unless otherwise approved by the Engineer.

- * Artificial coverings in accordance with Specification Section 104.
- * Seed and mulch, and sod in accordance with Specifiction Section 104.

Permanent:

- * Asphalt or concrete surface.
- Sod in accordance with Specification Section 575. The Contractor shall backfill and temporarily stabilize with sod all slopes within 48 hours of completion of the concrete curing time for box culvert.

2.a.2 Structural Practices:

In the Section 104 Erosion Control Plan, the contractor shall describe the proposed structural practices to control or trap sediment and otherwise prevent the discharge of pollutants from exposed areas of the site. Sediment controls shall be in place before disturbing soil upstream of the control. The structural practices shall include at least the following, unless otherwise approved by the Engineer.

- * Silt fence in accordance with Design Standard 102 and Specification
- * Baled hay or straw in accordance with Design Standard 102 and Specification

REVISIONS

DATE

- * Turbidity barrier in accordance with Design Standard 102.
- * Sandbags to control erosion and trap silt
- * Inlet protection in accordance with Design Standard 102.

DESCRIPTION

Permanent:

* Sod.

DATE BY

2.b Stormwater Management:

Several storm sewer systems will be constructed to convey runoff to two (2) stormwater retention/detention ponds. The facilities have been permitted by the South Florida Water Management District (SFWMD) and Orange County and comply with applicable design standards.

2.c Other Controls:

2.c./ Waste Disposal:

In the Section 104 Erosion Control Plan, the contractor shall describe the proposed methods to prevent the discharge of solid materials, including building materials, to waters of the United States. The proposed methods shall include at least the following, unless otherwise approved by the

- * Providing litter control and collection within the project during construction
- * Disposing of all fertilizer or other chemical containers according to EPA's standard practices as detailed by the manufacturer.
- st Disposing of solid materials including building and construction materials off the project site but not in surface waters, or wetlands.

2.c.2 Off-Site Vehicle Tracking & Dust Control:

In the Section 104 Erosion Control Plan, the contractor shall describe the proposed methods for minimizing offsite vehicle tracking of sediments and generating dust. The proposed methods shall include at least the following, unless otherwise approved by the Engineer.

- * Covering loaded haultrucks with tarpaulins.
- * Removing excess dirt from roads daily.
- * Stabilizing construction entrances according to Design Standard 106.
- * Using roadway sweepers during dust generating activities such as excavation and milling operations.

2.c.3 State and Local Regulations For Waste Disposal, Sanitary Sewer, Or Septic Tank Regulations:

In the Section IO4 Erosion Control Plan, the contractor shall describe the proposed procedures to comply with applicable state and local regulations for waste disposal, and sanitary sewer or septic systems.

2.c.4 Fertilizers and Pesticides:

In the Section 104 Erosion Control Plan, the contractor shall describe the procedures for applying fertilizers and pesticides. The proposed procedures shall comply with applicable subsections of either Section 570 or 577 of the Specifications.

2.c.5 Toxic Substances:

In the Section IO4 Erosion Control Plan, the contractor shall provide a list of toxic substances that are likely to be used on the job and provide a plan addressing the generation, application, migration, storage, and disposal of these substances.

2.d.4 Approved State and Local Plans and Permits:

- * FDEP Rule Chapter 62-25 F.A.C.
- Contractor is required to complete, sign, and send FL DEP NPDES Notice of Intent and Notice of Termination, as Operator.

3.0 MAINTENANCE:

DESCRIPTION

In the Section IO4 Erosion Control Plan, the contractor shall provide a plan for maintaining all erosion and sediment controls throughout construction. The maintenance plan shall at a minimum, comply with the following.

- * Silt Fence: Maintain per Section 104. The contractor should anticipate replacing silt fence on 12 month intervals.
- * Baled Hay or Straw: Remove sediment when it reaches $\frac{1}{2}$ height of bales or when water ponds in unacceptable amounts or areas. The contractor should anticipate replacing straw bales on 3-month intervals.
- * Turbidity Barrier: Maintain per Section 104.

Orange County FLORIDA

4.0 INSPECTIONS:

Qualified personnel shall inspect the following items at least once every seven calendar days and within 24 hours of the end of a storm that is 0.50 inches or greater. To comply, the contractor shall install and maintain rain gages and record the daily rainfall. Where sites have been permanently stabilized, inspections shall be conducted at least once every month. The contractor shall also inspect that controls installed in the field agree with the latest Stormwater Pollution Prevention Plan.

- * Points of discharge to waters of the United States.
- * Points of discharge to municipal storm sewer systems.
- * Disturbed areas of the site that have not been finally stabilized.
- * Areas used for storage of materials that are exposed to precipitation.
- * Structural controls.
- * Storm water management systems.
- * Locations where vehicles enter or exit the site.

The contractor shall initiate repairs within 24 hours of inspections that indicate items are not in good working order.

If inspections indicate that installed stabilization and structural practices are not sufficient to minimize erosion, retain sediment, and prevent discharging pollutants, the contractor shall provide additional measures, as approved by the Engineer.

5.0 NON-STORMWATER DISCHARGES:


In the Section IO4 Erosion Control Plan, the contractor shall identify all anticipated non-stormwater discharges (except flows from fire fighting activities). The contractor shall describe the proposed measures to prevent pollution of these non-stormwater discharges. If the contractor encounters contaminated soil or groundwater, contact Mr. Dennis Weatherford, Orange County Environmental Protection Division, Waste Management [(407)-836-1404] and the FDEP Central District Emergency Response [(407) 893-3337].

> HOLDEN A VENUE STORMWATER POLLUTION PREVENTION PLAN

SHEET NO.


262

ENGINEERS • SURVEYORS ENGINEERS SURVEIURS
201 SOUTH BUMBY AVENUE ORLANDO,FLORIDA 32803
(407) 896-5317 FAX; (407) 896-9167 EMAIL, WWW.LOCHRANE.COM
CERTIFICATE OF AUTHORIZATION NO.2856
THOMAS G. LOCHRANE, P.E. P.E. NUMBER 2011




Silt Fence to be paid for under the contract unit price for Prevention, Control, and Abatement of Erosion and Water Pollution (LS), Pay Item No. 104-14.


TYPE III SILT FENCE



Do not deploy in a manner that silt fences will act as a dam across permanent flowing watercourses. Silt fences are to be used at upland locations and turbidity barriers used at permanent bodies of water.



SILT FENCE APPLICATIONS



PROTECTION AROUND INLETS OR SIMILAR STRUCTURES

DAT

THE CONTRACTOR SHALL EXECUTE ALL MEASURES NECESSARY TO LIMIT THE TRANSPORT OF SEDIMENTS OUTSIDE THE LIMITS OF THE PROJECT TO THE VOLUME AND AMOUNT THAT ARE EXISTING PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. THIS CONDITION WILL BE SATISFIED FOR THE TOTAL ANTICIPATED CONSTRUCTION PERIOD. PROVISION MUST BE MADE TO PRESERVE THE INTEGRITO AND CAPACITY OF CHECK WEIRS, SEDIMENT BASINS, SLOPE DRAINS, GRADING PATTERNS, ETC. REQUIRED TO MEET THIS PROVISION THROUGHOUT THE LIFE OF THE CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE HAY BALES, SILT BARRIERS, TEMPORARY GRASSING, ETC. AS REQUIRED TO FULLY COMPLY WITH THE INTENT OF THIS SPECIFICATION.

2. PHASING OF IMPLEMENTATION

PHASE I - INSTALLATION OF EROSION CONTROL FEATURES

EROSION CONTROL FEATURES ARE TO BE INSTALLED THROUGHOUT THE AREA OF SOIL DISTURBING ACTIVITIES AND AT ENVIRONMENTALLY SENSITIVE AREAS OR AT AREAS AS DIRECTED BY THE ENGINEER. THESE FEATURES INCLUDE BUT ARE NOT LIMITED TO HAYBALES, STAKED SILT FENCES, STAKED TURBIDITY BARRIERS, FLOATING TURBIDITY BARRIERS, ETC. THESE CONTROL FEATURES ARE TO REMAIN IN PLACE UNTIL AFTER CONSTRUCTION ACTIVITIES ARE COMPLETE AND UNTIL THERE IS NO LONGER A THREAT OF WATER QUALITY VIOLATIONS

PHASE 2 - DRAINAGE SYSTEM OR STRUCTURE EROSION CONTROL FEATURES.

EROSION CONTROL FEATURES ARE TO BE INSTALLED AT ALL AREAS OF EXCAVATION OR FILL FOR DRAINAGE SYSTEM OR STRUCTURE CONSTRUCTION PRIOR TO SUCH EXCAVATION OR FILL. ALL STREAMS OR DITCHES ARE TO BE PROTECTED FROM EROSION OR SILTATION BY THE METHODS DETAILED ABOVE AND IN STANDARD INDEX NOS. 102-106. INLET ENTRANCES ARE ALSO TO BE PROTECTED FROM SILTATION. THE CONTROL FEATURES TO BE USED INCLUDE BUT ARE NOT LIMITED TO STAKED SILT FENCES AND HAYBALES.

PHASE 3 - MAINTENANCE OF EROSION CONTROL FEATURES

ALL ENVIRONMENTAL CONTROL FEATURES ARE TO BE MAINTAINED THROUGHOUT THE LIFE OF THE PROJECT AS NECESSARY FOR THE VARIOUS CONSTRUCTION PHASES. THE CONTRACTOR MUST ENSURE THAT ALL OF THESE FEATURES FUNCTION PROPERLY AT ALL TIMES.

- NO EXCAVATED MATERIAL SHALL BE STOCKPILED IN SUCH A MANNER AS TO DIRECT RUNOFF DIRECTLY OFF THE PROJECT SITE OR INTO ANY ADJACENT WATER BODY OR STORMWATER COLLECTION FACILITY.
- THE SURFACE AREA OF OPEN, RAW ERODIBLE SOIL EXPOSED BY CLEARING AND GRUBBING OPERATIONS OR EXCAVATION AND FILLING OPERATIONS SHALL BE CONTROLLED, SO THAT THIS OPERATION WILL NOT SIGNIFICANTLY AFFECT OFF-SITE DEPOSIT OF SEDIMENTS.
- INLETS AND CATCH BASINS SHALL BE PROTECTED FROM SEDIMENT LADEN STORMWATER RUNOFF UNTIL THE COMPLETION OF ALL CONSTRUCTION OPERATIONS THAT MAY CONTRIBUTE SEDIMENT TO THE INLET. (SEE NOTE 17)
- AREAS OPENED BY CONSTRUCTION OPERATIONS THAT ARE NOT ANTICIPATED TO BE DRESSED OR RECEIVE FINAL GRASSING TREATMENT WITHIN THIRTY DAYS SHALL BE SEEDED WITH A QUICK GROWING GRASS SPECIES WHICH WILL PROVIDE AN EARLY COVER, DURING THE SEASON IN WHICH IT IS PLANTED. TEMPORARY SEEDING SHALL BE CONTROLLED SO AS TO NOT ALTER OR COMPETE WITH PERMANENT GRASSING. THE RATE OF SEEDING SHALL BE 30 POUNDS PER ACRE.
- 7. THE SEEDED OR SEEDED AND MULCHED AREA(S) SHALL BE ROLLED AND WATERED AS REQUIRED TO ASSURE OPTIMUM GROWING CONDITONS FOR THE ESTABLISHMENT OF A GOOD GRASS COVER.
- IF AFTER 14 DAYS, THE TEMPORARY GRASSED AREAS HAVE NOT ATTAINED A MINIMUM OF 75% GOOD GRASS COVER, THE AREA WILL BE REWORKED AND ADDITIONAL SEED APPLIED TO ESTABLISH THE

- ALL FEATURES OF THE PROJECT SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENT AND SHALL BE MAINTAINED DURING THE LIFE OF THE CONSTRUCTION SO AS TO FUNCTION PROPERLY WITHOUT THE TRANSPORT OF SEDIMENTS OUTSIDE THE LIMITS OF THE PROJECT. THIS PROJECT MAY BE CONSTRUCTED IN PHASES, BUT THE EROSION CONTROL REQUIREMENTS AND PHASING OF IMPLEMENTATION SHALL
- 10. ALL DISTURBED AREAS OUTSIDE THE EXCAVATION AND FILL LIMITS WILL BE RESTORED TO A CONDITION EQUAL TO OR BETTER THAN THEIR CONDITION PRIOR TO CONSTRUCTION
- THE CONTRACTOR WILL BE RESPONSIBLE FOR MAINTENANCE OF ALL NEWLY PLANTED GRASSES OR VEGETATION AND RETENTION/DETENTION FACILITIES UNTIL THE WORK HAS BEEN ACCEPTED BY THE COUNTY.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STABILITY OF EMBANKMENTS AND SHALL REPLACE ANY PORTION, WHICH IN THE OPINION OF THE ENGINEER, HAS BECOME DISPLACED DUE TO EROSION OR DUE TO CARELESSNESS OR NEGLIGENCE ON THE PART OF THE
- THE CONTRACTOR SHALL COMPLY WITH ALL FEDERAL, STATE, AND LOCAL LAWS AND REGULATIONS CONTROLLING POLLUTION OF THE ENVIRONMENT. MEASURES SHALL BE TAKEN BY THE CONTRACTOR TO CONTROL FROSION AND SEDIMENT RUNDEF FROM THE SITE DURING CONSTRUCTION. SUCH METHODS SHALL BE IN ACCORDANCE WITH THE CURRENT FLORIDA DEPARTMENT OF TRANSPORTATION STANDARDS
- ABSOLUTELY NO WORK WILL BE ALLOWED WITHIN ANY CONSERVATION AREA, BUFFER AREA, MITIGATION AREA OR DESIGNATED WETLAND AREA UNLESS SO SPECIFICALLY DESCRIBED BY THE PLANS AND GRANTED BY REASON OF PERMIT FROM THE GOVERNMENTAL ENTITY HAVING JURISDICTION OVER SAID AREA.
- PRIOR TO CLEARING AND GRUBBING. THE LIMITS OF WETLANDS. BUFFERS, AND MITIGATION AREAS SHALL BE CLEARLY MARKED ALONG THE PROPOSED RIGHT OF WAY LINE TO PROTECT THESE AREAS FROM ENCROACHMENT FROM CONSTRUCTION ACTIVITIES.
- ALL FILL EMBANKMENT AND GRADED AREAS SHALL BE PROTECTED AGAINST EROSION BY METHODS STATED IN SECTION 104, "F.D.O.T. STANDARD SPECIFICATIONS FOR BRIDGE AND ROAD CONSTRUCTION" SIDE SLOPE MAY BE SEEDED AND MULCHED, PROVIDED THAT THE MULCH MATERIAL IS DISC HARROWED AND THE SIDE SLOPES ARE NEITHER GREATER THAN 3:1 NOR PART OF A DRAINAGE CONVEYANCE
- REFER TO POND DETAIL SHEETS FOR EROSION CONTROL MEASURES AT POND OUTFALLS. PIPE OR DITCH OUTFALLS OFF THE PROJECT SITE SHALL BE INSPECTED DAILY FOR POSSIBLE SEDIMENT BUILDUP OR TRANSPORT.
- EROSION CONTROL AT ALL INLET DRAINAGE STRUCTURES DURING CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH FDOT STANDARD
- LOCATION & QUANTITY OF FROSION CONTROL MEASURES IS APPROXIMATE ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.


 PAYMENT FOR ALL EROSION CONTROL MEASURES TO BE INCLUDED UNDER ITEM 104-14, "PREVENTION, CONTROL AND ABATEMENT OF EROSION & WATER POLLUTION" (LS).

SUMMARY OF STAKED SILT FENCE								
LOCATION		NUMBER OF	P	F	FIELD BOOK			
STA. TO STA.	SIDE	APPLICATIOI	VS LF	LF	REFERENCE			
HOLDEN AVE								
//+80 - 36+/4 *	RT		3355					
<i>37+17 - 62+83</i>	RT		2710					
37+30 - 42+80	LT		600					
50+40 - 62+91	LT		1380					
63+48 - 69+68	RT		699					
63+63 - 75+67 *	LT		1475					
72+00 - 75+96	RT		452					
JOHN YOUNG PARKWAY								
202+00 - 204+70	LT		270					
206+10 - 206+75	RT		65					
TEXAS AVE								
392+50 - 399+56	LT		708					
392+50 - 399+71	RT		794					
401+40 - 401+93	LT		53					
401+20 - 408+50	RT		711					
402+60 - 408+50	LT		620					
RIO GRANDE AVE								
401+00 - 407+34	LT		702					
401+00 - 407+32	RT		655					
410+70 - 414+40	LT		371					
410+81 - 414+40	RT		399					
POND 3	RT		1979					
SUBTOTAL			17,998					
I REPLACEMENT CYCLE (I		17,998						
TOTAL			35,976					
			1 3 70 . 0		1			


DOUBLE ROW SILT FENCE STA. II+80 - 20+80 RT. STA. 69+45 - 70+70 LT.

		REVIS	SIONS			
\TE	BY	DESCRIPTION	DATE	BY	DESCRIPTION	I III:HKANE
						LUGNNANE
						ENGINEERS • SURVEYORS
						20I SOUTH BUMBY AVENUE ORLANDO, FLORIDA 32803 PH: (407) 896-3317 FAX: (407) 896-9167 EMAIL: WWW.LOCHRAND
						CERTIFICATE OF AUTHORIZATION NO.2856
				1		FOREST W. ADKINS, P.E. P.E. NUMBER 56003






FLOATING TURBIDITY BARRIERS



LEGEND

- PILE LOCATIONS
- DREDGE OR FILL AREA
- → MOORING BUOY W/ ANCHOR
- → ANCHOR
- BARRIER MOVEMENT DUE
 TO CURRENT ACTION



NOTES:


- I. TURBIDITY BARRIERS ARE TO BE USED IN ALL PERMANENT BODIES OF WATER REGARDLESS OF WATER DEPTH.
- 2. NUMBER AND SPACING OF ANCHORS DEPENDENT ON CURRENT VELOCITIES.
- 3. DEPLOYMENT OF BARRIER AROUND PILE LOCATIONS MAY VARY TO ACCOMMODATE CONSTRUCTION OPERATIONS.
- 4. NAVIGATION MAY REQUIRE SEGMENTING BARRIER DURING CONSTRUCTION OPERATIONS.
- 5. FOR ADDITIONAL INFORMATION SEE SECTION 104 OF THE FDOT STANDARD SPECIFICATIONS.

TURBIDITY BARRIER APPLICATIONS N.T.S.

- I. STAKED SILT FENCE IS TO BE PLACED NO MORE THAN 6" FROM THE R.O.W. LINE OR THE FILL SLOPE EASEMENT LINE IF APPLICABLE.
- 2. FOR DOUBLE ROW SILT FENCE ADJACENT TO WETLANDS SECOND ROW OF SILT FENCE TO BE PLACED I' OR LESS BEHIND FIRST ROW ON CONSRUCTION SIDE OF FENCE. SEE DRAINAGE MAPS AND SFWMD PERMIT FOR WETLAND LOCATIONS.

TYPICAL STAKED SILT FENCE PLACEMENT

N.T.S.



STAKED TURBIDITY BARRIER

SUN	MARY OF STAKED 7	URBIDITY	BARRIERS	
STRUCTURE	LOCATION	SIDE	Р	F
NO.	STA. TO STA.	SIDE	(LF)	(LF)
	POND I	LT	1644	
	POND IOUTFALL	LT	1395	
	12+75 - 33+90	LT	2115	
	34+35 - 34+94	LT	59	
	42+80 - 47+04	LT	425	
	47+31 - 50+40	LT	310	
TOTAL			5948	

SUM	MARY OF FLOATING	TURBIDIT	TY BARRIERS	5
STRUCTURE	LOCATION	SIDE	Р	F
NO.	STATION	SIDE	(LF)	(LF)
JYP-2	11+47 - 11+87	LT	40	
JYP-3	11+47 - 11+85	RT	38	
HOLDEN AVE	33+90 - 34+50	LT	60	
	34+94 - 35+94	LT	100	
TEXAS AVE	401+93 - 402+60	LT	67	
	403+59 - 403+93	LT	34	
LB-0	46+29 - 46+51	RT	22	
	47+04 - 47+31	LT	27	
TOTAL			388	

SUMMARY OF INLET PROTECTION							
STRUCTURE	LOCATION	SIDE	P	F			
NO.	STA. TO STA.	SIDE	(EA)	(EA)			
	EXIST. INLETS						
	HOLDEN AVE.	RT.	7				
	TEXAS AVE.	RT.	2				
	RIO GRANDE AVE.	LT.	1				
	MILLENIA BLVD.	RT.	1				
	PROPOSED INLETS	LT. & RT.	87				
TOTAL			98				

R E V I S I O N S									
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION				


ENGINEERS • SURVEYORS
201 SOUTH BUMBY AVENUE ORLANDO, FLORIDA 32803
PH: (407) 896-3317 FAX: (407) 896-9167 EMAIL; WWW.LOCHRANE.COM
CERTIFICATE OF AUTHORIZATION NO. 2856
FOREST W. ADKINS, P.E. P.E. NUMBER 56003




HOLDEN A VENUE EROSION CONTROL PLAN SHEET NO.

264

2:42:13 PM H:\projects\02076v8\dgn\Roadway\eroconrd0I.dgn







		R E V I S	5 1 0 N S				
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION	<i>LOCHRANE</i>	_
			ł				
			ł			ENGINEERS • SURVEYORS	
			ł			20I SOUTH BUMBY AVENUE ORLANDO, FLORIDA 32803 PH: (407) 896-3317 FAX: (407) 896-9167 EMAIL: WWW.LOCHRAN	
		ŀ				CERTIFICATE OF AUTHORIZATION NO.2856	
			<u> </u>			FOREST W. ADKINS, P.E. P.E. NUMBER 56003	J





HOLDEN A VENUE EROSION CONTROL PLAN SHEET NO. 266






LONGITUDINAL SECTION





LEFT HEADWALL SECTION (Right Headwall Similar)



LEFT CUTOFF WALL SECTION (Right Cutoff Wall Similar)

NOTES:

- I. Space Bars DIIO and DII2 with a bar in each corner and the remaining bars placed at equal spacing.
- 2. Place Bars DII3 at even spaces between corner Bars DIIO and DII2.
- 3. All rebar splices shall be 48 bar diameter, minimum, unless noted otherwise on structural plans.

REVISIONS									
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION				






HOLDEN A VENUE

CONCRETE BOX CULVERT ELEVATION,


SECTION, AND WALL DETAILS

SHEET NO.



For small angles, the contractor may elect to fill the area between the box and the wingwall footing with unreinforced concrete. For wingwall skew angles less than 90 degrees, field bend wingwall reinforcement as necessay while maintaining cover. No additional payment will be made for this work. Typical both sides


DETAIL C - BOTTOM SLAB PLAN VIEW WINGWALL TO BOX CONNECTION (Left Begin Corner Shown - Other Corners Similar)



WINGWALL ELEVATION -Variable Height (Left End Shown - Other Corners Similar)

Notes:

- I. Wingwall Construction Joint perpendicular to Wingwall.
- 2. In the vicinity of the Construction Joint, field bend reinforcement as necessary to maintain minimum reinforcement cover.
- 3. For constant height wingwalls, variable length bars D403, D405, and D408 are not needed.
- 4. Wingwall Skew Angles are measures from the adjecent box exterior wall to the wingwall.
- 5. Turn Wingwall Cutoff Wall as necessary to meet Box Cutoff Wall.



REVISIONS									
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION				





			7	ABLE O	F BOX (CULVERT	VARIA	BLES (In	ches unle	ss shown	otherwi.	se)								
LOCATION	OCATION STRUCTURE BOX HEADWALL and CUTOFF WALL																			
EOCAT TON	OCATION Programme Programm															SR(deg)				
STA. 46+68	LB-0	8	4	12	10	12	10	1	94.3	3	16	31.5	16	30	12	36	12	36	27 .6	27 .6


				TA	BLE OF	BOX CUL	VERT V	ARIABLE	S (CONT.) (Inches	uniess s	hown oth	erwise)					
STRUCTURE		LEFT END WINGWALL LEFT BEGIN WINGWALL																
NUMBER	Rt																Lw(f1)	
LB-0 ·	18	10	32	16	118	0	6.5	6.5	15	18	10	32	16	115	0	4	6.5	15

				TA	BLE OF	BOX CUL	VERT V	ARIABLE	S (CONT.	J (Inches	uniess s	hown oth	erwise)						
STRUCTURE	WWDED																		
NUMBER	Rt	Rw	Rh	Rd	SW(deg)	B (deg)	He(ft)	Hs(ft)	Lw(ft)	RWO(ft)	Rt	Rw	Rh	Rd	SW(deg)	B(deg)	He(f1)	Hs(f1)	Lw(ft)
LB-0	18	10	32	16	130	0	4	6.5	15	4.17	18	10	32	16	118	0	6.5	6.5	20

				CON	CRETE	QUANTIT	IES (yd3)													
STRUCTURE	Lef†	Right	В	OX		Left	Right			FT END NGWALL	:		FT BEG	IN		IGHT EN INGWALL	D		GHT BEO	GIN	Culvert Total
NUMBER	Cutof f Wall	Cutoff Wall	Bottom Slab	Walls	Top Slab	Head Wall	Head Wall	Sub total	Footing	Wall	Sub total	Footing	Wali	Sub total	Footing	Wali	Sub total	Footing		Sub total	
LB-0	0.808	0.808	34.8	23.3	33.8	0.875	0.808	95.4	3.7	3.01	7.08	3.7	2.43	6.5	3.7	2.43	6.5	4.94	4.01	9.44	125
			·							·					·	·	·				

			MAIN S	TEEL RE	INFORCE	MENT S	PACING	in)							
STRUCTURE#	MAIN STEEL REINFORCEMENT SPACING (in) STRUCTURE# DIOI DIO2 DIO3 DIO4 DIO5 DIO6 DIO7 DIO8 D401 D501 D601 D701														
LB-0	6	6	6	6	6	6	6	6	8	8	8	8			

R E V I S I O N S DATE BY DESCRIPTION DATE BY DESCRIPTION





<u>NOTES.</u>

- I. Environmental Class Extremely Aggressive
- 2. Reinforcing Steel, Grade 60
- 3. Concrete Class IV, f'c = 5,500 psi
- 4. Soil Properties:
 Friction Angle 32°
 Modulus of Subgrade Reaction 100,000 ksi
 Nominal Bearing Capacity 2,000 psf
- 5. Reinforcing Steel Quantity 23,880 lbs.

HOLDEN AVENUE
CONCRETE BOX CULVERT
TABLE OF VARIABLES

SHEET NO.

' A	R K	LENGTH	NO	TYP	STY	' B	Ī	С	D	Ε	F	Н	J	κ	N	Ø
IZE	DES	FT IN	BARS	BAR	AIG	FT INFR	FT	INFR		FTINF		RFTINFE		FTINF	RNO	
·	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	LOCA	TION	<u>, </u>	MA	IN BOX			1 - 1 - 1 - 1 - 1		NO . REQU	IRED = I			.,	
	1 1	İ	ĺ	1 1	Ì	i 1	ĺ									
5	101	9-2	178		ı	9-2	1									
5	201	VARY	9	1	İ	8-11										
	1 1	4-8	0	1 71	İ	0-31/4	1									
5	301	VARY	9	1 1	İ	8-11										
	1 1	4-8	0	1 71	ı	0-31/4	1									
5	102	9-2	178		i	9-2										
5	202	VARY	9	1 /1	ı	8-11	1									
		4 - 8	0		-	0-31/4										
5	302	VARY	9	1 71	ł	8-11	•									
,		4-8	o		-	0-31/4										
5	103	9-2	184			9-2										
5	203	VARY	6	1 71	ł	6-01/2	ł									
J	203	3- 2	0			0-3 1/2										
5	303	VARY	4	1 11	ł	6-01/2	ŀ									
J	1202	3- 2	6			6-01/2						_			+ -	
5	100	9- 2	184	{	-	9-2	ł					+	-		+ +	
	104	9- 2 VARY	E	',								+			+ 1	
5	204		6		-	6-0 1/2	-					+	-	-	+ 1	
c	704	3-2	0			0-31/2						+	1	1	+	
5	304	VARY	6		-	6-01/2	ł								+	
_	1,00	3-2	0	/		0- 5 1/2						1				
5	105	7 - 0	376	10		2-10	4.	- 2				1			-	
5	106	7-0	376	10		2-10	4	- 2							+	
5	108	5-6	376	1	-	5-6										
4	109	96 - 0	12	41	- -	60-0	36						2-2		1	
4	110	96-0	12	41	ļ	60-0	36						2- 2		/	
4	[111]	95- 4	12	41		60-0		- 3 1/2					2- 2		/	
4	112	96 - 0	12	41	-	60-0	36-						2- 2		1	
4	[113]	96-0	24	41		60-0	36	0					2- 2		1	
			ļ		ļ		Į									
		LOCA	TION		ĻE	FT END WIL	NGWAL	<u>L L</u>			NO. REQU	IRED = I				
			ļ		ļ		ļ									
5	401	6-3	22	/		6-3										
5	402	14-6	10	/	ļ	14-6										
4	404	14-6	7	/		14-6										
4	406	6-3	15	$\perp \perp$		6-3										
5	407	6-0	22	10	ļ	1-10	4 -	- 2								
5	409	4-6	22] []		4-6]									
	410	4-6	22		ļ	4 - 6	ļ									
	411	14-6	10	[-t]	ĺ	14-6]									
5	412	2-0	9			2-0										
		LOCA	TION		ĻΕ	FT BEGIN V	WING	WALL			NO . REQU	IRED = I				
]				\perp										I	
5	501	VARY	22	- 1	\perp	6-11/2									$oxed{oxed}$	
		5- 0	0			3-10 1/2									<u> </u>	
5	502	14-6	6			14-6										
	503	VARY	3	1		11-9 1/2										
		15-10	0			19-9 1/2										
4	504	14-6	4			14-6										
	505	VARY	3			19-9 1/2										
		15-10	0			11-9 1/2										
4	506	VARY	15			6-11/2										
,		5- 0	0		\top	3-10 1/2										
		6-0	22			1-10		- 2				1				
	507	D = U			-		<u> </u>				+	1		1		
5	507 509					4 - 6										
5 5	509	4-6	22		+	4 - 6 4 - 6						+				
5 5 5				1		4-6 4-6 14-6										

NOTE:

REFER TO FDOT STANDARD INDEX NO. 21300 FOR STANDARD BAR BENDING DETAILS.

R E V I S I O N S

DATE BY DESCRIPTION DATE BY DESCRIPTION



AVCON, INC.

5555 MICHIGAN STREET, SUITE 200
ORLANDO, FLORIDA 32822-2779
PHONE: (407) 599-1122
FAX: (407) 599-1133
www.wo.coninc.com



HOLDEN AVENUE
CONCRETE BOX CULVERT
REINFORCING BAR LIST

SHEET NO.

	DES	LENGTH		TYP	STY	<u>B</u> FT IN FR	C ET IMER	D FT IN FR	E	F	H	J PET LINER	K	N R NO	
	512	2-0	9		4 0	2-0		I I III II II	i i jini ji i	177 1774 1775			1 1 111111	1 10	ť
						j									t
		LOCA	TION		RI	GHT END W	INGWALL		ı	NO. REQUI	RED = I		ı		_
5	601	VARY	00	,	-	6 11/									+
5	807	5- 0	22			6- 1 ½ 3-10 ½									t
5	602	14-6	6		ŀ	14-6									t
5	603	VARY	3	I		11-9 1/2									İ
		15-10	0			19-9 1/2									I
	604	14-6	4			14-6									Ŧ
4	605	VARY 15-10	0			19-9 1/2									+
4	606	VARY	15			6-11/2									t
		5-0	0	$ \cdot \rangle $		3-10 1/2									t
5	607	6-0	22	10		1-10	4-2								I
5	609	4 - 6	22	1		4-6									1
	610 611	4-6 14-6	22 10			4-6									+
	612	2-0	9			2-0									t
3	51	14-8	2		ER	TO WINGWA	I ALL OPENIN	G SHEET B	-7						t
5	DG	8- 0	8			TO WINGWA									İ
			<u> </u>				ļ								1
	1 1	LOCA'	<i>rion</i> l	1 1	R/	GHT BEGIN	<i>WINGWALL</i>]	[•	NO. REQUII	RED = 1 [1 —			Т
5	701	6-3	30		-	6-3						-			t
5	702	19-6	10	, ,		19-6	:								t
4	704	19-6	7			19-6									Ī
4	706	6-3	20			6-3	_								1
5	707	6-0	30	10		1-10	4-2								\downarrow
5 5	709 710	4-6 4-6	30 30	H H	-	4 - 6 4 - 6					}	·			t
4	711	19-6	10	i		19-6	:								t
5	712	2- 0	9			2-0									Ī
]]	4.00 •]									<u> </u>			1
	i i	LOCA'	i ion I	i i	LE.	<i>FT HEADWA.</i> İ	LL İ	i 1	,	NO. REQUII	RED = 1 	ı —			Т
6	801	10- 5	3	1 1	-	10- 4 3/4						·			t
6	802	10-5	3			10-4 3/4					İ				İ
4	803	6-5	11.	27	1	2-03/4	0-10		0-3	1-93/4	0-10	0-10			1
		LOCA	[T (O))			 GHT HEADW	 ^			 NO. REQUI	 				T
]]	LULA]]]	ï]]	[,	HO. NEQUI]			Τ
6	804	10- 5	3	1		10-4 3/4									İ
	805	10-5	3			10-4 3/4									Ţ
4	806	6-3	11	27	+	1-11 1/2	0-10		0- 3	1-81/2	0-10	0-10			+
		LOCA	L T 10N	<u> </u>	 F	 FT CUTOFF	WAII			 NO . REQUI	l RFD = /	L		I	T
		LUCA	. , , , , ,		Ť	307077	******			NEQUI	,,				Τ
4	807	10- 5	2	1		10-4 3/4									İ
	808	10- 5	2	1		10-43/4									Į
4	809	6-2	11	7	_	2-5 1/2	0-6	0- 4 1/2	0- 4 1/2						\downarrow
		LOCA	 T 10M		RI	 GHT CUTOF:	 F WΔ!!			 NO . REQUII	 RFD = '				L
		LOCA	, , , , , ,		$\frac{\alpha}{1}$		"ALL			NEQUI	- 1				Τ
4	810	10-5	2	1	\top	10-4 3/4									T
	811	10- 5	2	1		10-4 3/4									I
4	812	6-2	11	7		2-5 1/2	0-6		0- 4 1/2						L
								END OF L	I ST						

NOTE:

REFER TO FDOT STANDARD INDEX NO. 21300 FOR STANDARD BAR BENDING DETAILS.

R E V I S I O N S

DATE BY DESCRIPTION DATE BY DESCRIPTION








HOLDEN AVENUE

CONCRETE BOX CULVERT

REINFORCING BAR LIST (CONT.)

SHEET NO.



TYPICAL CULVERT WINGWALL OPENING

NOTES:

- Provide min. 2'-0" wide strip of filter fabric around pipe between pipe and outside face
 of wall.
- 2. Coordinate exact location of wall opening with Roadway Plans.
- 3. Bars DIO5 through Bars DIO9 will remain as whole length in bar schedule and later cut in the field. Refer to sections for bar references.

		R E V I :	SIONS		
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION
	l				
	l				
	l				
	l		1		
	ı			l	





GENERAL NOTES

I. CONSTRUCTION SPECIFICATIONS.

Florida Department of Transportation "Standard Specifications for Road and Bridge Construction", (current edition) and supplements thereto.

- 2. SPECIFICATIONS: American Assoc. of State Highway and Transportation officials (AASHTO) LRFD Bridge Design Specifications (17th edition). Florida Dept. of Transportation Structures Design Guidelines (January 2006).
- 3. MATERIAL STRESSES. All allowable stresses shall be in accordance with the current AASHTO Specifications for all the materials shown on the plans.
- a. Concrete Compressive Strength.
 - I. Precast Concrete Sheet Piles, Class ▼ (Special with Silica Fume), f'c = 6000 psi min.
 - 2. C-I-P Concrete Bulkhead, Class II, f'c= 3400 psi min.
 - 3. C-I-P Concrete Retaining Wall, Class $I\nabla$, f'c=5500 psi min.
- b. All Reinforcing Steel. ASTM A615, Grade 60.
- 4. DESIGN METHOD: Load Factor, except that internal and external stability shall be designed for service loads. Allowable bearing capacity equals 2 ksf.

The following minimum factors of safety shall be utilized in the design of the walls.

Overturning F.S. = 2.0 F.S. = 1.5 Sliding Bearing Capacity F.S. = 2.5

5. DESIGN LOADS.

Truck Loading • HS20-44

Sidewalk Loading: 85 lbs.per square foot

6. SURFACE FINISH.

A Class 5 Applied Finish Coating shall be applied to the top of the wall and the exposed face above ground line.

7. ARCHITECTURAL TREATMENT.

Alternate Architectural Treatments may be substituted for the Striated Pattern shown when approved by the Engineer. Concrete required for Architectural Treatment is not included in the quantitites.

8. ENVIRONMENTAL.

Environmental Classification. Extremely Aggressive

9. For Typical Sections along roadway, see Roadway Plans.

IO. BULKHEAD CONSTRUCTION.

Refer to Wall Plans for extent and refer to Concrete Sheet Pile Bulkhead Details sheet for size and reinforcing of bulkhead. Provide $\frac{1}{2}$ expansion joints in the bulkhead at 80 feet spacing using compressible filler material and provide 3/4" v-groove control joints at quarter points between expansion joints. Expansion and control joints shall be placed in-line with sheet pile joint, typical.

II. PHASING.

All Sheet Pile Walls shall be installed after the installation of adjacent drainage structures and other utilities. Contractor shall backfill and compact subgrade adjacent to these new underground utilities to ensure an adequate density of the soil in front of driven sheet pile wall.

	CON	CRETE S	SHEET PILL	E DATA TA	BLE	
WALL NUMBER	TYPE (See Detail A)	NUMBER REQUIRED	L (F † •)	T (In•)	X (F t•)	Φ (Degrees)
	Α	69	16	10	90.83	
2	В	2	16	10	90,83	45
	В	/	<i>1</i> 6	10	90.83	40
5A	Α	174	4	10	92 . 53	
5B	Α	244	8	10	94 . 53	
8	Α	15	26	10	<i>85.33</i>	

NOTE.

Work this sheet and Concrete Sheet Pile Data Table with FDOT Design Standards FY 2016-2017 Index No. 6010, 6040, and 6130. Costs to upgrade the precast panel to FY 2016-2017 shall be included in the bid.

LEGEND

B.F.O.W.= Back Face of Wall F.F.O.W.= Front Face of Wall

		REVIS	SIONS		
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION




ORANGE COUNTY ENGINEER OF RECORDS LUCA DELVERME, P.E. NO. 63055 F L O R I D A CERTIFICATE OF AUTHORIZATION NO. 5057





\$TIME\$


SHEET NO.


W-I
























WALL OPENING NOTES

- I. Contractor shall coordinate the location, extent, and orientation (skew into wall) of each wall opening for the penetration of all utilities, i.e. pipes with diameters greater than 12". Refer to roadway plans for all wall openings required along portions of the retaining wall.
- 2. Bars A and Bars G2 shall be set as indicated in the bar schedule and later cut in the field as required. Bars B shall replace all interupted Bars A and Bars G2 on each side of opening (each face). The length of Bars DG shall be a minimum 2x diameter of opening. Hook ends of Bars DG if necessary.



		REVI	SIONS		
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION
1					

TYPICAL DRAINAGE PIPE THRU WALL

Grout all around


.9

6"





HOLDEN A VENUE C-I-P RETAINING WALL SECTIONS SHEET NO. W-IO



C-I-P RETAINING WALL DATA

										WALL DI	MENSIONS	5													
Wall	Be	egin	E	nd			ight _	,	, w		D	w	L	001	L ,	0.0	Slope	D	oil	L _{kev}	D	V	Wall		Ftg.Cov.
No.	Station	Offset	Station	Offset	£ +	egin in.	£.	nd in.	ft.	ngth Lin	10	io	ft.		ft.	oe In.	Backwall	f+			key	step	Cover	(typ.)	(bot.)
					11.	1111.	//•	1//•		in.	in.	in.	//•	in.	11.	111.		11.	in.	in.	in.	in.	in.	in.	1//•
W - /	11+47.00	62.5	12+70.00	62.5	10	6	10	6	123	0	24	12	9	0	3	6	0	/	0	12	12	0	2	3	4
					1																				
					•																				
					•																				

													В	BILL OF RE	EINFORC	ING STE	EL													
	<i>y</i>					Bars J											Bars K									Bar	rs M			
Wall			Spacing -			Α			-	Ave	rage			Spacing		,	4			D	Avei	rage				Λ		D	Total	Longth
No.	Size	No.	Spacing	Be	gin	E	nd	1)	Total	Length	Size	No.	Spacing	Be	gin	Er	nd	')	Total i	Length	Size	No.	· /	4	В		Total Length	
			in.	ft.	in.	ft.	in.	ft.	in.	ft.	in.			in.	ft.	in.	ft.	in.	ft.	in.	ft.	in.			ft.	in.	ft.	in.	ft.	in.
W - / ·	6	185	8	5	8	5	8	4	0	9	8	0	0	0	0	0	0	0	0	0	0	0	6	124	5	0	5	0	10	0
•																														
•																														
•																														
•																														
•																														

														В	ILL OF	REINFO	RCING S	TEEL														
			Bars H					Bars GI					Bar	s R				Bars Z					B	ars A						Bars	В	
Wall			Spacing	100	ngth			Spacing	No. of	Total	Length			/ / /	ngth			Spacing	1 , 0	ngth				Len	gth		Ave.	rage			1 , 0	ength
No.	Size	No.	Spacing	LUI	igiii	Size	No.	Spacing	Lap	701012	_engin	Size	No.		ngm	Size	No.	Spacing	Lei	igiii	Size	No.	Be	gin	E	nd	Ler	ngth	Size	No.		<i>igiti</i>
			in.	ft.	in.			in.	Splices	ft.	in.			ft.	in.			in.	ft.	in.			ft.	in.	ft.	in.	ft.	in.			ft.	in.
W-/ ·	8	124	12	8	6	5	20	12	3	122	6	0	0	0	0	4	93	16	2	6	6	185	10	3	10	3	10	3	0	0	0	0
•																																1
•																																
•																																

															BILL	OF REII	VFORCIN	G STE	EL								
				Bars	F							Bars (G2					Bars	SI (See	Note 7	# 9)			Bars	DG (See	e Note	#9)
Wall			Spacing		Len	ngth		Ave	rage			Spacing	No. of	Total	Length			Lei	ngth	Ler	ngth	Ler	ngth			/ 00	ngth
No.	Size	No.	Spacing	Beg	gin	Ε	nd	Ler	ngth	Size	No.	Spacing	Lap	1 Ordi L	Lengin	Size	No.		A	1	3	(C	Size	No.	Len	ym
			in.	ft.	in.	ft.	in.	ft.	in.			in.	Splices	ft.	in.			ft.	in.	ft.	in.	ft.	in.			ft.	in.
W-/ ·	6	124	12	10	3	10	3	10	3	5	22	12	3	122	6	3	2	2	4.5	1	0	0	0	5	8	7	2
•																3	2	/	9.5	1	0	0	0	5	8	9	6
•																											
•																											
•																											
•																											

	ES	TIMATED QUA	NTITIES	
		Concrete		5
Wall No.	Footing	Wall	TOTAL	Reinf. Steel
	C.Y.	C.Y.	C.Y.	LBS.
W-/ ·	83	47.8	130.8	18233
•				
•				
•				

QUANTITIES NOTES.

(1) Includes concrete for shear key.

NOTES.

- I. Work the Sheet with Sheets W-IO and W-II.
- 2. A value of 'O' for Slope Backwall indicates front and back of wall are parallel.
- 3. Dsoil is typical depth of soil and is used for design purposes only. See Plan and Elevation for actual ground line.
- 4. Non-zero values for Lkey and Dkey indicate the existence of a shear key.
- 5. A non-zero value for Vstep indicates the existence of a footing step, see Wall Plan and Elevation for location.
- 6. Bars J, K, A and F vary uniformly between begin and end wall heights as indicated by begin and end dimensions.
- 7. The number of GI Bars includes 2 additional bars when a shear key is specified.
- 8. For walls with variable begin/end height, Bars G2 shall be fanned such that they are evenly spaced throughout length of wall.
- 9. Two sets of values are provided; First set corresponds to 42" SRCP, Second set corresponds to 30" SRCP. Contractor to verify bar SI and DG dimensions with overall Pipe diameter for Typical Wall Opening detail.

	REVIS	S 1 0 N S			Tr
BY	DESCRIPTION	DATE	BY	DESCRIPTION] ŀ
					٦Ļ
					lì
					•
	BY		R E V I S I O N S BY DESCRIPTION DATE		






HOLDEN A VENUE C-I-P RETAINING WALL DATA SHEET NO.

....

I2:48:05 PM S:\2003\2003.0I6.0I - Holden Ave Phase I\CAD\RetainingWall\RetWallData(W-I2).dg




TYPICAL SECTION THRU SIDEWALK

<u>Note•</u>

I. Concrete Quantity & Pay Item For Bulkhead Does Not Include The 4" Thick Portion Of Sidewalk.

2. Refer To General Notes Sheet For Joint Spacing And Other Information.



TYPICAL SECTION THRU SIDEWALK


@ Wall No. 6B


Ε	STIMATED QUA	NTITIES
Wall No.	Bulkhead Quantity (CY)	Reinforcing Steel (lbs.)
2	<i>32.</i> 4	1481
5A	76.7	3655
5B	107.4	5792
8	8.1	320

		R E V I :	SIONS			Тг
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION]
						٦Ļ
						1
						-
			1			1









SECTION A-A

WALL OPENING NOTE:

I. Contractor Shall Coordinate The Location, Extent, And Orientation (Skew angle of pipe Into Wall) Of Wall With Roadway Plans.

	ESTIMATED QUA	ANTITIES	
WALL NO.	ITEM	UNIT	QUANTITY
2	Class V Concrete (Special)	C.Y.	1.0
	Reinforcing Steel	LB.	<i>348</i>
8	Class V Concrete (Special)	C.Y.	2.3
0	Reinforcing Steel	LB.	800

		REVIS	SIONS			Т	Ξ
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION] !	⊩
						ו ך	L
						1	
							-

AVCON ENGINEER OF RECORD: LUCA DELVERME, P.E. NO.63055 CERTIFICATE OF AUTHORIZATION NO.5057

AVCON, INC.
5555 MICHICAN STREET, SUITE 200
ORLANDO, FLORIDA 32822-2779
PHONE: (407) 599-1122
FAX: (407) 599-1133
www.avconinc.com





HOLDEN A VENUE C-I-P WALL SEGMENT DETAILS SHEET NO. W - 14

12:52:34 PM S:\2003\2003.016.01 - Holden Ave Phase I\CAD\RetainingWall\WallDetails(W-14).dgn

TRAFFIC CONTROL PLANS FOR HOLDEN AVENUE (PHASE I) JOHN YOUNG PARKWAY TO ORANGE BLOSSOM TRAIL (US 441) ORANGE COUNTY, FLORIDA

DISTRICT 6





PROJECT LOCATION

GOVERNING STANDARDS AND SPECIFICATIONS: FLORIDA DEPARTMENT OF TRANSPORTATION, DESIGN STANDARDS FY 2016/2017, AND STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION DATED JANUARY 2017, AS AMENDED BY CONTRACT DOCUMENTS.

JERRY L. DEMINGS, COUNTY MAYOR

BOARD OF COUNTY **COMMISSIONERS**

BETSY VANDERLEY DISTRICT 1 DISTRICT 2 CHRISTINE MOORE DISTRICT 3 MAYRA URIBE MARIBEL GOMEZ CORDERO DISTRICT 4 EMILY BONILLA DISTRICT 5 VICTORIA P. SIPLIN DISTRICT 6

PLANS WERE PREPARED ACCORDING TO AVAILABLE INFORMATION TO ADEQUATELY ADDRESS CONDITIONS AS THEY EXISTED AT THE TIME OF PLAN PREPARATION. DEEDS, CONDITIONS, AND OWNERSHIP OF PROPERTIES MAY HAVE CHANGED SINCE THE PROJECT DESIGN, THE COUNTY'S REPRESENTATIVE WILL ADDRESS CHANGES AND NEEDS WITH THE PROPERTY OWNER OR THEIR REPRESENTATIVE. CONTRACTOR SHALL WORK WITH THE COUNTY'S REPRESENTATIVE IN ADDRESSING AND MEETING NEEDS AND CONDITIONS THAT MAY HAVE CHANGED SINCE PLANS PREPARATION.

CERTIFICATION TO PLANS

I HEREBY CERTIFY THAT THE DESIGN FOR THIS PROJECT AND THE ATTACHED CONSTRUCTION PLANS COMPLY WITH THE REQUIREMENTS OF SECTION 336.045 OF THE FLORIDA STATUTES AND ARE IN SUBSTANTIAL CONFORMANCE WITH THE STANDARDS CONTAINED IN THE EDITION OF THE "MANUAL OF UNIFORM MINIMUM STANDARDS FOR DESIGN, CONSTRUCTION AND MAINTENANCE FOR STREETS AND HIGHWAYS" IN EFFECT ON THIS DATE AS ADOPTED BY THE FLORIDA DEPARTMENT OF TRANSPORTATION PURSUANT TO SUBSECTION 336.045 (I) OF THE FLORIDA STATUTES.

DATE:	ENGINEER:				FLORIDA	REG.	NO.	37271	_
		DANTE	OADDIEL	0.					

PROJECT LOCATION LOCATION MAP

1	(INDEX OF SHEETS
	SHEET	DESCRIPTION
	M-/	KEY SHEET
	M-2	GENERAL NOTES
	M-3 - M-5	
	M-6 - M-16	
	M-17 - M-87	
	M-88 - M-94	TEMPORARY SIGNALIZATION
ι')

PLANS PREPARED BY:

UTILITIES ENCOUNTERED

DANTE A. GABRIEL, P.E. P.E. LICENSE NUMBER 37271 225 E. ROBINSON STREET, SUITE 300 ORLANDO, FL 32801 CERTIFICATE OF AUTHORIZATION 3932

REVISIONS	DATE	BY
DESIGNED BY: JMD DATE:7/13/2018		$\equiv \searrow$

DESIGNED BY: JMD	DATE:7/13/2018
CHECKED BY: DAG	DATE:7/13/2018
DRAWN BY: JMD	DATE:7/13/2018
APPROVED BY: DAG	DATE:7/13/2018
PROJECT NO: 62796	.00

GENERAL NOTES

- I. MAINTENANCE OF TRAFFIC SHALL BE IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (2009 ED.) AND THE FLORIDA DEPARTMENT OF TRANSPORTATION (FDOT) DESIGN STANDARDS (FY 2016/2017)
- 2. THE CONTRACTOR SHALL CONTACT ORANGE COUNTY ONE (I) WEEK PRIOR TO THE START OF ANY PHASE OF WORK TO REQUEST STREET, LANE OR SIDEWALK CLOSURE AUTHORIZATION.
- 3. LOCAL RESIDENTIAL/BUSINESS ACCESS SHALL BE MAINTAINED AT ALL TIMES. CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION TO THE RESIDENTS/BUSINESSES AFFECTED BY CONSTRUCTION ACTIVITIES, ONE (I) WEEK IN ADVANCE OF THE START OF ANY PHASE OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE COPIES OF THE NOTIFICATION TO THE TRAFFIC CONTROL MANAGER PRIOR TO DISTRIBUTION.
- 4. THE CONTRACTOR SHALL NOTIFY THE ORANGE COUNTY SCHOOL BOARD, SAFETY MANAGER, WINNIE GERKIN ((407) 521-2339), ONE (I) WEEK IN ADVANCE OF THE START OF ANY PHASE OF CONSTRUCTION TO COORDINATE SCHOOL BUS RE-ROUTING.
- 5. THE CONTRACTOR SHALL NOTIFY THE FDOT OFFICE A MINIMUM OF FORTY-EIGHT (48) HOURS IN ADVANCE OF ANY LANE CLOSURES OR ANY WORK WITHIN THE FDOT RIGHT-OF-WAY.
- 6. ORANGE COUNTY RESERVES THE RIGHT TO REQUIRE ADDITIONAL DEVICES AND/OR CHANGES TO THE TRAFFIC CONTROL PLAN BASED UPON CHANGING TRAFFIC CONDITIONS.
- 7. ANY CHANGES MADE TO THE TRAFFIC CONTROL PLAN BY THE CONTRACTOR, SHALL BE SIGNED AND SEALED BY A REGISTERED PROFESSIONAL ENGINEER AND APPROVED BY THE TRAFFIC CONTROL MANAGER PRIOR TO IMPLEMENTATION.
- 8. CONTRACTOR SHALL NOTIFY LYNX AT (407)841-2279 A MINIMUM OF ONE (I)WEEK PRIOR TO IMPLEMENTING ANY STREET CLOSURE OR DETOUR PLAN TO COORDINATE BUS RE-ROUTING.
- 9. THE NUMBER OF DEVICES SHOWN ON THESE PLANS ARE FOR ILLUSTRATION PURPOSES. ADDITIONAL DEVICES MAY BE REQUIRED TO PROPERLY PROTECT THE WORKERS AND WORK ZONE FROM VEHICULAR TRAFFIC.
- IO. IF TEMPORARY MARKINGS ARE REQUIRED ON FRICTION COURSE SURFACES, ALL MARKINGS SHALL BE INSTALLED USING 3M BRAND STAMARK REMOVABLE TAPE, SERIES 750, WET REFLECTIVE TEMPORARY TAPE. THE USE OF "FOIL BACK" TYPES OF TEMPORARY TAPE IS NOT PERMITTED.
- II. 3M BRAND REMOVABLE BLACK MASK TAPE, SERIES 145, IS THE ONLY APPROVED MATERIAL FOR "BLACKING OUT" OF EXISTING PAVEMENT MARKINGS ON FINAL ROADWAY SURFACES. UNDER NO CIRCUMSTANCES WILL BLACK PAINT OR GRINDING BE PERMITTED.
- 12. PAINT PRODUCTS AND RETRO-REFLECTIVE PAVEMENT MARKERS WILL BE CONSIDERED TEMPORARY PAVEMENT MARKING MATERIALS ON SURFACES THAT ARE TO BE MILLED AND RESURFACED.
- 13. EXISTING PAVEMENT MARKINGS, WHICH ARE TO BE OBLITERATED, SHALL BE RESTORED TO ORIGINAL CONDITION UPON COMPLETION OF CONSTRUCTION AND PRIOR TO REINSTATING VEHICULAR TRAFFIC.
- 14. ALL SIGNS AND TRAFFIC CONTROL DEVICES SHALL BE NEW OR LIKE NEW CONDITION. ALL SIGNS SHALL BE POST MOUNTED UNLESS OTHERWISE INDICATED.
- 15. CHANNELIZING DRUMS SHALL BE USED ON NEWLY PAVED ROADWAYS.

DATE

- 16. DURING NON-WORKING HOURS, NO EQUIPMENT, VEHICLES OR MATERIAL SHALL BE PARKED OR STORED WITHIN THE CLEAR ZONE OF A ROADWAY OPEN TO VEHICULAR TRAFFIC.
- IT. EXISTING REGULATORY AND WARNING SIGNS ARE TO BE MAINTAINED AT ALL TIMES UNLESS OTHERWISE NOTED. ALL EXISTING SIGNS WHICH CONFLICT WITH THE TRAFFIC CONTROL PLAN DURING A CONSTRUCTION PHASE SHALL BE REMOVED OR COVERED AS NECESSARY. THE CONTRACTOR SHALL MAINTAIN AND RELOCATE EXISTING ROADWAY SIGNS, AS CONDITIONS WARRANT IN EACH PHASE, THROUGHOUT THE DURATION OF CONSTRUCTION. THE COST OF THESE SIGNING OPERATIONS IS TO BE INCLUDED IN THE LUMP SUM MAINTENANCE OF TRAFFIC.
- 18. PEDESTRIAN CONTROL SHALL BE MAINTAINED ON ONE SIDE OF THE ROAD AT ALL TIMES. IF UNABLE TO DO SO, THE CONTRACTOR SHALL PROVIDE TEMPORARY WALKWAYS, BOARDWALKS AND/OR TEMPORARY CONCRETE SIDEWALKS.
- 19. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING EACH EMPLOYEE SUPERVISING THE SELECTION AND PLACEMENT OF MAINTENANCE OF TRAFFIC (MOT) CONTROL DEVICES SHALL BE PROPERLY TRAINED BY ATTENDING AND SUCCESSFULLY COMPLETING AN FDOT APPROVED MOT COURSE. THE TRAINING SHALL BE AT A LEVEL APPLICABLE TO THE EMPLOYEE'S LEVEL OF INVOLVEMENT. COPIES OF CERTIFICATIONS SHALL BE PROVIDED TO ORANGE COUNTY PRIOR TO IMPLEMENTING ANY PHASE OF MOT.

- 20. THE CONTRACTOR SHALL PROVIDE A TRAFFIC CONTROL SUPERVISOR (TCS) WHO IS RESPONSIBLE FOR INITIATING, INSTALLING AND MAINTAINING ALL TRAFFIC CONTROL DEVICES.
- 21. THE TCS SHALL BE AVAILABLE ON A 24-HOUR PER DAY BASIS, PARTICIPATE IN ALL CHANGES TO TRAFFIC CONTROL AND REVIEW THE PROJECT ON A DAY-TO-DAY BASIS.
- 22. THE TCS SHALL BE PRESENT DURING THE INITIAL SETUP OF THE TRAFFIC CONTROL PLAN AND ALL SUBSEQUENT PHASES OR CHANGES TO THE TRAFFIC CONTROL.
- 23. THE TCS SHALL IMMEDIATELY CORRECT ALL DEFICIENCIES.
- 24. THE CONTRACTOR SHALL ENSURE THE TCS BE AVAILABLE ON SITE WITHIN 45 MINUTES OF NOTIFICATION OF AN EMERGENCY SITUATION AND IS PREPARED TO RESPOND TO AND CORRECT THE TRAFFIC CONTROL OR PROVIDE ALTERNATE ARRANGEMENTS FOR CORRECTIVE ACTIONS.
- 25. THE TCS SHALL BE RESPONSIBLE FOR PERFORMING WEEKLY, DAYTIME AND NIGHT TIME INSPECTIONS OF ALL TRAFFIC CONTROL DEVICES, TRAFFIC FLOW, PEDESTRIAN, BICYCLIST MOVEMENT THROUGH THE WORK AREA AND BUSINESS ACCOMMODATIONS.
- 26. ORANGE COUNTY MAY DISQUALIFY AND REMOVE FROM THE PROJECT A TCS THAT FAILS TO COMPLY WITH THESE PROVISIONS. ORANGE COUNTY MAY ALSO SUSPEND ALL WORK ACTIVITIES UNTIL CORRECTIVE ACTIONS HAVE BEEN COMPLETED.
- 27. THE CONTRACTOR SHALL EITHER BACKFILL OR COVER BY AN APPROVED METHOD ALL OPEN TRENCHES AT THE END OF EACH WORK PERIOD.
- 28. THE CONTRACTOR SHALL REPLACE ANY VEHICLE DETECTION LOOPS DAMAGED DURING CONSTRUCTION, AS PER THE ORIGINAL CONTRACT PLANS.
- 29. MODIFICATIONS TO OR RELOCATION OF SIGNALS SHALL BE THE CONTRACTORS RESPONSIBILITY. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL MAINTENANCE MODIFICATIONS OR RELOCATIONS DURING EACH PHASE OF CONSTRUCTION. PAYMENT FOR ALL SIGNAL HEAD RELOCATIONS, MODIFICATIONS, AND TEMPORARY SIGNALIZATION SHALL BE INCLUDED AS PART OF THE LUMP SUM MAINTENANCE OF TRAFFIC.
- 30. ARROWS DENOTE DIRECTION OF TRAFFIC ONLY AND DO NOT REFLECT PAVEMENT MARKINGS. PAVEMENT MARKINGS HAVE BEEN LABELED AS NECESSARY.
- 31. TRAFFIC SHALL BE MAINTAINED ON PAVED SURFACES AT ALL TIMES.
- 32. POSITIVE DRAINAGE SHALL BE MAINTAINED AT ALL TIMES FOR THE ENTIRE PROJECT.
- 33. CHANNELIZING DEVICES ERECTED ALONG SIDE STREETS, BUSINESS DRIVEWAYS, AND RESIDENTIAL DRIVEWAYS SHALL BE SPACED AT 10' CENTER-TO-CENTER ALONG THE RETURN RADIUS UNLESS OTHERWISE NOTED.
- 34. ALL TEMPORARY PAVEMENT SHALL UTILIZE A FIRM AND UNYIELDING BASE WITH 2" ASPHALT PAVEMENT. PAVEMENT SHALL ADHERE TO PAVEMENT DESIGN FOR NEW ROADWAY. TEMPORARY PAVEMENT SHALL BE REPAIRED AS NEEDED OR AS DIRECTED BY THE ENGINEER AND PAYMENT SHALL BE INCLUDED IN THE LUMP SUM MAINTENANCE OF TRAFFIC.
- 35. ALL MAINTENANCE OF TRAFFIC PLANS SHOULD BE SHARED WITH LYNX AND ALL CHANGES PROVIDED WITH AT LEAST 48 HOURS NOTICE. THESE SHOULD BE SENT TO THE ASSISTANT CHIEF SUPERVISOR AT (407) 254-6207 (KTILLET@GOLINX.COM) WITH A COPY TO THE CHIEF SUPERVISOR AT (407) 254-6223 (RQUINONES@GOLINX.COM).
- 36. LYNX WILL MAINTAIN BUS SERVICE IN THE AREA DURING CONSTRUCTION. LINK 8 RUNS NORTH-SOUTH ON TEXAS AVE.
 AND EAST-WEST ON HOLDEN AVE. FROM TEXAS AVENUE TO ORANGE BLOSSOM TRAIL. LINK 57 RUNS NORTH-SOUTH ON
 JOHN YOUNG PARKWAY. THE CONTRACTOR MUST INCLUDE LYNX SERVICE, INCLUDING PEDESTRIAN ACCESS TO AND
 FROM THE BUS AT EACH BUS STOP.
- 37. AT LEAST 60 FEET FROM THE BACK OF THE STOPPED BUS TO THE TANGENT OF THE CURVE OF THE NEAREST DRIVEWAY OR 100 FEET FROM THE LOCATION OF THE BUS ARE REQUIRED TO ACCOMMODATE A TYPICAL 40 FOOT LONG LINX BUS. THE FRONT DOORS ARE LOCATED AT THE FRONT CORNER OF THE TRANSIT BUS. THE REAR DOORS ARE LOCATED 27 FEET FROM THE FRONT CORNER. NEITHER SHOULD EMPTY TO DRAINAGE AS ALIGHTING CUSTOMERS CAN TRIP AND BE INJURED.
- 38. NOTE THAT LYNX SIGNS ARE NOT TO BE REMOVED OR RELOCATED BY THE CONTRACTOR. THE CONTRACTOR WILL COORDINATE WITH LYNX PROVIDING AT LEAST 7 DAYS NOTICE FOR LYNX TO REMOVE OR RELOCATE SIGNS. THE CONTRACTOR WILL COORDINATE WITH LYNX BUS STOP COORDINATION AT (407) 254-6180 (1BROWN@GOLYNX.COM) WITH A COPY TO LYNX FACILITIES MAINTENANCE AT (407) 254-6010 (SROBINSON@GOLYNX.COM).
- 38. THE CONTRACTOR SHALL KEEP ALL SIGNALS AFFECTED BY CONSTRUCTION ACTIVITIES OPERATIONAL THROUGHOUT ALL PHASES OF CONSTRUCTION. VEHICLE DETECTION MUST BE MAINTAINED FOR ALL LANES AT ALL TIMES.
- 39. NO LANE CLOSURES ALLOWED 6AM-9AM AND 3PM-7PM.
- 40. NIGHT TIME LANE CLOSURES REQUIRE POLICE OFFICER IN MARKED CAR PRESENT ON APPROACH TO WORK ZONE.
- 41. DRUMS WITH LIGHTS SHALL BE USED FOR CHANNELIZING DEVICES.

ORANGE COUNG OVERNMENT OR I D

TRAFFIC CONTROL PLAN
GENERAL NOTES

SHEET NO.

M-2

PHASE IA:

- THE PURPOSE OF THIS PHASE IS TO CONSTRUCT TEMPORARY PAVEMENT ON HOLDEN AVENUE AND TEXAS AVENUE TO PREPARE FOR TRAFFIC SHIFTS THAT WILL BE UTILIZED TO COMPLETE SUBSEQUENT CONSTRUCTION ACTIVITIES AND TO PREPARE THE EXISTING DRAINAGE FACILITIES TO ACCOMMODATE POSITIVE DRAINAGE THROUGHOUT ALL PHASES OF CONSTRUCTION.
- 2. A TEMPORARY DRAINAGE SWALE SHALL BE CONSTRUCTED ALONG THE SOUTH SIDE OF HOLDEN AVENUE FROM APPROXIMATE STA. 50+30 TO APPROXIMATE STA. 60+50 OUTSIDE OF THE PROPOSED TEMPORARY PAVEMENT LIMITS TO COMPENSATE FOR THE EXISTING DRAINAGE SWALE IMPACTED BY THE TEMPORARY PAVEMENT TO BE CONSTRUCTED IN THIS PHASE. INDEX NO. 602 OF THE FDOT DESIGN STANDARDS SHALL BE UTILIZED DURING CONSTRUCTION OF THE TEMPORARY DRAINAGE SWALE.
- 3. THE EXISTING MITERED END SECTION AT APPROXIMATE STA. 50+30, THE EXISTING CROSS DRAIN AT APPROXIMATE STA. 53+00, AND THE EXISTING CURB INLET AND CROSS DRAIN AT APPROXIMATE STA. 75+15 LOCATED ALONG THE SOUTH SIDE OF HOLDEN AVENUE SHALL BE EXTENDED TO ALLOW FOR PLACEMENT OF TEMPORARY PAVEMENT. TO EXTEND THE EXISTING CROSS DRAINS AND DRAINAGE STRUCTURES, THE CONTRACTOR SHALL CUT OUT AND REMOVE THE DRAINAGE STRUCTURE AND EXTEND THE CROSS DRAIN PIPE BEFORE PLACING TEMPORARY PAVEMENT. INDEX NO. 602 OF THE FDOT DESIGN STANDARDS SHALL BE UTILIZED DURING EXTENSIONS OF EXISTING DRAINAGE STRUCTURES AND CROSS DRAINS.
- 4. THE EXISTING MITERED END SECTION AT APPROXIMATE STA. 60+50 AND THE EXISTING CURB INLET AT APPROXIMATE STA. 63+70 LOCATED ALONG THE SOUTH SIDE OF HOLDEN AVENUE SHALL BE EXTENDED TO ALLOW FOR PLACEMENT OF TEMPORARY PAVEMENT. TO EXTEND THE EXISTING DRAINAGE STRUCTURES, THE CONTRACTOR SHALL CUT OUT AND REMOVE THE DRAINAGE STRUCTURE AND EXTEND THE CROSS DRAIN PIPE BEFORE PLACING TEMPORARY PAVEMENT. ALL OF THE DRAINAGE STRUCTURES EXTENDED SHALL REMAIN CONNECTED TO THE EXISTING TRUNK LINE THAT RUNS FROM APPROXIMATE STA. 60+50 TO APPROXIMATE STA. 63+70. INDEX NO. 602 OF THE FDOT DESIGN STANDARDS SHALL BE UTILIZED DURING EXTENSIONS OF EXISTING DRAINAGE STRUCTURES AND CROSS DRAINS.
- 5. THE EXISTING CATCH BASIN INLET AT APPROXIMATE STA. 72+05, THE EXISTING CURB INLET AT APPROXIMATE STA. 72+50, AND THE EXISTING CATCH BASIN INLET AT APPROXIMATE STA. 73+20 LOCATED ALONG THE SOUTH SIDE OF HOLDEN AVENUE SHALL BE EXTENDED TO ALLOW FOR PLACEMENT OF TEMPORARY PAVEMENT. TO EXTEND THE EXISTING DRAINAGE STRUCTURES, THE CONTRACTOR SHALL CUT OUT AND REMOVE THE DRAINAGE STRUCTURE AND EXTEND THE CROSS DRAIN PIPE BEFORE PLACING TEMPORARY PAVEMENT. ALL OF THE DRAINAGE STRUCTURES EXTENDED SHALL REMAIN CONNECTED TO THE EXISTING TRUNK LINE THAT RUNS FROM APPROXIMATE STA. 72+05 TO APPROXIMATE STA 73+85. INDEX NO. 602 OF THE FDOT DESIGN STANDARDS SHALL BE UTILIZED DURING EXTENSIONS OF EXISTING DRAINAGE STRUCTURES AND CROSS DRAINS.
- 6. THE EXISTING BOX CULVERT AND CONCRETE HEADWALL AT APPROXIMATE STA. 46+80 LOCATED ALONG THE SOUTH SIDE OF HOLDEN AVENUE SHALL BE EXTENDED TO ALLOW FOR PLACEMENT OF TEMPORARY PAVEMENT. TO EXTEND THE EXISTING BOX CULVERT AND CONCRETE HEADWALL, THE CONTRACTOR SHALL CUT OUT AND REMOVE THE CONCRETE HEADWALL ON THE SOUTH SIDE OF HOLDEN AVENUE AND EXTEND THE BOX CULVERT BEFORE PLACING TEMPORARY PAVEMENT. INDEX NO. 602 OF THE FDOT DESIGN STANDARDS SHALL BE UTILIZED DURING EXTENSIONS OF EXISTING BOX CULVERTS AND CONCRETE HEADWALLS.
- 7. TEMPORARY PAVEMENT SHALL BE CONSTRUCTED ALONG THE WEST SIDE OF TEXAS AVENUE FROM STA. 392+08.58 TO STA. 400+16.20. TO CONSTRUCT TEMPORARY PAVEMENT ALONG TEXAS AVENUE, TRAFFIC SHALL BE SHIFTED INTO TWO ELEVEN FOOT LANES ALONG THE EAST SIDE OF TEXAS AVENUE. INDEX NO. 602 SHALL THEN BE UTILIZED DURING CONSTRUCTION OF TEMPORARY PAVEMENT ALONG TEXAS AVENUE.
- TEMPORARY PAVEMENT SHALL BE CONSTRUCTED ALONG THE SOUTH SIDE OF HOLDEN AVENUE FROM STA. 44+25.53 TO STA. 63+02.24, FROM STA. 63+45.18 TO STA. 65+26.52, AND FROM STA. 70+66.21 TO STA. 76+05.93. TO CONSTRUCT TEMPORARY PAVEMENT ALONG HOLDEN AVENUE, TRAFFIC SHALL BE SHIFTED INTO TWO ELEVEN (II) FOOT LANES ALONG THE NORTH SIDE OF HOLDEN AVENUE. INDEX NO. 602 SHALL THEN BE UTILIZED DURING CONSTRUCTION OF TEMPORARY PAVEMENT ALONG HOLDEN AVENUE.
- TEMPORARY SIGNALIZATION STRUCTURES AND EQUIPMENT SHALL BE ERECTED AT THE INTERSECTION OF HOLDEN AVENUE AND RIO GRANDE AVENUE. TWO WOOD POLES SHALL BE INSTALLED AT THE INTERSECTION, ONE IN THE NORTHEAST CORNER, AND ONE IN THE SOUTHWEST CORNER. A DIAGONAL SPAN WIRE ASSEMBLY SHALL BE UTILIZED FOR ALL APPROACHES TO THE INTERSECTION.
- IO. TEMPORARY SIGNALIZATION STRUCTURES AND EQUIPMENT SHALL BE ERECTED AT THE INTERSECTION OF HOLDEN AVENUE AND ORANGE BLOSSOM TRAIL. TWO WOOD POLES SHALL BE INSTALLED AT THE INTERSECTION, ONE IN THE NORTHEAST CORNER, AND ONE IN THE SOUTHWEST CORNER. A DIAGONAL SPAN WIRE ASSEMBLY SHALL BE UTILIZED FOR ALL APPROACHES TO THE INTERSECTION.

PHASE IB:

- THE PURPOSE OF THIS PHASE IS TO CONSTRUCT PORTIONS OF HOLDEN AVENUE. TEXAS AVENUE. RIO GRANDE AVENUE. MILLENIA BOULEVARD, AND THE NORTHBOUND RIGHT TURN LANE OF JOHN YOUNG PARKWAY. ALSO, PORTIONS OF THE PROPOSED CLOSED DRAINAGE SYSTEM WILL BE CONSTRUCTED.
- CONSTRUCTION OF THE ENTIRE WIDTH OF THE NEW SECTION OF HOLDEN AVENUE FROM JOHN YOUNG PARKWAY TO TEXAS AVENUE, INCLUDING ALL DRAINAGE FEATURES, FROM STA. 10+82.14 TO STA. 36+32.98 SHALL BEGIN IN PHASE IB.
- TRAFFIC SHALL BE SHIFTED TO THE EXISTING SOUTH SIDE OF HOLDEN AVENUE ONTO THE TEMPORARY PAVEMENT CONSTRUCTED IN PHASE IA. TRAFFIC SHALL BE MAINTAINED IN ONE ELEVEN FOOT WIDE LANE IN EACH DIRECTION AND THE USE OF BARRIER WALL WILL BE REQUIRED AS SHOWN IN THE PHASE IB TRAFFIC CONTROL PLANS. THE WESTBOUND LANES OF HOLDEN AVENUE SHALL BE CONSTRUCTED FROM STA. 36+84.79 TO STA. 76+06.59 INCLUDING THE DRAINAGE INLETS AND TRUNK LINE ON THE NORTH SIDE OF HOLDEN AVENUE. ALSO, CROSS DRAINS SHALL BE CONSTRUCTED ON THE NORTH SIDE OF HOLDEN AVENUE BETWEEN THE DRAINAGE INLETS AND THE LIMITS OF THE PHASE IB WORK ZONE. THE CONTRACTOR SHALL INSTALL PIPE PLUGS IN THE CROSS DRAINS AT THE LIMITS OF THE WORK ZONE. CONSTRUCTION OF THE WESTBOUND LANES OF HOLDEN AVENUE AND THE DRAINAGE TRUNK LINE WITHIN DRIVEWAY AND STREET OPENINGS SHALL BE COMPLETED DURING NIGHTTIME HOURS BY CLOSING THE DRIVEWAY OR STREET OPENING WHERE CONSTRUCTION ACTIVITIES ARE TO OCCUR. THE CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION ONE WEEK IN ADVANCE OF CONSTRUCTION OPERATIONS TO RESIDENTS/BUSINESSES WHOSE DRIVEWAYS ARE TO BE CLOSED. NO MEDIANS OR TRAFFIC SEPARATORS SHALL BE CONSTRUCTED IN PHASE IB ALONG HOLDEN AVENUE.
- THE EXISTING OUTSIDE LANE OF JOHN YOUNG PARKWAY NORTHBOUND SHALL BE CLOSED AND TRAFFIC SHALL BE SHIFTED TO THE CENTER AND MEDIAN LANES. CONSTRUCTION OF THE NORTHBOUND RIGHT TURN LANE ALONG JOHN YOUNG PARKWAY FROM STA. 202+15.62 TO STA. 206+58.51 SHALL BEGIN IN PHASE IB.
- 5. A PORTION OF TEXAS AVENUE SHALL BE CONSTRUCTED FROM STA. 392+50.00 TO STA. 408+50.00. TRAFFIC SHALL BE SHIFTED TO THE EXISTING EAST SIDE OF TEXAS AVENUE (NORTH) IN ONE ELEVEN FOOT WIDE LANE IN THE SOUTHBOUND DIRECTION ONLY BETWEEN HOLDEN AVENUE AND THE LIMITS OF CONSTRUCTION. NORTHBOUND TRAFFIC ALONG TEXAS AVENUE (NORTH) SHALL BE DETOURED AS SHOWN IN THE PHASE IB DETOUR PLAN. THE USE OF BARRIER WALL WILL BE REQUIRED AS SHOWN IN THE PHASE IB TRAFFIC CONTROL PLANS. THE DRAINAGE TRUNK LINE ALONG THE EAST SIDE OF TEXAS AVENUE (NORTH) SHALL BE CONSTRUCTED FROM STA. 402+00.00 TO STA. 404+30.00 ALONG WITH THE DRAINAGE INLETS ON THE EAST SIDE OF TEXAS AVENUE (NORTH). ALL OF THE DRAINAGE INLETS ON THE WEST SIDE OF TEXAS AVENUE (NORTH) AND THE CROSS DRAINS SHALL BE CONSTRUCTED FROM STA. 402+00.00 TO STA. 408+50.00. THE CONTRACTOR SHALL INSTALL PIPE PLUGS IN THE CROSS DRAINS AT THE LIMITS OF THE WORK ZONE. CONSTRUCTION OF PORTIONS OF TEXAS AVENUE (NORTH) AND THE DRAINAGE TRUNK LINE WITHIN DRIVEWAY AND STREET OPENINGS SHALL BE COMPLETED DURING NIGHTTIME HOURS BY CLOSING THE DRIVEWAY OR STREET OPENING WHERE CONSTRUCTION ACTIVITIES ARE TO OCCUR. THE CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION ONE WEEK IN ADVANCE OF CONSTRUCTION OPERATIONS TO RESIDENTS/BUSINESSES WHOSE DRIVEWAYS ARE TO BE CLOSED. NO MEDIANS OR TRAFFIC SEPARATORS SHALL BE CONSTRUCTED IN PHASE IB ALONG TEXAS AVENUE (NORTH).
- TRAFFIC SHALL BE SHIFTED TO THE WEST SIDE OF TEXAS AVENUE (SOUTH) ONTO THE TEMPORARY PAVEMENT CONSTRUCTED IN PHASE IA. TRAFFIC SHALL BE MAINTAINED IN ONE ELEVEN FOOT WIDE LANE IN EACH DIRECTION AND THE USE OF BARRIER WALL WILL BE REQUIRED AS SHOWN IN THE PHASE IB TRAFFIC CONTROL PLANS. THE NORTHBOUND LANES OF TEXAS AVENUE (SOUTH) SHALL BE CONSTRUCTED ALONG WITH THE DRAINAGE TRUNK LINE, DRAINAGE INLETS, AND CROSS DRAINS ON THE EAST SIDE OF TEXAS AVENUE (SOUTH). THE CONTRACTOR SHALL INSTALL PIPE PLUGS IN THE CROSS DRAINS AT THE LIMITS OF THE WORK ZONE. CONSTRUCTION OF PORTIONS OF TEXAS AVENUE (SOUTH) AND THE DRAINAGE TRUNK LINE WITHIN DRIVEWAY AND STREET OPENINGS SHALL BE COMPLETED DURING NIGHTTIME HOURS BY CLOSING THE DRIVEWAY OR STREET OPENING WHERE CONSTRUCTION ACTIVITIES ARE TO OCCUR. THE CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION ONE WEEK IN ADVANCE OF CONSTRUCTION OPERATIONS TO RESIDENTS/BUSINESSES WHOSE DRIVEWAYS ARE TO BE CLOSED. NO MEDIANS OR TRAFFIC SEPARATORS SHALL BE CONSTRUCTED IN PHASE IB ALONG TEXAS AVENUE (SOUTH).
- 7. A PORTION OF THE EAST SIDE OF RIO GRANDE AVENUE (NORTH) SHALL BE CONSTRUCTED FROM STA. 410+04.22 TO STA. 414+40.00 AND A PORTION OF THE EAST SIDE OF RIO GRANDE AVENUE (SOUTH) SHALL BE CONSTRUCTED FROM STA. 401+00.00 TO STA. 408+09.19. TRAFFIC SHALL BE SHIFTED TO THE EXISTING WEST SIDE OF RIO GRANDE AVENUE IN ONE ELEVEN FOOT WIDE LANE IN THE NORTHBOUND DIRECTION ONLY BETWEEN THE LIMITS OF CONSTRUCTION. SOUTHBOUND TRAFFIC ALONG RIO GRANDE AVENUE SHALL BE DETOURED AS SHOWN IN THE PHASE IB DETOUR PLAN. THE USE OF BARRIER WALL WILL BE REQUIRED AS SHOWN IN THE PHASE IB TRAFFIC CONTROL PLANS. THE NORTHBOUND LANES OF RIO GRANDE AVENUE SHALL BE CONSTRUCTED ALONG WITH THE DRAINAGE TRUNK LINE, DRAINAGE INLETS, AND CROSS DRAINS ON THE EAST SIDE OF RIO GRANDE AVENUE. THE CONTRACTOR SHALL INSTALL PIPE PLUGS IN THE CROSS DRAINS AT THE LIMITS OF THE WORK ZONE. CONSTRUCTION OF PORTIONS OF RIO GRANDE AVENUE (SOUTH) AND THE DRAINAGE TRUNK LINE WITHIN DRIVEWAY AND STREET OPENINGS SHALL BE COMPLETED DURING NIGHTTIME HOURS BY CLOSING THE DRIVEWAY OR STREET OPENING WHERE CONSTRUCTION ACTIVITIES ARE TO OCCUR. THE CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION ONE WEEK IN ADVANCE OF CONSTRUCTION OPERATIONS TO RESIDENTS/BUSINESSES WHOSE DRIVEWAYS ARE TO BE CLOSED.
- THE LEFT EASTBOUND LANE OF MILLENIA BLVD. WILL BE UNDER CONSTRUCTION FROM STA. 4+96.12 TO 9+56.64.

	REVIS	VHB		
TE	DESCRIPTION	DATE	DESCRIPTION	225 E. Robinson Street, Suite 300
				Landmark Center Two Orlando, FL 32801 (407) 839-4006 Certificate of Authorization #3932 Dante A. Gabriel, PE PE # 37271



TRAFFIC CONTROL PLAN PHASING NOTES

SHFFT NO.

M-3

PHASING NOTES

- THE PURPOSE OF THIS PHASE IS TO CONSTRUCT TEMPORARY PAVEMENT ON HOLDEN AVENUE. TEXAS AVENUE. AND RIO GRANDE AVENUE TO PREPARE FOR TRAFFIC SHIFTS THAT WILL BE UTILIZED TO COMPLETE SUBSEQUENT CONSTRUCTION
- TEMPORARY PAVEMENT SHALL BE CONSTRUCTED WITHIN THE INTERSECTION OF HOLDEN AVENUE AT TEXAS AVENUE AND HOLDEN AVENUE AT RIO GRANDE AVENUE TO PROVIDE A TRANSITION BETWEEN THE EXISTING PAVEMENT AT THE INTERSECTIONS AND THE NEWLY CONSTRUCTED PAVEMENT FROM PHASE IB. CONSTRUCTION OF TEMPORARY PAVEMENT SHALL OCCUR DURING NIGHTTIME HOURS UTILIZING A FLAGGING OPERATION AS SPECIFIED IN INDEX NO. 620 OF THE FDOT DESIGN STANDARDS.
- TEMPORARY PAVEMENT SHALL BE CONSTRUCTED IN THE MEDIAN AREA OF HOLDEN AVENUE FROM STA. 72+04.37 TO STA. 76+00.61 TO PROVIDE A TRANSITION BETWEEN THE EXISTING PAVEMENT ALONG HOLDEN AVENUE AND THE NEWLY CONSTRUCTED PAVEMENT FROM PHASE IB. CONSTRUCTION OF TEMPORARY PAVEMENT SHALL OCCUR DURING NIGHTTIME HOURS UTILIZING INDEX NO. 625, SHEET 1 OF 2, OF THE FDOT DESIGN STANDARDS.
- 4. TEMPORARY PAVEMENT SHALL BE CONSTRUCTED IN THE MEDIAN AREA OF TEXAS AVENUE (SOUTH) FROM STA. 392+50.00 TO STA. 393+66.39 TO PROVIDE A TRANSITION BETWEEN THE EXISTING PAVEMENT ALONG TEXAS AVENUE (SOUTH) AND THE NEWLY CONSTRUCTED PAVEMENT FROM PHASE IB. CONSTRUCTION OF TEMPORARY PAVEMENT SHALL OCCUR DURING NIGHTTIME HOURS UTILIZING INDEX NO. 621 OF THE FDOT DESIGN STANDARDS.
- TEMPORARY PAVEMENT SHALL BE CONSTRUCTED ALONG THE EAST SIDE OF TEXAS AVENUE (NORTH) FROM STA. 406+10.72 TO STA. 408+50.00 TO PROVIDE A TRANSITION BETWEEN THE EXISTING PAVEMENT ALONG TEXAS AVENUE (NORTH) AND THE NEWLY CONSTRUCTED PAVEMENT FROM PHASE IB. CONSTRUCTION OF TEMPORARY PAVEMENT SHALL OCCUR DURING NIGHTTIME HOURS UTILIZING INDEX NO. 621 OF THE FDOT DESIGN STANDARDS.
- TEMPORARY PAVEMENT SHALL BE CONSTRUCTED IN THE MEDIAN AREA OF RIO GRANDE AVENUE (SOUTH) FROM STA. 406+39.62 TO STA. 408+09.19 AND IN THE MEDIAN AREA OF RIO GRANDE AVENUE (NORTH) FROM STA. 410+04.22 TO STA. 412+74.57 TO PROVIDE A TRANSITION BETWEEN THE EXISTING PAVEMENT ALONG RIO GRANDE AVENUE AND THE NEWLY CONSTRUCTED PAVEMENT FROM PHASE IB. CONSTRUCTION OF TEMPORARY PAVEMENT SHALL OCCUR DURING NIGHTTIME HOURS UTILIZING INDEX NO. 621 OF THE FDOT DESIGN STANDARDS.
- 7. PRIOR TO PHASE IIB, A SHORT TERM NIGHT TIME FLAGGING OPERATION WILL BE REQUIRED FOR TRAFFIC ON HOLDEN AVE. FOR CONSTRUCTION OF A TRUNK LINE FROM STA. 400+23 TO 400+50 ACROSS HOLDEN AVE.

PHASE IIB:

PHASE IIA:

- THE PURPOSE OF THIS PHASE IS TO CONTINUE CONSTRUCTION OF HOLDEN AVENUE, TEXAS AVENUE, RIO GRANDE AVENUE, THE NORTHBOUND RIGHT TURN LANE OF JOHN YOUNG PARKWAY, MILLENIA BLVD., AND THE PROPOSED CLOSED DRAINAGE SYSTEM.
- CONTINUE CONSTRUCTION STARTED IN PHASE IB OF THE ENTIRE WIDTH OF THE NEW SECTION OF HOLDEN AVENUE FROM JOHN YOUNG PARKWAY TO TEXAS AVENUE, INCLUDING ALL DRAINAGE FEATURES, FROM STA. 10+82.14 TO STA. 36+32.98.
- 3. TRAFFIC SHALL BE SHIFTED ONTO THE NEWLY CONSTRUCTED WESTBOUND LANES OF HOLDEN AVENUE FROM PHASE IB. TRAFFIC SHALL BE MAINTAINED IN ONE ELEVEN FOOT WIDE LANE IN EACH DIRECTION AND THE USE OF BARRIER WALL WILL BE REQUIRED AS SHOWN IN THE PHASE IIB TRAFFIC CONTROL PLANS. THE EASTBOUND LANES OF HOLDEN AVENUE SHALL BE CONSTRUCTED FROM STA. 35+80.00 TO STA. 76+06.59 INCLUDING THE DRAINAGE INLETS ON THE SOUTH SIDE OF HOLDEN AVENUE. ALSO, CROSS DRAINS SHALL BE CONSTRUCTED ON THE SOUTH SIDE OF HOLDEN AVENUE BETWEEN THE DRAINAGE INLETS AND THE LIMITS OF THE PHASE IIB WORK ZONE. THE CONTRACTOR SHALL INSTALL PIPE PLUGS IN THE CROSS DRAINS AT THE LIMITS OF THE WORK ZONE IN THE EVENT CONNECTIONS TO THE CROSS DRAINS CONSTRUCTED IN PHASE IB ARE NOT POSSIBLE DUE TO MEDIAN WORK TO BE COMPLETED IN SUBSEQUENT PHASES. CONSTRUCTION OF THE EASTBOUND LANES OF HOLDEN AVENUE WITHIN DRIVEWAY AND STREET OPENINGS SHALL BE COMPLETED DURING NIGHTTIME HOURS BY CLOSING THE DRIVEWAY OR STREET OPENING WHERE CONSTRUCTION ACTIVITIES ARE TO OCCUR. THE CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION ONE WEEK IN ADVANCE OF CONSTRUCTION OPERATIONS TO RESIDENTS/BUSINESSES WHOSE DRIVEWAYS ARE TO BE CLOSED. NO MEDIANS OR TRAFFIC SEPARATORS SHALL BE CONSTRUCTED IN PHASE IIB ALONG HOLDEN AVENUE.
- 4. THE EXISTING OUTSIDE LANE OF JOHN YOUNG PARKWAY NORTHBOUND SHALL BE CLOSED AND TRAFFIC SHALL BE SHIFTED TO THE CENTER AND MEDIAN LANES. CONSTRUCTION OF THE NORTHBOUND RIGHT TURN LANE ALONG JOHN YOUNG PARKWAY FROM STA. 202+15.62 TO STA. 206+58.51 SHALL CONTINUE IN PHASE IIB.
- PORTIONS OF TEXAS AVENUE SHALL CONTINUE TO BE CONSTRUCTED FROM STA. 392+50.00 TO STA. 408+50.00. TRAFFIC SHALL BE SHIFTED TO THE NEWLY CONSTRUCTED WEST SIDE OF TEXAS AVENUE (NORTH) FROM PHASE IB. TRAFFIC SHALL BE MAINTAINED IN ONE ELEVEN FOOT WIDE LANE IN EACH DIRECTION AND THE USE OF BARRIER WALL WILL BE REQUIRED AS SHOWN IN THE PHASE IIB TRAFFIC CONTROL PLANS. THE REMAINING DRAINAGE TRUNK LINE ALONG THE EAST SIDE OF TEXAS AVENUE (NORTH) SHALL BE CONSTRUCTED ALONG WITH THE REMAINING DRAINAGE INLETS AND CROSS DRAINS ALONG THE EAST SIDE OF TEXAS AVENUE (NORTH). THE CONTRACTOR SHALL INSTALL PIPE PLUGS IN THE CROSS DRAINS AT THE LIMITS OF THE WORK ZONE IN THE EVENT CONNECTIONS TO THE CROSS DRAINS CONSTRUCTED IN PHASE IB ARE NOT POSSIBLE DUE TO MEDIAN WORK TO BE COMPLETED IN SUBSEQUENT PHASES. CONSTRUCTION OF PORTIONS OF TEXAS AVENUE (NORTH) WITHIN DRIVEWAY AND STREET OPENINGS SHALL BE COMPLETED DURING NIGHTTIME HOURS BY CLOSING THE DRIVEWAY OR STREET OPENING WHERE CONSTRUCTION ACTIVITIES ARE TO OCCUR. THE CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION ONE WEEK IN ADVANCE OF CONSTRUCTION OPERATIONS TO RESIDENTS/BUSINESSES WHOSE DRIVEWAYS ARE TO BE CLOSED. NO MEDIANS OR TRAFFIC SEPARATORS SHALL BE CONSTRUCTED IN PHASE IIB ALONG TEXAS AVENUE (NORTH).

- TRAFFIC SHALL BE SHIFTED TO THE EAST SIDE OF TEXAS AVENUE (SOUTH) ONTO THE NEWLY CONSTRUCTED NORTHBOUND LANES FROM PHASE IB. TRAFFIC SHALL BE MAINTAINED IN ONE ELEVEN FOOT WIDE LANE IN EACH DIRECTION AND THE USE OF BARRIER WALL WILL BE REQUIRED AS SHOWN IN THE PHASE IIB TRAFFIC CONTROL PLANS. THE SOUTHBOUND LANES OF TEXAS AVENUE (SOUTH) SHALL BE CONSTRUCTED ALONG WITH THE REMAINING DRAINAGE INLETS AND CROSS DRAINS ON THE WEST SIDE OF TEXAS AVENUE (SOUTH). THE CONTRACTOR SHALL INSTALL PIPE PLUGS IN THE CROSS DRAINS AT THE LIMITS OF THE WORK ZONE IN THE EVENT CONNECTIONS TO THE CROSS DRAINS CONSTRUCTED IN PHASE IB ARE NOT POSSIBLE DUE TO MEDIAN WORK TO BE COMPLETED IN SUBSEQUENT PHASES. NO MEDIANS OR TRAFFIC SEPARATORS SHALL BE CONSTRUCTED IN PHASE IIB ALONG TEXAS AVENUE (SOUTH).
- 7. A PORTION OF THE WEST SIDE OF RIO GRANDE AVENUE (NORTH) SHALL BE CONSTRUCTED FROM STA. 410+04.22 TO STA. 414+40.00 AND A PORTION OF THE WEST SIDE OF RIO GRANDE AVENUE (SOUTH) SHALL BE CONSTRUCTED FROM STA. 401+00.00 TO STA. 408+09.19. TRAFFIC SHALL BE SHIFTED ONTO THE NEWLY CONSTRUCTED EAST SIDE OF RIO GRANDE AVENUE FROM PHASE IB IN ONE ELEVEN FOOT WIDE LANE IN THE SOUTHBOUND DIRECTION ONLY BETWEEN THE LIMITS OF CONSTRUCTION. NORTHBOUND TRAFFIC ALONG RIO GRANDE AVENUE SHALL BE DETOURED AS SHOWN IN THE PHASE IIB DETOUR PLAN. THE USE OF BARRIER WALL WILL BE REQUIRED AS SHOWN IN THE PHASE IIB TRAFFIC CONTROL PLANS. THE SOUTHBOUND LANES OF RIO GRANDE AVENUE SHALL BE CONSTRUCTED ALONG WITH THE REMAINING DRAINAGE INLETS AND CROSS DRAINS ON THE WEST SIDE OF RIO GRANDE AVENUE. THE CONTRACTOR SHALL INSTALL PIPE PLUGS IN THE CROSS DRAINS AT THE LIMITS OF THE WORK ZONE IN THE EVENT CONNECTIONS TO THE CROSS DRAINS CONSTRUCTED IN PHASE IB ARE NOT POSSIBLE DUE TO MEDIAN WORK TO BE COMPLETED IN SUBSEQUENT PHASES. CONSTRUCTION OF PORTIONS OF RIO GRANDE AVENUE (SOUTH) WITHIN DRIVEWAY AND STREET OPENINGS SHALL BE COMPLETED DURING NIGHTTIME HOURS BY CLOSING THE DRIVEWAY OR STREET OPENING WHERE CONSTRUCTION ACTIVITIES ARE TO OCCUR. THE CONTRACTOR SHALL PROVIDE WRITTEN NOTIFICATION ONE WEEK IN ADVANCE OF CONSTRUCTION OPERATIONS TO RESIDENTS/BUSINESSES WHOSE DRIVEWAYS ARE TO BE CLOSED.
- 8. THE EASTBOUND CENTER LANE OF MILLENIA BLVD. WILL BE UNDER CONSTRUCTION FROM STA. 4+96.12 TO STA. 9+56.64.

PHASE IIIA:

- THE PURPOSE OF THIS PHASE IS TO CONSTRUCT TEMPORARY PAVEMENT ON RIO GRANDE AVENUE TO PREPARE FOR A TRAFFIC SHIFT THAT WILL BE UTILIZED TO COMPLETE SUBSEQUENT CONSTRUCTION ACTIVITIES.
- TEMPORARY PAVEMENT SHALL BE CONSTRUCTED IN THE MEDIAN AREA OF RIO GRANDE AVENUE (SOUTH) FROM STA. 401+00.00 TO STA. 404+22.23 TO PROVIDE A TRANSITION BETWEEN THE EXISTING PAVEMENT ALONG RIO GRANDE AVENUE (SOUTH) AND THE NEWLY CONSTRUCTED PAVEMENT FROM PHASES IB AND IIB. CONSTRUCTION OF TEMPORARY PAVEMENT SHALL OCCUR DURING NIGHTTIME HOURS UTILIZING INDEX NO. 621 OF THE FDOT DESIGN STANDARDS.

PHASE IIIB:

- THE PURPOSE OF THIS PHASE IS TO COMPLETE CONSTRUCTION OF THE NEW SECTION OF HOLDEN AVENUE AND THE NORTHBOUND RIGHT TURN LANE OF JOHN YOUNG PARKWAY, AND CONTINUE CONSTRUCTION OF THE EXISTING SECTION OF HOLDEN AVENUE, TEXAS AVENUE, RIO GRANDE AVENUE, MILLENIA BLVD., AND THE PROPOSED CLOSED DRAINAGE SYSTEM.
- COMPLETE CONSTRUCTION STARTED IN PHASE IB OF THE ENTIRE WIDTH OF THE NEW SECTION OF HOLDEN AVENUE FROM JOHN YOUNG PARKWAY TO TEXAS AVENUE, INCLUDING ALL DRAINAGE FEATURES, FROM STA. 10+82.14 TO STA. 36+32.98.
- 3. TRAFFIC SHALL BE MAINTAINED ON THE NEWLY CONSTRUCTED EASTBOUND AND WESTBOUND LANES OF HOLDEN AVENUE FROM PHASES IB AND IIB. TRAFFIC SHALL BE SHIFTED TO THE OUTSIDE IN TWO ELEVEN FOOT WIDE LANES IN EACH DIRECTION. THE FULL WIDTH MEDIANS AND TRAFFIC SEPARATORS ALONG HOLDEN AVENUE SHALL BE CONSTRUCTED FROM STA. 37+43.62 TO STA. 62+40.27, AND A MEDIAN PORTION OF HOLDEN AVENUE SHALL BE CONSTRUCTED FROM STA. 71+81.13 TO STA. 76+06.59, LESS THE MEDIAN AND TRAFFIC SEPARATOR. THE REMAINING CROSS DRAINS WITHIN THE MEDIANS OF HOLDEN AVENUE SHALL BE CONSTRUCTED.
- THE EXISTING OUTSIDE LANE OF JOHN YOUNG PARKWAY NORTHBOUND SHALL BE CLOSED AND TRAFFIC SHALL BE SHIFTED TO THE CENTER AND MEDIAN LANES. CONSTRUCTION OF THE NORTHBOUND RIGHT TURN LANE ALONG JOHN YOUNG PARKWAY FROM STA. 202+15.62 TO STA. 206+58.51 SHALL BE COMPLETED.
- CONSTRUCTION OF BOTH SHOULDERS AND CURB AND GUTTER WILL BE COMPLETED ON TEXAS AVE. FROM STA. 400+60.24 TO STA. 408+50.00. NORTHBOUND AND SOUTHBOUND TRAFFIC SHALL BE SHIFTED TO IO' LANES EACH.
- 6. THE REMAINDER OF TEXAS AVENUE (SOUTH) FROM STA. 392+50.00 TO STA. 399+81.67, INCLUDING FULL WIDTH MEDIANS AND TRAFFIC SEPARATORS, SHALL BE COMPLETED. THE MEDIAN LANE IN BOTH THE NORTHBOUND AND SOUTHBOUND DIRECTIONS SHALL BE CLOSED AND TRAFFIC SHALL BE SHIFTED TO THE OUTSIDE IN ONE ELEVEN FOOT WIDE LANE IN EACH
- 7. THE RIGHT EASTBOUND LANE OF MILLENIA BLVD. WILL BE UNDER CONSTRUCTION FROM STA. 4+96.12 TO STA. 9+56.64.

REVISIONS DATE DESCRIPTION DATE DESCRIPTION 225 E. Robinson Street, Suite 300 Landmark Center Two Orlando, FL 32801 (407) 839-4006 Certificate of Authorization #3932 Dante A. Gabriel, PE PE # 37271



TRAFFIC CONTROL PLAN PHASING NOTES

SHEET NO.

PHASING NOTES

PHASE IVA:

- THE PURPOSE OF THIS PHASE IS TO COMPLETE CONSTRUCTION OF HOLDEN AVENUE AND TEXAS AVENUE. AND TO CONTINUE CONSTRUCTION ON RIO GRANDE AVENUE.
- 2. TRAFFIC SHALL BE MAINTAINED ON THE NEWLY CONSTRUCTED EASTBOUND AND WESTBOUND LANES OF HOLDEN AVENUE FROM PHASES IB. IIB. AND IIIB. TRAFFIC SHALL BE SHIFTED TO THE OUTSIDE IN TWO ELEVEN FOOT WIDE LANES IN EACH DIRECTION AND THE FULL WIDTH MEDIAN AND TRAFFIC SEPARATOR ALONG HOLDEN AVENUE SHALL BE CONSTRUCTED FROM STA. 64+II.89 TO STA. 76+06.59.
- 3. TRAFFIC SHALL BE MAINTAINED ON THE NEWLY CONSTRUCTED NORTHBOUND AND SOUTHBOUND LANES OF TEXAS AVENUE (NORTH) FROM PHASES IB, IIB, AND IIIB. TRAFFIC SHALL BE SHIFTED TO THE OUTSIDE IN ONE TEN FOOT WIDE LANE IN EACH DIRECTION AND THE FULL WIDTH MEDIAN ALONG TEXAS AVENUE (NORTH) SHALL BE CONSTRUCTED FROM STA. 401+33.53 TO STA. 406+29.54.
- RIO GRANDE AVENUE (NORTH) SHALL BE CLOSED FROM STA. 410+04.22 TO STA. 414+40.00. NORTHBOUND AND SOUTHBOUND TRAFFIC SHALL BE DETOURED AS SHOWN IN THE PHASE IVA DETOUR PLAN. THE REMAINDER OF RIO GRANDE AVENUE (NORTH) SHALL BE CONSTRUCTED.
- TRAFFIC ALONG RIO GRANDE AVENUE (SOUTH) SHALL BE SHIFTED TO THE WEST SIDE IN ONE ELEVEN FOOT WIDE LANE IN THE SOUTHBOUND DIRECTION ONLY. NORTHBOUND TRAFFIC ALONG RIO GRANDE AVENUE (SOUTH) SHALL BE DETOURED AS SHOWN IN THE PHASE IVA DETOUR PLAN. PORTIONS OF THE MEDIAN AREA ALONG RIO GRANDE AVENUE (SOUTH) SHALL BE CONSTRUCTED FROM STA. 401+00.00 TO STA. 408+09.19.

PHASE IVB:

- I. THE PURPOSE OF THIS PHASE IS TO COMPLETE CONSTRUCTION OF RIO GRANDE AVENUE AND THE BEGIN AND END PROJECT TIE-IN POINTS.
- TRAFFIC ALONG RIO GRANDE AVENUE (SOUTH) FROM STA. 401+00.00 TO STA. 403+60.00 SHALL BE SHIFTED TO THE EAST SIDE IN ONE ELEVEN FOOT WIDE LANE IN THE SOUTHBOUND DIRECTION ONLY. NORTHBOUND TRAFFIC ALONG RIO GRANDE AVENUE (SOUTH) SHALL BE DETOURED AS SHOWN IN THE PHASE IVB DETOUR PLAN. THE REMAINDER OF THE MEDIAN AREA ALONG RIO GRANDE AVENUE (SOUTH) SHALL BE CONSTRUCTED FROM STA. 401+00.00 TO STA. 403+60.00.
- 3. CONSTRUCTION OF THE BEGIN AND END OF PROJECT TIE-IN POINTS SHALL BE COMPLETED AT THE END OF PHASE IVB. INDEX NO 5/32 S. 620 AND 622 OF THE FDOT DESIGN STANDARDS SHALL BE UTILIZED TO COMPLETE CONSTRUCTION AT THE BEGINNING AND END OF THE PROJECT LIMITS.

PHASE V:

- THE PURPOSE OF THIS PHASE IS TO CONSTRUCT THE FINAL FRICTION COURSE ALONG ALL ROADWAY SURFACES THAT ARE TO RECEIVE NEW PAVEMENT MARKINGS.
- 2. THE FINAL FRICTION COURSE ALONG HOLDEN AVENUE SHALL BE CONSTRUCTED BY FIRST CLOSING THE OUTSIDE LANE IN BOTH DIRECTIONS, THEN CLOSING THE MEDIAN LANE IN BOTH DIRECTIONS. LANE CLOSURES FOR PLACEMENT OF THE FINAL FRICTION COURSE SHALL BE PER THE FDOT DESIGN STANDARDS INDEX NO. 625, SHEET 1 OF 2.
- 3. THE FINAL FRICTION COURSE ALONG JOHN YOUNG PARKWAY NORTHBOUND SHALL BE CONSTRUCTED BY FIRST CLOSING THE OUTSIDE LANE, THEN CLOSING THE MEDIAN LANE, AND THEN CLOSING THE CENTER LANE. LANE CLOSURES FOR PLACEMENT OF THE FINAL FRICTION COURSE SHALL BE PER THE FDOT DESIGN STANDARDS INDEX NO. 625, SHEET 1 OF 2.
- 4. THE FINAL FRICTION COURSE ALONG TEXAS AVENUE (NORTH) SHALL BE CONSTRUCTED USING A FLAGGER OPERATION BY FIRST CLOSING THE NORTHBOUND LANE, THEN CLOSING THE SOUTHBOUND LANE. LANE CLOSURES FOR PLACEMENT OF THE FINAL FRICTION COURSE SHALL BE PER THE FDOT DESIGN STANDARDS INDEX NO. 621.
- 5. THE FINAL FRICTION COURSE ALONG TEXAS AVENUE (SOUTH) SHALL BE CONSTRUCTED BY FIRST CLOSING THE OUTSIDE LANE IN BOTH DIRECTIONS, THEN CLOSING THE MEDIAN LANE IN BOTH DIRECTIONS. LANE CLOSURES FOR PLACEMENT OF THE FINAL FRICTION COURSE SHALL BE PER THE FDOT DESIGN STANDARDS INDEX NO. 625. SHEET 1 OF 2.
- 6. THE FINAL FRICTION COURSE ALONG RIO GRANDE AVENUE (NORTH) SHALL BE CONSTRUCTED BY FIRST SHIFTING THE NORTHBOUND TRAFFIC INTO THE CENTER LANE AND CLOSING THE NORTHBOUND LANE, THEN CLOSING THE CENTER LANE, AND FINALLY BY SHIFTING THE SOUTHBOUND TRAFFIC TO THE CENTER LANE AND CLOSING THE SOUTHBOUND LANE. LANE CLOSURES FOR PLACEMENT OF THE FINAL FRICTION COURSE SHALL BE PER THE FDOT DESIGN STANDARDS INDEX NO. 625,
- 7. THE FINAL FRICTION COURSE ALONG RIO GRANDE AVENUE (SOUTH) SHALL BE CONSTRUCTED USING A FLAGGER OPERATION BY FIRST CLOSING THE NORTHBOUND LANE, THEN CLOSING THE SOUTHBOUND LANE. LANE CLOSURES FOR PLACEMENT OF THE FINAL FRICTION COURSE SHALL BE PER THE FDOT DESIGN STANDARDS INDEX NO. 621.
- 8. THE FINAL FRICTION COURSE ALONG MILLENIA BOULEVARD EASTBOUND SHALL BE CONSTRUCTED BY FIRST CLOSING THE OUTSIDE LANE, THEN CLOSING THE MEDIAN LANE, AND THEN CLOSING THE CENTER LANE. LANE CLOSURES FOR PLACEMENT OF THE FINAL FRICTION COURSE SHALL BE PER THE FDOT DESIGN STANDARDS INDEX NO. 625, SHEET 10F 2.


REVISIONS DESCRIPTION DESCRIPTION 225 E. Robinson Street, Suite 300 Landmark Center Two Orlando, FL 32801 (407) 839-4006 Certificate of Authorization #3932 Dante A. Gabriel, PE PE # 37271



TRAFFIC CONTROL PLAN PHASING NOTES

SHEET NO.


M-5



TYPICAL SECTION

HOLDEN AVENUE


STA. 10+81.55 TO STA. 36+84.92



TYPICAL SECTION

JOHN YOUNG PARKWAY

STA. 202+05.05 TO STA. 206+51.75



TYPICAL SECTION

HOLDEN AVENUE

STA. 36+84.92 TO STA. 76+06.61


REVISIONS				V H B
DATE	DESCRIPTION	DATE	DESCRIPTION	225 E. Robinson Street, Suite 300
				Landmark Center Two
				Orlando, FL 32801 (407) 839-4006 Certificate of Authorization #3932
				Dante A. Gabriel, PE
		1 1		PE # 37271




TRAFFIC CONTROL PLAN
TYPICAL SECTIONS
PHASE IB

SHEET NO. M-6

Andrew State Colored Control of C



TYPICAL SECTION TEXAS AVENUE STA. 392+50.00 TO STA. 400+60.24



TYPICAL SECTION TEXAS AVENUE STA. 400+60.24 TO STA. 408+50.00


REVISIONS				VHB
DATE	DESCRIPTION	DATE	DESCRIPTION	225 E. Robinson Street, Suite 300
				Landmark Center Two Orlando, FL 32801 (407) 839-4006 Certificate of Authorization #3932 Dante A. Gabriel, PE PE # 37271



TRAFFIC CONTROL PLAN TYPICAL SECTIONS PHASE IB

SHEET


M - 7



TYPICAL SECTION

RIO GRANDE AVENUE (SOUTH)

STA. 401+00.00 TO STA. 408+09.19



TYPICAL SECTION

RIO GRANDE AVENUE (NORTH)

STA. 410+04.22 TO STA. 414+40.00

REVISIONS				VHB
DATE	DESCRIPTION	DATE	DESCRIPTION	225 E. Robinson Street, Suite 300 Landmark Center Two Orlando, FL 32801 (407) 839-4006
				Certificate of Authorization #3932 Dante A. Gabriel, PE PE # 37271




TRAFFIC CONTROL PLAN
TYPICAL SECTIONS
PHASE IB


SHEET NO.

M - 8


760.00 Holdon Avo Bh 1 BD\ cad\ to\ ong\ cigning\ MOT\ t



TYPICAL SECTION HOLDEN AVENUE STA. 10+81.55 TO STA. 36+84.92



TYPICAL SECTION JOHN YOUNG PARKWAY STA. 202+05.05 TO STA. 206+51.75




HOLDEN AVENUE STA. 36+84.92 TO STA. 76+06.61

REVISIONS				VHB
DATE	DESCRIPTION	DATE	DESCRIPTION	225 E. Robinson Street, Suite 300
				Landmark Center Two Orlando, FL 32801 (407) 839-4006
				Certificate of Authorization #3932
				Dante A. Gabriel, PE PE # 37271



TRAFFIC CONTROL PLAN TYPICAL SECTIONS PHASE IIB


M - 9



TYPICAL SECTION

TEXAS AVENUE

STA. 392+50.00 TO STA. 400+60.24



TYPICAL SECTION

TEXAS AVENUE

STA. 400+60.24 TO STA. 408+50.00

REVISIONS				VHB
DATE	DESCRIPTION	DATE	DESCRIPTION	225 E. Robinson Street, Suite 300
				Landmark Center Two Orlando, FL 32801 (407) 839-4006 Certificate of Authorization #3932
				Dante A. Gabriel, PE PE # 37271



TRAFFIC CONTROL PLAN
TYPICAL SECTIONS
PHASE IIB

NO.

M-10